

1140-1150

Station	Main Studio	Freq	Power	Date
CBI	Sydney, NS	1140	10 kW/DA-N	2/28/62
CKTR	Three Rivers, QU	1140	10 kW/DA-2	11/29/68
CKXL	Calgary, AB	1140	50 kW/DA-2	8/25/81
CKXL	Calgary, AB	1140	10/50 kW/DA-2	2/22/65
CKXL	Calgary, AB	1140	10 kW/DA-N	5/28/59
NEW	Conroe, TX	1140	0.25 kW/DA-2	10/19/79
KCMJ	Palm Springs, CA	1140	5 kW/DA-N	12/4/80
KGEM	Boise, ID	1140	10 kW/DA-1	3/15/49
KLUC	North Las Vegas, NV	1140	2.5/10 kW/DA-N	9/21/77
KRAK	Sacramento, CA	1140	50 kW/DA-1	2/22/71
KRAK	Sacramento, CA	1140	50 kW/DA-2	3/3/58
KSOO	Sioux Falls, SD	1140	10 ND/5 kW/DA-N	3/19/52
NEW	Kentwood, MI	1140	5 kW/DA-D	10/20/76
WBZY	New Castle, PA	1140	5 kW/DA-D	4/29/70
WCJW	Warsaw, NY	1140	1 kW/DA-D	11/29/66
WCLW	Warsaw, NY	1140	0.25 kW/DA-D	3/28/69
WQBA	Miami, FL	1140	5/10 kW/DA-2	10/19/79
WQBA	Miami, FL	1140	10 kW/DA-2	9/21/48
WQBA	Miami, FL	1140	10 kW/DA-N	3/10/47
WQBA	Miami, FL	1140	5 kW/DA-N	3/10/47
WQBA	Miami, FL	1140	5 kW/DA-2	9/21/48
WQII	San Juan, PR	1140	10 kW/DA-1	1/25/78
WQIL	San Juan, PR	1140	10 kW/DA-1	1/28/65
WRVA	Richmond, VA	1140	50 kW/DA-1	2/7/57
XEMR	Monterrey, NL	1140	10 kW/DA-N	4/9/71
XEMR	Monterrey, NL	1140	50 kW/DA-N	8/3/77
NEW	Bay St. Louis, MS	1140	0.25 kW/DA-D	7/29/68

1140-1150

Station	Main Studio	Freq	Power	Date
NEW	Lexington, NC	1140	1 kW/DA-D	12/29/66
NEW	Gaspe, QU	1150	5 kW/DA-1	7/7/76
CJRC	Ottawa, ON	1150	5/10 kW/DA-1	8/24/62
CHSJ	St. John, NB	1150	5/10 kW/DA-2	5/28/59
CKIQ	Kelowna, BC	1150	10 kW/DA-N	4/7/78
CKOC	Hamilton, ON	1150	50 kW/DA-2	5/10/77
CKOC	Hamilton, ON	1150	10 kW/DA-2	8/26/66
CKTR	Three Rivers, QU	1150	1/10 kW/DA-2	5/27/60
CKTR	Three Rivers, QU	1150	1/5 kW/DA-2	7/8/58
CKX	Brandon, MB	1150	50/10 kW/DA-2	4/1/76
CKX	Brandon, MB	1150	10 kW/DA-N	2/22/71
KAGO	Klamath Falls, OR	1150	1/5 kW/DA-N	7/1/48
KAYO	Seattle, WA	1150	5 kW/DA-N	9/12/80
KBAI	Morro Bay, CA	1150	5 kW/DA-N	11/16/79
KCCT	Corpus Christi, TX	1150	1 kW/DA-D	2/22/71
KCKY	Coolidge, AZ	1150	1 kW/DA-N	2/26/63
KDEF	Albuquerque, NM	1150	0.5/1 kW/DA-N	9/25/58
KIIS	Los Angeles, CA	1150	5 kW/DA-N	10/19/79
KKEY	Portland, OR	1150	5 kW/DA-D	1/28/69
KKUZ	Burlington, IA	1150	0.5 kW/DA-D	9/13/60
KNED	McAlester, OK	1150	0.5/1 kW/DA-N	12/20/51
KPLS	Santa Rosa, CA	1150	0.5/5 kW/DA-2	5/17/57
KQAM	San Antonio, TX	1150	1 kW/DA-D	11/24/70
KSAL	Dallas, TX	1150	5 kW/DA-N	3/10/47
KSEN	Shelby, MT	1150	5 kW/DA-2	11/13/74
KSUZ	Port Neches, TX	1150	0.5 kW/DA-D	6/24/76
KVIL	Highland Park, TX	1150	1 kW/DA-D	12/21/59

1140-1150

Station	Main Studio	Freq	Power	Date
KWBZ	Englewood, CO	1150	1/5 kW/DA-N	10/19/79
KWBZ	Englewood, CO	1150	0.5/1 kW/DA-N	11/78
KWBZ	Englewood, CO	1150	5 kW/DA-2	9/12/80
KWKY	Des Moines, IA	1150	1 kW/DA-2	8/26/70
KXLR	North Little Rock, AR	1150	1/5 kW/DA-N	5/3/48
WCEN	Mt. Pleasant, MI	1150	0.5/1 kW/DA-N	6/27/69
WCOP	Boston, MA	1150	5 kW/DA-2	1/29/64
WCRK	Morristown, TN	1150	1/0.5 kW/DA-N	6/20/56
WCUE	Akron, OH	1150	1 kW/DA-D	2/23/49
WCUE	Akron, OH	1150	0.5/1 kW/DA-2	8/27/65
WDEL	Wilmington, DE	1150	5 kW/DA-2	8/9/48
WDEI	Wilmington, DE	1150	5 kW/DA-N	3/29/49
WDIX	Orangeburg, SC	1150	0.5/5 kW/DA-2	6/11/52
WGBR	Goldsboro, NC	1150	1/5 kW/DA-2	1/13/55
WGGH	Marion, IL	1150	5 kW/DA-D	7/18/55
WGOW	Chattanooga, TN	1150	1/5 kW/DA-N	3/27/70
WHMC	Gaithersburg, MD	1150	0.5/1 kW/DA-2	1/29/57
WIMA	Lima, OH	1150	1 kW/DA-N	3/24/71
WJBO	Baton Rouge, LA	1150	5 kW/DA-1	10/59
WJRD	Tuscaloosa, AL	1150	1/5 kW/DA-N	1/23/50
WJRL	Rockford, IL	1150	0.5 kW/DA-D	12/18/56
WKPA	New Kensington, PA	1150	1 kW/DA-D	5/27/66
WNDB	Daytona Beach, FL	1150	1 kW/DA-N	3/19/52
WRUN	Utica-Rome, NY	1150	1/5 kW/DA-2	4/14/47
WTAW	College Station, TX	1150	0.5/1kW/DA-N	10/13/77
WTMP	Temple Terrace, FL	1150	2.5/5 kW/DA-2	10/19/79
WTMP	Temple Terrace, FL	1150	5 kW/DA-D	12/18/56

1140-1150

Station	Main Studio	Freq	Power	Date
WYFE	Rockford, IL	1150	1 kW/DA-D	12/27/68
WYNE	Kimberly, WI	1150	5 kW/DA-2	11/16/79
WYNE	Kimberly, WI	1150	1 kW/DA-D	10/26/70
WYNS	Lehighton, PA	1150	1 kW/DA-D	7/8/59
NEW	Indianapolis, IN	1150	1 kW/DA-D	4/22/60
XEAD	Guadalajara, Jal.	1150	20 kW/DA-D	3/8/78
XEGE	Mexicali, Baja, CA	1150	0.5 kW/DA-N	8/27/65
XEJP	Mexico, DF	1150	10 kW/DA-N	8/23/63

X166
Description Sheet
(2-28-62ct)

Station CBI
Sydney, Nova Scotia

10kw, DA-N, U, Class II
1140 kc

CANADIAN BROADCASTING CORPORATION

ENGINEERING DIVISION MONTREAL
TITLE Engineering Brief for Station

CBI Sydney, N.S.

DWG. No.

DATE NOV. 20/61

ENG. J.H.S. APP. R.R.A.

DESCRIPTION OF ANTENNA ARRAY

Station: CBI

Main Studio: Sydney, Nova Scotia

Frequency: 1140 kc/s

Power: 10 kw

Class: II

Geographical Location of centre of antenna system: Lat.: 46° 8' 12" N.
Long: 60° 16' 15" W.

Notification List No. 166

Date: January 5, 1962

ANTENNA CHARACTERISTICS

Day and Night Operation: (DA-N)

Number of Elements: 2

Type of Elements: Series excited, uniform cross-section, guyed, vertical steel towers.

Towers:	East	West
Height Above Insulators	200' (87.5°)	200' (87.5°)
Overall Height Above Ground	206'	206'
Night Phasing	0°	90° (Lead)
Night Field Ratio	0.93 (0.93 / -90°)	1.0 (1.0 / 0°)

Spacing and Orientation: Elements are spaced 216' (90°) apart and lie on a line bearing 75°T.

Ground System: 120 radials per tower maximum length 345 ft. (0.4λ).
Radials joined along a line between towers.

Antenna Efficiency: 585 mv/m at 1 mile for 10 kw

185 mv/m at 1 mile for 1 kw



C.B.C. 1962

Transmission & Development Department

#166

CBI


Proposed Night
(2-28-62ct)

Station CBI
Sydney, Nova Scotia

10kw, DA-N, U, Class II
1140 kc

CODER BOOK COMPANY INC. NEW WOOD MANASQUETTES
PRINTED IN U.S.A.

NO. 3128 PULSES CO ORDINATE.



CKTR

Description Sheet
(11-29-68ct)Station CKTR
Three Rivers, Quebec10kw, DA-2, U, Class II
1140 kc

SUMMARY SHEET

STATION: CKTRMAIN STUDIO: Three Rivers, QuebecPOWER: 10 KWFREQUENCY: 1140 kHz CLASS: IINOTIFICATION LIST NO: 248DATE: October 29, 1968.GEOGRAPHICAL LOCATION:North latitude $46^{\circ} 14' 09''$
West longitude $72^{\circ} 33' 23''$ Antenna CharacteristicsMODE OF OPERATION:

DA-2

NUMBER OF ELEMENTS:

6

TYPE OF ELEMENTS:

Uniform Cross-Section, guyed steel towers, base insulated, for series feed.

TOWER:

#1N #2 #3 #4 #5 #6S

HEIGHT ABOVE INSULATORS:220'(91.8 $^{\circ}$) 220' 220' 220' 220' 220'OVERALL HEIGHT ABOVE GROUND:

225' 225' 225' 225' 225' 225'

FIELD RATIO: DAY
NIGHT

	0.333		1.000		
1.000	4.025	7.264	7.264	4.025	1.000

PHASING: DAY
NIGHT

-	0	-	+86 $^{\circ}$	-	-
-45 $^{\circ}$	108.2 $^{\circ}$	-98.0 $^{\circ}$	52.9 $^{\circ}$	-153.2 $^{\circ}$	0.0

SPACING:

285 $^{\circ}$	189.9 $^{\circ}$	95 $^{\circ}$	Ref.	95 $^{\circ}$	190 $^{\circ}$
----------------	------------------	---------------	------	---------------	----------------

ORIENTATION:

350.8 $^{\circ}$	351.3 $^{\circ}$	352.5 $^{\circ}$	Ref.	170.0 $^{\circ}$	170.0 $^{\circ}$
------------------	------------------	------------------	------	------------------	------------------

GROUND SYSTEM:

120 equally spaced radials of #10B and S bare copper wires per tower, buried approximately 8" length 346' (0.4 wavelength). 120 additional radials extend 50' from each tower. Each tower base to be connected by 2" wide copper strap.

PREDICTED EFFECTIVE FIELD:DAY: 600 mv/m (10 Kw) or 191 mv/m Kw
NIGHT: 650 mv/m (10 Kw) or 207 mv/m/KwRCA VICTOR COMPANY, LTD.
MONTREAL, QUEBEC

PROJECT 2840-H

CKTR


Proposed Day
(11-29-68ct)

Station CKTR
Three Rivers, Quebec

10kw, DA-2, U, Class II
1140 kc

CORDEE BOOK COMPANY, INC. NORWOOD, MASSACHUSETTS
PRINTED IN U.S.A.

NO. 8124 POLAR CO-ORDINATE



CKTR

Proposed Night
(11-29-68ct)

Station CKTR
Three Rivers, Quebec

10kw, DA-2, U, Class II
1140 kc

CODEX BOOK COMPANY, INC. NORWOOD, MASSACHUSETTS
PRINTED IN U.S.A.

NO. 3124 POLAR CO-ORDINATE




Figure 2
Horizontal Nighttime Pattern
CKTR
Three Rivers, Que.
1140 kHz 10 KW DA-2 Class II
Proj. 2840-H-3-B
RCA Victor Company, Ltd., Montreal, P.Q.




CKTR

Proposed Night Nulls
(11-29-68ct)

Station CKTR
Three Rivers, Quebec

10kw, DA-2, U, Class II
1140 kc



1140 10 KW DA-2 U, Class II 46 1322

RECEIVED 8-29-68

PROJECT #623

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CKXL

MAIN STUDIO: Calgary, Alberta

FREQUENCY: 1140 kHz

POWER: 50,000 Watts CLASS: II

NOTIFICATION LIST: 407

DATE: August 25, 1981

GEOGRAPHICAL LOCATION:

Latitude 50° 55' 25" North
Longitude 113° 49' 58" West

ANTENNA CHARACTERISTICS:

Mode of Operation:
Number of Elements:
Type of Elements:DA-2
4 (Four)
Guyed steel towers, uniform
cross-section, base insulated
for series feed

TOWERS:	#1 (W)	#2 (N)	#3 (E)	#4 (S)
Height above Base Insulators:	216' (90°)	216' (90°)	216' (90°)	216' (90°)
Overall Height:	220'	220'	220'	220'
Orientation:	Ref.	30°	82.2°	118.5°
Spacing:	Ref.	90°	151.87°	120°
Day Phasing:	Ref.	-30°	- -	45°
Night Phasing:	Ref.	-91.4°	-24.1°	67.3°
Day Field Ratio:	1.0	0.25	- -	0.2
Night Field Ratio:	1.0	0.87	0.896	1.03


GROUND SYSTEM:

120 equally spaced radials of
#10 bare soft copper wire
extending 345' (0.4 wavelength)
from the base of each tower with
the exception of those joined
along the common chords.

PREDICTED EFFECTIVE FIELD:

Night1250 mV/m at 1 mile for 50 kW
177 mV/m at 1 mile for 1 kWDay1273 mV/m at 1 mile for 50 kW
180 mV/m at 1 mile for 1 kWDecember 19, 1980
Revised August 5, 1981

Page 11



Description Sheet
(11-29-68ct)

Station CKXL
Calgary, Alberta
CORRECTED
DESCRIPTION SHEET

10kw, 50kw-LS, DA-2, U, Class II
1140 kc

STATION: CKAL MAIN STUDIO: Calgary, Alberta.
POWER: 50 KW D, 10 KW N FREQUENCY: 1140 Kc/s CLASS: II

NOTIFICATION LIST NO. 195 DATE: February 22, 1965

GEOGRAPHICAL LOCATION:

North Latitude: 50° 52' 36"
West Longitude: 114° 02' 30"

ANTENNA CHARACTERISTICS

MODE OF OPERATION: DA-2
NUMBER OF ELEMENTS: Three (3)
TYPE OF ELEMENTS: Guyed Steel Towers, uniform cross section, base insulated for series feed.

<u>TOWER:</u>	<u>North #1</u>	<u>Center #2</u>	<u>South #3</u>
HEIGHT ABOVE INSULATORS:	215' (90°)	215' (90°)	215' (90°)
OVERALL HEIGHT:	230'	230'	230'
FIELD RATIO - Night	.588	1.0	.588
PHASING - Night	+210.3°	0°	-210.3°
FIELD RATIO - Day	1.0	1.1	.45
PHASING - Day	0°	+125°	+45°

GROUND SYSTEM: 120 equally spaced radials per tower of No. 10 B & S gauge bare copper wire, buried approximately 8". Length of radials 345' (0.4 wavelength) with the exception of those joined along the common chords.

SPACING AND ORIENTATION:

The towers are on a line bearing 11° East of North and adjacent towers are spaced 191' (80°) apart.

PREDICTED EFFECTIVE FIELD:

Daytime: 1330 mv/m at 1 mile for 50 KW
188 mv/m at 1 mile for 1 KW
Nighttime: 575 mv/m at 1 mile for 10 KW
181.5 mv/m at 1 mile for 1 KW

NOTE: Please attach the nighttime pattern notified for CKXL in Canadian Change List No. 122, dated May 27, 1968 to this revised description sheet and daytime pattern. This only concerns a change in daytime operation.


FRS

CKXL

Proposed Day
(3-26-65ct)

Station CKXL
Calgary, Alberta

10kw, 50kw-LS, DA-2, U, Class II
1140 kc



6157, 23.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : NEW Main Studio: Conroe, Texas
 Frequency : 1140 KHz Power : Night .25 kW Day
 Notification : 1781 Date : Oct. 19, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 30 20 40
 West Longitude: 95 27 32

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-2)

Number of elements: 2


Type of elements : Series excited, uniform cross-section,
guyed vertical steel towers.

TOWER : W(#1) E(#2)
 HEIGHT ABOVE
 INSULATORS : 192' 192' (80.1°)
 DAY PHASING : 0° -75°
 DAY FIELD RATIO : 1 1
 SPACING AND
 ORIENTATION : The towers in a row are spaced 211' (88°)
 on a line bearing 96° True.
 GROUND SYSTEM : 120 - 215' to ' equally spaced copper
 radials plus 120 - 50' interspaced radials about each
 tower. Radials are shortened and bonded to a transverse
 strap along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	<u>88.4</u> mv/m	<u>90.4</u> mv/m	<u>92.8</u> mv/m
Night	<u> </u> mv/m	<u> </u> mv.m	<u> </u> mv/m

Note:



(NEW) CONROE, TEXAS
 Station
 1140 KHZ. 0.25 KW DA-D
 Frequency Power
 G1 = G2 = 192 FT. = 80.7
 Height of Antennas

Location
 N. LAT. 30° 20' 40"
 W. LNG. 95° 27' 32"

KCMJ
1140kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KCMJ Main Studio: Palm Springs, California
Frequency: 1140 kHz Power: 5kw Night 10kw Day
Notification List No. 1790 Date: December 4, 1980 Class: II

GEOGRAPHICAL LOCATION OF THE CENTERS OF THE DAYTIME AND NIGHTTIME ANTENNA SYSTEMS:

<u>DAYTIME</u>	<u>NIGHTTIME</u>
North Latitude: 33° 51' 41"	North Latitude: 33° 49' 43"
West Longitude: 116° 31' 44"	West Longitude: 116° 26' 16"

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
Number of elements: 5
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	SW(#1)	SWC(#2)	C(#3)	NEC(#4)	NE(#5)
HEIGHT ABOVE INSULATORS:	216'	216'	216'	216'	216' (90.12°)
NIGHT PHASING:	0°	+151.15°	-57.89°	+93.07°	-115.78°
NIGHT FIELD RATIO:	1.0	3.206	4.468	3.260	1.0
SPACING AND ORIENTATION:	Towers in a row are spaced 118.8° on a line bearing 53.3° true.				
GROUND SYSTEM:	120 - 216' equally spaced copper radials plus 120 - 50' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.				

DAYTIME ANTENNA CHARACTERISTICS


Authorized for Daytime operation. (ND-D)
Number of elements: 1
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.
* Includes top loading.

HEIGHT ABOVE INSULATORS:	150' (77.2°) *
GROUND SYSTEM:	120 - 180' to 262' equally spaced copper radials about each tower.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	<u>THEORETICAL</u> <u>RMS</u>	<u>RSS</u>	<u>STANDARD</u> <u>RMS</u>
Day	585 mv/m		
Night	392 mv/m	530 mv/m	412 mv/m

KCMJ
1140KHz



PROPOSED NIGHT & DAY


Station KGEM
Boise, Idaho

10kw, DA-1,U
1140 KC

3/15/49

SITE: 43° 33' 25" N
116° 18' 00" W

McNARY & WRATHALL
CONSULTING RADIO ENGINEERS




AMENDMENT RECD 3-11-49

KGEM, BOISE, IDAHO 1140 kc

KGEM, Boise, Idaho 1140 kc

1145



PROPOSED
NIGHT & DAY NULLS


KGEM, BOISE, IDAHO

10-17-49

10kw, DA-1

KGEM

1140 kc




KGEM

MEASURED
DAY & NIGHT

KGEM, BOISE, IDAHO

10kw, DA-1

1140 kc



DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KLUC Main Studio: North Las Vegas, Nevada
 Frequency : 1140 kHz Power : 2.5kw Night 10kw Day
 Notification List No.: 1750 Date : September 21, 1977 Class:1B

GEORGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 36° 16' 03"
 West Longitude: 115° 02' 41"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 4
 Type of elements : Series excited, uniform cross-section, guyed
 vertical steel towers.

TOWER	NW (#1)	EW (#2)	EE (#3)	SE (#4)
HEIGHT ABOVE INSULATORS	240'	240'	240'	240' (100.1')
PHASING	0°	+38.6°	+80.9°	+117.6°
FIELD RATIO	1	2.2	2.16	0.95

SPACING AND


ORIENTATION: Adjacent towers in a row are spaced 465' (19°) on a line bearing
 129.5° true.

GROUND SYSTEM: 120 - 216' equally spaced copper radials plus 120 - 50' interspaced
 about each tower.
 radials/ Radials are shortened and bonded to transverse
 straps along intersections between towers. Centers of system are
 together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	<u>RMS</u>	THEORETICAL <u>RSS</u>	STANDARD <u>RMS</u>
Day	613.5 mv/m		
Night	283.5 mv/m	359.7 mv/m	297.9 mv/m

Note: This notification concerns changes in the Daytime and Nighttime operation of the station.



1000

400

100

40

10

0

KLUC
KLUC BROADCASTING COMPANY
1140 KHZ 10 KW-D, CH 2.5 KM-N DA-N
NORTH LAS VEGAS, NEVADA
MARCH 1977

PROPOSED NIGHTTIME DIRECTIONAL
HORIZONTAL EXPANDED PATTERN
UNATTENUATED FIELD AT ONE MILE

NIGHTTIME STANDARD PATTERN

VIR JAMES
CONSULTING RADIO ENGINEER
100 COLORADO BLVD - DENVER, CO - 80202
(303) 733-7343



YEAR

W3VA

SCALE x 0.1

EXHIBIT E-6.02A

AMENDED:
NULLS DETAILED

360

300

240

180

120

60



AZIMUTH - DEGREES TRUE

mV/μm

Measured Day & Night
(2-22-71ct)

Station KRAK
Sacramento, California

KRAK
50kw, DA-1, U
1140 kc



**MEASURED
HORIZONTAL RADIATION PATTERN
DIRECTIONAL**

**UNATTENUATED FIELD INTENSITY
AT ONE MILE**

HAMMETT & EDISON
CONSULTING ENGINEERS
SAN FRANCISCO

RADIO STATION KRAK
1140 KHZ. 50 KW. DA-1
SACRAMENTO, CALIFORNIA

700601

FIGURE 10B

FCC File No. BL-12859
Accepted 2-8-71


Station KRAK
Sacramento, California

1140 kc

Measured Non-DA
(2-22-71ct)

Station KRAK
Sacramento, California

KRAK
50kw, DA-1, U
1140 kc



N. LAT 38 23 34
W. LONG 121 11 51
G - 100' 240 FT
RMS 903 MV/M

TOWER 2 EXCITED
TOWERS 1 3 4 & 5 FLICATING

HAMMETT & EDISON
CONSULTING ENGINEERS
SAN FRANCISCO

RADIO STATION KRAK
1140 KHZ 50 KW DA 1
SACRAMENTO CALIFORNIA

700501

MEASURED
HORIZONTAL RADIATION PATTERN
NON-DIRECTIONAL
UNATTENUATED FIELD INTENSITY
AT ONE MILE

FIGURE 10A

FCC File No. BL-12859
Accepted 2-8-71

Station KRAK
Sacramento, California

1140 kc

Proposed Day & Night Nulls
(5-27-69ct)

Station KRAK
Sacramento, California


KRAK
50kw, DA-1, U
1140 kc

RADIO STATION KRAK

CALCULATED RADIATION

ELEVATION ANGLE 0°

*BP-18564, Granted
5/27/69 C.P. To
change transmitter
location & make
changes in
directional
antenna
pattern*



681202.1

FCC File No. BP-18564
Accepted 5-26-69

HAMMETT & EDISON
CONSULTING ENGINEERS
Station KRAK
Sacramento, California

FIGURE 6C

1140 kc


KRAK

Proposed Day & Night
(5-27-69ct)

Station KRAK
Sacramento, California

50kw, DA-1, U
1140 kc

*51-15564
dated 5/27/69
change
transmitter
location
make changes
in directional
pattern*



RMS - 1340 MV/M G - 100° - 240 FT		0.2123 [116.97°] 5	
0.6306 [50.41°] 4		10000 [0°] 3	
0.8094 [97.25°] 2		TOWER LOCATIONS RELATIVE TO TOWER 3	
0.2486 [-160.05°] 1		TOWER	AZIMUTH DISTANCE
		1	N 251.19° E 330.00° 791.2 FT
		2	247.45° 149.96° 359.6
		4	73.85° 205.06° 491.7
		5	72.85° 336.85° 951.5
HAMMETT & EDISON CONSULTING ENGINEERS SAN FRANCISCO		RADIO STATION KRAK 1140 KHZ. 50 KW. DA-1 SACRAMENTO, CALIFORNIA	

PROPOSED
HORIZONTAL RADIATION
UNATTENUATED FIELD INTENSITY
AT ONE MILE

681202.1

FIGURE 6B

FCC File No. BP-18564
Accepted 5-26-69

Station KRAK
Sacramento, California

1140 kc


KRAK

Proposed Day & Night
(9-26-69ct)

Station KRAK
Sacramento, California

50kw, DA-1, U
1140 kc

BMP-12764
Granted
9-5-69 Modification
of CP to
change
antenna
transmitter
location



N. Lat. 38° 23' 34"
W. Long. 121° 11' 51"

RMS - 1340 MV/M
G - 100° - 240 FT

0.2123 116.97° 5

0.6306 50.4° 4

1.0000 0° 3

0.8094 97.25° 2

0.2486 160.05° 1

TOWER LOCATIONS RELATIVE TO TOWER 3

TOWER	AZIMUTH	DISTANCE
1	N 251.19° E	330.00° 791.2 FT
2	247.45°	149.96° 359.6
4	73.86°	205.06° 491.7
5	72.85°	396.85° 951.5

HAMMETT & EDISON
CONSULTING ENGINEERS
SAN FRANCISCO

RADIO STATION KRAK
1140 KHZ 50 KW DA-1
SACRAMENTO, CALIFORNIA 690609

PROPOSED
HORIZONTAL RADIATION

UNATTENUATED FIELD INTENSITY
AT ONE MILE

FCC File No. BMP-12764
Accepted 8-26-69

Station KRAK
Sacramento, California

1140 kc

FIGURE 3

KRAK

Sacramento


PROPOSED DAY
(3-3-58g)

Station KRAK
Stockton, California


50kw, DA-2,U

1140 KC

*Granted CP 7/9/58
for increase in
power & change from
DA-N to DA-2
Granted license
7-28-60
Shifting location
to Sacramento
7-27-60
12-22-61 granted CP
for DA-1 operation*



LAT. 38° 17' 30" N
LONG. 121° 05' 56" W




PROPOSED KRAK	DA	EXHIBIT
1140 KC-50 KW-U-DA2	HORIZONTAL	
STOCKTON, CALIF.	PLANE PATTERN	NO. E1-A(D)

FCC File No. BP-10,676
Accepted 10-1-57 (Amended) KRAK
Stockton, California

1140 KC

KRAK

MEASURED DAY
(5-27-60g)Sacramento
Station KRAK
Stockton, California
U50kw, DA-2,U
1140 KCFCC File No. BL-7886
Accepted 4-21-60KRAK
Stockton, California

1140 KC

KRAK


PROPOSED NIGHT
(3-3-58g)

Sacramento


Station KRAK
Stockton, California

50kw, DA-2,U
1140 KC

*Granted CP 7/9/58
for increase in
power & change
from DA-N to DA-2
Granted license
7-25-60
St. to document
7-27-60
[initials]*



LAT 38° 17' 30" N
LONG. 121° 05' 56" W



PROPOSED	KRAK	NIGHT	EXHIBIT
1140 KC-50 KW-U-DA2		HORIZONTAL	
STOCKTON, CALIF		PLANE PATTERN	NO. E1-A(N)

FCC File No. BP-10,676
Accepted 10-1-57 (Amended)

KRAK
Stockton, California


1140 KC

KRAK

MEASURED NIGHT
(5-27-60g)

Sacramento
Station KRAK
Stockton, California

50kw, DA-2,U
1140 KC



FCC File No. BL-7886
Accepted 4-21-60

KRAK
Stockton, California


1140 KC

KRAK

MEASURED NON-DA
(5-27-60g)

Sacramento
Station KRAK
Stockton, California
()

50kw, DA-2,U
1140 KC



FCC File No. BL-7886
Accepted 4-21-60

KRAK
Stockton, California

1140 KC


K500

MEASURED
NIGHT

K500, SIOUX FALLS, S. DAK.
3/19/52G

5 KW, 10KW-LS, U, DA-N

1140 KC



MEASURED HORIZONTAL PLANE
RADIATION PATTERN OF K500,
SIOUX FALLS, SOUTH DAKOTA
1140 KC; 10 KW-ND-DAY; 5 KW-DA-NIGHT
FEBRUARY, 1952

O INDICATES RADIAL MEASUREMENTS

APPL RECD 2/15/52 ACC 3/14/52 BL-4676

K500, SIOUX FALLS, S. DAK.


1140 KC

PROPOSED
NIGHT NULLS

KS00, SIOUX FALLS, S. D.

5kw, 10kw-LS, DA-N 1140 kc

KS00



AMENDMENT RECD. 8-24-50 ACC. 9-1-50 BP-7501


KS00, Sioux Falls, S. D. 1140 kc

PROPOSED
NIGHT

KS00, SIOUX FALLS, S. D.

5kw, 10kw-LS, DA-N 1140 kc

KS00



1/99° - 100° - 3.403/-130.6° - 100° - 4.837/0° - 100° - 3.403/130.6° - 100° - 1/-99° - 146°
Height - 92° - 220'

GRAPH OF HORIZONTAL PLANE PATTERN
FOR PROPOSED DIRECTIVE NIGHTTIME OPERATION
OF STATION KS00, SIOUX FALLS, SOUTH DAKOTA
1140 KC - 5 KW; 10 KW L.S. - DA(N)
UNATTENUATED FIELD AT ONE MILE
AUGUST 1950

AMENDMENT RECD. 8-24-50 ACC. 9-1-50 BP-7501

KS00, Sioux Falls, S. D. 1140 kc


KS00

MEASURED
NON-DA (Day)

KS00, SIOUX FALLS, S. DAK.
3/19/52G

5 KW, 10KW-LS, U, DA-N

1140 KC



MEASURED NON-DIRECTIONAL 10 KW
RADIATION FIELD PATTERN FOR KS00,
SIOUX FALLS, SOUTH DAKOTA
1140 KC; 10 KW-ND-DAY; 5 KW-DA-NIGHT
FEBRUARY, 1952

○ INDICATES RADIAL MEASUREMENTS

APPL RECD 2/15/52 ACC 3/14/52 BL-4676

KS00, SIOUX FALLS, S. DAK.

1140 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: (New) Main Studio: Kentwood, Michigan
 Frequency: 1140 kHz Power: 5 kW
 Notification List No. 1706 Date: October 20, 1976 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 56' 13"
 West Longitude: 85° 27' 20"

ANTENNA CHARACTERISTICS

Authorized for daytime operation. (DA-D)
 Number of elements: 3
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	W(#3)	C(#2)	E(#1)	
HEIGHT ABOVE INSULATORS:	216'	216'	216'	(90°)
PHASING:	+70.46°	+215.23	0°	
FIELD RATIO:	1.000	1.863	1.000	

SPACING AND

ORIENTATION: Adjacent towers in a row are spaced 192' (80°) on a line bearing 280° true.


GROUND SYSTEM: 120-216' equally spaced copper radials plus 120-50' inter-spaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL	STANDARD
	<u>RMS</u>	<u>RMS</u>
Day 1/ 459.57 mv/m	782.65 mv/m	482.98 mv/m

1/ By adjustment of input power.

NEW



CD. PATTERN
IS = 482.983 mV/m

HEO. PATTERN
IS = 459.570

HEO. PATTERN
SS = 782.648

THEO. PATTERN
RSS/RMS = 1.703


Standard Pattern

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 2	STATION DATA
G=90° S=80° 280° T. #3 — S — O — S — O — #1 #2	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	STANDARD HORIZONTAL PLANE PATTERN	CALL NEW FREQ 1140 kHz POWER 5 Kw TYPE DA TIME DAY LAT. N42-56-13 LONG. W89-27-20 E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
	No	G	S	U	F		
	1			0	1.		
	2			215.23	1.863		
	3			70.46	1.		
	4						
	5						
	6						
DAYTIME OPERATION ☒					NIGHTTIME OPERATION ☐	θ°	

Measured Day
(4-29-70ct)

Station WBZY
New Castle, Pennsylvania

WBZY
5kw, DA-D, D
1140 kc



HORIZONTAL RADIATION PATTERN

Spacing and Orientation of Array	
TOWER NO. 1	352 / -50.0°
TOWER NO. 2	1.0 / 105.0°
TOWER NO. 3	709 / -105.0°
TOWER NO. 4	211 / 50.8°

G - 82°

APPLICANT	Lawrence County Broadcasting Corp.
LOCATION	New Castle, Pennsylvania
FREQUENCY	1140 KC
POWER	5.0 Kw
LATITUDE	40 DEG 56 MIN 23 SEC
LONGITUDE	80 DEG 23 MIN 35 SEC
WHEN USED	Daytime
RMS FIELD	440 MV/M
DATE	December 1969
ROBERT L. PURCELL	
WASHINGTON, D. C.	

FCC File No. BL-12587
Accepted 4-9-70


Station WBZY
New Castle, Pennsylvania

1140 kc

Measured Non-DA
(4-29-70ct)

Station WBZY
New Castle, Pennsylvania

WBZY
5kw, DA-D, D
1140 kc



NON-DIRECTIONAL FIELD SURVEY

ROBERT J. PURCELL

WASHINGTON, D. C.

FCC File No. BL-12587
Accepted 4-9-70

Station WBZY
New Castle, Pennsylvania

1140 kc

WBZY

Proposed Day
(10-28-69ct)

Station WBZY
New Castle, Pennsylvania

5kw, DA-D, D.
1140 kc

EP-18648
Granted
10-7-69
CP To Relay
MEOV's





FIGURE 1-A

HORIZONTAL RADIATION PATTERN

Spacing and Orientation of Array



G - 82°

APPLICANT	Lawrence County Broadcasting Corp.
LOCATION	New Castle, Pennsylvania
FREQUENCY	1140 KC/S
POWER	5.0Kw
CAT-1-CT	40 DEG 56 MIN 23 SEC
LONG-T-USE	80 DEG 23 MIN 38 SEC
WHEN USED	Daytime
RMS FIELD	443 mv/m
DATE	July 1969

ROBERT L. PURCELL

WASHINGTON, D. C.

FCC File No. BP-18648
Accepted 10-2-69

Station WBZY
New Castle, Pennsylvania


1140 kc

Proposed Day Nulls
(10-28-69ct)

Station WBZY
New Castle, Pennsylvania

WBZY
5kw, DA-D, D
1140 kc

BP-18648
Granted
10-7-69
EP to relay
MEOV's.



EXPANDED VIEW

ROBERT L. PURCELL

WASHINGTON D C

FCC File No. BP-18648
Accepted 10-2-69

Station WBZY
New Castle, Pennsylvania

1140 kc

WCJW


Proposed Day
(11-29-66ct)

New; John B. Weeks
Warsaw, New York

1kw, DA-D, D
1140 kc

EUGENE DIETZEN CO.
MADE IN U. S. A.

EUGENE DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BP-17400
Accepted 11-2-66

New; John B. Weeks
Warsaw, New York

1140 kc


Measured Day
(3-28-69ct)

Station WCLW
Mansfield, Ohio

WCLW

250w, DA-D, D
1140 kc

SEE REVERSE SIDE



RMS --- 90.8 mV/m
MEOV

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS	FIGURE 4	STATION DATA																																																							
(Measured) 120° → 80.25°T 0.532/-56.8° 125° → 0.378/+123.5° 75° → 0.840/-165° 168.75°T G's=90°	<table><tr><th>TOWER No.</th><th>ELECTRICAL HEIGHT G'</th><th>SPACING S'</th><th>PHASING P'</th><th>FIELD RATIO F'</th></tr><tr><td>1</td><td></td><td></td><td></td><td></td></tr><tr><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>3</td><td></td><td></td><td></td><td></td></tr><tr><td>4</td><td></td><td></td><td></td><td></td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></table> DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐	TOWER No.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING P'	FIELD RATIO F'	1					2					3					4					5					6					7					8					9					10					MEASURED DIRECTIONAL PATTERN JANUARY 1969 θ° = 0	CALL WCLW FREQ 1140 kHz POWER 0.25 kW TYPE DA-D TIME DAYTIME LAT. 40-46-09 LONG. 82-32-23 E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER No.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING P'	FIELD RATIO F'																																																						
1																																																										
2																																																										
3																																																										
4																																																										
5																																																										
6																																																										
7																																																										
8																																																										
9																																																										
10																																																										

FCC File No. BL-12297
Accepted 3-18-69

Station WCLW
Mansfield, Ohio

1140 kc


WCLW

Measured Non-DA
(3-28-69ct)

Station WCLW
Mansfield, Ohio

250w, DA-D, D
1140 kc

SEE REVERSE SIDE



RMS = 102.5 Mv/M 210°
MEOV

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 5	STATION DATA																																																									
1-NU 120° 2-80.25° T NDA 125° 3-NU 75° 4-NU 168.75° T. G's=90°	<table><tr><th>TOWER</th><th>ELECTRICAL</th><th>SPACING</th><th>PHASING</th><th>FIELD</th></tr><tr><th>No.</th><th>HEIGHT</th><th>S*</th><th>W*</th><th>RATIO</th></tr><tr><td>1</td><td></td><td></td><td></td><td></td></tr><tr><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>3</td><td></td><td></td><td></td><td></td></tr><tr><td>4</td><td></td><td></td><td></td><td></td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></table>	TOWER	ELECTRICAL	SPACING	PHASING	FIELD	No.	HEIGHT	S*	W*	RATIO	1					2					3					4					5					6					7					8					9					10					MEASURED NON-DIRECTIONAL PATTERN ***** WCLW MANSFIELD, OHIO		CALL WCLW FREQ 1140 KHz. POWER 0.25 Kw TYPE DA-D TIME DAYTIME LAT. 40-46-09 LONG. 82-32-23 E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER	ELECTRICAL	SPACING	PHASING	FIELD																																																												
No.	HEIGHT	S*	W*	RATIO																																																												
1																																																																
2																																																																
3																																																																
4																																																																
5																																																																
6																																																																
7																																																																
8																																																																
9																																																																
10																																																																

FCC File No. BL-12297
Accepted 3-18-69

Station WCLW
Mansfield, Ohio


1140 kc

Proposed Day
(8-28-67ct)

Station WCLW
Mansfield, Ohio

250w, DA-D, D
1140 kc

over



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 4	STATION DATA	
G's = 90° 1/0" 120° 80.25' 0.96/-74° 125° 110.25' 0.63/115.5 75" 168.75' 0.74/189° 40" 168.75' 0.74/189°	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	PROPOSED DAYTIME DIRECTIONAL PATTERN *** WCLW MANSFIELD, OHIO *** JUNE 1967 6° = 0	CALL WCLW FREQ 1140 KHz POWER 0.25 Kw TYPE DA-D TIME DAY LATN-40-46-09 LONG.W-82-32-23 E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.	
	1	80.25'						
	2							
	3							
	4							
	5							
	6							
	7							
	8							
	9							
	10							
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐								

FCC File No. BMP-12146
Accepted 8-25-67

Station WCLW
Mansfield, Ohio

1140 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WCLW

Main Studio: Mansfield, Ohio

Frequency: 1140 kHz

Power: 0.25 kw

Notification List No. 1755

Date: November 2, 1977

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 40° 46' 09"

West Longitude: 82° 32' 23"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 4

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	NW(#1)	SW(#4)	NE(#2)	SE(#3)
HEIGHT ABOVE INSULATORS:	216'	216'	216'	216' (95°)
PHASING:	0°	+189°	-74°	+115.5°
FIELD RATIO:	1.00	0.74	0.96	0.63

SPACING AND
ORIENTATION:

From reference tower #1, tower #4 is spaced 179.7' (75°)
on a line bearing 168.75° true, tower #2 is spaced 287.5'
(120°) on a line bearing 80.25° true, and tower #3 is
on a line bearing 110.25° true.


GROUND SYSTEM: 120-155' to 300' equally spaced copper radials plus a 24'
square ground screen about each tower. Radials are shortened
and bonded to transverse straps along intersections between
towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL

RMS
Day 90 mv/m

This notification concerns only minor changes in m.e.o.v.s of radiation
in the directional antenna pattern.



$RMS_{THEO} = 90 \text{ mV/m}$

----- MEOV
 ——— 10X THEO. PATTERN EXPANSION

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 3	STATION DATA
	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	PROPOSED DAYTIME DIRECTIONAL PATTERN **** WCLW MANSFIELD, OHIO **** $\theta^{\circ} = 0$	CALL WCLW FREQ 1140 kHz. POWER 0.25 kW TYPE DA-D TIME DAYTIME LAT. N 40°46'09" LONG. W 82°32'23" E. HAROLD MUNN, JR. & ASSOCIATES, INC. COLDWATER, MICH.
	1	90°		0°	1.00		
	2	90°		-74°	0.96		
	3	90°		115.5°	0.63		
	4	90°		189°	0.74		
	5						
	6						
DAYTIME OPERATION					NIGHTTIME OPERATION		

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WQBA Main Studio: Miami, Florida
 Frequency : 1140 KHz Power : 5 kW Night 10 kW Day ____
 Notification : 1781 Date : Oct. 19, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 25 42 31
 West Longitude: 80 22 41

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 5

Type of elements : Series excited, uniform cross-section,
 guyed, Shunt excited, Self-supporting,
 tapered, vertical steel towers.

TOWER	:	<u>NW(1)</u>	<u>NWC(2)</u>	<u>C(3)</u>	<u>SEC(4)</u>	<u>SE(5)</u>	_____
HEIGHT ABOVE INSULATORS	:	<u>220'</u>	<u>220'</u>	<u>220'</u>	<u>220'</u>	<u>220'</u>	<u>(91.8°)</u>
NIGHT PHASING	:	<u>162°</u>	<u>80.8°</u>	<u>0°</u>	<u>-80.8°</u>	<u>-162°</u>	_____
NIGHT FIELD RATIO:		<u>0.2304</u>	<u>0.7212</u>	<u>1.0</u>	<u>0.7212</u>	<u>0.2304</u>	_____
DAY PHASING	:	<u>---</u>	<u>---</u>	<u>0°</u>	<u>-150°</u>	<u>---</u>	_____
DAY FIELD RATIO	:	<u>---</u>	<u>---</u>	<u>1.0</u>	<u>0.60</u>	<u>---</u>	_____

SPACING AND
ORIENTATION

The towers in a row are spaced 446' (186°)
 on a line bearing 305° true.

GROUND SYSTEM

: 120 - 215' equally spaced copper radials plus
 under a 48' square ground each tower. Also an
 inverted copper box on each tower pier is bonded
 to the ground system.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD	
	<u>RMS</u>		<u>RSS</u>	<u>RMS</u>
Day	<u>600</u>	mv/m	<u> </u>	630 mv/m
Night	<u>410</u>	mv/m	<u> </u>	<u>430.50</u> mv/m

Note: Please retain the Daytime directional antenna radiation pattern notified for Station WHIE (now WQBA) in United States Change Lists Numbers 265 and 235 dated February 20, 1948 and July 10, 1947 and attach to this Revised Description Sheet Nighttime pattern. This notification concerns only a change in the Nighttime operation of the station with Daytime operation continued as previously notified.

CTR NO

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
IN HORIZONTAL PLANE


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 5 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 10 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 15 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 20 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 25 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 30 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 35 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW. 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 40 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA 2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 45 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 50 DEGREES


SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 55 DEGREES

SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA


1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates Consulting Electronics Engineers

WQBA

Figure 1
Sheet 14 of 14

APRIL 1978



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 60 DEGREES

SUSQUEHANNA BROADCASTING COMPANY

STATION WQBA MIAMI, FLORIDA

1140 KHZ 5 KW, 10 KW-LS U DA-2

Jules Cohen & Associates

Consulting Electronics Engineers

WQBA

SUPPLEMENTAL DIRECTIONAL ANTENNA
DESCRIPTION SHEET

Station: WQBA

Main Studio: Miami, Florida

Frequency: 1140 kHz

Power: 5 kW Night 10 kW Day

Notification List No. 1659

Date: November 17, 1975 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude:	25°	42'	31"
West Longitude:	80°	22'	41"

Authorized for Day and Night operation (DA-2).


Note: Please retain the description sheet and directional antenna radiation patterns notified for station WHIE (now WQBA) in United States Change Lists Numbers 265 and 235, dated February 20, 1948 and July 10, 1947 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates of the center of the antenna system.

CTR NO 30869A4


September 15, 1948

9/21/48G

WQBA

~~WMIE~~
1140

RMS MEASURED — 582 MVM
RMS THEORETICAL — 600 MV/M



HORIZONTAL RADIATION PATTERN DAY TIME

ANT	Q	DEG	S	DEG	Q	DEG	FIELD	K	F	GND	H	DEG
3							1.0					95
4	180°	185			-15		.6					95

WMIE
MIAMI, FLORIDA

10 KW.

DA-2

1140 KC.

GLENN D. GILLET AND ASSOCIATES
CONSULTING RADIO ENGINEERS
NATIONAL PRESS BUILDING
WASHINGTON 4, D. C.

PATTERN NO 480913

SUPERSEDES



APP 4 A

WVQA

~~WAVE~~

MIAMI, FLA.
1140

25-43-00
10-23-00



HORIZONTAL RADIATION PATTERN
DAY TIME

10 KW DAN.

1140 KC.

ANT	Q-DEG	S-DEG	Q-DEG	FIELD	K	F-GND	H-DEG
0			0	1.0	600	95	
1	180	185	-15	0.6	600	95	

LINCOLN OPERATING CO.,
MIAMI, FLA

GLENN D GILLET AND ASSOCIATES
CONSULTING RADIO ENGINEERS
NATIONAL PRESS BUILDING
WASHINGTON 4, D C

PATTERN NO 410127

SUPERSEDES


APP 3c

~~WHITE~~
WQBA


Measured Night
(8-23-63ct)

Station WMIE
Miami, Florida

5kw, 10kw-LS, DA-2, U
1140 kc



HORIZONTAL RADIATION PATTERN



APPLICANT	WMIE
LOCATION	MIAMI, FLORIDA
FREQUENCY	1140 KC/S
POWER	10KW-LS, 5 KW-N, DA-2
LATITUDE	25 DEG 43 MIN 00 SEC
LONGITUDE	80 DEG 23 MIN 00 SEC
WHEN USED	NIGHT
RMS FIELD	440 MV/M
DATE	JANUARY 1963

RAYMOND E. ROHRER & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FCC File No. BZ-5013
Accepted 8-12-63

Station WMIE
Miami, Florida


1140 kc

~~WHITE~~
WQBA

Measured Night Nulls
(8-23-63ct)

Station WMIE
Miami, Florida

5kw, 10kw-LS, DA-2, U
1140 kc





EXPANDED VIEW

RAYMOND E. ROHRER & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FCC File No. BZ-5013
Accepted 8-12-63

Station WMIE
Miami, Florida

1140 kc



HORIZONTAL RADIATION PATTERN NIGHT TIME

5 KW. DAN. 1140 KC.

AN	Q	DEG. S	DEG. Ø	DEG. FIELD	K	F-GND	H-DEG
4	0	370	+162	1.0	410	95°	
3	0	185	+80.8	3.13	410	95°	
0			0	4.34	410	95°	
1	180	185	-80.8	3.13	410	95°	
2	180	370	-162	1.0	410	95°	

LINCOLN OPERATING CO.,
 MIAMI, FLA

GLENN D GILLET AND ASSOCIATES
 CONSULTING RADIO ENGINEERS
 NATIONAL PRESS BUILDING
 WASHINGTON 4 D C

PATTERN NO 410127


SUPERSEDES

APP 3 A

WQBA

~~WITE~~

MIAMI
1140



HORIZONTAL RADIATION PATTERN
NIGHTTIME - NULL DETAIL
5 KW. DAN. 1140 KC.

LINCOLN OPERATING CO.,
MIAMI, FLA.

ANT. α -DEG. S-DEG. ϕ -DEG. FIELD K F-GND. H-DEG.

GLENN D GILLET AND ASSOCIATES
CONSULTING RADIO ENGINEERS
NATIONAL PRESS BUILDING
WASHINGTON 4, D C

PATTERN NO 470611

SUPERSEDES 410127


APP 3 b 1a

September 15, 1948


9/21/48G

~~WQBA~~ ~~WMIE~~

1140



RMS MEASURED — 432 MV/M
RMS THEORETICAL ---- 410 MV/M



MEASURED
HORIZONTAL RADIATION PATTERN
NIGHT TIME

ANT	Q	DES	DES	DES	DES	DES	DES	DES	DES
1	0	370	162	1.0					95°
2	0	185	80.8	3.14					95°
3				4.44					95°
4	180	185	-80.8	3.14					95°
5	180	370	-162	1.0					95°

WMIE
MIAMI, FLORIDA

5 KW. DA - 8 1140 KC.


GLENN D GILLET AND ASSOCIATES
CONSULTING RADIO ENGINEERS
NATIONAL PRESS BUILDING
WASHINGTON 4, D C

PATTERN NO 460913

SUPERSEDES

APP 3A

WMIE L-3373 10/28/48G



1682 DIRECTIONAL ANTENNA DESCRIPTION SHEET

Location: WQHI Main Studio: San Juan, Puerto Rico
 Frequency: 1140 kHz Power: 10kw
 Notification List No. 1767 Date: January 26, 1978 Class: II

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 18° 21' 30"
 West Longitude: 66° 08' 05"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-1)
 Number of elements: 4
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	W(#3)	N(#4)	S(#2)	E(#1)
HEIGHT ABOVE INSULATORS:	200'	200'	200'	200' (83.5°)
PHASING:	+234°	+72°	+162°	0°
FIELD RATIO:	0.33	0.71	0.47	1

SPACING AND
 ORIENTATION: The towers are located at the vertices of a parallelogram the
 long sides of which are 287.5' (120°) in length on a line bearing
 300° true. The short sides are 215.5' (90°) in length on a
 line bearing 220° true.


GROUND SYSTEM: 120 - 215' equally spaced copper radials plus a 40'square ground
 screen interspaced radials about each tower. Radials are shorten-
 ed and bonded to transverse straps along intersections between towers.
 Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


THEORETICAL
RFS
 595 mv/m

Note: Please retain the directional antenna radiation patterns notified for Station
 WITA in United States Change List Number 1110 dated May 5, 1965 and attach to
 this Revised Description Sheet and pattern. This notification concerns only
 changes to add m.e.o.v.'s of radiation to the directional antenna patterns.

DECEMBER 1976



PROPOSED HORIZONTAL PLANE RADIATION PATTERN




METRO BROADCASTING COMPANY, INC.
 SAN JUAN, PUERTO RICO
 Jules Cohen & Associates
 Consulting Electronics Engineers


STATION WQHI
 1140 KHZ
 10 KW, DA 1, U

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

WQIL



Measured Parameters




H = 83.5' ± 200'
S = 80° ± 215 S
B = 120° ± 267 S

North Latitude 18° 21' 30"
West Longitude 66° 08' 05"

MEASURED HORIZONTAL PLANE RADIATION PATTERN
FOR DIRECTIVE OPERATION OF
WQIL, SAN JUAN, PUERTO RICO
1140 KHz, 10 KW, DA-1, U
NOVEMBER 1969

WQIL

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.



MEASURED NON-DIRECTIONAL UNATTENUATED
FIELD INTENSITY AT ONE MILE FOR
WITA, SAN JUAN, PUERTO RICO
1140 KHz, 10 KW, DA-1, U
NOVEMBER 1969

WQ1L



Proposed Day & Night
(1-28-65ct)

Station WITA
San Juan, Puerto Rico

10kw, DA-1, U
1140 kc

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.


V=0°



COMPUTED HORIZONTAL
PLANE RADIATION PATTERN
FOR PROPOSED OPERATION OF
WITA, SAN JUAN, PUERTO RICO
1140 KC - 10 KW - DA-1
SEPTEMBER 1964

NORTH LATITUDE: 18° 21' 30"
WEST LONGITUDE: 66° 04' 00"
H = 63.5' ± 20.3'
S = 97° ± 215.5'
S = 120° ± 20.75'

WQIL

Measured Day & Night
(4-29-68ct)Station WITA
San Juan, Puerto Rico10kw, DA-1, U
1140 kcFCC File No. BL-11922
Accepted 4-10-68Station WITA
San Juan, Puerto Rico


1140 kc

WQIL

Measured Non-DA
(4-29-68ct)

Station WITA
San Juan, Puerto Rico

10kw, DA-1, U
1140 kc



FCC File No. BL-11922
Accepted 4-10-68

Station WITA
San Juan, Puerto Rico

1140 kc

WRVA


PROPOSED NIGHT & DAY
(2/7/57g)

Station WRVA
Richmond, Virginia

50 KW, DA-1, U

1140 KC

37°24'15"
71°18'55"



PAUL F. GODLEY
DIRECTOR
U.S. DEPT. OF COMMERCE

FCC File No.
BL-916

WRVA
Richmond, Virginia


1140 KC

WRVA

Measured Day & Night
(12-28-62ct)

Station WRVA
Richmond, Virginia

50kw, DA-1, U
1140 kc



FCC File No. BZ-4786
Accepted 12-3-62

Station WRVA
Richmond, Virginia


1140 kc

Rec'd 4-12-41

37-23-4J
77-19-10

(Harbo)

WRVA
1140



DIRECTIONAL ANTENNA DESCRIPTION SHEET
(Issued April 9, 1971)

Station: XEMR Main Studio: Monterrey, Nuevo Leon
Frequency: 1140 kHz Power: 10 kw Night
Notification List No. (*) Date: (*) Class: 1-B

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM: North Latitude: $25^{\circ} 40' 11''$
West Longitude: $100^{\circ} 18' 26''$

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
Number of elements: 2
Type of elements: guyed, vertical steel towers

TOWER:	SW(#1)	NE(#2)
HEIGHT ABOVE INSULATORS:	395'	395' (164.78°)
NIGHT PHASING:	0°	$+75^{\circ}$
NIGHT FIELD RATIO:	1	1

SPACING AND
ORIENTATION: Elements are spaced 287.6' (120°) on a line bearing 64° true.


GROUND SYSTEM: 120 - 215.6 equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap along
intersections between towers.

Predicted effective Night Field: 711.495 mv/m at rated power.

FCC Note: Notification of basic information for this change in a Notification List has not been received as of this issue date. Supplementary information was transmitted by letter of March 17, 1971 in accordance with provisional procedures for exchange of notifications established in a Memorandum of Understanding between Delegations of the United States and Mexico signed in Washington on November 27, 1968.

CTR NO 20429A3


XEMR



PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/m. A 1609M

ESQUEMA DE LOS TUBOS Y LA TORRENTA EN CON
RESPECTO AL NORTE GEOGRAFICO

AZIMUT 64°



XEMR

MONTERREY, N.L.

1140 KHZ.


REPRESENTACIONES ELECTRONICAS
S. A.

L.E.O.


Proposed Day
(7-29-68ct)

New; Michael D. Haas
Bay St. Louis, Mississippi

250w, DA-D, D
1140 kc



RMS = 94.7 MV/M



WILLIS E. BECHER
CONSULTING ENGINEER
WASHINGTON, D. C.

Figure 6
Calculated Horizontal Plane Pattern
Michael D. Haas
Bay Saint Louis, Mississippi
1140Kc 0.25Kw D, DA-D
March 1968

FCC File No. BP-18154
Accepted 7-3-68

New; Michael D. Haas
Bay St. Louis, Mississippi

1140 kc


NEW

Proposed Day
(12-29-66ct)

New; Harry D. & Robert E. Stephenson
Lexington, North Carolina


1kw, DA-D, D
1140 kc

BP 17021
Amended
3-17-68
application
to correct
error in
transmitter
site spec-
ifications
Lat. 35° 48' 10"
Long. 80° 13' 50"



RMS = 186 mV
--- M.E.O.V.
N. LAT. 35° 48' 20"
W. LONG. 80° 13' 45"

HORIZONTAL RADIATION PATTERN
LEXINGTON, N.C.



PROPOSAL FOR LEXINGTON, N.C.
1140 KC 1.0 KW DA-DAY
APPLICANTS: HARRY D. STEPHENSON
ROBERT E. STEPHENSON
P.O. BOX 281, CARY, N. CAROLINA
ENGINEER: Robert E. Stephenson
3/15/65 Mt. Airy, N.C.

PATTERN NO
SUPERSEDES
APP

FCC File No. BP-17021 New; Harry D. & Robert E. Stephenson
Accepted 11-9-66 Lexington, North Carolina

1140 kc

XEMR

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: XEMR

Main Studio: Monterrey, N.L.

Frequency: 1140 kHz

Power: 50 kW

Notification List No. (*)

Date: (*)

Class: I-B

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 25° 40' 11"

West Longitude: 100° 18' 26"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER: #1(SW) #2(NE)

HEIGHT ABOVE

INSULATORS: 392.9' 392.9' (163.8°)

PHASING: 0° +86°

FIELD RATIO: 1 1

SPACING AND

ORIENTATION: The towers are spaced 215.8' (90°) on a line bearing 32°
true.

GROUND SYSTEM: 120-215.8' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap
along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

• THEORETICAL

RMS

Night 1591 mv/m

*(FCC Note: This supplementary data was not received in connection with
a notification list.)

CTR NO 20429A4

DESCRIPCION DEL SISTEMA DIRECCIONAL DE RADIACION DISEÑADO.OPERACION NOCTURNAESTACION: XEMR

UBICACION: MONTERREY, N.L.

FRECUENCIA: 1140 KHZ.

POTENCIA: 50 KW.

LISTA DE NOTIFICACIONES:

CLASE: I-B.

LOCALIZACION GEOGRAFICA

DEL SISTEMA RADIADOR:

LATITUD NORTE : 25° 40' 11"

LONGITUD OESTE: 100° 18' 26"

CARACTERISTICAS DEL SISTEMA

AUTORIZADO PARA OPERACION: AD-N.

NUMERO DE ELEMENTOS RADIADORES:

DOS.

TIPO DE ELEMENTOS RADIADORES:

TORRES VERTICALES.

TORRES:

DOS TORRES CON RETENIDAS.

ALTURA SOBRE LOS AISLADORES: 119.74 M.

ALTURA EN GRADOS ELECTRICOS : 163.80°

NORESTE

SUROESTE

119.74 M.

119.74 M.

163.80°

163.80°

SEPARACION ENTRE TORRES: 90°

MAGNITUDES RELATIVAS DE CORRIENTES: 1:1

DEFASAMIENTO: 86°

AZIMUT DEL EJE DE LAS TORRES: 32°

RAIZ CUADRATICA MEDIA TEORICA: 1591 mV/m.

INTENSIDAD DE CAMPO R.C.M. NO ATENUADO
A 1609M. POR KW. DE POTENCIA: 225 mV/m.

REVISOR

DIRECC. GEN. DE TELECOMUNICACIONES
 Departamento de Telecomunicaciones
 Oficina de Asesoría Técnica

TORRE 2
 + 86°

TORRE 1
 0°

APROBO
 INGENIERO DE PERITO EN
 TELECOMUNICACIONES NUM. 97

ING. CARLOS A. CABALLERO
 Cédula Profesional No. 26855

XEMR

XEMR

50 KW.

MONTERREY, N.L.

1140 KHZ.

PATENTE DE PERITO EN
TELECOMUNICACIONES NUM. 97PATRON DE RADIACION HORIZONTAL
TABULADO


$$E_h = 2209.72 \cos. (45^\circ \cos. \phi + 43^\circ)$$

ING. CARLOS A. C. BALLERO
Cédula Profesional No. 24355

			A	B	E _h mV/m.
AZIMUT		ϕ	$45^\circ \cos. \phi$	$\cos (A + 43^\circ)$	2209.72 B
32°	32°	0°	45.000000	0.034900	77.12
29°	35°	3°	44.938350	0.035975	79.49
22°	42°	10°	44.316360	0.046822	103.46
19°	45°	13°	43.846650	0.055009	121.55
12°	52°	20°	42.286185	0.082179	181.59
02°	62°	30°	38.971170	0.139672	308.64
352°	72°	40°	34.472025	0.216916	479.32
342°	82°	50°	28.925460	0.310254	685.57
332°	92°	60°	22.500000	0.414694	916.36
322°	102°	70°	15.390945	0.524121	1158.16
312°	112°	80°	7.814160	0.631838	1396.18
302°	122°	90°	0.000000	0.731354	1616.09
292°	132°	100°	-7.814160	0.817288	1805.98
282°	142°	110°	-15.390945	0.886130	1958.10
272°	152°	120°	-22.500000	0.936672	2069.78
262°	162°	130°	-28.925460	0.969980	2143.38
252°	172°	140°	-34.472025	0.988944	2185.29
242°	182°	150°	-38.971170	0.997529	2204.26
232°	192°	160°	-42.286185	0.999922	2209.55
222°	202°	170°	-44.316360	0.999736	2209.14
212°	212°	180°	-45.000000	0.999391	2208.37

XEMR

OPERACION NOCTURNA




PATENTE DE PERITO EN
TELECOMUNICACIONES NUM. 9

ING. CARLOS A. CABALLERO

PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/m. A 1609M.

Esquema de las torres y su orientacion con respecto al Norte Geografico.



RADIODIFUSORA:

XEMR

MONTERREY, N.L.

FRECUENCIA:



1140 KHZ.

DISEÑO:

DIBUJO:

A.R.T.

XEMR



$$E_v = 2209.72 \cos.(45^\circ \cos.\psi \cos.\theta + 43^\circ)$$

Valores Tabulados.

θ	E mV/m.
0°	121.55
10°	140.26
20°	184.08
30°	224.91
40°	237.76
50°	214.88
60°	166.11
70°	111.12
80°	53.63
90°	0.00

Valores Tabulados.

θ	E mV/m
0°	103.46
10°	123.30
20°	170.11
30°	214.85
40°	231.44
50°	211.55
60°	164.66
70°	107.98
80°	53.53
90°	0.00

DIRECC. GEN.

Reporte

07/02/2019

REVISO

PATENTE DE PERITO EN
TELECOMUNICACIONES NUM. 97

ING. CARLOS A. CABALLERO
Cédula Profesional No. 26855

PATRONES DE RADIACION EN EL PLANO VERTICAL

FRECUENCIA:



1140 KHZ.

RADIODIFUSORA:

XEMR

MONTERREY, N.L.

DISENO:



$$E_v = 2209.72 \cos(45^\circ \cos \psi \cos \theta + 43^\circ)$$

Valores Tabulados.

θ	E mV/m.
0°	79.49
10°	100.82
20°	151.60
30°	201.52
40°	223.18
50°	207.14
60°	162.72
70°	107.34
80°	53.41
90°	0.00

Valores Tabulados.

θ	E mV/m.
0°	181.59
10°	196.56
20°	230.42
30°	258.23
40°	258.51
50°	225.88
60°	170.93
70°	110.08
80°	53.93
90°	0.00

DISEÑO: C.A.

REVISÓ:

[Signature]
REVISÓ

PATENTE DE PERITO EN TELECOMUNICACIONES NUM. 97

[Signature]

ING. CARLOS A. CABALLERO
Cédula Profesional No. 54355

PATRONES DE RADIACION EN EL PLANO VERTICAL

FRECUENCIA:

RADIODIFUSORA:

DISEÑO:

1140 KHZ.

XEMR

MONTERREY, N.L.

CHMG

DIRECTIONAL ANTENNA DESCRIPTION SHEET

(Revised August 23/76)

STATION:	New - Gaspe	POWER:	5 kW
MAIN STUDIO:	Gaspe, Quebec	CLASS:	III
FREQUENCY:	1150 kHz	SITE LOCATION:	48° 49' 00" N. 64° 24' 12" W.
NOTIFICATION LIST NO. :	359	DATE:	October 4, 1976

ANTENNA ARRAY.

Number of Elements: 3
Type of Elements: Uniform cross sectional steel, guyed vertical, series fed. No top loading.

<u>Tower No. :</u>	<u>1</u>	<u>2</u>	<u>3</u>
	(60°)	(60°)	(60°)
Height above Insulator:	142.6	142.6	142.6
Overall Height:	146.0	146.0	146.0
Spacing:	REF.	70°	140°
Orientation:	REF.	0°	0°
Phase:	REF.	-126.27°	-254.07°
Field Ratio:	1.0	1.658	0.720

Ground System.


Effective area of 120 radials, 0.4 wavelengths long, No. 10 AWG soft drawn copper wire, buried 8 inches below ground surface.

Predicted Effective Field.

435 mV/m at 1 mile for 5 kW
194.54 mV/m at 1 mile for 1 kW

46 4410

K-E POLAR CO-ORDINATE
MATHIEU & FISCH CO. NEW YORK



HORIZONTAL RADIATION PATTERN
DAY AND NIGHT

NEW CASPE, QUEBEC.

11.5 MHz 5 kW DA-1 III U

Brian Sawyer and Associates.

July 2, 1976

7.8

2
Description Sheet
(8-24-62ct)

New Station
Ottawa, Ontario

5kw, 10kw-LS, DA-1, U, Class III
1150 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

STATION: New MAIN STUDIO: Ottawa, Ontario,
FREQUENCY: 1150 KC POWER: 10KW D CLASS: III
5 KW N
NOTIFICATION LIST NO. 172 DATE: July 9, 1962

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM:

North Latitude: 45° 15' 29"
West Longitude: 75° 38' 51"

ANTENNA CHARACTERISTICS

Mode of Operation: 10 d/5 N (DA-1)
Number of elements: Four (4)
Type of elements: Uniform cross-section, guyed steel towers,
base insulated for series feed.


TOWER	No.1 (N)	No.1 (NC)	No.2 (SC)	No.3 (S)
HEIGHT				
ABOVE INSULATORS	200' (84.1°)	200' (84.1°)	200' (84.1°)	200' (84.1°)
OVERALL HEIGHT	205'	205'	205'	205'
SPACING	80°	80°	80°	
PHASING	0°	154.2°	-49.2°	110.5°
FIELD RATIO	.85	1.9	1.75	.68
ORIENTATION	Towers on line bearing 162°			
GROUND SYSTEM	120 equiangularly spaced radials extend from the base of each tower to a distance of 352 feet (0.4 wavelength) with the exception of those radials joined along a common chord. The ground wires consist of solid copper wire No. 10 B & S gauge and are buried to a depth of approximately 8 inches.			
PREDICTED EFFECTIVE FIELD:	595 MV/M at 1 mile for 10KW 420 MV/M at 1 mile for 5 KW 188 MV/M at 1 mile for 1 KW			

Proposed Day & Night
(8-24-62ct)

New Station
Ottawa, Ontario

5kw, 10kw-LS, DA-1, U, Class III
1150 kc

CJRC




CHSJ

PROPOSED DAY
5-28-59g)

Station CHSJ
St. John, New Brunswick, Canada

5kw, 10kw-LS, DA-2,U, Class III
1150 KC



Sect. 6.3
PROPOSED
HORIZONTAL RADIATION PATTERN
DAY TIME
CHSJ St. John, N.B.
1150 KC/8 10 KW
CANADIAN GENERAL ELECTRIC CO. LTD.
Electronic Equipment & Tube Dept.
TORONTO CANADA
RGT Feb. 18, 1959 H.Z. Rogers, P.Eng.

Station CHSJ Main Studio St. John, N.H.
 Power 5 Kw. Frequency 1150 Kc.

Location: North Latitude $45^{\circ} 18' 40''$
 West Longitude $66^{\circ} 01' 40''$

Antenna:


Authorized for NIGHT operation
 2 elements, South; Self supporting, insulated, tapered, no top loading
 North; Guyed, uniform cross-section, insulated no top loading

Tower:	<u>South</u>	<u>North</u>
Height above insulators:	225' 48'	445' 187'
Spacing:	107'	45'
Phasing:	156°	0
Field Ratio:	0.82	1.0
Ground System:	South tower, 120 equally spaced radials, .4 (3.3') long except at intersections. North tower, 120 equally spaced radials, .5 (4.2') long except at intersections. For each tower: 120 radials 3' long interspaced.	
Orientation:	On a line bearing 358° true.	
Predicted effective field	503 mv/m (225 for 1 kw)	

See Information Only

*Custom
6/15/59
1150-450*

Corrected 4/9/59



PROPOSED
FEDERAL BUREAU OF INVESTIGATION
U.S. DEPARTMENT OF JUSTICE
WASHINGTON, D.C. 20535
MADE IN U.S.A.

Radio Station CHSL
St. John, N.B.
1150 Kc. 5 Kw.
HORIZONTAL PATTERN
Northern Electric Co.

1,2
DESCRIPTION SHEET
(10-2-59g)

Station CHSJ
Saint John, New Brunswick, Canada

CHSJ
5kw, 10kw-LS, DA-2, U, Class III

1150 KC

CORRECTED

2.4 - DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: CHSJ

Main Studio: Saint John, N.B.

Frequency: 1150 Kc

Power: 10 Kw D Class: III
5 Kw N

Notification List No.: 132

Date: April 9, 1959.

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM:

North Latitude: 45° 18' 40"

West Longitude: 66° 01' 40"

ANTENNA CHARACTERISTICS

Mode of Operation: DA-2

Number of Elements: Two

Type of elements: North Tower - Blaw Knox, uniform
cross-section, insulated, guyed. South Tower - Blaw Knox
self-supporting, square tapered, insulated.

TOWER:	North	South
HEIGHT ABOVE INSULATORS:	444' (188°)	225' (95°)
OVERALL HEIGHT:	447'	229'
SPACING:	0	107' (45°)
PHASING:		
Night	0	+156
Day	0	+151
FIELD RATIO:		
Night	1	.82
Day	1	.35
ORIENTATION:	Towers on a line bearing 2° east of north.	

GROUND SYSTEM: North Tower - 120 equally spaced radials, 428' long except at intersections.
South Tower - 120 equally spaced radials, 343' long except at intersections.

Predicted effective field 621 mv/m (197 mv/m for 1Kw)

Measured Effective Night Field: 456 mv/m (204 mv/m for 1 Kw)

NOTE: The night field pattern has not been changed. This revised sheet will correct the night field ratio of the South tower from .833 to .82, the original previously notified value.

PROJECT #11007

CKIQ

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CKIQ LOCATION: Kelowna, B. C.
FREQUENCY: 1150 kHz POWER: 10 kW CLASS III
NOTIFICATION LIST NO. 372 DATE: April 7, 1978

GEOGRAPHICAL LOCATION: Latitude 49° 50' 52" North
Longitude 119° 27' 54" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-N
Number of Elements: 3 (Three)
Type of Elements: Guyed steel towers, uniform cross-section, base insulated for series feed


Tower	#1 (S)	#2 (C)	#3 (N)
Height above base insulator:	215' (90.4°)	215' (90.4°)	215' (90.4°)
Overall Height:	220'	220'	220'
Field Ratio Nighttime:	.5	1.0	.5
Phasing Nighttime:	0°	-143°	+80°
Spacing:	Reference	90° (214')	180° (428')
Orientation:	Reference	335°	338°

GROUND SYSTEM: 120 equally spaced radials of No. 10 bare copper wire extend from each tower base, buried approximately 8 inches. The ground system radials have been adjusted so as to have an effective radial length of 0.4 wavelength. The minimum length of any radial, with the exception of those joined along the common chord, is 222' (94°).

PREDICTED EFFECTIVE FIELDS:

Nighttime: 638 mV/m at 1 mile for 10 kW
202 mV/m at 1 mile for 1 kW
Daytime: 600 mV/m at 1 mile for 10 kW
190 mV/m at 1 mile for 1 kW

September 19, 1975






FIGURE 4

HORIZONTAL RADIATION PATTERN
 WIGHTTIME - EXPANDED PLOT

CKIQ 1150 kHz 10 kW DA-N CLASS III
 KELOWNA B.C.
 PROJECT #11007 SEPTEMBER 19, 1975

DEMVALEN & ASSOCIATES LTD

CKIQ

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CKOC LOCATION: Hamilton, Ontario

FREQUENCY: 1150 kHz POWER: 50 kW CLASS III

NOTIFICATION LIST NO. 363 DATE: May 10, 1977

GEOGRAPHICAL LOCATION: Latitude 43° 03' 04" North
Longitude 79° 48' 42" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-2
 Number of Elements: 10 (Ten)
 Type of Elements: Guyed steel towers, uniform cross-section, base insulated for series feed

TOWER HEIGHTS: All tower heights are of equal height above base insulator 290 ft. (122°).
 Overall height 295 ft.

Tower No.	Orientation	Spacing	Daytime		Nighttime	
			Field Ratio	Phasing	Field Ratio	Phasing
1	Ref.	Ref.	.28	0°	.204°	0°
2	343°	190.2' (80°)	.85	-145.4°	.703	-155.9°
3	343°	380.4' (160°)	1.0	+69°	1.0	+46.1°
4	343°	570.6' (240°)	.61	-74.7°	.703	-111.3°
5	343°	760.8' (320°)	.2	+146.6°	.2	+92.9°
6	120°	475.5' (200°)	Unused		.203	+20°
7	99.1°	359' (151°)	Unused		.703	-135.3°
8	67.4°	320.9' (135°)	Unused		1.0	+67°
9	38.5°	387.5' (163°)	Unused		.701	-90.7°
10	20.5°	518.3' (218°)	Unused		.203	+113.5°

GROUND SYSTEM: 120 equally spaced radials of No. 10 bare copper wire extend from each tower base. Radial length is 342.3' (144°), with the exception of those joined along the common chords; an additional 120 100-ft. radials are at the base of each tower. Radials are buried approximately 8 inches.

PREDICTED EFFECTIVE FIELDS:

Nighttime	Daytime
1573 mV/m at 1 mile for 50 kW	1614 mV/m at 1 mile for 50 kW
222 mV/m at 1 mile for 1 kW	228 mV/m at 1 mile for 1 kW

August 27, 1976




FIGURE 5
HORIZONTAL RADIATION PATTERN
NIGHTTIME - POLAR PLOT

CKOC	HAMILTON, ONTARIO		
1150 kHz	50 kW	DA-2	CLASS III
PROJECT #14502		AUGUST 27, 1976	
D.E.M. ALLEN & ASSOCIATES LTD. CONSULTING ENGINEERS			

13-48 HUFFMAN & BUSH CO. MADE IN U.S.A.




FIGURE 6
HORIZONTAL RADIATION PATTERN
NIGHTTIME - EXPANDED PLOT
CKOC HAMILTON, ONTARIO
1150 kHz 50 kW DA-2 CLASS III
PROJECT #14502 AUGUST 27, 1976
D.E.M. ALLEN & ASSOCIATES LTD




FIGURE 3

HORIZONTAL RADIATION PATTERN
DAYTIME - POLAR PLOT

CKOC	HAMILTON, ONTARIO		
1150 kHz	50 kW	DA-2	CLASS III
PROJECT #14502	AUGUST 27, 1976		

D.E.M. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS

40 1320

K&E 10 X 10 TO 1/4 INCH 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.






FIGURE 4

HORIZONTAL RADIATION PATTERN
DAYTIME - EXPANDED PLOT

CKOC HAMILTON, ONTARIO
1150 kHz 50 kW DA-2 CLASS III
PROJECT #14502 AUGUST 27, 1976

DEM ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 7



CKOC
1150 kHz
PROJECT #14502

50 kW

DA-2

HAMILTON, ONTARIO
CLASS III
AUGUST 27, 1976

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 8



CKOC
1150 kHz
PROJECT #14502

50 kW

DA-2

HAMILTON, ONTARIO
CLASS III
AUGUST 27, 1976

D. E. M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 9



CKOC
1150 kHz
PROJECT #14502

50 kW

DA-2

HAMILTON, ONTARIO
CLASS III
AUGUST 27, 1976

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 10

CKOC
1150 kHz
PROJECT #14502

50 kW

DA-2



HAMILTON, ONTARIO
CLASS III
AUGUST 27, 1976

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

G8-10159 (NO. 101V)

CALOR CO-ORDINATE
MADE IN CANADA

CALOR
MICROGRAPH



VERTICAL RADIATION PATTERNS

FIGURE 11

CKOC
1150 kHz
PROJECT #14502



50 kHz

DA-2

HAMILTON, ONTARIO
CLASS III
AUGUST 27, 1976

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

RJK



VERTICAL RADIATION PATTERNS

FIGURE 12

CKOC
1150 kHz
PROJECT #14502

50 kHz


DA-2

HAMILTON, ONTARIO
CLASS III
AUGUST 27, 1976

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

216

CKOC

Description Sheet
(8-26-66ct)Station CKOC
Hamilton, Ontario10kw, DA-2, U, Class III
1150 kcDirectional Antenna Description Sheet

AUG 1966

Station

RECEIVED

Frequency

1150 kc

NOTES & FILES

Notification List No.

216

CKOC

Main Studio : Hamilton, Ontario

Power : 10 kw Class : III

Date : July 26, 1966

Geographical Location

of Antenna System : N. Lat. 43° 10' 40" , W. Lng. 79° 47' 00"

Antenna Characteristics : Mode of Operation : DA-2

Number of Elements : 6

Type of Element : guyed, uniform
cross-section,
no top loading.

<u>Tower</u>	<u>#1 (SW)</u>	<u>#2 (SE)</u>	<u>#3 (EC)</u>	<u>#4 (WC)</u>	<u>#5 (NW)</u>	<u>#6 (NE)</u>
Height above insul'r	200'	200'	200'	200'	200'	200'
Overall Height	205'	205'	205'	205'	205'	205'
Spacing	See Orientation below					
Night Phasing	+116°	+110°	0°	+6°	-104°	-110°
Night Field Ratio	0.8	1.0	1.94	1.552	0.8	1.0
Day Phasing	-	+140°	+10.7°	-	-	-140°
Day Field Ratio	-	1.0	1.7	-	-	1.0

Orientation : 4 towers are at corners of a square, 476' x 476',
(200° x 200°) whose sides lie in Azimuths 352° and 82°.
The other two towers are at the centres of the sides
which lie in Azimuth 352°.

Ground System : Around each tower base, 120 radials, 342' long,
spaced 3°.


Predicted

Effective Field : Night - 574 mv/m at 1 mile (181 per kw)
Day - 584 mv/m at 1 mile (185 per kw)

oooooooooooooooooooooooooooo

216

10kw, DA-2, U, Class III
1150 kc



~~FIG. 2~~

KEITH A. MACKINNON
CONSULTING RADIO ENGINEER
OTTAWA — CANADA

~~OKOC - HAMILTON~~

1150 KA, 10 EW, DA-2


DAY ARRAY

HORIZONTAL PATTERN

MAY 5, 1966

216

CKOC

Proposed Night
(8-26-66ct)Station CKOC
Hamilton, Ontario10kw, DA-2, U, Class F1
1150 kcK·E
POLAR CO-ORDINATE
SCALES
359-31G
JOHN W. PETERSON CO.

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CKOC LOCATION: Hamilton, Ontario

FREQUENCY: 1150 kHz POWER: .50 kW CLASS III

NOTIFICATION LIST NO.: 382 DATE: March 8, 1979

GEOGRAPHICAL LOCATION: Latitude 43° 03' 04" North
Longitude 79° 48' 42" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-2
Number of Elements: 10 (Ten)
Type of Elements: Guyed steel towers, uniform cross-section, base insulated for series feedTOWER HEIGHTS: All tower heights are of equal height above base insulator 215 ft. (90.4°).
Overall height 220 ft.

Tower No.	Orientation	Spacing	Daytime		Nighttime	
			Field Ratio	Phasing	Field Ratio	Phasing
1	Ref.	Ref.	.2	0°	.204	0°
2	343°	190.2' (80°)	.61	-138.7°	.703	-155.9°
3	343°	380.4' (160°)	1.0	+77.6°	1.0	+46.1°
4	343°	570.6' (240°)	.85	-68°	.703	-111.3°
5	343°	760.8' (320°)	.28	+146.6°	.2	+92.9°
6	120°	475.5' (200°)	Unused		.203	+20°
7	99.1°	359' (151°)	Unused		.703	-135.3°
8	67.4°	320.9' (135°)	Unused		1.0	+67°
9	38.5°	387.5' (163°)	Unused		.701	-90.7°
10	20.5°	518.3' (218°)	Unused		.203	+113.5°

GROUND SYSTEM: 120 equally spaced radials of No. 10 bare copper wire extend from each tower base. Radial length is 342.3' (144°), with the exception of those joined along the common chords; an additional 120 100-ft. radials are at the base of each tower. Radials are buried approximately 8 inches.

PREDICTED EFFECTIVE FIELDS:

Nighttime	Daytime
1375 mV/m at 1 mile for 50 kW	1411 mV/m at 1 mile for 50 kW
194 mV/m at 1 mile for 1 kW	199 mV/m at 1 mile for 1 kW

Revised January 5, 1979

CKOC




FIGURE 3

HORIZONTAL RADIATION PATTERN
DAYTIME - POLAR PLOT

CKOC HAMILTON, ONTARIO
1150 kHz 50 kW DA-2 CLASS III
PROJECT #14502 REV. JANUARY 5, 1979

D.E.M. ALLEN & ASSOCIATES LTD
CONSULTING ENGINEERS




FIGURE 4

HORIZONTAL RADIATION PATTERN
DAYTIME - EXPANDED PLOT

CKOC HAMILTON, ONTARIO
1150 kHz 50 kW DA-2 CLASS III
PROJECT #14502 REV. JANUARY 5, 1979

D.E.M. ALLEN & ASSOCIATES LTD
CONSULTING ENGINEERS

CKOC




FIGURE 5
HORIZONTAL RADIATION PATTERN
NIGHTTIME - POLAR PLOT

CKOC HAMILTON, ONTARIO
1150 kHz 50 kW DA-2 CLASS III
PROJECT #14502 REV. JANUARY 5, 1979

D.E.M. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS




FIGURE 6

HORIZONTAL RADIATION PATTERN
NIGHTTIME - EXPANDED PLOT



CKOC HAMILTON, ONTARIO
1150 kHz 50 kW DA-2 CLASS III
PROJECT #14502 REV. JANUARY 5, 1979

DE.M. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS

CG-10159 (NO. 10LV)

ALIAS CO-ORDINATE
VALID IN CANADA



(MICRO FILM)



VERTICAL RADIATION PATTERNS

FIGURE 7

CKOC		HAMILTON, ONTARIO
1150 kHz	50 kW	CLASS III
PROJECT #14502	DA-2	REV. JANUARY 5, 1979
D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS		



VERTICAL RADIATION PATTERNS

FIGURE 8



CKOC
1150 kHz
PROJECT #14502

50 kW

DA-2

HAMILTON, ONTARIO
CLASS III
REV. JANUARY 5, 1979

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 9

CKOC
1150 kHz
PROJECT #14502

50 kW

DA-2

HAMILTON, ONTARIO
CLASS III
REV. JANUARY 5, 1979

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

CKOC

MADE IN CANADA

MICRO GRAPH

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CKX

STATION LOCATION: BRANDON, MAN.

FREQUENCY: 1150 kHz

POWER: 50 kW Day, 10 kW Night

NOTIFICATION LIST: 353

DATE: April 1, 1976

GEOGRAPHICAL LOCATION:

Latitude: 49° 50' 28" North
Longitude: 100° 03' 19" West

ANTENNA CHARACTERISTICS:

Mode of Operation:

DA-2

Number of Elements:

4 (Four)

Type of Elements:

Guyed steel towers, uniform cross-section, base insulated for series feed.

Tower	#1(N)	#2(EC)	#3(W)	#4(S)
Height above base insulator:	190' (80°)	220' (92.5°)	220' (92.5°)	220' (92.5°)
Overall Height:	195'	225'	225'	225'
Night Field Ratio:	1.0	1.0	.175	--
Night Phasing:	0°	-200°	-315°	--
Day Field Ratio:	1.0	--	--	1.0
Day Phasing:	0°	--	--	30°
Orientation:	Ref.	205°	250°	180°
Spacing:	Ref.	107' (45°)	321' (135°)	214' (90°)

GROUND SYSTEM: 120 equally spaced radials of #10 bare soft copper wire extend from the base of each tower for a distance of 342 feet (0.4 wavelength) with the exception of those joined along the common chords. The radials are buried approximately 8 inches.


PREDICTED EFFECTIVE FIELDS:

DAYNIGHT

1273 mV/m at 1 mile for 50 kW
180 mV/m at 1 mile for 1 kW

613 mV/m at 1 mile for 10 kW
194 mV/m at 1 mile for 1 kW

June 30, 1975



10kw, DA-N, U, Class III
1150 kc


D.E.M. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS



CKX

Proposed Night
(2-22-71ct)

Station CKX
Brandon, Manitoba

10kw, DA-N, U, Class III
1150 kc





VERTICAL RADIATION PATTERNS

FIGURE 10

CKOC

1150 kHz

PROJECT #14502

50 kW



DA-2

HAMILTON, ONTARIO

CLASS III

REV. JANUARY 5, 1979

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 11

CKOC

1150 KHz

PROJECT #14502

50 kW

DA-2



HAMILTON, ONTARIO

CLASS III

REV. JANUARY 5, 1979

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

CKOC



VERTICAL RADIATION PATTERNS

FIGURE 12

CKOC
1150 kHz
PROJECT #14502

50 kW

DA-2

HAMILTON, ONTARIO

CLASS 1B

REV. JANUARY 5, 1972

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

GD-10159 (NO 101V)

POLAR CO-ORDINATE
1:101 1/4 CANADA

CCS
MICRO-GRAPH

CKTR

DESCRIPTION SHEET
(5-27-60g)

Station CKTR 1kw, 10kw-LS, DA-2, U, Class III
Three Rivers, Quebec, Canada 1150 KC

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2

STATION CALL: CKTR
MAIN STUDIO: Three Rivers, Quebec.
FREQUENCY: 1150 kc/s
POWER: Day -10,000W, 1000 W Night.
CLASS: III
TIME: Unlimited

NOTIFICATION REFERENCE: 145 Date April 8, 1960
.....

GEOGRAPHICAL LOCATION: N.Lat. 46°18'50"
W.Lon. 72°31'55"

ANTENNA CHARACTERISTICS: Three elements, guyed, uniform cross section, base insulated, series feed.
(Elements top loaded to effect an estimated electrical height of 72 degrees.

ELEMENT	SOUTH	CENTRE	NORTH
HEIGHT	143.0'*	143.0'*	143.0'*
SPACING	ref.	182.5' 76.6°	395' 166°
DAY RATIO	1.0		0.6
PHASING	0°		-42°
NIGHT RATIO	1.0	1.8	1.0
PHASING	116°	0°	-114°
BEARING	ref	340°	340°

GROUND SYSTEM 120 radials per tower, #10 AWG bare soft copper wire, uniformly spaced, depth approximately 8 inches. Radials bonded to soft copper strap at tower bases. Maximum radial length 343 feet.

TOP LOADING Each element top loaded with three wires each 40.5 feet long at 45° to vertical.

PREDICTED R.M.S. 180 mv/m at 1 mile for 1 kw Night
575 mv/m at 1 mile for 10 kw Day

GM 21/2/58

5

145


CKTR

PROPOSED DAY
(5-27-60g)

Station CKTR
Three Rivers, Quebec, Canada
1kw, 10kw-L.S., DA-2, U, Class III
1150 KC

North Latitude 46° 18' 50"
West Longitude 72° 31' 55"

K-E POLAR CO-ORDINATE
KEUPPEL & ZIEBER CO. BOSTON, U.S.A.




AB 10/1/58

#66

Proposed Night Nulls
(2-22-71ct)

Station Y
Brandon, Manitoba

10kw, DA-N, U, Class III
1150 kc



CKX

DESCRIPTION SHEET
(1-29-60g)

Station CFX
Brandon, Manitoba, Canada

10/1kw, U, Class III
1150 KC

3



ADDITIONAL DESCRIPTION SHEET

OMNI-DIRECTIONAL

STATION NAME: CFX
MAIN SITE: Brandon, Manitoba.
FREQUENCY: 1150 kc/s
POWER: Day 10000 Watts - 1000 Watts Night
CLASS: III
TYPE: Unlimited
NOTIFICATION REFERENCE: #141 DATE: December 4, 1959

LOCATION: N. 49° 40' 28"
W. 100° 03' 12"

HEIGHT: One element, guyed, uniform cross section, base insulated, series feed.

LENGTH: 170 feet (10°)

BRUSH: 120 radials, 110 AWG bare soft copper wire, uniformly spaced, length approximately 6 inches. Radials banded to a soft copper strap at tower base. Maximum radial length 342 feet.

FIELD STRENGTH: 167 mv/m at 1 mile for 1 kw.
402 mv/m at 1 mile for 10 kw.

OPERATION: One element


1-15/59

KAGO

1-5067

JUN 28 1948 G


Exhibit 338



DIRECTIVE ANTENNA
HORIZONTAL PATTERN

Center line of towers, Az. 50.6°
Two towers spaced 130°
Phase angle 170°
Current ratio 1:1

KJJI BROADCASTERS
KLAMATH FALLS, OREGON



KAGO

MEASURED
NIGHT

KFJI, KLAMATH FALLS, OREGON

1kw, 5kw

340° 20° EXHIBIT A-1 1150KC

330°


340°

350°

0

350°
10°

1-3-50



KAGO


MEASURED
DAY (Non-DA)

KFJI, KLAMATH FALLS, OREGON

1kw, 5kw-LS, DAN

1150 kc

EXHIBIT E-3



KAGO

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KAGO

Main Studio: Kkamath Falls, Oregon

Frequency: 1150 kHz

Power: 1 kW Night 5 kW Day

Notification List No. 1701

Date: September 8, 1976

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 12' 56"

West Longitude: 121° 47' 56"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER: W(#2) E(#1)

HEIGHT ABOVE
INSULATORS: 230' 230' (96.77°)

PHASING: -170° 0°

FIELD RATIO: 0.75 1.0

SPACING AND

ORIENTATION: Towers are spaced 310' (130.4°) on a line bearing 260.6°
true.GROUND SYSTEM: 120-340' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap
along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL

RMS


Day 431.6 mv/m

Night 193.7 mv/m

(Over)

This notification concerns only minor changes in the Nighttime operation of the station with Daytime operation continued as previously notified. Note that the antenna height shown as 97.5 degrees on the attached horizontal radiation pattern is in error.

CTR NO: 30885A4



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
G = 230'	TOWER NO.	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION °	SPACING ft	PHASING °	HORIZONTAL FIELD PATTERN °	FIELD RATIO F	ELEVATION ANGLE °	ELEVATION ANGLE °	CALL	KAGO
	1	97.5	0	0	0	0	1.0	0	0	FREQUENCY	1150
	2	97.5	260.6	130	-170	0	0.75	0	0	POWER	1.0
	3									TIME OF OPERATION	NIGHT
	4									TYPE OF OPERATION	DA
	5									DAYTIME TOWERS	
	6									NIGHTTIME TOWERS	2
	7									NO. RADIALS PER TOWER	
	8									LENGTH OF RADIALS	
	9									GROUND SCREEN DIMENSIONS	
										AT	42' x 12' x 56'
										LONG	21' x 47' x 50'
										SUPERSEDES	
										PATTERN NO.	
GEORGE LYNCH, CONSULTING ENGINEER MOORESTOWN, CALIFORNIA		RADIO STATION KAGO KLAMATH FALLS, OREGON								FIGURE B REVISED 5/76	
APPLICATION TO MODIFY DA-N PATTERN ~ 1150 KHZ, 1 KW/5 KW LS DA-N ~ MAY 1976											

KAYO
1150KHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KAYO Main Studio: Seattle, Washington
Frequency: 1150 kHz Power 5kw Night 5 kw Day
Notification List No. 1789 Date: September 12, 1980 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 47° 35' 33"
West Longitude: 122° 11' 31"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
Number of elements: 3
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	C(#1)	NE(#2)	SW(#3)
HEIGHT ABOVE INSULATORS:	240'	240'	240' (101°)
NIGHT PHASING:	0°	169.3°	-152.2°
NIGHT FIELD RATIO:	1.0	0.7	1.18

SPACING AND ORIENTATION:

With Tower #1 as reference, Tower #2 is spaced 199.6'
(84°) on a line bearing 50° true and Tower #3 is
spaced 199.6' (84°) on a line bearing 249.5° true.

GROUND SYSTEM: 120 - 215' or to property edge equally spaced copper
radials about each tower.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Night	394 mv/m	767.56 mv/m	413.70 mv/m

(Amended February 18, 1980)

KBAI
1150 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KBAI Main Studio: Morro Bay, California
Frequency: 1150 kHz Power: 5kw Night 5kw Day
Notification List No. 1785 Date: November 16, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 35° 21' 34"
West Longitude: 120° 49' 29"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
Number of elements: 3
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.


TOWER:	SW(#1)	C(#2)	NE(#3)
HEIGHT ABOVE INSULATORS:	220'	220'	220' (92.6°)
PHASING:	0°	+150°	-60.1°
FEED RATIO:	1.0	1.58	0.62
SPACING AND ORIENTATION:	Towers are spaced 213.8' (90°) on a line bearing 53° true.		

GROUND SYSTEM: 120-214' equally spaced copper radials plus 120-50' interspaced radials about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL RMS	RCS	STANDARD RMS
Day 427.1 mv/m			
Night 466.7 mv/m	726.7 mv/m		490.43 mv/m


KBA1
1150 kHz
DA-N



RES = 726.7 MV/M
RMS = 490.42 MV/M (STANDARD)

HORIZONTAL RADIATION PATTERN

FIGURE 1-A




APPLICANT	Radio Station KBA1
LOCATION	Marine Base, California
FREQUENCY	1150 KC/SEC
POWER	5 KW
LATITUDE	35 20' N 121 40' W
LONGITUDE	120 40' W 19 40' N
WHEN USED	NIGHTTIME
WAS FIELD	400.7 MV/M (STANDARD)
DATE	MARCH 1957

ROBERT L. THOMSON


WASHINGTON 25

1kw, DA-D, D
1150 kc

Station KCCT
Corpus Christi, Texas



THEORETICAL PERMANENCE
OF A B-10

[illegible]
$$- \frac{1}{2} \frac{d}{dt} \left(\frac{1}{\rho} \right) = \frac{1}{2} \frac{d}{dt} \left(\frac{1}{\rho} \right) = 0$$

Station KCCT
Corpus Christi, Texas


1150 kc

KCCT

Measured Non-DA
(2-22-71ct)

Station KCCT
Corpus Christi, Texas

1kw, DA-D, D
1150 kc



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT	INTERNATIONAL RADIO CO
LOCATION	CORPUS CHRISTI, TEXAS
FREQUENCY	1150 KC/S
POWER	1000 WATTS
LATITUDE	27°06' 45" N 145°00'
LONGITUDE	97°06' 28" W 43°50'
WHEN USED	NON-DIRECTIONAL SURVEY
AWS FIELD	203 MV/M (MEASURED)
DATE	SEPTEMBER 1970

FIGURE 3-B

FCC File No. BL-12781
Accepted 2-11-71

Station KCCT
Corpus Christi, Texas

1150 kc

1000
2

93866

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Stations: (New) Main Studio: Corpus Christi, Texas
 Frequency: 1150 kc Power: 1 kw
 Notification List No. 518 Date: August 5, 1953 Class III
 GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 27° 52' 49"
 West Longitude: 97° 27' 06"

ANTENNA CHARACTERISTICS

Authorized for daytime operation.
 Number of elements: two
 Type of elements: Series-fed, uniform cross-section, guyed vertical
 steel towers.

TOWER:	S.W. (#1)	N.E. (#2)
HEIGHT ABOVE INSULATORS:	90°	90°
PHASING:	0°	93.1°
FIELD RATIO:	1.0	0.8
SPACING AND ORIENTATION:	Elements spaced 90° on a line bearing 40° True.	
GROUND SYSTEM:	120 - 214' equally spaced radials plus 120 - 50' inter- spaced radials about each tower base. Radials are shortened and bonded to a transverse strap along inter- sections between towers.	

Predicted effective Field: 120 mv/m (at rated power)


KCCT

Proposed Day
(12-27-68ct)


Station KCCT
Corpus Christi, Texas

1kw, DA-D, D
1150 kc

P-18415
Station
- 2150 3F
7.3449
International
Broadcast
- See
2004-6
2115



HORIZONTAL RADIATION PATTERN



$$G_1 = G_2 = 90^\circ$$

APPLICANT :	KCCT
LOCATION :	CORPUS CHRISTI, TEXAS
FREQUENCY :	1150 KC/S
POWER :	1000 WATTS
LATITUDE :	27 DEG 48 MIN 1.4 SEC.
LONGITUDE :	97 DEG 28 MIN 13.8 SEC
WHEN USED :	DAYTIME
R.M.S. FIELD :	185.3
DATE :	OCTOBER 1968

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-18415
Accepted 12-19-68

Station KCCT
Corpus Christi, Texas

1150 kc

KCC 1


PROPOSED DAY
(2/7/57g)

Station KCCT
Corpus Christi, Texas

1KW, DA-D,D
1150 KC

LAT. $27^{\circ} 52' 49''$
LONG. $97^{\circ} 27' 06''$

Maximum Expected
Operating Value
(Enlarged Scale)



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON D. C.

KCCT

Corpus Christi, Texas

Daytime

NEW, Corpus Christi, Texas


1000 W 1150 KC

1150 KC

KCCT

MEASURED KCCT, Corpus Christi, Texas 1KW, Da, DA-D
DAY (5/20/54G)

1150 kc



KCKY

Proposed Night
(2-26-63ct)

New; Coolidge Broadcasting Co.
Coolidge, Arizona


1kw, DA-N, U
1150 kc

Horizontal Radiation Pattern

NIGHTTIME PATTERN 0° Level.

Craig E. Davids, Kathleen E. Davids,
and Paul Dean Ford d. b. a. Coolidge
Broadcasting Company, Application
for 1150 kc. 1000W, DA-N, U,
Coolidge, Arizona. This Exhibit
Prepared January 7, 1963 by Paul
Dean Ford, Engineer.

4/24/64
printed CP
on new station




H = 203 feet or 90°

Measured Night
(3-26-65ct)

Station KCKY
Coolidge, Arizona

KCKY
1kw, DA-N, U
1150 kc

Measured Horizontal Nighttime Radiation Pattern
Radio Station KCKY, Coolidge, Arizona
Pinal County Broadcasting System
1150 kc. 1000W, U, DA-N



FCC File No. BL-10795
Accepted 3-10-65

Station KCKY
Coolidge, Arizona

1150 kc

KCKY

Measured Non-DA
(3-26-65ct)


Station KCKY
Coolidge, Arizona

1kw, DA-N, U
1150 kc

10-10-8-65

Measured Non-Directional Pattern from KCKY No. 2 (South) Tower
No. 1 (North) Tower Open Circuited for Non-Directional Operation
Radio Station KCKY, Coolidge, Arizona Pinal County Broadcasting
System. 1150 kc. 1000W, U, DA-N

RMS = 195 mv/m



Paul Dean Ford, Engineer, November 4, 1964.

FCC File No. BL-10795
Accepted 3-10-65

Station KCKY
Coolidge, Arizona


1150 kc

P-4677

KCKY

COOLIDGE, ARIZ.

5/15/64
later News
Coolidge
remitter
pposition
to new Am
station



KDEF

PROPOSED NIGHT
(9-25-58g)


Station KDEF
Albuquerque, New Mexico

5/1 500w, DA-N, U

1150 KC

PROPOSED NIGHTTIME DIRECTIONAL
HORIZONTAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

PROPOSED OPERATION - ALBUQUERQUE, N.M.
KDEF BROADCASTING COMPANY
1150 KC 1KW, LS .5KW, N (DA-N)
JUNE 1958



FCC File No. BP-12,293
Accepted 9-23-58

KDEF
Albuquerque, New Mexico

1150 KC


KDEF

Measured Night
(6-22-62ct)

Station KDEF
Albuquerque, New Mexico

500w, DA-N, U
1150 kc

8-10-62
rented L for
A-N (change in
working operation)
CP 1-19-66



FCC File No. BL-9364
Accepted 6-15-62

Station KDEF
Albuquerque, New Mexico

1150 kc


KDEF

Measured Non-DA
(6-22-62ct)

Station KDEF
Albuquerque, New Mexico

500w, DA-N, U
1150 kc

P 1-19-66



North Latitude 35° 07' 52"
West Longitude 106° 40' 35"

MEASURED DAY HORIZONTAL
RADIATION PATTERN
RADIO STATION KDEF 1150 KC
1 KW, G=218 FT, = 90.5°

E. L. GEMOETS
APRIL 10, 1962

FCC File No. BL-9364
Accepted 6-15-62

Station KDEF
Albuquerque, New Mexico

1150 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KIIS Main Studio: Los Angeles, California
 Frequency : 1150 KHz Power : 5 kW Night 5 kW Day
 Notification : 1781 Date : Oct. 19, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 34 05 05
 West Longitude: 118 12 10

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation.(DA-N)

Number of elements: 3

Type of elements : Three vertical, series excited raditors.
 End towers (#1 and #3) guyed, center
 tower (#2) self-supporting.


TOWER : #1(NE) #2(c) #3(SW) _____
 HEIGHT ABOVE
 INSULATORS : 214'(90°) 216'(909°) 214'(90°) _____
 NIGHT PHASING : 151.3° 0° -105.9° _____
 NIGHT FIELD RATIO: 0.542 1.000 1.510 _____
 SPACING AND
 ORIENTATION : The towers in a row are spaced 225.8' (95°)
 on a line bearing 44.9 ° true.
 GROUND SYSTEM : 120 - 220 equally spaced copper radials plus 120 - 50'
 interspaced radials about each tower. Radials are
 shortened and bonded to copper strap along inter-
 sections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	<u>424.9</u> mv/m		
Night	<u>454.9</u> mv/m	_____ mv/m	<u>477.9</u> mv/m

Note:


Standard Pattern



RMS_{STO} = 477.9 MV/M
RMS_{THEC} = 454.9 MV/M

E_{RSS} = 546.4 MV/M
S₁ = S₂ = 225.8 FT = 95°

G₂ = 216 FT = 90.9°
G₁ = G₃ = 214 FT = 90°



N. LAT 34°05'05"
W. LONG 118°12'10"

PROPOSED STANDARD
HORIZONTAL RADIATION
NIGHTTIME
UNATTENUATED FIELD STRENGTH
AT ONE MILE

HAMMETT & EDISON, INC.
CONSULTING ENGINEERS
SAN FRANCISCO

RADIO STATION KIIS
1150 KHZ. 5 KW. DA-N
LOS ANGELES, CALIFORNIA


770501

FIGURE 3B

RADIO STATION KIIS

Standard Pattern

PROPOSED STANDARD RADIATION - NIGHTTIME



Hammett & Edison, Inc.
Consulting Engineers


Measured Day
(1-28-69ct)

Station KKEY
Portland, Oregon

KKEY
5kw, DA-D, D
1150 kc

BL12221
Granted
2-6-69
license
covering
increase
in power
installation
of doppler
directional
antenna
& change
in radiation
pattern

NO. 3501-D, 100-100, 100-100, 100-100
RECEIVED IN OREGON



J. B. HATFIELD
CONSULTING RADIO ENGINEER
908 36TH AVENUE
SEATTLE, WASHINGTON 98122

FCC File No. BL-12221
Accepted 1-3-69

Station KKEY
Portland, Oregon


1150 kc

Measured Non-DA
(1-28-69ct)

Station KKEY
Portland, Oregon

KKEY
5kw, DA-D, 0
1150 kc

BP-12221
Granted
2/6/69
license
covering
increase
in
power
to station
of daytime
directional
antenna
change
in
station
location



FCC File No. BL-12221
Accepted 1-3-69

Station KKEY
Portland, Oregon

1150 kc

KKEY

Proposed Day
(11-29-66ct)


Station KKEY

5kw, DA-D, D
1150 kc

PORTLAND, ORE. ~~Vancouver, Washington~~

North Latitude 45° 38' 34"
West Longitude 122° 36' 49"

11-22-67
GRANTED
APPL. TO
CHANGE FROM
1 KW TO 5 KW
OBTAINABLE




FCC File No. BP-17277
Accepted 9-21-66

Station KKEY
Vancouver, Washington

1150 kc

500w, DA-D,D
1150 KC





KKUZ ~~KYND~~ KYED

Measured Day
(1-28-66ct)

Station KYED
Burlington, Iowa

500w, DA-D, D
1150 kc

LC 12-28-65



MEASURED RADIATION PATTERN
KYED 1150 KC 0.5 KW DA
BURLINGTON, IOWA
AUG. 1965

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

FIG. 1

KKUZZ

~~KYED~~

~~KYED~~

Measured Non-DA
(1-28-66ct)


Station KYED
Burlington, Iowa

500w, DA-D, D
1150 kc

10.12.28.65

EUDEN
MA
U. S. A.

NO. 340-P DIE
POLAR
JRDINATE



FCC File No. 81-11067
Accepted 8-31-65 Amended

Station KYED
Burlington, Iowa

1150 kc


1150 KC

MEASURED
NIGHT (7/10/53)

KNED, MCALESTER, OKLA.

500W, 1KW-LS, U, DA-N

1150 kc




1150

MEASURED
DAY (7/10/53G)

KNED, MCALESTER, OKLA.

500W, 1KW-LS, U, DA-N

1150 kc




Santa Rosa
California
KPLS

PROPOSED DAY
(5/17/57g)

New, Radio Santa Rosa
Santa Rosa, California

500w,5kw-LS,DA-2,U
1150 KC

*Granted CP 7/9/58
for new station*



LATITUDE: 38° 27' 06" LONGITUDE: 122° 39' 34"	ANTENNA PARAMETERS G=88.4°	FIGURE 4 DAYTIME HORIZONTAL PATTERN RADIO SANTA ROSA SANTA ROSA, CALIF 1150 KC 0.5KW,5KW-LS,DA-2,U
JOHN H. MULLANEY CONSULTING RADIO ENGINEERS WASHINGTON, D. C.		

FCC File No. BP-11,084 (Amended)
Accepted 5/8/57

Radio Santa Rosa
Santa Rosa, California


1150 KC

K.PLS

MEASURED DAY
(2-2-59g)

Station KJAX
Santa Rosa, California

500w, 5kw-LS. DA-2,U
1150 KC



$E_{RMS} = 440 \text{ MV/M}$

LAT $38^{\circ} 27' 13.5''$

LONG. $122^{\circ} 39' 31''$




FIGURE 10

MEASURED DAYTIME PATTERN

KJAX
SANTA ROSA, CALIF.

1150 KC 0.5 / 5 KW DA2 U

NOV 1958

FCC File No. BL-7344
Accepted 1-23-59

KJAX
Santa Rosa, California

1150 KC


Santa Rosa
California
KPLS

PROPOSED NIGHT
(5/17/57g)

New, Radio Santa Rosa
Santa Rosa, California

500w,5kw-LS,DA-2,U
1150 KC

Granted CP 7/9/58
for new station



LATITUDE: 38° 27' 06" LONGITUDE: 122° 39' 34"	ANTENNA PARAMETERS G=88.4°	FIGURE 6 NIGHTTIME HORIZONTAL PATTERN RADIO SANTA ROSA SANTA ROSA, CALIF. 1150 KC 05KW,5KW-LS,DA-2,U
JOHN H. MULLANEY CONSULTING RADIO ENGINEER WASHINGTON, D. C.		

FCC File No. BP-11,084 (Ammended)
Accepted 5/8/57

Radio Santa Rosa
Santa Rosa, California


1150 KC

MEASURED NIGHT
(2-2-59g)

Station KJAX
Santa Rosa, California

500w, 5kw-LS, DA-2,U
1150 KC

KPLS



$E_{RMS} = 139 \text{ MV/M}$

LAT $38^{\circ}27'13.5''$

LONG. $122^{\circ}39'31''$




FIGURE 11

MEASURED NIGHTTIME PATTERN

KJAX

SANTA ROSA, CALIF.

1150 KC 0.5/5 KW DA2 U

NOV. 1958

ACC File No. BL-7344
Accepted 1-23-59

KJAX
Santa Rosa, California

1150 KC

MEASURED NON-DA
(2-2-59g)

Station KJAX
Santa Rosa, California

500w, 5kw-LS, DA-2,U
1150 KC

KPLS




FIGURE 9

PATTERN PRODUCED BY CENTER TOWER OF ARRAY 500 WATTS
INDEPENDENT TOWERS FLOATING.

K J A X

SANTA ROSA, CALIF

NOV 1958

FCC File No. BL-7344
Accepted 1-23-59

KJAX
Santa Rosa, California


1150 KC

KQAM

Proposed Day
(11-24-70ct)


Station KBER
San Antonio, Texas

1kw, DA-D, D
1150 kc



$E_{RMS} = 192.0 \text{ MV/M}$

----- = ME0V



FCC File No. BP-18913
Accepted 11-5-70

Station KBER
San Antonio, Texas

1150 kc


PROPOSED DAY
(7-8-59g)

New; Alamo B/Cstrs.
San Antonio, Texas

1kw, DA-D, D
1150 KC

KQAM 2

*Printed of for new station
7-7-60*
*--- 1-61 granted map
--- 1-61 granted map
NL: 4-1-53-15
WL: 98-53-46*





TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
		TOWER No.	ELECTRICAL HEIGHT G	TRUE TOWER ORIENTATION θ	SPACING S	PHASING φ	HORIZONTAL FIELD E	FIELD RATIO F	ELEV ANGLE θ	ELEVATION RMS FIELD E ₀	CALL
		1	90	0	0	-140	158.2	1.0000	0	192.0	FREQUENCY 1150
		2	90	118	60	0	312.5	1.9754	10		POWER 1.0
		3	90	118	120	140	158.2	1.0000	20		TIME OF OPERATION DAY TIME
		4							30		TYPE OF OPERATION DIRECTIONAL
		5							40		DAYTIME TOWERS 3
		6							50		NIGHTTIME TOWERS
		7							60		NO. RADIALS PER TOWER 240
		8							70		LENGTH OF RADIALS 50-200
		9							80		GROUND SCREEN DIMENSION
ALAMO BCSTG. CO. NEW AM 1150 KC 1000-D(DA) SAN ANTONIO, TEXAS		DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐								E ₀	LAT. 29 25 38
		EXHIBIT V-1C PROPOSED HORIZONTAL RADIATION PATTERN								P ₀	LONG 98 25 30
ALAMO BCSTG. CO. NEW AM 1150 KC 1000-D(DA) SAN ANTONIO, TEXAS		DAWKINS ESPY CONSULTING RADIO ENGINEERS BEVERLY HILLS, CALIF.								1w	SUPERSEDES
		DAWKINS ESPY CONSULTING RADIO ENGINEERS BEVERLY HILLS, CALIF.									PATTERN NO.

FCC File No. BP-11676
Accepted 6-22-59

Alamo Broadcasting Company
San Antonio, Texas

1150 KC

KQAM

Measured Day
(2-28-62ct)Station KBER
San Antonio, Texas1kw, UA-D, U
1150 kcANTENNA
PLACEMENT
SKETCHFCC File No. BL-8867
Accepted 1-23-62

DIRECTIONAL ANTENNA PARAMETERS

STATION KBER
FREQUENCY 1150 KCLOCATION SAN ANTONIO, TEX.
RATED POWER 1 KW.

Antenna No.	True Bearing	Spacing	Phasing	Current Ratio	Horizontal Field Intensity	Electrical Height
1	0°	0°	-138°	.506		90°
2	118°	60°	0°	1.000		90°
3	118°	120°	+140°	.533		90°

Station KBER
San Antonio, Texas


1150 kc

KQAM

Measured Non-DA
(2-28-62ct)

Station KBER
San Antonio, Texas

1kw, DA-D, D
1150 kc



North Latitude 29° 23' 15"
West Longitude 98° 23' 46"

Engineer: Kenneth R. Hyman

NON DIRECTIONAL HORIZONTAL RADIATION PATTERN

NON DIRECTIONAL ANTENNA PARAMETERS						
STATION <u>KBER</u>			LOCATION <u>San Antonio, Texas</u>			
FREQUENCY <u>1150</u> KC			RATED POWER <u>1 KW.</u>			

EXHIBIT NO. 5


FCC File No. BL-8867
Accepted 1-23-62

Station KBER
San Antonio, Texas

1150 kc

KSAL

1150



① — 135° — ② — 209° — ③ — 135° — ④ — N 102.2° E →

ALL G'S = 90 DEGREES

A. EARL CULLUM, JR.

CONSULTING RADIO ENGINEERS

DALLAS

TEXAS

TOWER	1	2	3	4
FIELD	0.496	0.80	0.62	1.00
PHASE	+18	+63	-45	00


Radio Station Kansas
RADIO STATION KSAL

PROPOSED 1150 KC 5 KW DA-N

FIGURE 5A

KSAL

1150



①—135°—②—209°—③—135°—④—N 102.2°E→

ALL G'S = 90 DEGREES

A. EARL CULLUM, JR.

CONSULTING RADIO ENGINEERS

DALLAS

TEXAS

TOWER	1	2	3	4
FIELD	0.496	0.80	0.62	1.00
PHASE	+18	+63	-45	00

Radio Kansas
RADIO STATION KSAL

PROPOSED 1150 KC 5 KW DA-N

FIGURE 5A

MEASURED
DAY (non-DA)

KSAL, SALINA, KANS.

5-13-49



5kw, DAN

1150 kc

KSAL

N. LAT. 38° 53' 08" 5/19/49G
W. LONG. 97° 30' 58"

DAY



RADIO STATION KSAL
SALINA, KANSAS
1150 KC 5 KW ND-D

PATTERN BASED ON
FIELD INTENSITY
MEASUREMENTS

A. EARL CULLUM, JR.
CONSULTING RADIO ENGINEERS
490501 FIGURE 2A

KSAL, Salina, Kans. 1150 kc

SUPPLEMENTAL DIRECTIONAL ANTENNA
DESCRIPTION SHEET

Station: KSEN

Main Studio: Shelby, Montana

Frequency: 1150 kHz

Power: 5 kW

Notification List No. 1606

Date: November 13, 1974 Class: III

GEOGRAPHICAL LOCATION OF THE

CENTER OF THE ANTENNA SYSTEM: North Latitude: 48° 28' 54"

West Longitude: 111° 53' 03"

Authorized for Daytime and Nighttime operation (DA-2).

Predicted effective Day Field: 438 mv/m at rated power.

Predicted effective Night Field: 392 mv/m at rated power.

Note: Please retain the nighttime verticle angle directional antenna radiation patterns notified for KSEN in United States Change List Number 1240, dated November 3, 1967, and the description sheet and daytime and nighttime horizontal radiation patterns notified in United States Change List Number 1308, dated February 19, 1969, and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates of the center of the antenna system.

CTR NO 30460A5

CORRECTION RECEIVED

MAY 15 1975

WASHINGTON, D.C.

KSEN


Proposed Night
(2-28-69ct)

Station KSEN
Shelby, Montana

5kw, DA-2, U
1150 kc

BMP12648
Granted
2-17-69
mod of
P to
make
changes in
directional
system

POLAR CO-ORDINATE



FCC File No. BMP-12648
Accepted 2-13-69


Station KSEN
Shelby, Montana

1150 kc

Measured Night
(8-22-69ct)

Station KSEN
Shelby, Montana

KSEN
5kw, DA-2, U
1150 kc



RMS = 393 MV/M FOR 5 K.W.

MEOV

G = 90°, TOP LOADED TO 105°

N. LAT. 48° 29' 64"
W. LONG 111° 53' 26"

MEASURED KSEN HORIZONTAL RADIATION PATTERN

FOR NIGHTTIME OPERATION ON 1150 K.C.

5 K.W., U, DA-2, SHELBY, MONTANA

MAY 1969

Engineer: J. B. Hatfield

KSEN

Proposed Day
(2-28-69ct)


Station KSEN
Shelby, Montana

5kw, DA-2, U
1150 kc

BMP-12648
handed
-19-69
1st. of CP
to make
changes
in dist.
of antenna
system

EUREKA DIEZIG CO.
MADE IN U.S.A.

NO. 340 P. DIEZIG GRAPH CO. INC.
POLAR CO-ORDINATE



FCC File No. BMP-12648
Accepted 2-13-69

Station KSEN
Shelby, Montana


1150 kc

KSEN


Measured Day
(8-22-69ct)

Station KSEN
Shelby, Montana

5kw, DA-2, U
1150 kc



N. LAT. 48° 29' 00"
W. LONG 111° 53' 26"



RMS = 442 MV/M FOR 5 K.W.

G = 90°, TOP LOADED TO 105°

MEASURED KSEN HORIZONTAL RADIATION PATTERN

FOR DAYTIME OPERATION ON 1150 K.C.

5 K.W., U, DA-2, SHELBY, MONTANA

Engineer: J. B. Hatfield

MAY 1969

FCC File No. BL-12422
Accepted 8-15-69

Station KSEN
Shelby, Montana

1150 kc


KSEN

Measured Non-DA
(8-22-69ct)

Station KSEN
Shelby, Montana

5kw, DA-2, U
1150 kc

Handwritten notes:
1. 10-31-69
2. 11-1-69
3. 11-2-69
4. 11-3-69
5. 11-4-69
6. 11-5-69
7. 11-6-69
8. 11-7-69
9. 11-8-69
10. 11-9-69
11. 11-10-69
12. 11-11-69
13. 11-12-69
14. 11-13-69
15. 11-14-69
16. 11-15-69
17. 11-16-69
18. 11-17-69
19. 11-18-69
20. 11-19-69
21. 11-20-69
22. 11-21-69
23. 11-22-69
24. 11-23-69
25. 11-24-69
26. 11-25-69
27. 11-26-69
28. 11-27-69
29. 11-28-69
30. 11-29-69
31. 11-30-69
32. 12-1-69
33. 12-2-69
34. 12-3-69
35. 12-4-69
36. 12-5-69
37. 12-6-69
38. 12-7-69
39. 12-8-69
40. 12-9-69
41. 12-10-69
42. 12-11-69
43. 12-12-69
44. 12-13-69
45. 12-14-69
46. 12-15-69
47. 12-16-69
48. 12-17-69
49. 12-18-69
50. 12-19-69
51. 12-20-69
52. 12-21-69
53. 12-22-69
54. 12-23-69
55. 12-24-69
56. 12-25-69
57. 12-26-69
58. 12-27-69
59. 12-28-69
60. 12-29-69
61. 12-30-69
62. 12-31-69



RMS = 192 MV/M

G = 90° (214')

KSEN 1.0 K.W. HORIZONTAL PATTERN

FOR #2 TOWER, NON-DIRECTIONAL

AUGUST 1968

FCC File No. BL-12422
Accepted 8-15-69

Station KSEN
Shelby, Montana

1150 kc

KSUZ

SUPPLEMENTAL DIRECTIONAL ANTENNA
DESCRIPTION SHEET

Station: KSUZ

Main Studio: Port Neches, Texas

Frequency: 1150 kHz

Power: 0.5 kW

Notification List No. 1690

Date: June 24, 1976

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 30° 05' 04"
West Longitude: 93° 58' 13"

Authorized for Daytime operation (DA-D).

Predicted effective Day Field: 127 mv/m at rated power.


Note: Please retain the description sheet and directional antenna radiation patterns notified for a new station at Port Neches, Texas, in United States Change List Number 790, dated December 23, 1958, and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a change in the geographical coordinates of the center of the antenna system.

PROPOSED DAY
(5-8-58g)

New; Mid-County Radio
Port Neches, Texas


500w, DA-D,D
1150 KC

*Granted CP
12/23/58 for
new station*



S=170°=404.2"

--- MEQV



RMS=127 MV/M

G'S=92.5°=220'

580220

J. G. ROUNTREE
CONSULTING RADIO ENGINEER
5622 DYER STREET
DALLAS 6, TEXAS

MID-COUNTY RADIO
PORT NECHES, TEXAS
1150 KC, 500 W, DA, D

FIGURE 4A

FCC File No. BP-11,943
Accepted 4-28-58

Mid-County Radio
Port Neches, Texas


1150 KC

MEASURED DAY
(9-4-59g)

Station KPNG
Port Neches, Texas

500w, 1

KSUZ
1150 KC



NL 30° 04' 58"
WL 93° 57' 46"

MEASURED DA PATTERN

② ← S → ① → 85° T

SEE FIGURE 2 FOR OPERATING PARAMETERS

RMS = 126.0 MV/M

S = 170° = 404' 2"

J. G. ROUNTREE
CONSULTING RADIO ENGINEER
5622 DYER STREET
DALLAS 6, TEXAS

RADIO STATION KPNG
PORT NECHES, TEXAS
1150 KC, 500W, DA-D

590620

FIGURE 3B

FCC File No. BL-7578
Accepted 8-25-59

KPNG
Port Neches, Texas

1150 KC

*granted L for new station
11-18-59*


KSUZ

MEASURED NON-DA
(9-4-59g)

Station KPNG
Port Neches, Texas

500w, DA-D, D
1150 KC

granted L for new station
11-18-59



NL 30° 04' 58"
WL 93° 57' 40"

MEASURED ND PATTERN

(2) ← S → (1) → 85° T
(DETUNED)

RMS = 130.6 MV/M

S = 170° = 404' 2"

J. G. ROUNTREE
CONSULTING RADIO ENGINEER
6622 DYER STREET
DALLAS 9, TEXAS

RADIO STATION KPNG
PORT NECHES, TEXAS
1150 KC, 500W, DA-D

590620

FIGURE 3A

FCC File No. BL-7578
Accepted 8-25-59

KPNG
Port Neches, Texas

1150 KC


KVIL

PROPOSED DAY
(12-21-59g)


Station KVIL
Highland Park, Texas

1kw, DA-D, D
1150 KC

4-5-01
sited Met
to 1 kw
1-6-51
sited Met
to 1 kw
1-6-51
sited Met
to 1 kw



$S_1 = 91.5^\circ = 217'$
 $S_2 = 180^\circ = 428'$
 $G_{1,2,3,4,5,6} = 91.5^\circ = 217'$
 $RMS = 177 \text{ MV/M}$
 $N \text{ LAT. } 32^\circ 53' 36''$
 $W \text{ LONG } 96^\circ 55' 33''$



HORIZONTAL RADIATION PATTERN

UNATTENUATED FIELD INTENSITY
AT ONE MILE

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION KVIL
1150 KC, 1KW, DA-D
HIGHLAND PARK, TEXAS

590909

FIGURE 4B

FCC File No. BMP-8789
Accepted 11-24-59

KVIL
Highland Park, Texas


1150 KC

KVIL


MEASURED DAY
(9-20-61ct)

Station KVIL
Highland Park, Texas

1kw, DA-D, D
1150 kc



$S_1 = 91.5^\circ = 217'$
 $S_2 = 180^\circ = 428'$
 $G_{2,3,4,5} = 91.5^\circ = 217'$
 RMS = 177 MV/M
 N. LAT $32^\circ 53' 36''$
 W. LONG $96^\circ 55' 33''$



MEASURED HORIZONTAL RADIATION PATTERN DAYTIME

UNATTENUATED FIELD INTENSITY
AT ONE MILE

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION KVIL
1150 KC, 1KW, DA-D
HIGHLAND PARK, TEXAS

610628

FIGURE 108


FCC File No. BL-8622
Accepted 8-21-61

Station KVIL
Highland Park, Texas

1150 kc

9-20-61 1150 KC 1KW DA-D

KVIL

MEASURED NON-DA
(9-20-61ct)Station KVIL
Highland Park, Texas1kw, DA-D, D
1150 kcN. LAT. 32° 53' 36"
W. LONG. 96° 55' 33"

G=91.5-217'

RMS=96 MV/M

TOWER 5 EXCITED
PRIOR TO ERECTION OF OTHER FIVE TOWERS.HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCORADIO STATION KVIL
1150 KC, 1KW, DA-D
HIGHLAND PARK, TEXAS

610628

MEASURED
HORIZONTAL RADIATION PATTERN
250 WATTS NON-DIRECTIONAL TESTUNATTENUATED FIELD INTENSITY
AT ONE MILE

FIGURE 10A

FCC File No. BL-8622
Accepted 8-21-61Station KVIL
Highland Park, Texas

1150 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KWBZ	Main Studio: Englewood, Colorado
Frequency: 1150 kHz	Power: 1kw Night 5kw Day
Notification List No. 1781	Date: October 19, 1979 Class: III
Geographical Location of the Center of the Antenna System:	North Latitude: 39° 36' 18" West Longitude: 104° 50' 25"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 4
 Type of elements: Series excited, uniform, cross-section
 guyed, vertical steel towers.

TOWER:	W(#1)	WC(#2)	EC(#3)	E(#4)
HEIGHT ABOVE INSULATORS:	140'	140'	140'	140' (58.9°)
NIGHT PHASING:	0°	170.6°	-34.9°	143.1°
NIGHT FIELD RATIO:	1.0	0.53	0.69	0.81
SPACING AND ORIENTATION:	The towers in a row are spaced 285.1' (119.91°) on a line bearing 102° true.			
GROUND SYSTEM:	120 - 210" equally spaced copper radials plus 120 - 50' interspaced radials about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers. Centers of system are bonded together.			

STANDARD DISK 508 REFERENCE A/2

2.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	<u>RMS</u>	THEORETICAL <u>RSS</u>	STANDARD <u>RMS</u>
Day 1/	<u>438.3</u> mv/m		
Night	<u>178.3</u> mv/m	<u>286.9</u> mv/m	<u>187.4</u> mv/m


Note:

KWBZ
WESTERN BROADCASTING CORPORATION
1150 kHz 5000 WATTS D, 1000 WATTS N, DAN
ENGLEWOOD, COLORADO
NOVEMBER 1978

NIGHTTIME DIRECTIONAL
HORIZONTAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

84°T Expanded Sector 69°- 99°T (J= 18.326)
120.5°T Expanded Sector 105.5°- 135.5°T (J= 18.522)

MODIFIED STANDARD PATTERN



ELECTRICAL DESCRIPTION

POWER = 1000 Watts
G's = 58.9° [42.7 m]
 K_a = 184.7 mV/m
TH. RMS = 178.3 mV/m
RSS = 286.9 mV/m
RMS
RSS = 0.62
 $Q(\theta) = 7.17 f_G(\theta) [G = 58.9^\circ]$
STD RMS = 187.4 mV/m
[301.6 mV/m/kW @ 1 km]

NL: 39° 36' 18"
WL: 104° 50' 25"

Larry D. Ellis, P.E.

TELECOMMUNICATIONS CONSULTING ENGINEER
BOX 22835 • DENVER, COLORADO 80222 • 303/759-1327
OFFICE: 2055 SOUTH ONEIDA • SUITE 190





EXHIBIT 821

PROPOSED NIGHTTIME DIRECTIONAL
EXPANDED HORIZONTAL PATTERN
UNATTENUATED FIELD AT ONE MILE

MODIFIED STANDARD PATTERN - NIGHTTIME

KWBZ
WESTERN BROADCASTING CORPORATION
1150 kHz 5000 WATTS D, 1000 WATTS N, DAN
ENGLEWOOD, COLORADO
NOVEMBER 1978



* EXPANDED SCALE
SCALE VALUE x 0.1

Larry D. Ellis, P.E.
TELECOMMUNICATIONS CONSULTING ENGINEER
101754 1127
OFFICE 2055 SOUTH OAKDALE • SUITE 190
DENVER, COLORADO 80222

360
300
240
180
120
60
0
AZIMUTH - °T

mV/M

DIRECTIONAL ANTENNA DESCRIPTION SHEET

STATION: KWBZ
 FREQUENCY: 1150 kHz
 Notification List No. 1748

Main Studio: Englewood, Colorado
 Power: 1 kW Night 5 kW Day
 Date: September 7, 1977 Class: III

Geographical Locations of the centers of the Day and Night antenna System:

Daytime
 North latitude: 39° 38' 35"
 West Longitude: 105° 00' 48"

NIGHTTIME
 North latitude: 39° 36' 18"
 West Longitude: 104° 50' 25"

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 4

Type of elements: Series excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	W(#1)	WL(#2)	EC(#3)	E(#4)	
HEIGHT ABOVE INSULATORS: 140'		140'	140'	140'	(58.9°)
PHASING:	0	+170.6°	-34.9°	+143.1°	
FIELD RATIO:	1	0.53	0.69	0.81	

SPACING AND

ORIENTATION: The towers are located in a row spaced 285' (120" on a line bearing 102° true.

NIGHT GROUND SYSTEM: 120-210 equally spaced copper radials plus 120 50' interspace radials tower. Radials are shortened and bonded to transverse straps along interesections between towers.

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (ND)

HEIGHT ABOVE

INSULATORS: 250'

DAY GROUND SYSTEM: 120-250' equally spaced copper radial about the tower.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	Theoretical rms	Standard rms
day	438 mv/m	- mv/m
night	178.3 mv/m	187.4 mv/m

Note:

This notification concerns only a change to nighttime add new operation nighttime with daytime operation continued as previously notified.

K W B Z
WESTERN BROADCASTING CORPORATION
1150 kHz 5 kW-D 1 kW-N DA-N
ENGLEWOOD, COLORADO
FEBRUARY 1977


EXHIBIT E-6.01A

AMENDED

PROPOSED NIGHTTIME DIRECTIONAL
HORIZONTAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

NIGHTTIME STANDARD PATTERN

Standard Pattern



ELECTRICAL DESCRIPTION

POWER = 1000 Watts
G's = 58.9° [42.7 m]
 K_{Ω} = 184.7 mV/m
TH. RMS = 178.3 mV/m
RSS = 286.9 mV/m
RMS / RSS = 0.62
 $Q(\theta) = 7.17 f_G(\theta) [G = 58.9^\circ]$
STD RMS = 187.4 mV/m
[301.6 mV/m/kW @ 1 km]

--- EXPANDED SCALE


NL: 39° 36' 18"
WL: 104° 50' 25"

VIR JAMES
CONSULTING RADIO ENGINEERS
345 COLORADO BLVD. DENVER, CO 80208
PHONE (303) 333-5782

1.00/0°
S₁ 0.53/170.6°
S₁ 0.69/-34.9°
S₁ 0.81/143.1°
102° T

G = 58.9° (42.7 m)
S₁ = 120° (86.9 m)

KPI



KWBZ
1150kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KWBZ Main Studio: Englewood, Colorado
Frequency: 1150 kHz Power: 5kw Night 5kw Day
Notification List No. 1789 Date: September 12, 1980 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 39° 36' 18"
West Longitude: 104° 50' 25"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation (DA-2)
Number of elements: 4
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	#(#1)	WC(#2)	EC(#3)	E(#4)
HEIGHT ABOVE INSULATORS:	140'	140'	140'	140' (58.9°)
NIGHT PHASING:	0°	+17.6°	-34.9°	+143.1°
NIGHT FIELD RATIO:	1.0	0.53	0.69	0.81
DAY PHASING:	—	0°	45°	—
DAY FIELD RATIO:	—	1.0	0.55	—

SPACING AND
ORIENTATION: Towers in a row are spaced 285.2' (120°) on a line bearing
102° true.

GROUND SYSTEM: 120 - 210' equally spaced copper radials plus 120 - 50'
interspaced radials about each tower. Radials are shortened
and bonded to transverse straps along intersections
between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	RMS	RSS	RMS
Day	396.405 mv/m	377.718 mv/m	416.464 mv/m
Night	178.3 mv/m	286.9 mv/m	187.4 mv/m

KWBZ
1150kHz

NOTE: Please retain the Nighttime directional antenna radiation pattern notified for Station KWBZ in United States Change List Number 1781 dated October 19, 1979 and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in the Daytime operation of the station with Nighttime operation continued as previously notified.


OCTOBER 1979

KWBZ

1150kHz

STANDARD HORIZONTAL RADIATION PATTERN

KWBZ
 WESTERN BROADCASTING CORPORATION
 1150 KHz 5000 WATTS D, 1000 WATTS N, DA-2
 ENGLEWOOD, COLORADO
 OCTOBER 1979



THEO. RMS = 396.405
 THEO. RSS = 377.718
 STD. RMS = 416.464
 Q = 13.4164
 K FACTOR = 330.962
 HEIGHT = 58.9°

PROPOSED SITE:

N. LAT. 39° 36' 18"
 W. LONG. 104° 50' 25"

Larry D. Ellis, P.E. ■


TELECOMMUNICATIONS CONSULTING ENGINEER
 BOX 22835 • DENVER, COLORADO 80222 • 303/789-1327
 OFFICE 2056 SOUTH ONEIDA • SUITE 190

Measured Non-DA
(8-26-70oct)

Station KWKY
Des Moines, Iowa

KWKY
1kw, DA-2, U
1150 kc

See Reverse Side



FCC File No. BL-12695
Accepted 8-13-70

Station KWKY
Des Moines, Iowa


1150 kc

Measured Day
(8-26-70ct)

Station KWKY
Des Moines, Iowa

KWKY
1kw, DA-2, U
1150 kc

SEE REVERSE SIDE



FCC File No. BL-12695
Accepted 8-13-70

Station KWKY
Des Moines, Iowa


1150 kc

Measured Night Nulls
(8-26-70 Oct)

Station KWKY
Des Moines, Iowa

KWKY
1kw, DA-2, U
1150 kc

SEE REVERSE SIDE



FCC File No. BL-12695
Accepted 8-13-70

Station KWKY
Des Moines, Iowa


1150 kc

Measured Night
(8-26-70ct)

Station KWKY
Des Moines, Iowa

KWKY
1kw, DA-2, U
1150 kc

SEE REVERSE SIDE



FCC File No. BL-12695
Accepted 8-13-70

Station KWKY
Des Moines, Iowa


1150 kc

Proposed Day
(7-28-69ct)

Station KWKY
Des Moines, Iowa

KWKY
1kw, DA-2, U
1150 kc

BP-18556
wanted
21-69
application
for 1150 kc
Norseman
Broadcasting Co.
Des Moines, Iowa



LATITUDE: 41° 27' 07" LONGITUDE: 93° 40' 44"	ANTENNA PARAMETERS G = 92.5° ± 220°	FIGURE 1 PROPOSED DAYTIME DIRECTIONAL PATTERN NORSEMAN BROADCASTING CORPORATION DES MOINES, IOWA 1150 KHz 1 KW, DA-2, U
JOHN H. MULLANEY AND ASSOCIATES		

FCC File No. BP-18556
Accepted 5-21-69


Station KWKY
Des Moines, Iowa

1150 kc

Proposed Night
(7-28-69ct)

Station KWKY
Des Moines, Iowa

KWKY
1kw, DA-2, U
1150 kc



FCC File No. BP-18556
Accepted 5-21-69


Station KWKY
Des Moines, Iowa

1150 kc

Proposed Night Nulls
(7-28-69ct)

Station KWKY
Des Moines, Iowa

KWKY
1kw, DA-2, U
1150 kc



FCC File No. BP-18556
Accepted 5-21-69


Station KWKY
Des Moines, Iowa

1150 kc

PATTERN NO.: 470221
SUPERSEDES: 470122


KWKY

DES MOINES, IOWA
NEW - 1150KC



40 G

5-3-48



5-3-48

KXLR


MEASURED
NIGHT

(3/4/53)

KXLR, N. LITTLE ROCK, ARK.

1kw, 5kw-LS, DA-N

1150 kc



KXLR

HORIZONTAL RADIATION PATTERN
MEASURED

ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6
PHASE DEG	0°	161.9°	-37.6°	124.2°		
HEIGHT DEG	90°	90°	90°	90°		
FIELD RATIO	1.0	2.26	2.26	1.0		
HOW OR ANT						
IN-LINE ARRAY BEARING N 60° E TRUE				SPACING 90°		

FREQUENCY 1150 KC
 ASSIGNMENT 5 KW-LS, 1 KW-N(DA)
 LONGITUDE 92 DEG 11 MIN 51 SEC
 LATITUDE 54 DEG 45 MIN 55 SEC
 WHEN USED NIGHTTIME
 RMS FIELD 179 MV/M (MEASURED)
 DATE DECEMBER 1952

ROBERT M. SILLIMAN
 CONSULTING RADIO ENGINEERS
 WASHINGTON, D. C.

FCC File No. BL-4904 Date Accepted 2/16/53

KXLR, N. Little Rock, Ark. 1150 kc

KXLR


MEASURED
NIGHT NULLS

(3/4/53)

KXLR, N. LITTLE ROCK, ARK.


1kw, 5kw-LS, DA-N

1150 kc



KXLR HORIZONTAL RADIATION PATTERN ENLARGED VIEW (MEASURED)						FREQUENCY 1150 KC ASSIGNMENT 5 KW-LS, 1 KW-N(DA) LONGITUDE 92 DEG 11 MIN 51 SEC LATITUDE 34 DEG 45 MIN 53 SEC WHEN USED NIGHTTIME RMS FIELD 179 MV/M (MEASURED) DATE DECEMBER 1952
S.W.		N.E.				
ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6
PHASE DEG.	0°	161.9°	-37.6°	124.2°		
HEIGHT DEG.	90°	90°	90°	90°		
FIELD RATIO	1.0	2.26	2.26	1.0		
NON-DA ANT.	*					
IN-LINE ARRAY BEARING 160° E TRUE				SPACING 90°		
ROBERT M. SALLIMAN CONSULTING RADIO ENGINEERS WASHINGTON, D. C.						

MEASURED KXLR, N. LITTLE ROCK, ARK. 1kw, 5kw-LS, DA-N 1150 kc
 NON-D.A. (NON-D.A.) 3/4/53



KXLR

HORIZONTAL RADIATION PATTERN
 NON-DIRECTIONAL (MEASURED)

FREQUENCY 1150 KC
 ASSIGNMENT 5 KW-LS, 1 KW-N(DA)
 LONGITUDE 92 DEG 11 MIN 51 SEC
 LATITUDE 34 DEG 45 MIN 55 SEC
 WHEN USED DAYTIME
 RMS FIELD 427 MV/M (MEASURED)
 DATE DECEMBER 1952

ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6
PHASE DEG						
HEIGHT DEG						
FIELD RATIO						
NON DA ANT	*					

ROBERT M. SILLIMAN
 CONSULTING RADIO ENGINEER
 WASHINGTON, D. C.


WCEN

Measured Night
(6-27-69ct)

Station WCEN
Mt. Pleasant, Michigan

500w, 1kw-LS, DA-N, U
1150 kc

-12360
anted
sense
using
angle



RMS - 127.4 Mv/M
MEOV
10X -----

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 6	STATION DATA
6.85° T. #3 0.549/-156° #2 1.000/0.0° #1 0.618/+156°	TOWER No. 1 2 3 4 5 6 7 8 9 10	ELECTRICAL HEIGHT G° 5° 5° 5° 5° 5° 5° 5° 5° 5°	SPACING S° 5° 5° 5° 5° 5° 5° 5° 5° 5°	PHASING P° 5° 5° 5° 5° 5° 5° 5° 5° 5°	FIELD RATIO F 5° 5° 5° 5° 5° 5° 5° 5° 5° 5°	MEASURED NIGHTTIME PATTERN ***** WCEN MOUNT PLEASANT MICHIGAN 0° - 0°	CALL WCEN FREQ 1150 KHz. POWER 0.5 Kw TYPE DA-N TIME UNLIMITED LAT. 43-34-36 LONG. 84-45-57 E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
DAYTIME OPERATION ☐					NIGHTTIME OPERATION ☒		

FCC File No. BL-12360
Accepted 5-28-69

Station WCEN
Mt. Pleasant, Michigan

1150 kc


WCEN

Measured Non-DA
(6-27-69ct)

Station WCEN
Mt. Pleasant, Michigan

500w, 1kw-LS, DA-N, U
1150 kc

BL 12360
Granted
license
covering
change 7/28/69



RMS = 196.4 mV/m^{10°}
MEOV

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 1	STATION DATA	
6.85°T #3 ○ NU #2 ○ S NU #1 ● NDA G's=90.5° s=70°	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	MEASURED NON-DIRECTIONAL PATTERN ***** WCEN MOUNT PLEASANT MICHIGAN θ° = 0°	CALL	WCEN
	No.	G'	S'	P'	F		FREQ	1150 kHz.
	1						POWER	1.0 Kw
	2						TYPE	DA-N
	3						TIME	UNLIMITED
	4						LAT.	43-34-36
	5						LONG.	84-45-57
	6						E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.	
	7							
	8							
	9							
	10							
DAYTIME OPERATION ☒					NIGHTTIME OPERATION ☐			

FCC File No. BL-12360
Accepted 5-28-69

Station WCEN
Mt. Pleasant, Michigan

1150 kc


WCEN

Proposed Night
(10-28-68ct)

Station WCEN
Mt. Pleasant, Michigan

500w, 1kw-LS, DA-N, U
1150 kc

*Granted 10/16/68
P to make
changes in
antenna
system*



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 4	STATION DATA	
#3 6.85' 1.00/57.4' #2 1.79/208.7' #1 1.00/0' 90° 70'	TOWER	ELECTRICAL WEIGHT	SPACING	PHASING	FIELD RATIO	PROPOSED NIGHTTIME PATTERN ***** WCEN MOUNT PLEASANT, MICHIGAN E ⁰ 0'	CALL WCEN FREQ 1150 KHz. POWER 0.5 Kw TYPE DA-N TIME UNLIMITED LAT. N-43-34-36 LONG. W-84-45-57	
	1	6"	5"	4"	1			
	2							
	3							
	4							
	5							
	6							
	7							
	8							
	9							
10								

FCC File No. BP-18344
Accepted 10-11-68

Station WCEN
Mt. Pleasant, Michigan

1150 kc



WCOP

Proposed Day
(1-29-64ct)

Station WCOP
Boston, Massachusetts

5kw, DA-2, U
1150 kc

1-22-64
granted CP to
make changes
in antenna system
SEE MEASURED



FCC File No. BP-16053
Accepted 1-9-64

Station WCOP
Boston, Massachusetts

FIGURE 4
DAYTIME HORIZONTAL PLANE
PLOUGH BROADCASTING COMPANY, INC.
WCOP 5 KW-U, DA-2 1150 KC
BOSTON, MASSACHUSETTS
Prepared by
Lohnes and Culver Washington 4, D.C.
September 1963 1150 kc

WHUE



WCOP

Measured Day
(11-27-64ct)

Station WCOP
Boston, Massachusetts

5kw, DA-2, U
1150 kc

BL-10669
GRANTED
12-31-64



42° 24' 49"
71° 12' 40"

FIGURE 8
MEASURED RADIATION PATTERN
(DA-D OPERATION)
PLOUGH BROADCASTING COMPANY, INC.
WCOP 5 KW-U, DA-2 1150 KC
BOSTON, MASSACHUSETTS
Prepared by
Lohnes and Culver Washington, D. C.
May 1964
1150 kc

FCC File No. BL-10669
Accepted 11-6-64

Station WCOP
Boston, Massachusetts

W HUE WCOP

Proposed Night
(1-29-64ct)

Station WCOP
Boston, Massachusetts

5kw, DA-2, U
1150 kc

1-22-64
3 wanted CPT
made changes
in antenna system.
SEE MEASURED





FIGURE 1
NIGHTTIME HORIZONTAL PLANE
RADIATION PATTERN
PLOUGH BROADCASTING COMPANY, INC.
WCOP 5 KW-U, DA-2 1150 KC
BOSTON, MASSACHUSETTS

Prepared by
Lohnes and Culver Washington 4, D.C.
September 1963 1150 kc

FCC File No. PB-16053
Accepted 1-9-64

Station WCOP
Boston, Massachusetts

Measured Night
(11-27-64ct)

Station WCOP
Boston, Massachusetts

WAVE **WCOP**
5kw, DA-2, U
1150 kc

3L-10669
GRANTED
12-31-64





FIGURE 9
MEASURED RADIATION PATTERN
(DA-N OPERATION)
PLOUGH BROADCASTING COMPANY, INC.
WCOP 5 KW-U, DA-2 1150 KC
BOSTON, MASSACHUSETTS

Prepared by
Lohnes and Culver Washington, D. C.

FCC File No. BL-10669
Accepted 11-6-64

Station WCOP
Boston, Massachusetts


May 1964
1150 kc

Measured Non-DA
(11-27-64ct)

Station WCOP
Boston, Massachusetts

WCOP
5kw, DA-2, U
1150 kc

BL-10669
GRANTED
12-31-64



42° 24' 49"
71° 12' 40"

FIGURE 7
NON-DIRECTIONAL RADIATION PATTERN
(5 KW TEST OPERATION)
PLOUGH BROADCASTING COMPANY, INC.
WCOP 5 KW-U, DA-2 1150 KC
BOSTON, MASSACHUSETTS

Prepared by
Lohnes and Culver Washington, D. C.

May 1964

FCC File No. BL-10669
Accepted 11-6-64

Station WCOP
Boston, Massachusetts

1150 kc

1150 KC



Granted change
of operation
12/19/56





FIG. 2
PROPOSED NIGHTTIME HORIZONTAL
RADIATION PATTERN
($\theta = 90^\circ$)
WCRK 1150KC 1KW, 500W DA-N
MORRISTOWN, TENN.

WCRK

MEASURED NIGHT
(10/30/57g)

Station WCRK 500w, 1kw-LS, DA-N, U
Morristown, ~~Pennsylvania~~ Tenn. 1150 KC



*Granted license
11/21/57 for change
in facilities & instal.
of DA system*





FIG 19 (AMENDED)
MEASURED NIGHTTIME HORIZONTAL
RADIATION PATTERN
WCRK 1150 KC 0.5-1KW DA-N
MORRISTOWN, TENN.

FCC File No. BL-6783
Accepted 10/16/57

WCRK
Morristown, Pennsylvania

1150 KC

5

WCRK

MEASURED NIGHT NULL
(10/30/57g)

Station WCRK 500w, 1kw - LS, DA-N, U
Morristown, Pennsylvania Tenn 1150 KC



*Granted license
11/21/57*




FIG. 20 (AMENDED)
MEASURED NIGHTTIME HORIZONTAL
RADIATION PATTERN
(EXPANDED SCALE)
WCRK 1150 KC 0.5-1 KW DA-N
MORRISTOWN, TENN.

FCC File No. BL-6783
Accepted 10/16/57

WCRK
Morristown, Pennsylvania

1150 KC

WCRK

MEASURED NON-DA
(10/30/57g)

Station WCRK 500w, 1kw-LS, DA-N, U
Morristown, Pennsylvania Tenn 1150 KC



*graphed by
12/21/57*




FIG. 20
MEASURED NON-DIRECTIONAL DAYTIME
HORIZONTAL RADIATION PATTERN
WCRK 1150 KC 0.5-1 KW DA-N
MORRISTOWN, TENN.

PROPOSED
DAY

NEW, AKRON, OHIO
Akron Bg. Corp.

WCUE AKRON, O

2/21/49

1kw, D, DA

NEW-1150 KC

2/23/49G

330°

340°

350°

10°

20°

30°

320°

310°

300°

290°

280°

270°

260°

250°

240°

230°

220°

40°

50°

60°

70°

80°

90°

100°

110°

120°

130°

140°

① — 194° — ② — 85.5° TRUE →
1/20° 1.3/12°
G = 105° = 250'

SITE: 41° 07' 30" N
81° 31' 14" W



R & C - 2/49

MY/M
300

200

100

CRUC
88 MI

RMS-177 MV/M

MEOV

WIMA
139 MI

WRPA
98 MI

FIGURE 1

PROPOSED HORIZONTAL PLANE RADIATION PATTERN

NEW STATION

AKRON BROADCASTING CORPORATION
AKRON, OHIO

1150 kc - 1 kw - D - DA

A. D. RING & Co.

CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

RING
&
CLARK
12/45

210°

200°

190°

180°

170°

160°


150°

MEASURED
DAYTIME

WCUE, AKRON, OHIO

1kw, DA, D

WCUE - 1150 KC




Measured Night
(8-27-65ct)

Station WCUE
Cuyahoga Falls, Ohio

WCUE
500w, 1kw-LS, DA-2, U
1150 kc

EUBENE DIETZGEN CO.
MADE IN U.S.A.

NO. 340R-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE




FCC File No. BZ-2712
Accepted 8-2-65

Station WCUE
Cuyahoga Falls, Ohio

1150 kc

WCUE

4-18-63
granted modification
of CP to make changes
in nighttime DA pattern.



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
		TOWER No.	ELECTRICAL HEIGHT h	TRUE TOWER ORIENTATION θ	SPACING r	PHASING φ	HORIZONTAL FIELD E _h	FIELD RATIO F	ELEV. ANGLE θ	ELEVATION PER FIELD E _h	CALL WCUE
		1	90	65	232.2	74	1.0	1.0	0	130	FREQUENCY 1150
		2	90	44.5	187.4	187.4	1.0	1.0	10	10	POWER 0.5
		3	90	0	0	0	1.838	1.838	20	20	TIME OF OPERATION U
		4	90	340	90	180	1.838	1.838	30	30	TYPE OF OPERATION DA-2
		5	90	245	232.2	-74	1.0	1.0	40	40	DAYTIME TOWERS 2
		6	90	300	172.6	172.6	1.0	1.0	50	50	NIGHTTIME TOWERS 6
		7	90	300	172.6	172.6	1.0	1.0	60	60	Nb. RADIALS PER TOWER 120
		8	90	300	172.6	172.6	1.0	1.0	70	70	LENGTH OF RADIALS 90° 214'
		9	90	300	172.6	172.6	1.0	1.0	80	80	GROUND SCREEN DIMENSION
		10	90	300	172.6	172.6	1.0	1.0	90	90	LAT. 41° 12' 05"
										LAT. 81° 31' 25"	
										LONG. 81° 31' 25"	
										SUPERSEDES 601000	
										PATTERN No. 630327	

FIG. 3.1

CALCULATED NIGHT HORIZONTAL PATTERNS

Carl E. Smith
Consulting Radio Engineers


WCUE Radio, Inc.
Cuyahoga Falls, Ohio
1150 kc, 500 w, 1 kw-LS, U, DA-D 630327

WCUE

Measured Non-DA
(6-28-63ct)

Station WCUE
Cuyahoga Falls, Ohio

500w, 1kw-LS, DA-2, U
1150 kc




TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
	TOWER No.	ELECTRICAL HEIGHT G'	TRUE TOWER ORIENTATION B°	SPACING S'	PHASING V°	HORIZONTAL FIELD mV/m E	FIELD RATIO F	ELEV. ANGLE θ°	ELEVATION RMS FIELD mV/m E _θ	CALL WCUE	
	1								136	FREQUENCY 1160	
	2								10	POWER 0.5	
	3	90							20	TIME OF OPERATION U	
	4								30	TYPE OF OPERATION DA-2	
	5								40	DAYTIME TOWERS 2	
	6								50	NIGHTTIME TOWERS 0	
	7								60	NO RADIALS PER TOWER 120	
	8								70	LENGTH OF RADIALS 90	
	9								80	GROUND SCREEN DIMENSION 24 x 24	
DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☐									LAT. 41° 12' 05"		
									LONG. 81° 31' 25"		
									SUPERSEDES PATTERN NO. 630115		

FIG. 5.16
MEASURED ND HORIZONTAL PATTERN
WCUE Radio, Inc.
Cuyahoga Falls, Ohio
1150 kc 500 w, 1 kw-LS, U, DA-2

Carl E. Smith
Consulting Radio Engineers

WDEL
1150

AUG 9 1948



CALCULATED HORIZONTAL PLANE PATTERN
PROPOSED NIGHT OPERATION
WDEL-WILMINGTON, DEL.
1150 KC - 5 KW - DA-2


Amendment Recd. 8-3-48 BR-6222

1150 kc

3/29/49G

SITE: 39° 48' 54" N
75° 31' 47" W

SECRETARY AND WRATHAL
RADIO ENGINEERING
4470 10th, 10th St. S.W.
WASHINGTON, D.C.



WDEL, Wilmington, Del. 1150kc


WDEL

MEASURED
NIGHT

WDEL, WILMINGTON, DEL.

5kw, DA-2

1150 kc




WDEL

MEASURED
NIGHT NULLS


WDEL, WILMINGTON, DEL.

5kw, DA-2

1150 kc



WDEL
1150



CALCULATED HORIZONTAL PLANE PATTERN
PROPOSED DAY OPERATION
WDEL-WILMINGTON, DEL.
1150 KC - 5 KW - DA-2

Amendment Recd. 8-8-48 BP-6606


WDEL

MEASURED
DAY

WDEL, WILMINGTON, DEL.

5kw, DA-2

1150 kc




WDEL

MEASURED DAY NULLS
(10-24-58g)

Station WDEL
Wilmington, Delaware

5kw, DA-2,U
1150 KC



FCC File No. BZ-4048
Accepted 10-14-58

WDEL
Wilmington, Delaware


1150 KC

WDIX

~~WRNO~~PROPOSED
DAYWRNO, ORANGEBURG, S. C.
6/11/52G

500W, 5KW-LS, U, DA-2

1150 KC



APPL RECD 5/19/52 ACC 6/5/52 BP-8500

WRNO, ORANGEBURG, S. C.

1150 KC


WDIX

MEASURED DAY
(11/22/54G)

STATION WDIX
ORANGEBURG, S. C.

500 W, 5 KW
DA-2, U

1150 KC



File No. BL-5500

Accepted 10/29/54

STATION WDIX
ORANGEBURG, S.C.

1150 KC


WDIX

MEASURED NIGHT
(11/22/54G)

STATION WDIX
ORANGEBURG, S. C.

500 W, 5 KW
DA-2, U

1150 KC




File No. BL-5500

Accepted 10/29/54

STATION WDIX
ORANGEBURG, S.C.


1150 KC

1150 KC



1150 KC

1150 KC




WGBR

MEASURED DAY
(4-9-56G)

STATION WGBR
GOLDSBORO, NORTH CAROLINA

1KW-N, 5KW-D
DA-2, U

1150 KC




MEASURED
NIGHT NULLS
9/19/51G

WGBR, GOLDSBORO, N.C.

1 kw, U, DA-2

1150 KC

WGBR



APPL RECD 8/31/51

BL-4531

WGBR, GOLDSBORO, N.C.

1150 KC


WGBR

MEASURED
NIGHT
9/19/51G

WGBR, GOLDSBORO, N.C.

1 kw, U, DA-2

1150 KC



WGER, Goldsboro, N. C. 1150 kc


WGBR

PROPOSED
NIGHT NULLS

WGBR, GOLDSBORO, N. C.

1kw, DA-2

1150 kc




WGBR, Goldsboro, N. C. 1150 kc

MEASURED
NON-DA
9/19/51G

WGBR, GOLDSBORO, N.C.

1 KW, U, DA-2

WGBR
1150 KC



WGGH


PROPOSED DAY
(7-18-55G)

WGGH, MARION,
ILLINOIS

5 KW
DA-D, D

ARC TOWER
EQ. AS HT. 316

1150 KC
NQ




WGGH

MEASURED
DAY (2/29/56g)

STATION WGGH
MARION, ILLINOIS

5 KW
DA-D,D

1150 KC




WGGH

MEASURED
NON-DA (2/29/56g)

STATION WGGH
MARION, ILLINOIS

5 KW
DA-D,D


1150 KC



Measured Night
(3-27-70ct)


Station WGOW
Chattanooga, Tennessee

WGOW
1kw, 5kw-LS, DA-N, U
1150 kc



HORIZONTAL RADIATION PATTERN

SHADING AND ORIENTATION



APPLICANT TURNER ADVERTISING COMPANY
LOCATION CHATTANOOGA, TENN. WGOW
FREQUENCY 1150 KES
POWER 1 KW-LS, 1 KW-N, 1 KW-U
LATITUDE 35° DEG 04' MIN 00 SEC
LONGITUDE 83° DEG 07' MIN 00 SEC
WHEN USED NIGHTTIME
RMS FIELD 100 DBM
DATE 3-27-70

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-12507
Accepted 2-25-70


Station WGOW
Chattanooga, Tennessee

1150 k

Measured Non-DA
(3-27-70ct)

Station WGOW
Chattanooga, Tennessee

WGOW
1kw, 5kw-LS, DA-N, U
1150 kc



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT: *Chattanooga, Tennessee*
 LOCATION: *Chattanooga, Tennessee*
 FREQUENCY: *1150 KC*
 POWER: *1 KW*
 LATITUDE: *35° 00' 00" N*
 LONGITUDE: *83° 00' 00" W*
 WHEN USED: *3-27-70*
 NAME FILED: *3-27-70*
 DATE: *3-27-70*

SILLIMAN, MOFFET & KOWALSKI
 CONSULTING RADIO ENGINEERS
 WASHINGTON, D.C.

FCC File No. BL-12507
Accepted 2-25-70


Station WGOW
Chattanooga, Tennessee

1150 kc

1kw,5kw-LS,DA-N,U
1150 kc

1150 kc

330"
30"



-14-62
anted MIP
increase
weight




Fig. 1
Directional Antenna Pattern
Proposed New Station,
Gaithersburg, Md.
1150kc 1 kw DA-D
November 1956

Gaithersburg 174


WHMC

PROPOSED NIGHT
(10/11/57g)

New; Nick J. Chaconas
Gaithersburg, Maryland

500W, 1kw-LS, DA-2, U
1150 KC

12-7-60
ranked CF for
new station
7-14-62
granted MCP
increase height



FCC File No. BP-10,996
Accepted 10/1/57 (Amended)

Nick J. Chaconas
Gaithersburg, Maryland

1150 KC

WHMC

Measured Night
(2-26-63ct)


Station WHMC
Gaithersburg, Maryland

500w, 1kw-LS, DA-2, U
1150 kc

3-16-64
Grant
license
for new
station

EUGENE E. HUGEN, C.E.

NO. 3409 P. DIEZEL, GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-9737
Accepted 2-18-63

Station WHMC
Gaithersburg, Maryland

1150 kc

WHMC


Measured Non-DA
(2-26-63ct)

Station WHMC
Gaithersburg, Maryland

500w, 1kw-LS, DA-2, U
1150 kc

3-16-64
Quoted
for
New station

NO. 3109 P. DIETZGEN GRAPH MAPS
FIDELITY, INC. QUINCY, ILL.



GREUTZ & SNOWBERGER
Consulting Engineers
724-14TH STREET, NORTHWEST
WASHINGTON, D. C.

Figure 11 (Amended)
Measured Non-Directional Pattern
Radio Station WHMC
Gaithersburg, Maryland
1150Kc 0.5/1Kw DA-2
September 1962

FCC File No. BL-9737
Accepted 2-18-63

Station WHMC
Gaithersburg, Maryland

1150 kc

WHMC

Measured Day
(2-26-63ct)


Station WHMC
Gaithersburg, Maryland

500w, 1kw-LS, DA-2, U
1150 kc

3-16-64
wanted
license
for new
station

EUGENE CREUTZ, INC.

NO. 3400 DIST. CO. CO-ORDINAT



WIMA

July 7, 1971 K & E

SUPPLEMENTAL
DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WIMA

Main Studio: Lima, Ohio

Frequency: 1150 kHz

Power: 1 kw

Notification List No. 1417

Date: March 24, 1971 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 40° 40' 46"

West Longitude: 84° 06' 34"

Predicted effective Day Field: (omnidirectional) 197 mv/m at rated power.

Note: Please retain the description sheet and directional antenna radiation patterns notified for station WIMA in United States Change List Number 295, dated October 27, 1948 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates of the center of the antenna system.



CTR NO 30883A4

FER73
BP-19149
D. B ADD
WECV

DUPLICATE

COHEN & DIPPILL
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON, D. C. 20004

WIMA



COMPUTED
HORIZONTAL PLANE RADIATION PATTERN
FOR THE PRESENT NIGHTTIME OPERATION OF
WIMA, LIMA, OHIO
1150 kHz - 1 Kw - DA-N U
NOVEMBER 1971


NORTH LATITUDE 40° 40' 46.5"
WEST LONGITUDE 84° 06' 34"


40-40-32
84-06-32

WIMA


WIMA 1150 KC

GEORGE C. DAVIS
CONSULTING RADIO ENGINEER
WASHINGTON 4, D. C.






WIMA 1150 KC




WIMA 1150 KC


GEORGE C. DAVIS
CONSULTING RADIO ENGINEER
WASHINGTON 4, D. C.



WIMA 1150 KC



acted CP
13/59 to
range
station - trans
cation to
0° 27' 47"
31° 16' 10"



MONROE & CHAMBERS
RADIO ENGINEERS
WASHINGTON, D.C.


WJBO
PROPOSED HORIZONTAL PLANE
RADIATION PATTERN
5000 WATTS - 1120 KC
7-3-40

RMS FIELD
492 MV/M

1.5/0°
41/±6°
16/±41°

NORTH LATITUDE 10 37.47
WEST LONGITUDE 91 16.10

GEORGE C. DAVIS
CONSULTING ENGINEER
RADIO-TELEVISION
WASHINGTON 4, D. C.



1 / 0° 2.7 / +5° 1.08 / +27°
 185° 185° N 7° E →
 H = 94° H = 196° H = 94°

COMPUTED
HORIZONTAL PLANE PATTERN
WJBO, BATON ROUGE, LOUISIANA
1150 KC, 5 KW, DA-1
OCTOBER 1959


VVJBU

Baseline

CLEVELAND INSTITUTE OF RADIO ELECTRONICS
CLEVELAND OHIO

NO. 10 H

POLAR CO-ORDINATE
MAG. IN DB



CP VALUES

	MV/M	MB
N10°E 190 MV/M	170	
N45°E 182 MV/M	170	
N130°E 600 MV/M	570	
N330°E 177 MV/M	170	

*Granted CP
3/3/59 to change
con.*

NL	30° 25' 25"	30° 27' 47"
WL	91° 10' 30"	91° 16' 10"

*delete from - 1405
Send to info*

RMS - 495 MV/M




FIGURE
Measured Horizontal Radiation Pattern
WJBO Baton Rouge, La.
1150 KC, 5kw, DA-1, U
June 1954

2-2011


MEASURED DAY & NIGHT
(1-17-61g)

Station WJBO
Baton Rouge, Louisiana

5kw, DA-1, U
1150 KC

North Latitude 30° 27' 47"
West Longitude 91° 16' 10"

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4 D C



1/0° 2.7/±5° 1.08/±27°
 185° 185° N 7° E
 H = 94° H = 196° H = 94°

MEASURED HORIZONTAL PLANE PATTERN
WJBO - 1150 KC - 5 KW - DA-1
BATON ROUGE, LOUISIANA
SEPTEMBER 1959

FCC File No. BL-7728
Accepted 11-30-59

WJBO
Baton Rouge, Louisiana

1150 KC


granted 4-6-6-60

MEASURED NON-DA
(12-21-59g)

Station WJBO
Baton Rouge, Louisiana

5kw, DA-1, U
1150 KC

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.



NORTH LATITUDE 30° 27' 47"
WEST LONGITUDE 91° 16' 10"

MEASURED HORIZONTAL PLANE PATTERN
1 KW NON-DIRECTIONAL OPERATION
WJBO - 1150 KC - BATON ROUGE, LOUISIANA
SEPTEMBER 1959

FCC File No. BL-7728
Accepted 11-30-59

WJBO
Baton Rouge, Louisiana

1150 KC

6660

WJRD

PROPOSED
NIGHT


WJRD, TUSCALOOSA, ALA.

N

150°
10

1kw, 5kw-LS, DAN

1150 kc




Rec'd 11-25-46 APR 6 20 1948 G

WJRD 1150

N 4-5-48

May 1 1948




MEASURED NIGHT

Station WARD
Tuscaloosa, Alabama

11, 12, 13, 14, 15, 16
1150 KC

VV JRD




MEASURED NIGHT NULLS

Station WJRD
Tuscaloosa, Alabama

1kw, 5kw-LS, DA-N, U
1150 KC

WJRD




Rockford, Ill.

WJCL

PROPOSED DAY Town & Country Radio, Inc. 500 W. DA-d, D
(12-18-56g) Rockford, Illinois

1150 KC

Granted CP for new Sta. 2-3-60




FCC File No. Accepted 11-29-56 Town & Country Radio, Inc.
BP-10,484(Amended) Docket #11835 Rockford, Illinois 1150 KC

MEASURED DAY
(7-29-60g)

Station WJRL
Rockford, Illinois

500w, DA-D,D
1150 kc

1-7-60
series L for
all stations



FCC File No. BL-7985
Accepted 7-12-60

WJRL
Rockford, Illinois


1150 kc

MEASURED NON-DA
(7-29-60g)

Station WJRL
Rockford, Illinois

500w, DA-D,D
1150 kc

North Latitude 42° 14' 26"
West Longitude 89° 01' 47"



NON-DIRECTIONAL PROOF OF PERFORMANCE
FOR RADIO STATION WJRL ROCKFORD, ILL.
ON 1150 KCS WITH 500 WATTS, DA-DAYTIME
USING CENTER TOWER WITH 500 WATTS
BP-10,484
RALPH J. BITZER, CONSULTING RADIO ENG.

FCC File No. BL-7985
Accepted 7-12-60

WJRL
Rockford, Illinois

1150 kc


WKPA

Proposed Day
(5-27-66ct)

Station WKPA
New Kensington, Pennsylvania


1kw, DA-D, D
1150 kc

-P CHG DA-SYS
6-2-66



LATITUDE 40° 34' 24"
LONGITUDE 79° 46' 58"

ANTENNA PARAMETERS



G₁ = 187.2° / 445
G₂ = 347.5° / 225

FIGURE 1
HORIZONTAL POLAR PATTERN

RADIO STATION WKPA
NEW KENSINGTON, PENNA.

1150 KC

1 KW, DA-D, D

JOHN H. MULLANEY
AND
ASSOCIATES

A DIVISION OF MULTONICS INC.

FCC File No. BP-17212
Accepted 5-6-66

Station WKPA
New Kensington, Pennsylvania

1150 kc

WKPA

Measured Day
(2-28-68ct)

Station WKPA
New Kensington, Pennsylvania

1kw, DA-D, D
1150 kc


3-13-68
GRANTED
LICENSE
COV. CHANGE
IN ANTENNA
SYSTEM

THEORETICAL PARAMETERS:

- #1 1.0 $\angle 0^\circ$
- #2 0.825 $\angle 166^\circ$

MEASURED PARAMETERS:

- #1 1.0 $\angle 0^\circ$
- #2 0.807 $\angle 108^\circ$




$E_{RMS} = 180 \text{ MV/M}$

LATITUDE 40° 34' 24"
LONGITUDE 79° 46' 58"

JOHN H. MULLANEY
AND
ASSOCIATES

ANTENNA PARAMETERS



$G_1 = 187.2^\circ / 44.5'$
 $G_2 = 94.7^\circ / 22.5'$

FIGURE 1
HORIZONTAL POLAR PATTERN
(MEASURED)

RADIO STATION WKPA
NEW KENSINGTON, PENNA.

1150KC

1 KW, DA-D, D

JULY 1967

FCC File No. BL-11742
Accepted 2-7-68

Station WKPA
New Kensington, Pennsylvania

1150 kc

MEASURED NON-DA
(5-8-58g)


Station WKPA

1kw, DA-D,D

NEW Kensington, Pennsylvania

1150 KC

NL 40° 34' 24"
WL 79° 46' 58"



FCC File No. BL-7099
Accepted 4-25-58

WKPA
Kensington, Pennsylvania

1150 KC


WNDB

MEASURED
NIGHT

WNDB, DAYTONA BEACH, FLA.
3/19/52G

1 KW, U, DA-N


1150 KC



APPL RECD 2/15/52 ACC 3/14/52 BL-4675

WNDB, DAYTONA BEACH, FLA.

1150 KC




WNDB

MEASURED
NON-DA

WNDB, DAYTONA BEACH, FLA.
3/19/52G

1 KW, U, DA-N

1150 KC



APPL RECD 2/15/52 ACC 3/14/52 BL-4675

WNDB, DAYTONA BEACH, FLA.


1150 KC

DAY HORIZONTAL PLANE RADIATION

PROP. 1150 KC, 5 KW-D, 1 KW-N, DA-2
UTICA-ROME, N. Y.

PAUL GODLEY CO.
CONSULTING RADIO ENGINEERS
LABORATORIES: GREAT NOTCH, N.J. 11/46

FIG. 6



WRUN




MEASURED
DAY

WRUN, UTICA, N. Y.

1kw, 5kw-LS, DA-2

1150 kc

7/14/49G



SITE: 43° 10' 31" N
75° 21' 03" W

WRUN

PROPOSED
NIGHT


WRUN, UTICA, NY

11/22/48G

11-18-48L

1kw, 5kw-LS, DA2

1150 kc



WRUN

PROPOSED
NIGHT
NULLS

WRUN, UTICA, NY

11/22/48G


1kw, 5kw-LS, DA2

1150 kc

30° 330° 20° 340° 10° 350° 350° 10° 340° 20° 330° 30°

11-18-48

--- MAXIMUM EXPECTED OPERATING VALUE

SITE: 43° 10' 31" N. Lat.
75° 21' 03" W. Long.

WRUN


MEASURED
NIGHT

WRUN, UTICA, N. Y.

1kw, 5kw-LS, DA-2

1150 kc

7/14/49G



AMENDMENT RECD 7-11-49 BL-3291

WRUN, Utica, N. Y. 1150 kc


WRUN

MEASURED
NIGHT NULLS

WRUN, UTICA, N. Y.

1kw, 5kw-LS, DA-2

1150 kc



AMENDMENT RECD 7-11-49 BL-3291

WRUN, Utica, N. Y. 1150 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WTAW Main Studio: College Station, Texas
 Frequency : 1150 kHz Power : 0.5kw Night 1kw Day
 Notification List No.: 1753 Date : October 13, 1977 Class: 1

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 30° 38' 05"
 West Longitude: 96° 21' 20"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 3
 Type of elements : Towers #1 and #3 are series excited, uniform cross-section, guyed. Tower #2 is shunt excited folded unipole, self supporting, tapered. All are vertical steel towers.

TOWER	N(#1)	SW(#2)	SE(#3)
HEIGHT ABOVE INSULATORS :	142'	222' (93.4°)	142' (60°)
NIGHT PHASING:	0°	-93.0°	+95.0°
NIGHT FIELD RATIO :	1	1.020	0.776

SPACING AND

ORIENTATION: From reference tower #1, tower #2 is located 278.0' (117.0°) on line a/bearing 194.0° true, and tower #3 is located 412.8' (173.7°) on a line bearing 173.5° true.

GROUND SYSTEM: 120 - 310' equally spaced copper radials about tower #2, 120-80' to 300' copper radials about tower #1 and #3, plus a 24' square ground screen about towers #1 and #3. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of system are bonded together.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	<u>RMS</u>	THEORETICAL	<u>RSS</u>	STANDARD <u>RMS</u>
Day	192	mv/m		
Night	133.31	mv/m	165.83 mv/m	139.98 mv/m

Note: This notification concerns only a change to add new nighttime operation with Daytime operation continued as previously notified.



LATITUDE: 30° 38' 05"
LONGITUDE: 96° 21' 20"




LBA

LAWRENCE BEHR ASSOCIATES, INC.

GREENVILLE, N C 20894

ANTENNA PARAMETERS


$$\begin{aligned} S_1 &= 117^\circ \\ S_2 &= 173.7^\circ \\ G_2 &= 93.4^\circ \\ G_3 * G_3 &= 60^\circ \end{aligned}$$

RSS_{TH}/RMS_{TH}	=	1.244
RSS_{TH}	=	165.831
RSS_{STD}	=	174.122
RMS_{TH}	=	133.310
RMS_{STD}	=	139.976
$R(1,2,3)$	=	1.0 OHMS

FIGURE 9A

PROPOSED STANDARD NIGHTTIME HORIZONTAL PATTERN

RADIO BRYAN, INC.
RADIO STATION WTAW
COLLEGE STATION, TEXAS

1150 KHZ; 1.00/0.5N

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WTMP Main Studio: Temple Terrace, Florida
 Frequency: 1150 kHz Power: 2.5kw Night 5 kw Day
 Notification List No. 1781 Date: October 19, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS
OF THE ANTENNA SYSTEMS:

DAYTIME			NIGHTTIME		
North Latitude:	27° 56' 51"		North Latitude:	28° 03' 49"	
West Longitude:	82° 23' 50"		West Longitude:	82° 18' 43"	

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-2)
 Number of elements: 6
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	#1	#2	#3	#4	#5	#6
HEIGHT ABOVE INSULATORS:	1,237.98'	6332.1(136°)	1237.98'	1237.98'	1237.98'	1237.98'(100.17°)
NIGHT PHASING:	0	-21.48°	-19.43°	-22.87°	-0.04°	-.83
NIGHT FIELD RATIO:	1	1.419	3.308	1.677	1.926	2.4

SPACING AND
ORIENTATION:

With tower #1 as reference, tower #2 is spaced 253.74°
 on a line bearing 214° true, tower #3 is spaced 263.75°
 on a line bearing 291.32° true, tower #4 is spaced 417.94°
 on a line bearing 313.95° true, tower #5 is spaced 342.13°
 on a line bearing 347.98° true, tower #6 is spaced 169.63°
 on a line bearing .03° true

GROUND SYSTEM:

120 - 215' equally spaced copper radials plus
 120 - 50' interspaced radials about each tower.
 Radials are shortened and bonded to copper straps
 along intersections between towers.

100.17° 257.98'
 136° 325.11'

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day 1/	400 mv/m		
Night	<u>341.05</u> mv/m	<u>600.9</u> mv.m	<u>358.10</u> mv/m

Note: Please retain the Daytime directional antenna radiation pattern notified for Station WIOK in United States Change List Number 708 dated May 29, 1957 and attach to this Revised Description Sheet and Nighttime pattern. This notification concerns only a change in the Nighttime operation of the station with Daytime operation continued as previously notified.


CTR NO

Geographic Coordinates:

N. Lat. 28° 03' 49"
W. Long. 82° 18' 43"

STANDARD PATTERN

WTMP



RSS_{ch} = 600.9
RMS_{ch} = 341.05 mv/m

RSS_{std} = 630.945
RMS_{std} = 358.10 mv/m

ANGLE	FIELD	SPACING	AZIMUTH	ANGLE
DEGREES	RATIO	DEGREES	DEGREES	DEGREES
0.00	1.000	0.00	0.00	0.00
1.00	1.019	253.74	241.00	-21.48
2.00	1.108	338.75	291.31	-19.67
3.00	1.277	417.99	313.96	-12.87
4.00	1.526	342.13	347.95	-0.13
5.00	2.498	189.65	0.00	-0.00

PROPOSED NIGHTTIME
RADIO STATION WTMP
TEMPLE TERRACE, FLA.,
1150KHz 2.5KW DA-2

JAMES M. JOHNSON & ASSOCIATES
RADIO ENGINEERING
5912 Barbados Way West
West Palm Beach, Florida 33407

FIGURE 9


TAMPA, FLA

WTMI

PROPOSED DAY Rounsaville of Charlotte, Inc.
(12-18-56g) Tampa, Florida

5 KW DA-D, D

1150 KC

*Granted CP 5/29/57 to change
from N-D to DA-D operation**grant license for increase
in power and installation of
DA.* $E_{RMS} = 400 \text{ MV/M}$

---- MEOV


LATITUDE: $27^{\circ} 56' 50.8''$
LONGITUDE: $82^{\circ} 23' 50''$ JOHN H. MULLANEY
CONSULTING RADIO ENGINEER
WASHINGTON, D. C. $G_2 = 90.5^{\circ}$
 $G_1, G_3 = 75.8^{\circ}$

FIGURE 4

DAYTIME
HORIZONTAL POLAR PATTERNRADIO STATION WIOK
TAMPA, FLORIDA

1150 KC

5 KW-DA-D

FCC File No.
BP-10,926

Accepted 12-10-56

Station, Rounsaville of Charlotte, Inc.
Tampa, Florida 1150 KC


WTMP

MEASURED DAY
(9-25-58g)

Station WTMP
Tampa, Florida

5kw, DA-D,D
1150 KC

*Granted license for increase in
power and DA-7-16-59*



ERMS = 398 MW/M

LATITUDE: 27° 56' 50.8"
LONGITUDE: 82° 23' 50"

JOHN H. MULLANEY
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.




FIGURE 20
MEASURED DAYTIME
HORIZONTAL POLAR PATTERN

RADIO STATION WTMP
TAMPA, FLORIDA

1150 KC

5 KW-DA-D

FCC File No. BL-7206
Accepted 9-18-58

WTMP
Tampa, Florida

1150 KC





FIGURE 1

WYFE

Proposed Day
(12-27-68ct)

Station WYFE
Rockford, Illinois

1kw, DA-D, D
1150 kc



FCC File No. BP-18292
Accepted 12-6-68

Station WYFE
Rockford, Illinois

1150 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

WYNE
1150kHz

Station: WYNE

Main Studio: Kimberly, Wisconsin

Frequency: 1150 kHz

Power: 5kw Night 5kw Day

Notification List No. 1785

Date: November 16, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 44° 08' 48"

West Longitude: 88° 28' 54"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation (DA-2)

Number of elements: 5

Type of elements: Series excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	N(#1)	NC(#2)	C(#3)	SC(#4)	S(#5)
HEIGHT ABOVE INSULATORS:	215'	215'	215'	215'	215' (90.5°)
NIGHT PHASING:	-130°	25°	180°	-25°	130°
NIGHT FIELD RATIO:	1.0	2.9425	3.97	2.9425	1.0
DAY PHASING:	-32°	102.32°	-117.01°	32°	---
DAY FIELD RATIO:	1.0	1.5392	1.1762	.3802	---


SPACING AND
ORIENTATION:Five towers in a row are spaced 237' (100°) on a line
bearing 20° true.

GROUND SYSTEM:

120 - 200' to equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap along
intersections between towers. Centers of system are bonded
together.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	428 mv/m	597.6 mv/m	449 mv/m
	430 mv/m	991.5 mv/m	452 mv/m




HORIZONTAL RADIATION PATTERN		Standard Pattern																		
	$E_{th}(RMS) = 428$ $E_{st}(RMS) = 450$ $E_{rss} = 597.6$	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr><td style="padding: 2px;">APPLICANT :</td><td style="padding: 2px;">WJNE</td></tr> <tr><td style="padding: 2px;">LOCATION :</td><td style="padding: 2px;">Kimberly, Wisconsin</td></tr> <tr><td style="padding: 2px;">FREQUENCY :</td><td style="padding: 2px;">1150 KC/S</td></tr> <tr><td style="padding: 2px;">POWER :</td><td style="padding: 2px;">5000 Watts</td></tr> <tr><td style="padding: 2px;">LATITUDE :</td><td style="padding: 2px;">44 DEG 08 MIN. 42 SEC.</td></tr> <tr><td style="padding: 2px;">LONGITUDE :</td><td style="padding: 2px;">88 DEG 22 MIN. 54 SEC.</td></tr> <tr><td style="padding: 2px;">WHEN USED:</td><td style="padding: 2px;">Daytime</td></tr> <tr><td style="padding: 2px;">R.M.S. FIELD:</td><td style="padding: 2px;">428 MV/M</td></tr> <tr><td style="padding: 2px;">DATE</td><td style="padding: 2px;">November 15th, 1977</td></tr> </table>	APPLICANT :	WJNE	LOCATION :	Kimberly, Wisconsin	FREQUENCY :	1150 KC/S	POWER :	5000 Watts	LATITUDE :	44 DEG 08 MIN. 42 SEC.	LONGITUDE :	88 DEG 22 MIN. 54 SEC.	WHEN USED:	Daytime	R.M.S. FIELD:	428 MV/M	DATE	November 15th, 1977
APPLICANT :	WJNE																			
LOCATION :	Kimberly, Wisconsin																			
FREQUENCY :	1150 KC/S																			
POWER :	5000 Watts																			
LATITUDE :	44 DEG 08 MIN. 42 SEC.																			
LONGITUDE :	88 DEG 22 MIN. 54 SEC.																			
WHEN USED:	Daytime																			
R.M.S. FIELD:	428 MV/M																			
DATE	November 15th, 1977																			
	A - 215/220' (90°)	RALPH J. BITZER CONSULTING RADIO ENGINEERS ST. LOUIS, MISSOURI																		

Standard Pattern



HORIZONTAL RADIATION PATTERN

Standard Pattern 0°



$E_{th}(RMS) = 430.0$

$E_{st}(RMS) = 452.3$

$E_{rss} = 991.5$

A - 215/220' (90°)

APPLICANT	WYNE
LOCATION	Kimberly, Wisconsin
FREQUENCY	1150 KC/S
POWER	5000 Watts
LATITUDE	41 DEG 08 MIN 48 SEC
LONGITUDE	88 DEG 28 MIN 34 SEC
WHEN USED	Middnight
RMS FIELD	100 MV/M
DATE	November 25th, 1950



RALPH J. BITZER
CONSULTING RADIO ENGINEERS
ST. LOUIS, MISSOURI

Proposed Day
(10-26-70ct)

Station WYNE
Appleton, Wisconsin

SEE REVERSE SIDE

WYNE
1kw, DA-D, D
1150 kc




DIRECTIONAL RADIATION PATTERN	
TOTAL RADIO, INC	
☐ MEASURED	☒ PROPOSED
FREQ: 1150 (KHZ)	POWER: 1.0 (KW)
N. LAT. 44° 11' 50"	☒ DA-D
W. LONG. 88° 30' 30"	☐ DA-N
☐ N-D	
LOCATION: Appleton, Wisconsin	
DATE: June 1969	
ROBERT A. JONES CONSULTING ENGINEERS LA GRANGE, ILLINOIS	

FCC File No. BP-18319
Accepted Amended 9-9-69

Station WYNE
Appleton, Wisconsin

1150 kc

WYNG
1kw, DA-0,0
1150 kc




1150 kc

Measured Non-DA
(10-26-70oct)

Station WYNE
Appleton, Wisconsin

WYNE
1kw, DA-D, D
1150 kc



FCC File No. BL-12730
Accepted 9-30-70

Station WYNE
Appleton, Wisconsin

1150 kc

WYNS


Lehigh Valley, Pa

PROPOSED DAY
(7-8-59g)

New Valley B/C Co.
Lehigh Valley, Pennsylvania

1kw, DA-D, D
1150 KC

61 Dated
7-27-60



FCC File No. BP-11651
Accepted 5-15-59 (Amended)

Valley Broadcasting Company
Lehigh Valley, Pennsylvania

1150 KC

WYNS


Measured Day
(5-25-62ct)

Station WYNS
Leighton, Pennsylvania

1kw, DA-D, D
1150 kc

*6-21-62
granted X for
a new station*

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.



MEASURED
HORIZONTAL PLANE PATTERN
FOR DIRECTIONAL DAYTIME OPERATION
WYNS - LEIGHTON, PENNSYLVANIA
1150 KC - 1 KW - DA-D
MARCH 1962

FCC File No. BL-9250
Accepted 5-14-62

Station WYNS
Leighton, Pennsylvania

1150 kc

WYNS


Measured Non-DA
(5-25-62ct)

Station WYNS
Lehigh, Pennsylvania

1kw, DA-D, D
1150 kc

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

*6-21-62
granted for a
new station*



MEASURED
HORIZONTAL PLANE PATTERN
FOR NON-DIRECTIONAL DAYTIME OPERATION
WYNS - LEHIGH, PENNSYLVANIA
1150 KC - 0.5 KW - ND-D
MARCH 1962

FCC File No. BL-9250
Accepted 5-14-62


Station WYNS
Lehigh, Pennsylvania

1150 kc

PROPOSED DAY
(4-22-60g)

New; Hoosier B/C Co.
Indianapolis, Indiana

1kw, DA-D, D
1150 KC



FCC File No. BP-14000
Accepted 4-6-60

Hoosier Broadcasting Company
Indianapolis, Indiana


1150 KC

Indianapolis, Ind.

PROPOSED DAY
(4-22-60g)

New; Independent Indianapolis B/C Corp.
Indianapolis, Indiana

1kw, DA-D,D
1150 KC



FCC File No. BP-14032
Accepted 4-12-60


Independent Indianapolis Broadcasting Corp.
Indianapolis, Indiana
1150 KC

PROPOSED DAY
(2-17-61q)

New; Sands Bcstng. Corp.
Indianapolis, Indiana

1kw, DA-D.D
1150 KC

SANDS BROADCASTING CORPORATION 1150 Kc. 1000 W-D. DA-D
INDIANAPOLIS, INDIANA November 14, 1960 PAUL DEAN FORD, Engineer
N. L. $39^{\circ} 49' 23''$
W. L. $86^{\circ} 03' 34''$



FCC File No. BP-12700
Accepted 2-14-61 (Amended)

Sands Broadcasting Corporation
Indianapolis, Indiana 1150 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: XEAD

Main Studio: Guadalajara, Jal.

Frequency: 1150 kHz

Power: 20 kw

Notification List No. 283

Date: March 8, 1978

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 20° 39' 52"

West Longitude: 103° 14' 44"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 3

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	W(#2)	C(#1)	E(#3)
HEIGHT ABOVE INSULATORS:	214'	214'	214' (90°)
PHASING:	-135°	0°	+135°
FIELD RATIO:	0.55	1	0.55

SPACING AND
ORIENTATION:

Adjacent towers are spaced 190.2' (80°) on a line
bearing 106° true.

GROUND SYSTEM:

120 - 214' equally spaced copper radials about each
tower. Radials are shortened and bonded to transverse
straps along intersections between towers. Centers of
system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL

RMS

968.6 mV/m

1. LISTA DE CAMBIOS -----
2. FECHA -----
3. FRECUENCIA 1150 KHz.
4. DISTINTIVO XEAD
5. POBLACION GUADALAJARA, JAL
6. UBICACION. PREDIO RUSTICO, MPIO. TONALA, JAL. LAT. NORTE 20°30'52"
7. POTENCIA 20 KW LON. OESTE 103°14'44"
8. CLASE III

CARACTERISTICAS TECNICAS DEL RADIADOR

9. TIEMPO DE OPERACION DIURNO
10. SISTEMA DEL RADIADOR DIRECCIONAL
11. NUMERO DE ELEMENTOS 3

TIPO DE ELEMENTOS RADIADORES

12. TIPO DE ALIMENTACION SERIE
13. SECCION TRANSVERSAL FORMA TRIANGULAR..DIMENSIONES..60 CENTIMETROS
14. TIPO DE ELEMENTO RADIADOR ARRIOSTRADA
15. TIPO DE SOPORTE CON RETENIDAS..TIPO DE RETENES..CARLE TRENZADO CON AISLADORES
16. LONGITUD DE TOPETE CAPACITIVO NO USA
17. PERDIDAS DE IMPEDANCIA EN LA BASE EN SERIE 3 OHMS
18. No. DE ELEMENTOS RADIADORES 3
19. ALTURA SOBRE EL AISLADOR 90°E (65.22 METROS) CADA TORRE
20. DEFASAMIENTO $\pm 135^\circ$ CON REFERENCIA A LA TORRE CENTRAL
21. RELACION DE CORRIENTES 0.55
22. DESCRIPCION DE LA ORIENTACION DEL SISTEMA RADIADOR
AZIMUT DEL EJE DE LAS TORRES 106°

SISTEMA DE TIERRA

23. No. DE RADIALES POR ELEMENTO 120
24. LONGITUD DE LOS RADIALES 65.22 METROS
25. TIPO DEL RADIAL ALAMBRE DE COBRE AWG, No. 10

RADIACION DEL SISTEMA

26. INTENSIDAD DE CAMPO EFECTIVO TEORICO (OMNIDIRECCIONAL)
DE LA POTENCIA RADIADA (RCM) 968.0 mV m
27. INTENSIDAD DE CAMPO EFECTIVO TEORICO A 1600 METROS POR
KILOWATT DE POTENCIA RADIADO 194.0 mV m
28. NOTA

Handwritten signature





DIAGRAMA DE RADIACION HORIZONTAL CALCULADO EN mV/m A 1609 m.

2 - ESQUEMA DE LAS TORRES Y SU ORIENTACION CON RESPECTO AL NORTE GEOGRAFICO
 AZIMUT
 106° 00' 00"



3 - FRECUENCIA:

1150 KHZ

XEAD

COORDENADAS GEOGRAFICAS

L.N. 20° 39' 52"

L.O. 103° 14' 44"

4. - PERITO EN TELECOMUNICACIONES

ING. JOSE LUIS GONZALEZ CORTEZ

Nº 26.

[Handwritten signature]

DISEÑO:

FILIBERTO SOLIS CERVANTES

GUADALAJARA, JAL. JUNIO DE 1978

DIAGRAMA DE RADIACION HORIZONTAL TABULADO

1. OPERACION DIURNA

2. X E A D

3. 1150 KHz


4. PREDIO MPIO. TONALA, JAL.

5. 20 Kw

$$E = 1257.41 [0.909 + \cos(80 \cos \phi + 135)]$$

Azimut $\phi = \gamma + 254^\circ$		A	B	C	D	E	F
							mV/m a 1609m
γ	ϕ	$\cos \phi$	$80 \times (A)$	$B + 135$	$\cos(C)$	$0.909 + D$	$1257.706 \times (E)$
0°	254°	-0.276	-22.050	112.949	-0.390	0.519	652.706
2°	256°	-0.242	-19.353	115.646	-0.433	0.476	598.761
4°	258°	-0.208	-16.633	118.367	-0.475	0.434	545.567
5°	259°	-0.191	-15.265	119.735	-0.496	0.413	519.318
7°	261°	-0.156	-12.515	122.465	-0.537	0.372	467.653
10°	264°	-0.105	-8.362	126.638	-0.597	0.312	392.622
20°	274°	0.070	5.580	140.580	-0.773	0.136	171.614
26°	280°	0.174	13.892	148.892	-0.856	0.053	66.399
28°	282°	0.208	16.633	151.633	-0.880	0.029	36.563
30°	284°	0.242	19.354	154.354	-0.902	0.008	9.451
35°	289°	0.326	26.045	161.045	-0.946	-0.037	-46.243
40°	294°	0.407	32.539	167.539	-0.976	-0.067	-84.803
46°	300°	0.500	40.000	175.000	-0.996	-0.087	-109.639
50°	304°	0.559	44.735	179.735	-0.999	-0.091	-114.411
55°	309°	0.629	50.345	185.345	-0.996	-0.087	-108.955
60°	314°	0.695	55.573	190.573	-0.983	-0.074	-93.077
65°	319°	0.755	60.377	195.377	-0.964	-0.055	-69.413
70°	324°	0.809	64.721	199.721	-0.941	-0.032	-40.670
78°	329°	0.857	68.573	203.573	-0.917	-0.008	-9.492
85°	339°	0.934	74.686	209.686	-0.869	0.040	50.612
90°	344°	0.961	76.900	211.901	-0.849	0.060	75.491
95°	349°	0.982	78.630	213.630	-0.834	0.075	94.815
100°	354°	0.995	79.562	214.562	-0.824	0.086	107.489
105°	359°	0.999	79.968	214.968	-0.819	0.090	112.822
106°	360°	1.000	80.000	215.000	-0.819	0.090	112.975
116°	10°	0.985	78.704	213.705	-0.831	0.078	97.909

Altitude $\phi = \gamma + 254^\circ$		A	B	C	D	E	F mW/m at 1609m
γ	ϕ	$\cos \phi$	$80 \times (A)$	$B + 135$	$\cos (C)$	$0.909 + D$	$1257.706 \times (E)$
126°	20°	0.940	75.175	210.175	-0.865	0.045	55.965
136°	30°	0.866	69.282	204.282	-0.911	-0.003	- 3.184
146°	40°	0.766	61.283	196.283	-0.960	-0.051	- 63.984
156°	50°	0.643	51.423	186.423	-0.994	-0.035	-106.531
166°	60°	0.500	40.000	175.000	-0.996	-0.087	-109.639
176°	70°	0.342	27.361	162.361	-0.953	-0.044	- 55.310
186°	80°	0.174	13.891	148.891	-0.856	0.053	66.399
196°	90°	0.000	0.000	135.000	-0.707	0.202	253.862
10°	91°	-0.017	- 1.396	133.603	-0.689	0.219	275.790
198°	92°	-0.035	- 2.791	132.208	-0.671	0.237	298.226
199°	93°	-0.052	- 4.186	130.813	-0.653	0.255	321.150
200°	94°	-0.070	- 5.580	129.419	-0.634	0.274	344.538
201°	95°	-0.087	- 6.972	128.027	-0.616	0.293	368.370
203°	97°	-0.122	- 9.749	125.250	-0.577	0.332	417.269
205°	100°	-0.174	-13.891	121.108	-0.516	0.392	493.338
216°	110°	-0.342	-27.361	107.638	-0.303	0.605	761.979
226°	120°	-0.500	-40.000	95.000	-0.087	0.822	1033.395
236°	130°	-0.643	-51.423	83.576	0.112	1.021	1283.649
246°	140°	-0.766	-61.283	73.716	0.280	1.189	1495.552
256°	150°	-0.866	-69.282	65.717	0.411	1.320	1660.068
266°	160°	-0.939	-75.175	59.824	0.503	1.412	1775.021
276°	170°	-0.984	-78.784	56.215	0.556	1.465	1842.196
286°	180°	-1.000	-80.000	55.000	0.573	1.482	1864.206
296°	190°	-0.984	-78.784	56.215	0.556	1.465	1842.196
306°	200°	-0.939	-75.175	59.824	0.503	1.412	1775.021
316°	210°	-0.866	-69.282	65.717	0.411	1.320	1660.068
326°	220°	-0.766	-61.233	73.716	0.280	1.189	1495.552
336°	230°	-0.643	-51.423	83.576	0.111	1.020	1283.649
346°	240°	-0.500	-40.000	95.000	-0.087	0.822	1033.395
356°	250°	-0.342	-27.361	107.638	-0.303	0.606	761.979
360°	254°	-0.275	-22.050	112.949	-0.389	0.519	652.706



SISTEMA DE TIERRA

2. LOS RADIALES SON DE ALAMBRE DE COBRE AWG. N° 10 EN CADA TORRE 120, DE 65.25 METROS DE LONGITUD LOS MAYORES, EL RESTO COMO SE INDICA EN EL PLANO.

TODO EL SISTEMA ESTA ENTERRADO A 30 CM.

3.

XEAD

L.N. 20° 39' 52"

L.O. 103° 14' 44"

4.

1150 KHz

5. PERITO TELECOM. N° 26
ING. JOSE LUIS GONZALEZ C.

JUNIO _____ 1970.

Description Sheet
(8-27-65ct)

Station XEGE
Mexicali, Baja California

500w, DA-N, U, Class III
1150 kc

XEGE

DIRECTIONAL ANTENNA DESCRIPTION SHEET
(Issued July 21, 1965)

Station: XEGE

Main Studio: Mexicali, Baja California

Frequency: 1150 kc/s

Power: 0.5kw

Notification List No. (*)

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: $32^{\circ} 38' 07''$

West Longitude: $115^{\circ} 29' 13''$

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 2

Type of elements: Series-excited, guyed, vertical steel towers.

TOWER:	North	South
HEIGHT ABOVE INSULATORS:	214.0'	214.0' (90°)
PHASING:	0°	180°
FIELD RATIO:	1	1

SPACING AND
ORIENTATION: Elements are spaced 142.6' (60°) on a line bearing 20° true.

GROUND SYSTEM: 60 - 214.0' equally spaced copper radials about each tower.

(See diagram attached)

Predicted effective Night Field: 123.70 mv/m at rated power.


(*) FCC Note: This "supplementary" information corresponds to a change in an existing station assignment concerning which official notification has not been received in the Commission as of July 21, 1965.

XEGE

Proposed Night
(8-27-65ct)


Station XEGE
Mexicali, Baja California

500w, DA-N, U, Class III
1150 kc



PATRON DE RADIA CION HORIZONTAL CALCULADO EN mV/M A 1609 mts

Esquema de las
Torres



RADIODIFUSORA

XEGE

Mexicali B. C

1150 khz.

500 Watts. N.

MANUEL CASTELLANOS
Ingenieria de COMUNICACIONES

22
24

Description Sheet
(8-23-63ct)

Station XEJP
Mexico, D.F.

10kw, DA-N, U, Class III
1150 kc

DESCRIPCION DEL SISTEMA DIRECCIONAL DE RADIACION

OPERACION NOCTURNA

ESTACION	<u>X E J P</u>	ESTUDIOS EN	Articulo 123 No. 90 D.F.
FRECUENCIA	1150 KHz.	POTENCIA	10,000 Watts.
CLASE:	III	LISTA DE CAMBIOS.	
		FECHA:	DICIEMBRE DE 1959.
LOCALIZACION GEOGRAFICA DEL SISTEMA RADIADOR:		LONGITUD O :	99° 04' 56"
		LATITUD N :	19° 30' 15"
AUTORIZADO PARA OPERACION.		AD - N.	
NUMERO DE ELEMENTOS RADIADORES:		DOS.	
TIPO DE ELEMENTOS RADIADORES.		TORRES VERTICALES DE SECCION CONSTANTE; CUADRANGULAR LA NORTE Y TRIANGULAR LA SUR SOPORTADAS CON RETENIDAS ALIMENTACION TIPO SERIE.	
TORRES		NORTE	SUR
		(No. 1)	(No. 2)
ALTURA SOBRE AISLADORES		65.20 M.	65.20 M.
		(90°)	(90°)
SEPARACION ENTRE TORRES:		43.50 M	(60°)
MAGNITUDES RELATIVAS DE CORRIENTES:		1	1
DEFASAMIENTO:		135°	0°
AZIMUT DEL EJE DE LAS TORRES:		MOSTRADO EN EL LOBULO HORIZONTAL =	30°
RAIZ CUADRATICA MEDIA TEORICA:		553.38	mV/M.
INTENSIDAD DE CAMPO R.C.M. NO ATENUADA A UNA MILLA POR KILO WATT DE POTENCIA RADIADA.		175	mV/M.

— . . 0 0 0 . —

DESCRIPTION SHEET
(1-10-58g)

Station XEJP
Mexico, D.F., Mexico

10kw, DA-N, Class III-A
1150 KC

MODIFIED
DIRECTIONAL ANTENNA DESCRIPTION SHEET
(Issued 1-2-58)

54109

Station: XEJP

Main Studio: Mexico, D.F.

Frequency: 1150 kc

Power: 10 kw

Notification List No. 151

Date: July 30, 1952 Class: III-A

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 19° 30' 46"

West Longitude: 99° 05' 14"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation (DA-N)

Number of elements: Two

Type of elements: Series-fed uniform cross section, guyed, vertical
steel towers.

TOWER:	South	North
HEIGHT ABOVE INSULATORS:	214'	214' (90°)
SPACING:	214 or 90° between adjacent towers.	
PHASING:	0°	90°
FIELD RATIO:	1	1
ORIENTATION:	Elements on a line bearing 0° true.	
Ground System:	120-114' equally spaced radials about each tower base. Radials are shortened and bonded by transverse straps along intersections between towers. Centers of systems bonded together.	


Predicted effective Field: 553.4 mv/m at rated power.

Note: The purpose of this modified description sheet is to correct errors
in the height of the towers and the spacing between towers which
occurred in converting meters to feet.

Proposed Night
(8-23-63ct)

Station XEJP
Mexico, D.F.

10kw, DA-N, U, Class III
1150 kc




XEJP

PROPOSED
NIGHT (2/3/53G)

XEJP, MEXICO, D. F.

10kw, DA-N

1150 kc/s



Orientation: Elements on a line bearing 0° true.
Ground System: 120-114' equally spaced radials about each tower base. Radials are shortened and bonded by transverse straps along intersections between towers. Centers of systems bonded together.
- Predicted effective field: 553.4 mv/m at rated power.

Tower: North
Height Above Insulators: 113.85' 113.85' (90°)
Spacing: 113.85' or 90° between adjacent towers.
Phasing: 0° 90°
Field Ratio: 1 1