

1410-1420

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
CFMB	Montreal, QU	1410	10 kW/DA-1	2/27/59
CFUN	Vancouver, BC	1410	50 kW/DA-2	3/28/68
CFUN	Vancouver, BC	1410	10 kW/DA-N	11/16/59
CIGO	Pt. Hawkesbury, NS	1410	10 kW/DA-2	12/7/79
CKSL	London, ON	1410	10 kW/DA-2	10/30/63
KAHL	North Platte, NE	1410	0.5/1 kW/DA-N	2/28/66
KAHL	North Platte, NE	1410	0.5/5 kW/DA-N	8/24/76
KBAN	Bowie, TX	1410	0.5 kW/DA-D	7/19/57
KBCC	Cuba, MO	1410	1 kW/DA-D	6/2/77
KBUL	Wichita, KS	1410	1/5 kW/DA-2	7/8/58
KCAL	Redlands, CA	1410	0.5/5 kW/ND-D	6/3/75
KCAL	Redlands, CA	1410	0.5/5 kW/DA-2	9/28/65
KCLO	Leavonworth, KS	1410	1 kW/DA-D	11/16/59
KCOL	Ft. Collins, CO	1410	1 kW/DA-N	1/13/50
KDOX	Marshall, TX	1410	500 kW/DA-D	12/3/56
KDOX	Marshall TX	1410	0.5 kW/DA-D	8/18/58
KJCH	Cleveland, TX	1410	0.5 kW/DA-2	6/18/53
KKOK	Lompoc, CA	1410	0.5 kW/DA-D	10/2/59
KMYC	Martysville, CA	1410	1/5 kW/DA-2	1/11/56
KMYC	Martysville, CA	1410	1 kW/DA-N	10/20/52
KNAL	Victoria, TX	1410	0.5 kW/DA-N	5/10/50
KQV	Pittsburgh, PA	1410	5 kW/DA-2	7/28/69
KRIG	Odessa, TX	1410	1 kW/DA-D	10/45
KRWB	Roseau, MN	1410	1 kW/DA-N	12/29/65
KVEG	N. Las Vegas, NV	1410	5 kW/DA-N	8/22/80
WAZY	Lafayette, IN	1410	1 kW/DA-D	12/21/59

1410-1420

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WDOE	Dunkirk, NY	1410	0.5 kW/DA-N	12/9/49
WDOV	Dover, DE	1410	5 kW/DA-N	11/29/65
WELM	Elmira, NY	1410	1/0.5 kW/DA-N	7/29/60
WHAG	Hagerstown, MD	1410	1 kW/DA-D	7/27/62
WING	Dayton, OH	1410	5 kW	9/46
WIZM	La Crosse, WI	1410	5 kW/DA-N	10/46
WLAQ	Rome, GA	1410	1 kW/DA-N	5/19/50
WLBj	Bowling Green, KY	1410	1 kW/DA-N	3/23/49
WLBj	Bowling Green, KY	1410	1/5 kW/DA-2	2/26/62
WLSH	Lansford, PA	1410	5 kW/DA-D	4/59
WLSH	Lansford, PA	1410	1 kW/DA-D	3/62
WMYR	Ft. Myers, FL	1410	5 kW/DA-N	8/26/70
WMYR	Ft. Myers, FL	1410	0.5/1 kW/DA-N	10/19/53
WOKW	Brockton, MA	1410	1 kW/DA-D	11/28/61
WOTT	Watertown, NY	1410	1/5 kW/DA-N	4/14/71
WPOP	Hartford, CT	1410	5 kW/DA-2	3/19/76
WPXC	Prattville, AL	1410	1/5 kW/DA-2	8/22/69
WRMN	Elgin, IL	1410	0.5/1 kW/DA-N/ND-D	10/26/79
WSRC	Durham, NC	1410	5 kW/DA-D	6/28/78
WTIM	Taylorville, IL	1410	1 kW/DA-D	11/2/77
WUNI	Mobile, AL	1410	5 kW	9/52
NEW	Calgary, AB	1420	1/0.5 kW/DA-2	12/21/71
NEW	Calgary, AB	1420	10 kW/DA-2	11/82
CJMT	Chicoutimi, QU	1420	1 kW/DA-1	10/11/57
CJVR	Melfort, Saskatchewan	1420	1 kW/DA-N	8/28/67
CKPT	Peterborough, ON	1420	10/5 kW/DA-2	7/8/75

1410-1420

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
NEW	Trenton, NJ	1420	0.5 kW/DA-D	9/12/80
NEW	Granbury, TX	1420	0.5/5 KW/DA-2	10/26/79
KBTN	Neosho, MO	1420	0.5 kW/DA-N/ND-D	10/26/79
KITI	Centralia-Chehalis, WA	1420	1 kW/DA-N	8/30/78
KITI	Centralia-Chehalis, WA	1420	1 kW ND/1 kW DA-N	6/76
KLFB	Lubbock, TX	1420	0.5 kW	8/22/80
KLUF	Shreveport, LA	1420	1 kW/DA-N	9/26/69
KOOO	Omaha, NE	1420	1 kW/DA-D	12/3/68
KPAR	Granbury, TX	1420	0.5 kW/DA-2	9/12/80
KPEL	Lafayette, LA	1420	0.5 kW/DA-N	12/15/50
KPEL	Lafayette, LA	1420	0.5/1 kW/DA-N	9/19/51
KREN	Renton, WA	1420	0.5 kW/DA-D	5/25/62
KSCR	Renton, WA	1420	0.5 kW/DA-D	10/26/79
KSTN	Stockton, CA	1420	1 KW/DA-N	11/45
KSTN	Stockton, CA	1420	1/5 kW/DA-2	6/56
KSTN	Stockton, CA	1420	5 kW/DA-D	10/29/59
KSTN	Stockton, CA	1420	1 kW/DA-N	10/29/59
KSTN	Stockton, CA	1420	1 kW/NON-DA	10/29/59
KTAN	Sierra Vista, AZ	1420	1/0.5 kW/DA-N	10/5/64
KTOE	Mankato, MN	1420	5 kW/DA-N	7/16/54
KUJ	Walla Walla, WA	1420	5 kW/DA-N	12/47
KULY	Ulysses, KS	1420	0.5/1 kW/DA-2	7/17/64
WACK	Newark, NY	1420	0.5 kW/DA-N	6/28/78
WAMM	Flint, MI	1420	0.5 kW/DA-D	10/1/75
WAVO	Decatur, MI	1420	1 kW/DA-D	10/22/75
WBEC	Pittsfield, MA	1420	1 kW/DA-2	1/67

1410-1420

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WBRD	Bradenton, FL	1420	1 kW/DA-D	7/11/56
WBSM	New Bedford, MA	1420	1 kW/DA-1	7/55
WBSM	New Bedford, MA	1420	1/5 kW/DA-2	12/57
WCED	Du Bois, PA	1420	0.5/5 kW/DA-2	5/56
WCOJ	Coatesville, PA	1420	5 kW/DA-N	10/55
WDBF	Delray Beach, FL	1420	0.5/5 kW/DA-2	10/62
WHK	Cleveland, OH	1420	5 kW/DA-N	8/28/63
WIMS	Michigan City, IN	1420	5 kW/DA-2	8/30/79
WIMS	Michigan City, IN	1420	0.5/5 kW/DA-2	6/60
WIMS	Michigan City, IN	1420	0.1/0.5 kW/N(DA)	9/52
WINI	Murphysboro, IL	1420	0.5 kW/DA-N	7/1/77
WKPR	Kalamazoo, MI	1420	1 kW/DA-D	12/56
WKSR	Pulaski, TN	1420	0.25 kW/DA-N	6/1/51
WLNA	Peekskill, NY	1420	1/5 kW/DA-2	11/2/79
WOC	Davenport, IA	1420	5 kW/DA-2	3/22/55
WRBL	Columbus, GA	1420	5 kW/DA-N	5/45
WVJS	Owensboro, KY	1420	1/5 kW/DA-2	4/60
WVJS	Owensboro, KY	1420	1 kW/DA-2	4/21/47
WVOT	Wilson, NC	1420	0.5/1 kW/DA-N	2/9/49
XEEW	Matamoros, Tamaulipas	1420	1 kW/DA-1	6/29/56
NEW	Digby, NS	1420	1 kW/DA-1	9/26/68

#131
DESCRIPTION SHEET
(5-28-59g)

New Station
Montreal, Quebec, Canada

CFMB
10kw, DA-1, U, Class III
1410 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: New

Main Studio: Montreal, Que.

Frequency: 1410 KC/S

Power: 10 KW

Class: III

Notification List No. 131

Date: February 27, 1959


GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM:

North Latitude: $45^{\circ} 24' 10''$

West Longitude: $73^{\circ} 24' 52''$

ANTENNA CHARACTERISTICS

Mode of Operation: Same pattern day and night (DA-1)
Number of elements: Four (4)
Type of elements: Uniform cross section guyed steel towers,
base insulated for series feed



TOWER:	#1 (S)	#2 (SC)	#3 (NC)	#4 (N)
HEIGHT ABOVE INSULATORS:	200' (103.3°)	200' (103.3°)	200' (103.3°)	200' (103.3°)
OVERALL HEIGHT:	205'	205'	205'	205'
SPACING:	174.2' (90°) between adjacent towers			
PHASING:	0°	-141°	+77°	-75°
FIELD RATIO:	1.0	2.3	2.07	.875
ORIENTATION	All towers on line bearing 348° East of True North			
GROUND SYSTEM:	120 equiangularly spaced radials extend from the base of each tower to a distance of 280 feet (0.4 wavelength) with the exception of those radials joined along the common chords. The ground wires consist of solid copper wire #10 B & S gauge and are buried to a depth of approximately 8 inches.			

Predicted effective field: 700 mv/m at 1 mile (221 mv/m for 1 KW)

131


CFMB

PROPOSED DAY & NIGHT
(5-28-59g)

New Station
Montreal, Quebec, Canada

10kw, DA-1, U, Class III

1410 KC



POLAR CO-ORDINATE 359-31
KEUFFEL & ESSER CO. MADE IN U.S.A.


FIGURE 1
HORIZONTAL RADIATION PATTERN
NEW
MONTREAL, QUE.
1410 KC 10KW DA-1 CLASS III
RCA VICTOR CO. LTD., MONTREAL
PROJ 2793-A JAN 1959

#131

CFMB

PROPOSED DAY & NIGHT NULLS
(5-28-59g)

New Station 10kw, DA-1,U,Class III
Montreal, Quebec, Canada 1410 KC



Description Sheet
(3-28-68ct)

Station CFUN
Vancouver, B. C.

50kw, DA-2, U, Class III
1410 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

STATION : CFUN MAIN STUDIO : Vancouver, B.C.

FREQUENCY : 1410 KC/S POWER : 50 KW

NOTIFICATION LIST NO: 240 DATE MARCH 11, 1968

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM : North Latitude $49^{\circ} 07' 41''$
West Longitude $123^{\circ} 01' 41''$

ANTENNA CHARACTERISTICS

MODE OF OPERATION : DA-2 (Directional, Full Time, Different Patterns
Day and Night)

NUMBER OF ELEMENTS : Three (3)

TYPE OF ELEMENTS : Uniform cross-section guyed steel towers, base
insulated for series feed, no top loading

TOWER : 1 (S) 2 (MW) 3 (N)

HEIGHT ABOVE INSULATORS: 350' 350' 350'
(180.5') (180.5') (180.5')

OVERALL HEIGHT : 355' 355' 355'

SPACING AND ORIENTATION: Tower 1 & 2 203.5' (105°) apart
on line 317° E. of true N.
Tower 1 & 3 232.6' (120°) apart on line 0° true N.

PHASING - DAY : 0° — -48°
- NIGHT : 0° -90° —

FIELD RATIO -DAY : 1.00 — 1.00
-NIGHT : 1.00 .85 —

GROUND SYSTEM : 120 equally spaced radials of B&S No. 10 bare copper
wire per tower, extending to a distance of 280' ($.4$
wavelength) except where banded on the common chord
equidistant between towers and buried approximately 8".

PREDICTED EFFECTIVE FIELD:

DAY : 1640 MV/M at 1 mile (232 MV/M for 1 KW)
NIGHT : 1670 MV/M at 1 mile (236 MV/M for 1 KW)

NOTE: This notification reflects a change of transmitter site, only from
that notified on List #216. To this description sheet attach the
radiation patterns previously distributed relative to notification
on list 216.

Description Sheet
(8-26-66ct)

Station CFUN
Vancouver, B. C.

50kw, DA-2, U, Class III
1410 kc

CFUN

DIRECTIONAL ANTENNA DESCRIPTION SHEET

STATION : CFUN MAIN STUDIO : Vancouver, B.C.

FREQUENCY : 1410 KC/S POWER : 50 KW

NOTIFICATION LIST NO : 226 DATE : July 26, 1966

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM : North Latitude 49° 08' 45"
West Longitude 122° 58' 55"

ANTENNA CHARACTERISTICS

MODE OF OPERATION : DA-2 (Directional, Full Time, Different Patterns Day and Night)

NUMBER OF ELEMENTS : Three (3)

TYPE OF ELEMENTS : Uniform cross-section guyed steel towers, base insulated for series feed, no top loading

TOWER : 1 (S) 2 (NW) 3 (N)

HEIGHT ABOVE INSULATORS : 350' 350' 350'
(180.5°) (180.5°) (180.5°)

OVERALL HEIGHT	: 355'	355'	355'
----------------	--------	------	------

SPACING AND ORIENTATION: Tower 1 & 2 203.5' (105°) apart
on line 317° E. of true N.
Tower 1 & 3 232.6' (120°) apart on line 0° true N.

PHASING	-	DAY	:	0°	---	-48°
	-	NIGHT	:	0°	-90°	---

FIELD RATIO - DAY	:	1.00	---	1.00
- NIGHT	:	1.00	.85	---

GROUND SYSTEM : 120 equally spaced radials of B&S No. 10 bare copper wire per tower, extending to a distance of 280' (.4 wavelength) except where banded on the common chord equidistant between towers and buried approximately 8".

PREDICTED EFFECTIVE FIELD :

DAY	:	1640 MV/M at 1 mile (232 MV/M for 1 KW)
NIGHT	:	1670 MV/M at 1 mile (236 MV/M for 1 KW)


216
PO #139

CFUN

Proposed Day
(8-26-66ct)

Station CFUN
Vancouver, B. C.

50kW, DA-2, U, Class III
1410 kc



N. J. PAPPAS & ASSOCIATES

CFUN Vancouver, B.C.
1410 KC 50 KW DA-2

Horizontal Day-time Radiation Pattern

May 20/66

Project 5038

A.L.


216
20#139

CFUN

Proposed Night
(8-26-66ct)

Station CFUN
Vancouver, B. C.

50kw, DA-2, U, Class III
1410 kc



N. J. PAPPAS & ASSOCIATES		
CFUN	Vancouver, B.C.	
1410 KC	50 KW	DA-2
Horizontal Night-time Radiation Pattern		
May 20/66	Project 5038	<i>a.l.</i>

CFUN

DESCRIPTION SHEET
(11-16-59g)

Station CFUN 10kw, DA-N,U, Class III
Vancouver, British Columbia, Canada 1410 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : CFUN Main Studio: Vancouver, B.C.
Frequency: 1410 kcs. Power: 10 KW. Class: III
Notification List No. 139 Date: October 5, 1959

GEOGRAPHICAL LOCATION

OF THE ANTENNA SYSTEM: North Latitude: 49° 11' 51''
West Longitude: 123° 02' 38''

ANTENNA CHARACTERISTICS

Mode of Operation: DA/N
Number of elements: 2
Type of elements: Vertical, guyed radiators,
uniform cross-section,
series fed, no top loading.

TOWERS:	#1 (SE)	#2 (NW)
HEIGHT ABOVE INSULATORS:	176' (90°)	350' (180°)
OVERALL HEIGHT:	182'	357'
SPACING:	292' (150°)	
PHASING:	0	-50
RATIO:	1.0	0.65
GROUND SYSTEM: 120 radials per tower 0.4 wavelengths long except where intersected. Bonded to common cherd at intersections.		

PREDICTED: EFFECTIVE FIELD: Day: 750 mv/m at 1 mi. (237 mv/m for 1 KW.)
Night: 700 mv/m at 1 mi. (220 mv/m for 1 KW.)

ORIENTATION: 315° True.


139
20

CFUN

PROPOSED NIGHT
(11-16-59g)

Station CFUN
Vancouver, British Columbia, Canada

10kw, DA-N,U, Class III
1410 KC



FORM FOR THE APPLICATION OF ARTICLE 4 OF THE AGREEMENT 1 2
CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

PART I	GENERAL INFORMATION
--------	---------------------

① Administration

CANADA

Sheet No.

416

Date _____

830110

Assigned frequency (kHz)		02	1 4 1 0
Transmitting station	Name of the station	03	P O R T H A W K E S B U R
	Call sign	04	C I G O
	Additional identification	05	N S
	Station class	06	
	Operational Status	07	
Country		08	CAN
Geographical coordinates of the transmitting station		09	6 1 W 2 6 0 9 4 5 N 0 5 8

(11) a) New assignment ☐ b) Modification of characteristic of an assignment recorded in the plan ☒ c) Cancellation of an assignment ☐





(12) Modification under Section 4.2.14 Yes ☒ No ☐

(13) Date of bringing into service or cessation of operation

7	5	1	0	2	2
---	---	---	---	---	---

Year Month Day

Withdraw proposed change 820405, List 411.

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	(21) 	(31)  No change
r.m.s. value of radiation for station power (mV/m at 1 km)	(25) 	(35) 
Antenna type	(26) 	(36) 
Simple vertical antenna electrical height (degrees)	(27) 	(37) 

44 Remarks	COORDINATION UNDER ARTICLE 4:							
	COUNTRY	USA						
	IN PROGRESS							
	ACCEPTANCE OBTAINED							

FRB Serial No.

1	2	3	6	8
---	---	---	---	---

Description of a directional antenna consisting of vertical conductors

416 830110

Date _____

У	Н
---	---

CAN

8

P	O	R	T	H	A	W	E	S	B	J	R
---	---	---	---	---	---	---	---	---	---	---	---

Name of transmitting station

8

H	J	Hours of operation
1	1	1
2	2	2
3	3	3
4	4	4
5	5	5
6	6	6
7	7	7
8	8	8
9	9	9
10	10	10
11	11	11
12	12	12
13	13	13
14	14	14
15	15	15
16	16	16
17	17	17
18	18	18
19	19	19
20	20	20
21	21	21
22	22	22
23	23	23
24	24	24
25	25	25
26	26	26
27	27	27
28	28	28
29	29	29
30	30	30
31	31	31
32	32	32
33	33	33
34	34	34
35	35	35
36	36	36
37	37	37
38	38	38
39	39	39
40	40	40
41	41	41
42	42	42
43	43	43
44	44	44
45	45	45
46	46	46
47	47	47
48	48	48
49	49	49
50	50	50
51	51	51
52	52	52
53	53	53
54	54	54
55	55	55
56	56	56
57	57	57
58	58	58
59	59	59
60	60	60
61	61	61
62	62	62
63	63	63
64	64	64
65	65	65
66	66	66
67	67	67
68	68	68
69	69	69
70	70	70
71	71	71
72	72	72
73	73	73
74	74	74
75	75	75
76	76	76
77	77	77
78	78	78
79	79	79
80	80	80
81	81	81
82	82	82
83	83	83
84	84	84
85	85	85
86	86	86
87	87	87
88	88	88
89	89	89
90	90	90
91	91	91
92	92	92
93	93	93
94	94	94
95	95	95
96	96	96
97	97	97
98	98	98
99	99	99
100	100	100

⑧

**Total number
of towers**

[illegible]

(14) r.m.s. value of radiation mV/m at 1 km 9.9.7.1.6.	(15) Type of pattern mV/m at 1 km	(16) Special quadrature factor mV/m at 1 km
---	---	---

17) SUPPLEMENTARY INFORMATION

2190
1410

FORM FOR THE APPLICATION OF ARTICLE 4 OF THE AGREEMENT

1,2368

CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

PART I **GENERAL INFORMATION**

ⓐ Administration

CANADA

Sheet No.

41

Date _____

82.4.5

Assigned frequency (kHz)		02	1410
Transmitting station	Name of the station	03	PORT HAWKESBUR
	Call sign	04	CIGA
	Additional identification	05	
	Station class	06	
	Operational Status	07	
Country		08	CAN
Geographical coordinates of the transmitting station		09	61W 26 09 45N 40 58

Correction

11 a) New assignment ☐ b) Modification of characteristic of an assignment recorded in the plan ☒ c) Cancellation of an assignment ☐

12 Modification under Section 4.2.14 Yes ☐ No ☒

13 Date of bringing into service or cessation of operation

8	2	0	7	0	1
---	---	---	---	---	---

Year Month Day

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	(21) 1.0	(31) No Change
r.m.s. value of radiation for station power (mV/m at 1 km)	(25) → 96.8	(35)
Antenna type	(26) → A	(36)
Simple vertical antenna electrical height (degrees)	(27) → 9.0	(37)

44 Remarks	COORDINATION UNDER ARTICLE 4:							
	COUNTRY	USA						
	IN PROGRESS	X						
	ACCEPTANCE OBTAINED							

SECTION IV : DIRECTIONAL ANTENNA - DESCRIPTION SHEET

Call Sign : CIGC

Main Studio : Port Hawkesbury, N.S.

Frequency : 1410 kHz

Class : III

Power : 10 kW

Mode : DA-2

Notification List No. : 392

Date : December 7, 1979

Geographical Location : 45° 40' 58" North Latitude
 of the Antenna System : 61° 26' 09" West Longitude

Antenna Characteristics : Number of Elements : Two (2)


Type of Elements : Uniform cross-section,
 guyed steel towers, series
 fed, base insulated. No
 top loading.


Tower Number	:	1 (W)	2 (E)
Height above insulator	:	174.2' (90°)	174.2'
Overall Height	:	177'	177'
Field Ratio (Day)	:	1.0	1.0
Phasing (Day)	:	Ref	-75°
Field Ratio (Night)	:	1.0	1.0
Phasing (Night)	:	Ref	-120°
Orientation	:	On a line bearing 90°E	
Spacing	:	145.1' (75°) betw. twrs.	
Ground System	:	120 equiangularly spaced radials of No. 10 AWG soft-drawn, bare copper wire and buried approximately 8" in ground. Each radial is 279' long excluding those joined along the common chord. This represents a 0.4λ equivalent ground system.	


Measured Effective Field : 620 mV/m at 1 mile for 10 kW, DAY
 196 mV/m at 1 mile for 1 kW;

565 mV/m at 1 mile for 10 kW, NIGHT
 179 mV/m at 1 mile for 1 kW.

This notification concerns only a decrease in the effective night-time field from the value notified on Change List 337 dated January 8, 1975. The measured effective day-time field of 620 mV/m is within acceptable tolerance of the notified value of 610 mV/m. Accordingly, please retain the January 8, 1975 day-time pattern.







HORIZONTAL RADIATION NIGHT PATTERN

CIGO - Port Hawkesbury, N.S.
 1410 kHz 10 kW III DA-2

October 1979

PETER CAHN & ASSOCIATES
 CONSULTING ENGINEERS

#181
Description Sheet
(10-30-63ct)

Station CKSL
London, Ontario

10kw, DA-2, U, Class III
1410 kc

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2

STATION CALL: C K S L
MAIN STUDIO: London, Ontario.
FREQUENCY: 1410 kc/s
POWER: Day 10 kw, 10 kw Night
CLASS: III
TIME: Unlimited

NOTIFICATION REFERENCE: 181

September 30, 1963

GEOGRAPHICAL LOCATION:

Lat 42°52'59" Lon 81°13'25"

ANTENNA CHARACTERISTICS:

Five elements, guyed, uniform cross section, base insulated, series feed. No top loading. height 174.5 feet or 90 degrees.

Tower	Day Ratio	Day Phase	Night Ratio	Night Phase
# 1	1.0000	00.0°	1.000	00.0°
# 2	1.8130	-153.2°	2.380	-148.6°
# 3	1.4070	50.7°	2.631	59.6°
# 4	0.3825	-99.0°	1.535	-89.4°
# 5	---	---	0.378	126.0°

Orientation Elements on a line bearing 352°

Spacing Adjacent elements 174.5 ft (90°)

Ground system 120 radials per tower, #10 AWG bare soft copper wire, buried 8 inches. Radials joined along line between towers and bonded to soft copper strap at tower base. Average length 279 feet.


Predicted R M S 600 mv/m at 1 mile for 10 kw
190 mv/m at 1 mile for 1 kw

May 1963

5

91

10kw, DA-2, U, Class III
1410 kc



DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: New Main Studio: Port Hawkesbury, N.S.
Power: 10 kw (day and night) Frequency: 1410 kc
Canadian Change List. No. 337 dated January 8, 1975.

CLASS: III

Site: North latitude: $45^{\circ} 41' 02''$
West longitude: $61^{\circ} 26' 19''$

Antenna

Characteristics: Series fed, uniform cross-section guyed, vertical
steel towers
Authorized for day-time and night-time operation (DA-2)

Number of elements: 2

Tower:	<u>No 1 (west)</u>	<u>No 2 (east)</u>
--------	--------------------	--------------------

Height above insulators:	174.2 (90°)	174.2 (90°)
-----------------------------	------------------------	------------------------

Spacing:	Ref.	75°
----------	------	--------------

Orientation:	Ref.	90°
--------------	------	--------------

Day

Phasing	0°	$- 75^{\circ}$
---------	-------------	----------------

Field ratio	1.0	1.0
-------------	-----	-----

Night

Phasing	0°	$- 120^{\circ}$
---------	-------------	-----------------

Field ratio	1.0	1.0
-------------	-----	-----


Ground system: 120 radials per tower, 0.4 wavelength or to chords,
bonded, buried 8" #10 AWG

Predicted
effective 611 mV/m (day)
field: 630 nV/m (night)



Communications Consultants


Communications Consultants
February 20, 1975



DAYTIME RADIATION PATTERN
NEW AM PORT HAWKESBURY
NOVA SCOTIA



10 KW- DA-2 , 1410 kc
PROJECT BLC-517-74
BRUNELLE, LAMBERT CONSULTANTS

FEBRUARY 26 1974



NIGHTTIME RADIATION PATTERN
NEW AM PORT BATHURST
NOVA SCOTIA



10 kw DA-2 1410 kc
Project BLC-517-74 Feb 74
BRUNELLE LAMBERT CONSULTANTS



VERTICAL RADIATION PATTERNS

PROPOSED VERTICAL RADIATION PATTERN
NEW PORT HAWKESBURY, N.S.
1410 kc 10 kw PA-2 Class III
Project BNL-517-71 Feb 74

Communications Consultants
January 26, 1974



VERTICAL RADIATION PATTERNS



PROPOSED VERTICAL RADIATION PATTERN
 NEW PORT HARTSFORD, N.S.
 1410 kc 10 kw EA-2 Class: 111
 Project ELC-517-71 Feb 74



Brunelle Lambert Consultants Ltd.

Communications Consultants

Telephone 26, 1971




VERTICAL RADIATION PATTERNS

PROPOSED VERTICAL RADIATION PATTERN
 NEW PORT HURSTORY, N.S.
 1410 kc 10 kc NA-2 Class: 1
 Project DAC-517-74 Feb 74



Cronin Lambert Conrath & Co.

Communications Consultants
 1201 Avenue A, N.S.



PROPOSED VERTICAL RADIATION PATTERNS
 NEW PORT HAVESSEY, N.S.
 1410 kc 10 kw 3A-2 Class III
 Project MCH-517-74 Feb 74



Brennitz Lambert Consultants Ltd.

Communications Consultants

Ref: 100-10-1

KAHL


~~KNOP~~

Measured Non-DA
(2-28-66ct)

Station KNOP
North Platte, Nebraska

500w, 1kw-LS, DA-N, U
1410 kc

IC 3-15-66



Broadcast Maintenance Service

Rea Bowman, Route 5, Topeka, Kansas 66608
MUrdock 8-1872

FCC File No. BL-11202
Accepted 2-9-66

Station KNOP
North Platte, Nebraska

1410 kc

KAHL

~~K100~~

Proposed Night
(2-28-64ct)


Station KNOP
North Platte, Nebraska

500w, 1kw-LS, DA-N, U

1410 kc


Figure 6A
Sheet 1

#201-8-26-64
franted MCP
w/ DA-N, and
0.5-1kw-LS



SITE COORDINATES
41 10' 30" N
100 45' 07" W

PROPOSED NIGHT HORIZONTAL PLANE RADIATION PATTERN



NORTH PLATTE TELEVISION, INC.
NORTH PLATTE, NEBRASKA

Julius Cohen & Associates
Consulting Electronics Engineers

PROPOSED OPERATION
RADIO STATION KNOP

1410 KC
0.5 KW, 1 KW-LS U DA-N
Pattern 631220
Amended

FCC File No. BMP-11164
Accepted 2-13-64

Station KNOP
North Platte, Nebraska

1410 kc

KAHL

~~KNOP~~


Measured Night
(2-28-66ct)

Station KNOP
North Platte, Nebraska

500w, 1kw-LS, DA-N, U
1410 kc

DATE: 12-15-65

LIC. 3-15-66



Broadcast Maintenance Service

Rm Bowman, Route 5, Topeka, Kansas 66608
MUrdock 8-1872

FCC File No. BL-11202
Accepted 2-9-66

Station KNOP
North Platte, Nebraska

1410 kc

KAHL

~~KNOT~~

Proposed Night Nulls
(2-28-64ct)

Station KNOP
North Platte, Nebraska

500w, 1kw-LS, DA-N, U
1410 kc




Figure 6A
Sheet 2

FCC File No. BMP-11164
Accepted 2-13-64

Station KNOP
North Platte, Nebraska

1410 kc

SUPPLEMENTAL DIRECTIONAL ANTENNA
DESCRIPTION SHEET

Station: KAHL

Main Studio: North Platte, Nebraska

Frequency: 1410 kHz

Power: 0.5 kW Night 5 kW DAY

Notification List No. 1699

Date: August 24, 1976 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 10' 30"

West Longitude: 100° 45' 07"

Authorized for Night operation (DA-N).

Predicted effective Day Field: (omnidirectional) 436 mV/m at rated power.

Note: Please retain the description sheet and directional antenna radiation patterns notified for station KNOP in United States Change List Number 1076, dated September 2, 1964 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only an increase in daytime power from 1 kW with nighttime operation continued as previously notified.

CTR NO 31097A

Bowie, Texas

KBAN

PROPOSED DAY
(7/19/57g)


New, Bowie-Nocona Bestng. Co.
Bowie, Texas

500w, DA-D,D
1410 KC

2

N 33° 33' 09"
W 97° 48' 06"

M.E.O.V.



Granted CP
2/3/59 for a
new station



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

WASHINGTON, D. C.

PATTERN: PROPOSED DAYTIME

FOR: BOWIE, TEXAS

POWER: 500 Watts FREQ: 1410 KC

DATE: 7/1/57

FCC File No. BP-11,241
Accepted 7/15/57 (Amended)

Bowie-Nocona Bestng. Co.
Bowie, Texas

1410 KC


Fig 3

MEASURED DAY
(7-8-59g)

Station KBAN
Bowie, Texas

500w, DA-D, D
1410 KC

TRUE
NORTH



Theoretical Values 0.59/0° ① — S — ② 1.0/104.8° 1150T G = 90° = 175' S = 80° = 155.1'	RADIO STATION KBAN BOWIE, TEXAS MEASURED DIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN 1410 KC DA-D 500 WATTS	
051659-3	MERL SAXON CONSULTING RADIO ENGINEER LUFKIN, TEXAS	
FIGURE 3		

FCC File No. BL-7515
Accepted 6-30-59

KBAN
Bowie, Texas

1410 KC


granted for new station
11-18-59

11-18-57 granted L for
new station

MEASURED NON-DA
(7-8-59g)

Station KBAN
Bowie, Texas
TRUE
NORTH

500w, DA-D, D
1410 KC



0.5 KW (1) Isolated (2) $G = 90^\circ = 175'$ $S = 80^\circ = 155.1'$	RADIO STATION KBAN BOWIE, TEXAS	
	MEASURED NON-DIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN 1410 KC 500 WATTS	
	051659-2	MERL SAXON CONSULTING RADIO ENGINEER LUFKIN, TEXAS
FIGURE 2		

FCC File No. BL-7515
Accepted 6-30-59

KBAN
Bowie, Texas

1410 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

KBCC

Station: (New)

Main Studio: Cuba, Missouri

Frequency: 1410 kHz

Power: 1 kW

Notification List No. 1736

Date: June 2, 1977

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 38° 05' 06"
West Longitude: 91° 18' 40"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 3

Type of elements: Series excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	SW(#3)	C(#1)	NE(#2)
HEIGHT ABOVE INSULATORS:	100'	100'	100' (51.6°)
PHASING:	-128.4°	0°	+92.3°
FIELD RATIO:	0.5	1	0.5


SPACING AND
ORIENTATION: From reference tower #1, tower #2 is spaced 174.5' (90°)
on a line bearing 47° true, and tower #3 is spaced 174.5'
(90°) on a line bearing 207° true.

GROUND SYSTEM: 120-174.5' equally spaced copper radials about each tower.
Radials are shortened and bonded to transverse straps along
intersections between towers.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL	STANDARD
	<u>RMS</u>	<u>RMS</u>
Day	178.779 mv/m	187.723 mv/m
	<u>RSS</u>	
	192.196 mv/m	

EXHIBIT E-5.1



STANDARD HORIZONTAL RADIATION PATTERN



K-FACTOR 156.927 mv/m
 THEO RMS 178.779 mv/m
 THEO RSS 192.196 mv/m
 Q FACTOR 6
 STD RMS 187.723 mv/m


ELECTRICAL HEIGHT
 51.6° 100 Feet

APPLICANT Crawford B'd Co. Inc.
 LOCATION Cuba, Missouri
 FREQUENCY 1410 KC/S
 POWER 1 KW
 LATITUDE 38 DEG 05 MIN 05 SEC
 LONGITUDE 91 DEG 18 MIN 40 SEC
 WHEN USED Daytime
 RMS FIELD
 DATE September 1975

ROBERT L. MIERS
 CONSULTING RADIO ENGINEER
 ROLLA, MISSOURI 65401

K W B D

1kw,5kw-LS, DA-2,U
1410 KC



1410 KC

Wichita, Kansas


KWBB
F. J. OL

MEASURED DAY
(9-4-59g)

Station KWBB
Wichita, Kansas

1kw, 5kw-LS, DA-2, U
1410 KC

granted L for change in DA
11-18-59



FCC File No. BL-7547
Accepted 8-20-59

KWBB
Wichita, Kansas

1410 KC


KBUL

KWBB

JUN 30 1948

6-29-48

KWBB - 1410 kc




KBUL KWBB

MEASURED
NIGHT

KWBB, WICHITA, KANS.

1kw, DA-2


1410 kc



KWBB, Wichita, Kans. 1410 kc

KIBUL

KWBB

MEASURED NON-DA
(9-4-59g)Station KWBB
Wichita, Kansas1kw, 5kw-LS, DA-2, U
1410 KC*Granted L for change in DA
11-18-59*FCC File No. BL-7547
Accepted 8-20-59KWBB
Wichita, Kansas

1410 KC

KCAL

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KCAL Main Studio: Redlands, California
 Frequency: 1410 kc/s Power: 0.5 kw Night 5 kw Day
 Notification List No. 1635 Date: June 3, 1975 Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS OF THE DAY AND NIGHT ANTENNA SYSTEMS:

<u>Daytime</u>	<u>Nighttime</u>
North Latitude: 34° 04' 08"	North Latitude: 34° 06' 40"
West Longitude: 117° 12' 06"	West Longitude: 117° 09' 10"

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 3
 Type of elements: Series-excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	S(#3)	C(#1)	N(#2)
HEIGHT ABOVE INSULATORS:	213'	213'	213' (110°)
NIGHT PHASING:	-153°	0°	+153°
NIGHT FIELD RATIO:	0.5	1.0	0.5

SPACING AND ORIENTATION: Adjacent elements are spaced 174.2' (90°) on a line bearing 20° true.

GROUND SYSTEM: 120-175' equally spaced copper radials plus 120-50' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

Predicted effective Night Field: 145.4 mv/m at rated power.

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (ND-D)
 Number of elements: 1
 Type of element: Series-excited, uniform cross-section, guyed, vertical steel tower.

HEIGHT ABOVE INSULATOR: 186' (95.9°)

contd.

Station KCAL

2.

GROUND SYSTEM: 120-150' to 200' equally spaced copper radials plus
120-50' interspaced radials about the tower.

Predicted effective Day Field: (omnidirectional) 392 mv/m at rated
power by adjustment of input power.

Note: Please retain the Nighttime directional antenna radiation pattern
notified for Station KCAL in United States Change List Number 978
dated October 3, 1962, and attach to this Revised Description Sheet.
This notification concerns only a change in the Daytime operation of
the station with Nighttime operation continued as previously notified.

CTR NO 30643A3


KCAL

Proposed Day
(9-28-65ct)

Station KCAL
Redlands, California

500w, 5kw-LS, DA-2, U
1410 kc

ICP 8-30-65
-HG, DAY DA
PA 8-3-66
DA-N



FCC File No. BMP-11578
Accepted 8-26-65

Station KCAL
Redlands, California

1410 kc

KCAL

Measured Day
(7-28-66ct)


Station KCAL
Redlands, California

500w, 5kw-LS, DA-2, U
1410 kc

RA. DA-N
B-3-66
6-7-67
GRANTED
- 135VSE
R2 CHANGE
- 135VSE
- 135VSE

EUDENE DIETZGEN CO.
MADE IN U.S.A.

EUDENE DIETZGEN CO. (DA-2) PAPER
MADE IN U.S.A.



FCC File No. BL-11341
Accepted 6-30-66

Station KCAL
Redlands, California

1410 kc


KCAL

Proposed Night
(10-30-63ct)

Station KCAL
Redlands, California


500w, 5kw-LS, DA-2, U
1410 kc

P.A. DA-N
8-3-66



HORIZONTAL RADIATION PATTERN — FIGURE No. 4

Antenna Parameters



Floyd Hall
Radio Engineering
Consultant

Club San Moritz
Crestline,
California

APPLICANT: KCAL

LOCATION: REDLANDS, CALIFORNIA

FREQ.: 1410 KC/S POWER: 0.5 KW

LAT: 34° 06' 39" N LONG: 117° 09' 02" W

TIME OF OPERATION: NIGHT

TYPE OF OPERATION: DA-2

RMS FIELD: 145.4 MV/M

PATTERN No. 620524-R1 SUPERSEDES 620524-R

DATE: 8-27-63 BY:

FCC File No. BMP-11032
Accepted 10-23-63

Station KCAL
Redlands, California

1410 kc

KCAL

Measured Night
(7-28-66ct)

Station KCAL
Redlands, California

500w, 5kw-LS, DA-2, U
1410 kc


PA. DAN
8-3-66
6-7-67
RECEIVED
FEDERAL
COMMUNICATIONS
COMMISSION

Fred W. Volken
Engineering Consultant
Sierra Madre, California

GRAPH *AF AH*
Measured Nighttime Directional
Horizontal Radiation Pattern

KCAL
1410 kc
Redlands, California

EUGENE DIETZEN CO.
MADE IN U.S.A.



FCC File No. BL-11341
Accepted 6-30-66

Station KCAL
Redlands, California

1410 kc


KCAL

Measured Non-DA
(7-28-66ct)

Station KCAL
Redlands, California

500w, 5kw-LS, DA-2, U
1410 kc

A. DA-N
3-66
6-7-67
-24V780
1-ENUSE
FOR CHANGE
DA SYSTEM



FCC File No. BL-11341
Accepted 6-30-66

Station KCAL
Redlands, California

1410 kc

KCLO


PROPOSED DAY
(4/24/57g)

Station KCLO
Leavenworth, Kansas

5kw, DA-D,D
1410 KC

*Granted CP
2-3-59 to
increase day
power to 5 KW
DA-D*

POLAR COORDINATE
KEUTELA LAMER CO.



FCC File No. BP-11,195
Accepted 4/17/57

KCLO
Leavenworth, Kansas

1410 KC


granted L for increase in power
indication of DA - 12-31-59

MEASURED DAY
(11-16-59g)

Station KCLO
Leavenworth, Kansas

5kw, DA-D,D
1410 KC

KCLO




KCLO

MEASURED NON-DA
(11-16-59g)

Station KCLO
Leavenworth, Kansas

5kw, DA-D,D
1410 KC

North Latitude
39° 16' 30"
West Longitude
94° 54' 30"



FCC File No. BL-7636
Accepted 10-28-59

KCLO
Leavenworth, Kansas

1410 KC


Plotted for increase in power
and installation of DA 12-31-59

2-25-48

KCOL

EXHIBIT NO. I-C-1 1410

10



PAT # H319M11

NO. TOWERS: 2

1 KM RMS : 197.4

KM RMS : —

YL Deg. : 103.17°

YL Feet : 200.0'

QA Feet : 205.0'

PAT. UNIT RMS : 1.0196

K: 193.6

297.3°
0.58 / 0°
272°
1.0 / 0°



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON, D. C. HOLLYWOOD

PATTERN PROPOSED NIGHTTIME
FOR KCOL, FORT COLLINS, COLO.

POWER 1000 Watts FREQ 1410 KCS.

DATE August 19, 1947

BY EFL

2-25-48

MEASURED
NIGHT

KCOL, FORT COLLINS, COLO.


1kw, DAN

CORRECTED

EXHIBIT NO. E-10

KCOL

1410Kc.




HARRISON, TEX

KDOX

PROPOSED DAY Caddo B/C Company 500 KW, DA-D, D
(12-3-56g) / Harrison, Texas

2/17/57



Granted Mod of
CP 10/3/57 to
change antenna
site & altitude
location

FCC File No.
BP-10, 320 (Amended)

Accepted 11-19-56

Caddo B/C Company
Harrison, Texas

1410 KC

KDOX

MEASURED DAY
(8-18-58g)

Station KADO
Marshall, Texas

500w, DA-D,D
1410 KC

*renewed license
1/10/58 for new
station*




Figure 1
MEASURED DAYTIME HORIZONTAL
RADIATION AND EXPANDED
KADO - 1410KC MARSHALL, TEX
500 Watts DA-D

#1 — 80° — #2 — 30° T
1/128 — 1/0

G = 160/165 ft.

KDOX

MEASURED NON-DA
(8-18-58g)

Station KADO
Marshall, Texas

500w, DA-D,E
1410 KC

revised license
1/16/58 for new
station




Figure 2
MEASURED NON-DIRECTIONAL
HORIZONTAL RADIATION
KADO - 1410 KC MARSHALL, TEX
500 Watts DA-D

KJCH


CLEVELAND BROADCASTING CO.

~~KVLE~~PROPOSED
DAY (6/18/53G)

CLEVELAND BROADCASTING CO. CLEVELAND, TEXAS


500w, U, DA-2

1410 kc



THOMAS W. KIRKLEY
CIVIL ENGINEERING
5110 AVENUE F
AUSTIN, TEXAS 78751

WIFE AND ALVIN'S BROTHERS, A
AND ALVIN'S BROTHERS
FATHER AND MOTHER OF ONE SON



$\Delta \text{H} = -90.7 \pm 0.8$ kJ mol⁻¹

A. LAT. $20^{\circ} 29' 05''$

W. 1239. 95° 05' 20"

$\frac{1}{2} \times \frac{1}{2} = \frac{1}{4}$

1050 2001

90° 135'

40 2012

^ 67-56/-150

1. 2. 3.

1

1

01/07/22

0.000000

BL-13,659


EXHIBIT E-3
(AMENDED)

FROM
1410 RMA., C-5 PM., DA-2
CLEVELAND, TEXAS
APRIL 2, 1974

~~KVL~~

1410 KC

SAME PATTERN
DAY & NIGHT

FIGURE 13


KJCH

WILLIAM W. RINESEY
CONSULTING ENGINEER
540 AVENUE B
AUSTIN, TEXAS 78751

WINDSPEEDS IN KNOTS PER HOUR
BASED ON 10 MIN. AVERAGE
WINDSPEEDS BASED ON 10 MIN. AVERAGE

WINDSPEEDS IN KNOTS PER HOUR
BASED ON 10 MIN. AVERAGE

WINDSPEEDS IN KNOTS PER HOUR
BASED ON 10 MIN. AVERAGE



COORDINATES:
N. LAT. 30° 19' 05"
W. LONG. 95° 05' 20"

WIND 123.4 KPH
S 103° 200'
S 200° 383'

1.0/0°
0.89/210°
700° TRUE

BL-13,659

EXHIBIT E-2
(AMENDED)

WIND
1410 KPH, 0.5 KPH, DR-2
CLEVELAND, TEXAS
APRIL 2, 1974


KJCH

KVLB

MEASURED
NCN-DAKVLB, Cleveland, Texas
(3/1/54G)

500W, DA-2

1410 kc



KKOK

PROPOSED DAY ^{#156}
(10-2-59g) *Amended*

New; Ison, McCulla and Masterson
Lompoc, California

500w, DA-D, D
1410 KC

*granted op
for new station
7-18-61*

SITE COORDINATES
34° 39' 46" N
120° 23' 08" W


Figure 6

Horizontal Radiation Pattern

Aubrey H. Ison, James A. McCulla and
Paul C. Masterson, a Partnership
Lompoc, California

1410 kc, 500 w, DA-D

August, 1959



NUGENT S. SHARP
REGISTERED PROFESSIONAL ENGINEER
WASHINGTON, D. C.

FCC File No. BP-13445
Accepted 9-24-59

Aubrey H. Ison, James A. McCulla, and Paul C. Masterson
Lompoc, California
1410 KC

KKOK

Measured Day
(5-28-63ct)


Station KKOK
Lompoc, California

500w, DA-D, D
1410 kc

8-5-63
Granted
new A M
station

EUGENE DIETZEN CO.
MADE IN U.S.A.

NO. 340R-P DIETZEN GRAPH PAPER
POLAR CO-ORD. TE



FCC File No. BL-9966
Accepted 5-1-63

Station KKOK
Lompoc, California

1410 kc

KKOK

Measured Non-DA
(5-28-63ct)


Station KKOK
Lompoc, California

500w, DA-D, D
1410 kc

8-3-63
Granted
license for
new AM
station

EUGENE DIETZEN CO.
MADE IN U.S.A.

NO. 340R-P DIETZEN 0-100 PH PAPER
POLAR CO-ORDI



FCC File No. BL-9966
Accepted 5-1-63

Station KKOK
Lompoc, California


1410 kc

KMYC

PROPOSED
DAY 1/11/56G

STATION KMYC
MARYSVILLE, CALIF. DA-2, U


1410 KC



MEASURED
DAY (9-14-56g)

STATION K M Y C 5 KW, D-1KW, N, U
Marysville, California DA-2

KMYC
1410 KC



FCC File
BL-6286

Accepted 9-6-56

Station KMYC
Marysville, Calif.

1410 KC

KMYC

PROPOSED
NIGHT


KMYC, MARYSVILLE, CAL.

1kw, DA-N

1410 kc

2/26/51G

2-21-51




TOWER PLACEMENT SKETCH		PATTERN PARAMETERS										STATION DATA	
		TOWER	ELECTRICAL HEIGHT	TRUE TOWER ELEVATION	SPECIFIC	PHASING	MINORITIAL FIELD	FIELD RATIO	ELEV. ANGLE	ELEVATION	RECEIVED FIELD	CALL	KMYC
		1	80'	117° E	70'	117° E	1.00	0	117° E	1410	20		
		2	80'	117° E	70'	117° E	1.00	10	117° E	1410	20		
		3											
		4											
		5											
		6											
		7											
		8											
		9											
10													
		DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☒										PATTERN NO. 510107	
MARYSVILLE-YUBA CITY BROADCASTERS MARYSVILLE, CALIFORNIA												FIGURE 1 A GEORGE P. ADAIR Radio Engineering Consultants WASHINGTON, D. C.	

MEASURED
NIGHT

KMYC, MARYSVILLE, CALIF.
10/20/52G

1 KW, U, DA-N

KMYC
1410 KC




MEASURED
NON-DA

KMYC, MARYSVILLE, CALIF.
10/20/52G

1 KW, U, DA-N

1410 KC

KMYC



APPL RECD FCC 8/26/52 ACC 10/8/52 BL-1785

KMYC, MARYSVILLE, CALIF.

1410 KC

KNAL

PROPOSED
NIGHT

KNAL, VICTORIA, TEXAS



500w, DAN

1410 kc

5/10/50G

HORIZONTAL RADIATION PATTERN

5-8-50



KNAL		Victoria, Texas	
Station	1410 kc	0.5 kw	Location 134 mv/m (190/kw)
Frequency	2	Power	R.M.S Field
No. of Elements	MEASURED ☐ CALCULATED ☒	200 ft., 0.286 λ or 103'	Height of Antenna
Pattern	PROPOSED NIGHTTIME PATTERN	No.	500h18.1
Remarks			

Fig. 1

KNAL, Victoria, Tex. 1410 kc

MEASURED
NIGHT


KNAL, VICTORIA, TEXAS

500w, DA-N

KNAL
1410 kc

5/1/51G

4-23-51



O MEASURED VALUES

KNAL

HORIZONTAL RADIATION PATTERN

CALCULATED ——— MEASURED ———

FREQUENCY: 1410 KC.

ASSIGNMENT: 0.5 KW.-U(DA-N)

LONGITUDE: 97 DEG. 00 MIN. 08 SEC.

LATITUDE: 28 DEG. 46 MIN. 48 SEC.

WHEN USED: Nighttime

R.M.S. FIELD: 134 MV/M (Measured)

DATE: April 1951

ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6
PHASE DEG.	00	-250				
HEIGHT DEG.	1030	1030				
FIELD RATIO	1.00	0.90				
NON-DA ANT.	*					

ROBERT M. SILLIMAN

CONSULTING RADIO ENGINEERS

WASHINGTON, D.C.

KNAL, Victoria, Texas 1410 kc

MEASURED
DAY (NON-DA)


KNAL, VICTORIA, TEXAS

500w, DA-N

1410 kc

5/1/51G

4-23-51.



KNAL

HORIZONTAL RADIATION PATTERN
NON-DIRECTIONAL OPERATION

FREQUENCY: 1410 KC.

ASSIGNMENT: 0.5 KW.-U(DA-N)

LONGITUDE: 97 DEG. 00 MIN. 08 SEC.

LATITUDE: 28 DEG. 46 MIN. 48 SEC.

WHEN USED: Daytime

R.M.S. FIELD: 139.5 MV/M (Measured)

DATE: April 1951


ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6
PHASE DEG.						
HEIGHT DEG.						
FIELD RATIO						
NON-DA ANT.						

ROBERT M. SULLIMAN

CONSULTING RADIO ENGINEERS

WASHINGTON, D. C.

KNAL, Victoria, Texas 1410 kc




MEASURED DAY
(4/5/57g)

Station KQV
Pittsburg, Pennsylvania

5kw, DA-2,U

1410 KC



FCC File No. BZ-3637
Accepted 1/7/55

KQV
Pittsburg, Pennsylvania

1410 KC

Description Sheet
(7-28-69ct)

Station KQV
Pittsburgh, Pennsylvania

KQV
5kw, DA-2, U
1410 kc

RECEIVED

EXHIBIT 1

DESCRIPTION OF DAY AND NIGHT ANTENNA SYSTEM
KQV, INCORPORATED
KQV 5 KW-U DA-2 1410 KHz
PITTSBURGH, PENNSYLVANIA

F. C. C.
OFFICE OF THE SECRETARY

- (a) Number Of Towers 3 day 5 night
- (b) Type Of Towers Blaw-Knox Type SK
Self-Supporting
Tapered, series fed.
- (c) Height Of Towers 350 feet above insulators (180°)
355 feet above ground
- (d) Spacing & Orientation Towers are spaced 90°, or 174°
between adjacent towers and are on
a line 330° true.
- (e) Ground System 120-174' minimum length buried copper
radials equally spaced about each
tower. The expanded mesh ground screen
at the base of each tower is 48' square
and is covered with 3/4" asphalt top.
Between adjacent towers a 4" copper
strap runs perpendicular to the line
of towers for the purpose of termination
intersecting radials.
- (f) Top Loading None
- (g) Relative Amplitude
- | | <u>Tower</u> | <u>Daytime</u> |
|--------------------------|--------------|----------------|
| Phase Of The Theoretical | 1 (N.W.) | - |
| Radiated Field With #3 | 2 | .4 / 141/6° |
| Tower As Reference, | 3 | 1.0 / 0° |
| | 4 | .4 / -113.4° |
| | 5 (S.E.) | - |
-
- | | <u>Tower</u> | <u>Nighttime</u> |
|--|--------------|------------------|
| | 1 (N.W.) | .422 / -45° |
| | 2 | .955 / 158.6° |
| | 3 | 1.0 / 0° |
| | 4 | .557 / -159.7° |
| | 5 (S.E.) | .128 / 42° |

North Latitude 40° 31' 17"
West Longitude 80° 00' 34"

FCC File No. BZ-7235
Accepted 7-15-69

Station KQV
Pittsburgh, Pennsylvania

1410 kc

KQV


Measured Day
(7-28-69ct)

Station KQV
Pittsburgh, Pennsylvania

5kw, DA-2, U
1410 kc

WEST

EAST



DAYTIME DIRECTIONAL
HORIZONTAL RADIATION PATTERN
KQV INCORPORATED

KQV 5 KW-U DA-2
1410 KHz
PITTSBURGH, PENNSYLVANIA
Station KQV
Pittsburgh, Pennsylvania


FCC File No. BZ-7235
Accepted 7-15-69

1410 kc

Measured Non-DA
(7-28-69ct)

Station KQV
Pittsburgh, Pennsylvania

KQV
5kw, DA-2, U
1410 kc



NON-DIRECTIONAL
HORIZONTAL RADIATION PATTERN
KQV INCORPORATED

KQV 5 KW-U DA-2
1410 KHz
PITTSBURGH, PENNSYLVANIA

FCC File No. BZ-7235
Accepted 7-15-69

Station KQV
Pittsburgh, Pennsylvania

1410 kc

40-31-17
80-00-34

KQV-1410K


330

0

30

POLAR GRAPH SHOWING
HORIZONTAL PLANE PATTERN
KQV DIRECTIVE ARRAY
5 KW — 1410 KC
SEPTEMBER, 1945


GEORGE C. DAVIS
CONSULTING RADIO ENGINEER
WASHINGTON 4, D. C.



Measured Night
(7-28-69ct)

Station KQV
Pittsburgh, Pennsylvania

KQV
5kw, DA-2, U
1410 kc



NIGHTTIME DIRECTIONAL
HORIZONTAL RADIATION PATTERN
KQV INCORPORATED

KQV 5 KW-U DA-2
1410 KHz
PITTSBURGH, PENNSYLVANIA

FCC File No. BZ-7235
Accepted 7-15-69

Station KQV
Pittsburgh, Pennsylvania


1410 kc

KQV

Measured Night
(9-28-65ct)

Station KQV
Pittsburgh, Pennsylvania

5kw, DA-2, U
1410 kc



FCC File No. BRC-2739
Accepted 9-17-65

Station KQV
Pittsburgh, Pennsylvania


1410 kc

330


0

KRIG ODESSA, TEX.
30 1410

RADIO STATION KRIG
MEASURED HORIZONTAL PATTERN
A EARL CULLUM, JR.
CONSULTING RADIO ENGINEERS
DALLAS 460608



FREQ. 1410 KC.
POWER 1000 WATTS
HOURS DAY & NIGHT
SITE ODESSA, TEXAS
RMS 188 MV/M




KRWB

Proposed Night
(4-24-64)

Station KRWB
Roseau, Minnesota

1kw, DA-N, U
1410 kc

SP-16134
4-19-65 CP
-MG. D to U, DA-N



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
		TOWER No.	ELECTRICAL HEIGHT h	TRUE TOWER ORIENTATION θ	SPACING S	PHASING φ	HORIZONTAL FIELD E	FIELD RATIO F	ELEV. ANGLE θ	ELEVATION RMS FIELD Eg	CALL KRWB
		1	90	166	100	0	1.0	0	190.6	FREQUENCY 1410	
		2	90	346	100	-92	0.8	10		POWER 1.0	
		3						20		TIME OF OPERATION U	
		4						30		TYPE OF OPERATION DA-N	
		5						40		DAYTIME TOWERS 2	
		6						50		NIGHTTIME TOWERS 1, 2	
		7						60		NO. RADIALS PER TOWER 120	
		8						70		LENGTH OF RADIALS 180 ft.	
		9						80		GROUND SCREEN DIMENSION	
		10						90		LAT. 48° 51' 06"	
										LONG. 95° 42' 52"	
										SUPERSEDES	
										PATTERN NO. 631212	
		DAYTIME OPERATION ☐		NIGHTTIME OPERATION ☒							

KRWB


MEASURED

Proposed Night
(12-29-65ct)

Station KRWB
Roseau, Minnesota

1kw, DA-N, U
1410 kc

PAUSED 9/2/68
LICENSE COVERING
AUG 511 HOURS OF
OPERATION ADDITIONAL



C. J. Thomforde Consulting Engineer Grand Forks, No. Dak.	Figure 16 Sept. 1965	HORIZONTAL RADIATION PATTERN K R W B Roseau, Minnesota
--	---------------------------------	---

KVEG
1410 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KVEG Main Studio: North Las Vegas, Nevada
Frequency: 1410 kHz Power: 5kw Night 5kw Day
Notification List No. 1788 Date: August 22, 1980 Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS OF THE DAYTIME AND NIGHTTIME ANTENNA SYSTEM:

DAYTIME

North Latitude: 36° 05' 04"
West Longitude: 115° 00' 34"

NIGHTTIME

North Latitude: 36° 00' 53"
West Longitude: 115° 09' 35"

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
Number of elements: 6
Type of elements: Series excited, uniform cross-section, guyed,
vertical steel towers.

TOWERS:	#1	#2	#3	#4	#5	#6
HEIGHT ABOVE INSULATORS:	160'	160'	160'	160'	160'	160' (82.6°)
NIGHT PHASING:	+23.5°	-21.1°	0°	-19.7°	-6.5°	-23.5°
NIGHT FIELD RATIO:	1.0	1.461	1.09	1.392	0.654	0.569

SPACING AND
ORIENTATION: Adjacent towers in a row are spaced 281' (145°) on a line
bearing 94° true.

GROUND SYSTEM: 120 - 170' equally spaced copper radials plus 120-49'
interspaced radials about each tower. Radials are shortened
and bonded to transverse straps along intersections between
towers.

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (ND-D-482#)
Number of elements: 1
Type of elements: Series excited, uniform cross-section, guyed,
vertical steel towers.

HEIGHT ABOVE
INSULATORS: 430'

GROUND SYSTEM: 120 - 200' equally spaced copper radials about the tower.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL <u>RMS</u>	<u>RSS</u>	STANDARD <u>RMS</u>
Day <u>1</u> /	482 mv/m		
Night	399.9 mv/m		420.2 mv/m

1/ By adjustment of input power.

150°


LAF WAZY

PROPOSED
DAY (2/21/56G)

J.E. WILLIS
LAFAYETTE, IND.

1 KW
DA-D

1410 KC



granted CP 6-24-59

FCC FILE NO. BP-10,253

DATE ACCEPTED 1-3-56

J.E. WILLIS
LAFAYETTE, IND.

1410 KC


WAZY

MEASURED DAY
(12-21-59g)

Station WAZY
Lafayette, Indiana

1kw, DA-D, D
1410 KC


frontier - for new antenna
6-22-60



MEASURED NON-DA
(12-21-59g)

Station WAZY
Lafayette, Indiana

1kw, DA-D, D
1410 KC



FCC File No. BL-7736
Accepted 12-1-59

WAZY
Lafayette, Indiana

1410 KC



Rec'd 12-1-47 30"

20"

1950 TO KPV
Dunkirk - ~~Indiana~~ N.Y.

WDOE ~~1410~~
DUNKIRK, N.Y.
1410

Granted license
1/9/59 for
change from
DA-2 to DA-14



DUNKIRK BROADCASTING CORP.
AMENDMENT OF PROPOSED
1410KC - 500W - U - DA(N)
DUNKIRK, NEW YORK
HORIZONTAL PLANE RADIATION

LAT: 42° 27' 51"
LONG: 79° 21' 21"

RMS = 125 MV/M

DEC. 1947

RUSSELL P. MAY
Consulting Radio Engineer
Washington 4, D. C.

FIG. NO. 2


150° 210° 160° 200° 170° 190° 180° 190° 170° 200° 160° 210° 150°

Rec'd 12-1-47
330

340 *Dunkirk - 1 ~~Delaware~~ New York* 343
20

WDOE

350 DUNKIRK, N.Y.
1410



DUNKIRK BROADCASTING CORP.
AMENDMENT OF PROPOSED
1410KC - 500W - U - DA(N)
DUNKIRK, NEW YORK
ENLARGED
HORIZONTAL PLANE RADIATION

LAT: $42^\circ 27' 31''$
LONG: $79^\circ 21' 21''$


RMS = 125 MV/M

DEC. 1947

RUSSELL P. MAY
Consulting Radio Engineer
Washington 4, D. C.

FIG. NO. 3

*Granted license
1/9/59 for
change from
A-2 to DA-N*



saer

WDOE

MEASURED
NIGHT



WFCB, DUNKIRK, N. Y.

500w, DAN

1410 kc

*Granted CP
10/1/58 to change
from 8A-7 to 8A-N
↑
Granted license
1/9/59
application to
increase power
to 1 Kw*

*Granted CP
2-23-62
to increase day
ND power to 1 Kw
6-24-62
Granted K for
increase in
ND-D power*



DUNKIRK BROADCASTING CORP.
WFCB - 1410 KC - 500 W - DA(M) - U
DUNKIRK, NEW YORK
THEORETICAL AND MEASURED PATTERN

LAT: 42° 27' 51"
LONG: 79° 21' 21"

RMS = 125 MV/M
12/9/49

RUSSELL P. MAY
Consulting Radio Engineer
Washington 4, D. C.

EXHIBIT NO. 5


1410 kc

Granted CP
10/1/58 to change
from PA-2 to PA-N

Granted license
1/9/59

Application to
Increase day
power to 1 Kw
9-9-59

6-24-62
granted & for
increase in
ND day power



WFCB, Dunkirk, N. Y. 1410 kc


WDOE

MEASURED
DAY(non-DA)

WFCB, DUNKIRK, N. Y.

500W, DAN


1410 kc



WFCB, Dunkirk, N. Y. 1410 kc

5kw, DA-N, U
1410 kc

203-10-27-6
rented MCP
to increase #3
over height
194' | 387
300-7-29-64
change hour
operation -
WA-N - granted




LATITUDE: 39° 12' 03"
LONGITUDE: 75° 33' 55"

JOHN H. MULLANEY
AND
ASSOCIATES

A DIVISION OF MULTRONICS INC.

ANTENNA PARAMETERS



Station WDOV
Dover, Delaware

FIGURE 4

NIGHTTIME HORIZONTAL
POLAR PATTERN

RADIO STATION WDOV
DOVER, DELAWARE

1410 KC 5 KW, DA-N, U

1410 kc

FCC File No. BP-15456
Accepted 7-30-63 Amended


Measured Night
(11-29-65ct)

Station WDOV
Dover, Delaware

5kw, DA-N, U
1410 kc

WDOV

10.12-28-65



FCC File No. BL-11069
Accepted 10-27-65


Station WDOV
Dover, Delaware

1410 kc

Measured Non-DA
(11-29-65ct)

Station WDOV
Dover, Delaware

WDOV
5kw, DA-N, U
1410 kc



LATITUDE: 39° 12' 03"
LONGITUDE: 75° 33' 55"

JOHN H. MULLANEY
AND
ASSOCIATES

A DIVISION OF MULTRONICS, INC.

ANTENNA PARAMETERS

TOWER #1
G=100°
RESISTOR CONTROLLED
RADIATION

FIGURE 24

MEASURED NON-DIRECTIONAL
POLAR PATTERN

RADIO STATION WDOV
DOVER, DELAWARE

1410 KC

5 KW, DA-N, U

FCC File No. BL-11069
Accepted 10-27-65

Station WDOV
Dover, Delaware

1410 kc

WELM

PROPOSED NIGHT
(5-28-59g)

Station WELM
Elmira, New York

500w, 1kw-LS, DA-N,U
1410 KC

(Amended)
M. E. O. V.
(Enlarged Scale)

granted - 1-22-57 - for
change and DA-N


as granted in per WELM

1410 KC

WELM - Elmira, New York; BMP-8752. Granted (11-2-59) modification of CP to change transmitter location. New coordinates are:

North Latitude 42° 07' 11"
West Longitude 76° 48' 37"

(This application was accepted for filing on October 23rd.) Make notation on Proposed Night pattern dated 5-28-59g.





COMMERCIAL RADIO EQUIPMENT CO.
RADIO ENGINEERING CONSULTANTS
WASHINGTON, D. C.

HORIZONTAL PATTERN
PROPOSED NIGHTTIME
WELM, Elmira, N. Y.
1-D/0.5-N 1410 KC
4-20-59

FCC File No. BP-12063
Accepted 5-6-59

WELM
Elmira, New York


1410 KC

MEASURED NIGHT
(7-29-60g)

Station WELM
Elmira, New York

500w, 1kw-LS, DA-N, U
1410 kc


9



HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION

TRUE NORTH



APPLICANT	WELM
LOCATION	ELMIRA, NEW YORK
FREQUENCY	1410 KC/S
POWER	1 KW-LS; 0.5 KW-N(DA-N)
LATITUDE	42 DEG 07 MIN 11 SEC
LONGITUDE	76 DEG 48 MIN 37 SEC
WHEN USED	NIGHTTIME
RMS FIELD	140 MV/M
DATE	JUNE 1960

ROBERT M. SILLIMAN & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-8003
Accepted 7-20-60

WELM
Elmira, New York


1410 kc

MEASURED NON-DA
(7-29-60g)

Station WELM
Elmira, New York

500w, 1kw-LS, DA-N,U
1410 kc

10



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

NOTE: No. 2 TOWER USED FOR DAYTIME NON-DIRECTIONAL OPERATION

APPLICANT :	WELM
LOCATION :	ELMIRA, NEW YORK
FREQUENCY :	1410 KC/S
POWER :	1 KW-LS; 0.5 KW-N(DA-N)
LATITUDE :	42 DEG 07 MIN 11 SEC
LONGITUDE :	76 DEG 48 MIN 37 SEC
WHEN USED :	DAYTIME
RMS FIELD :	192 MV/M
DATE :	JUNE 1960

ROBERT M. SILLIMAN & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-8003
Accepted 7-20-60

WELM
Elmira, New York

1410 kc

PROPOSED DAY
(6-20-58g)

New; Regional B/C Co. 1kw, DA-D,D
Halfway-Funkstown, Maryland 1410 KC

10-13-61
granted CP for
new station
over
10-26-62
granted L for
new station




Figure 1
Proposed Daytime
Horizontal Radiation Pattern
Regional Broadcasting Company
Halfway-Funkstown, Maryland
1410kc 1kw DA-D
May, 1958

WHAG


Measured Day
(8-28-67ct)

Station WHAG
Halfway, Maryland

1kw, DA-D, D
1410 kc

EUGENE DIETZEN, ED.
MADE IN U. S. A.

NO. 340R - P. DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BRC-3165
Accepted 8-25-67

Station WHAG
Halfway, Maryland

1410 kc

WHAG

Measured Day
(7-27-62ct)


Station WHAG
Halfway, Maryland

1kw, DA-D, D
1410 kc

0-26-62
printed for
new station

LUGENE DIVISION CO.

NO 140R - P. DIETZGEN, GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-9404
Accepted 6-22-62


Station WHAG
Halfway, Maryland

1410 kc

PROPOSED DAY NULLS
(6-20-58g)

New; Regional B/C Co.
Halfway-Funkstown, Maryland

1kw, DA-D,D
1410 KC



FCC File No. BP-11,646
Accepted 6-4-58 (Amended)


Regional Broadcasting Company
Halfway-Funkstown, Maryland 1410 KC

WHAG

Measured Non-DA
(7-27-62ct)

Station WHAG
Halfway, Maryland

1kw, DA-D, D
1410 kc




FCC File No. BL-9404
Accepted 6-22-62

Station WHAG
Halfway, Maryland

1410 kc


GEORGE C. DAVIS
CONSULTING RADIO ENGINEER
WASHINGTON, D. C.




PATTERN No. 440222
SUPERSEDES:
REINSTATES:


POLAR GRAPH OF
GROUND PLANE PATTERN FOR
WING PROPOSED DIRECTIVE ARRAY


GEORGE C. DAVIS
CONSULTING RADIO ENGINEER
WASHINGTON 4, D. C.





WIZM





WLAQ


PROPOSED
NIGHT

WLAQ, ROME, GA.

1kw, DAN

FIGURE 10

1410 kc



WLAQ

MEASURED
NIGHT


WLAQ, ROME, GA.

5-17-50


1kw, DAN

1410 kc
FIGURE 9

5/19/50G



MEASURED HORIZONTAL PLANE RADIATION PATTERN FOR NIGHTTIME OPERATION



WLAQ
NEWS PUBLISHING COMPANY
ROME GEORGIA

WELDON & CARR
CONSULTING RADIO ENGINEERS
WASHINGTON DALLAS SEATTLE

WLAQ
ROME GEORGIA
1410 KC 1 KW U DA-N
W 500506 B

WLAQ, Rome, Ga. 1410 kc

WLAQ


PROPOSED
NIGHT NULLS

WLAQ, ROME, GA.

1kw, DAN

FIGURE 11

1410 kc



CALCULATED HORIZONTAL PLANE RADIATION PATTERN FOR NIGHTTIME OPERATION

DETAILS IN MINIMA	RADIO STATION WLAQ NEWS PUBLISHING COMPANY ROME GEORGIA	PROPOSED WLAQ OPERATION ROME GEORGIA 1410 KC 1 KW U DAN W 490702 B
	WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON DC DALLAS TEXAS	


MEASURED
NIGHT NULLS

WLAQ, ROME, GA.

5-17-50

1kw, DAN

WLAQ
1410 kc
FIGURE 10



MEASURED HORIZONTAL PLANE RADIATION PATTERN FOR NIGHTTIME OPERATION

DETAIL IN MINIMA	WLAQ NEWS PUBLISHING COMPANY ROME GEORGIA	WLAQ ROME GEORGIA 1410 KC 1 KW U DA-N W 500806 A
	WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON DALLAS SEATTLE	

WLAQ, Rome, Ga. 1410 kc


MEASURED
DAY(non-DA)

WLAQ, ROME, GA.

5-17-50

1kw, DAN

1410 kc
FIGURE 11



MEASURED NON-DIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN FOR DAYTIME OPERATION

6° 30'	WLAQ NEWS PUBLISHING COMPANY ROME GEORGIA WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON DALLAS SEATTLE	WLAQ ROME GEORGIA 1410 KC 1 KW U DA-N # 500608 C
---------------	--	--

WLAQ, Rome, Ga. 1410 kc

PROPOSED
NIGHT 3/23/49G.

WLBK, BOWLING GREEN, KY.

3-21-49



1kw, DAN

1410kc

over WLBK

Application
accepted for
change of A-N to
D-A-N

2-26-62
partially L for
3A-N operation
BL 9233
2-15-62 -
granted L
for class
operation



SITE: 36° 59' 46" N
86° 24' 13" W

PROPOSED HORIZONTAL PLANE PATTERN

WLBK

BOWLING GREEN BROADCASTING COMPANY
BOWLING GREEN, KENTUCKY

PRESENT: 1340 KC - 250 W - U
PROPOSED: 1410 KC - 1 KW - U - DA - M

A. D. RING & CO.
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

WLBJ

MEASURED
NIGHT


WLBJ, BOWLING GREEN, KY.

1 kw, 5kw-LS, DA-2


1110 KC

*Application
adapted to
DA-2 to
DA-N*

*2-26-62
granted
for DA-N
operation*



WLBJ, BOWLING GREEN, KY. 1110 kc





WLSH

Measured Day
(5-25-62ct)

Station WLSH
Lansford, Pennsylvania

1kw, DA-D, D
1410 kc

*8-13-62
rented L for
increase in day power
and DA D*



North Latitude 40° 50' 40"
West Longitude 75° 50' 37"

FIGURE 8
HORIZONTAL RADIATION PATTERN
(DIRECTIONAL OPERATION)
MINERS BROADCASTING SERVICE, INC.
WLSH 1KW-D, DA 1410KC
LANSFORD, PENNSYLVANIA

Prepared by
Lohnes and Culver Washington 4, D.C.
March 1962

FCC File No. BL-9273
Accepted 5-16-62

Station WLSH
Lansford, Pennsylvania


1410 kc

WLSH

Measured Non-DA
(5-25-62ct)

Station WLSH
Lansford, Pennsylvania

1kw, DA-D, D
1410 kc



North Latitude 40° 50' 40"
West Longitude 75° 50' 37"

FIGURE 7
HORIZONTAL RADIATION PATTERN
(NON-DIRECTIONAL #1 TOWER TEST OPERATION)
MINERS BROADCASTING SERVICE, INC.
WLSH 1KW-D, DA 1410 KC
LANSFORD, PENNSYLVANIA

Prepared by

Lohnes and Culver

Washington 4, D.C.

March 1962

1410 kc


FCC File No. BL-9273
Accepted 5-16-62

Station WLSH
Lansford, Pennsylvania

Measured Night Nulls
(9-25-70ct)

Station WMYR
Ft. Myers, Florida

WMYR
5kw, OA-N, U
1410 kc



FCC File No. BL-12718
Accepted 8-26-70

Station WMYR
Ft. Myers, Florida


1410 kc

WMYR

Measured Non-DA
(9-25-70oct)

Station WMYR
Ft. Myers, Florida

5kw, DA-N, U
1410 kc



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT: ROBERT C. HECKSHER
LOCATION: FORT MYERS, FLORIDA
FREQUENCY: 1410 KHz
POWER: 5 KW
LATITUDE: 26 DEG 32 MIN 25 SEC
LONGITUDE: 81 DEG 51 MIN 18 SEC
WHEN USED: NIGHTTIME
RMS FIELD: 436 MV/M
DATE: JANUARY 1970

SILLIMAN, MOFFET & KOWALSKI

CONSULTING RADIO ENGINEERS

WASHINGTON, D.C.

FCC File No. BL-12718
Accepted 8-26-70

Station WMYR
Ft. Myers, Florida

1410 kc


WMYR

Proposed Night
(11-29-62ct)

Station WMYR
Fort Myers, Florida


5kw, DA-N, U
1410 kc

PL 4-29-65
N TO 5 KW
P-17943
GRANTED
CP
12-28-67
O REPLACE
EXPIRED
PERMIT



HORIZONTAL RADIATION PATTERN

AMENDED



APPLICANT	ROBERT C. HECKSHER
LOCATION	FORT MYERS, FLORIDA
FREQUENCY	1410 KC/S
POWER	5 KW
LATITUDE	26 DEG 37 MIN 23 SEC
LONGITUDE	81 DEG 51 MIN 18 SEC
WHEN USED	N. QUIT TIME
R.M.S. FIELD	442.9 MV/M
DATE	AUGUST 1962

SILLIMAN, HOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-14378
Accepted 11-16-62 Amended

Station WMYR
Fort Myers, Florida

1410 kc


WMYR

Proposed Night Nulls
(11-29-62ct)

Station WMYR
Fort Myers, Florida

5kw, DA-N, U
1410 kc

APL 9-29-65
N 70.5 KW
BP-17943
GRANTED
CP TO
REPLACE
EXPIRED
PERMIT.
12-28-62



--- MAXIMUM EXPECTED OPERATING VALUES

FIGURE 1-B

HORIZONTAL RADIATION PATTERN

AMENDED

WMYR - FORT MYERS, FLORIDA

EXPANDED VIEW

APPLICANT	ROBERT C. HECKSHER		
LOCATION	FORT MYERS, FLORIDA		
FREQUENCY	1410 KC/S		
POWER	5 KW		
LATITUDE	26 DEG 37 MIN	23 SEC	
LONGITUDE	81 DEG 51 MIN	18 SEC	
WHEN USED	NIGHTTIME		
RMS FIELD	449.9 MV/M		
DATE	AUGUST 1962		

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-14378
Accepted 11-16-62 Amended

Station WMYR
Fort Myers, Florida

1410 kc


WMYR

PROPOSED
NIGHT (10/19/53G)

WMYR, FT. MYERS, FLORIDA

500W, 1KW, -LS, U, DA-N

1410 kc




STATION WMYR FORT MYERS, FLORIDA DIRECTIONAL ANTENNA PATTERN	Figure 1
	1410 KC 500 WATTS NIGHT
	FRANK H. McINTOSH Consulting Radio Engineer Wyatt Building Washington, D. C.

Measured Night
(9-25-70ct)


Station WMYR
Ft. Myers, Florida

WMYR
5kw, DA-N, U
1410 kc



HORIZONTAL RADIATION PATTERN

G - 103°



APPLICANT	ROBERT C. HECKSHER
LOCATION	FORT MYERS, FLORIDA
FREQUENCY	1410 KC/S
POWER	5 KW
LATITUDE	26 DEG 37 MIN 23 SEC
LONGITUDE	81 DEG 51 MIN 18 SEC
WHEN USED	NIGHTTIME
RMS FIELD	440 MV/M
DATE	JANUARY 1970

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, DC

FCC File No. BL-12718
Accepted 8-26-70

Station WMYR
Ft. Myers, Florida

1410 kc


WMYR

MEASURED NIGHT
(10/18/54G)

STATION WMYR,
FORT MYERS, FLORIDA

500 KW, 1KW-LS
DA-N

1410 KC



STATION WMYR FORT MYERS, FLORIDA	Figure 7
	1410 KC 500 WATTS DA-N
MEASURED DIRECTIONAL PATTERN	FRANK H. McINTOSH
	Consulting Radio Engineer Wyatt Building Washington, D. C.


MEASURED DAY
(10/18/54G)

STATION WMYR
FORT MYERS, FLORIDA

500 KW, 1KW-LS
DA-N

WMYR

1410 KC



STATION WMYR
FORT MYERS, FLORIDA

MEASURED NON-DIRECTIONAL
PATTERN

Figure 6

1410 KC
1000 WATTS
DAY

FRANK H. McINTOSH


Consulting Radio Engineer
Wyatt Building
Washington, D. C.

PROPOSED DAY
(5-28-59g)

New; Associated Enterprises
Brockton, Massachusetts

1kw, DA-D,D
1410 KC

11-22-60
granted CP for
new station
11-28-61
granted for
new station



WOKW

MEASURED DAY
(8-22-61ct)

WOKW
Brockton, Massachusetts

1kw, DA-D, D
1410 KC

N 42° 03' 30"
W 71° 02' 40"

11-28-61
order of 10
new station





FIGURE 4
HORIZONTAL RADIATION PATTERN
WOKW, INC.
WOKW 1 KW-D, DA 1410 KC
BROCKTON, MASSACHUSETTS

Prepared by
Lohnes and Culver Washington 4, D.C.
1410 KC June 1961

FCC File No. BL-8601
Accepted 8-16-61

WOKW
Brockton, Massachusetts

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WOTT Main Studio: Watertown, New York
Frequency: 1410 kHz Power: 1kw Night 5kw Day
Notification List No. 1420 Date: April 14, 1971 Class: III

GEOGRAPHICAL LOCATIONS OF THE CENTERS OF THE DAY AND NIGHT ANTENNA SYSTEMS:

<u>Daytime</u>			<u>Nighttime</u>		
North Latitude:	44° 00' 11"		North Latitude:	43° 57' 08"	
West Longitude:	75° 57' 00"		West Longitude:	75° 52' 33"	

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
Number of elements: 4
Type of elements: Series-excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	NW(#1)	SW(#3)	NE(#2)	SE(#4)
HEIGHT ABOVE INSULATORS:	387'	387'	387'	387' (200°)
PHASING:	0°	+36°	+10°	+46°
FIELD RATIO:	1.00	0.98	0.98	0.96

SPACING AND ORIENTATION: The towers are located at the vertices of a parallelogram the long sides of which are 402.6' (208°) in length on a line bearing 174° true. The short sides are 387.2' (200°) in length on a line bearing 69° true.

GROUND SYSTEM: 120 - 162' to 348' equally spaced copper radials plus 120 - interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

Predicted effective Night Field: 210.0 mv/m at rated power.

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (ND-D)
Type of element: Series-excited, uniform cross-section, guyed, vertical steel tower.

2.

WOTT (Cont'd.)

HEIGHT ABOVE


INSULATOR: 175' (90.3°)

GROUND SYSTEM: 120 - 175' equally spaced copper radials plus 120 - 50' inter-spaced radials about the tower.

Predicted effective Day Field: (omnidirectional) 425 mv/m at rated power.

Note: This notification concerns only a change to add new Nighttime operation
of the station with Daytime operation continued as previously notified.

CTR NO 31301A3




TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 8	STATION DATA
#1 200° 69° #2 208° 248.46° #3 122.06° #4	TOWER No.	ELECTRICAL HEIGHT h	SPACING s	PHASING φ	FIELD RATIO F	PROPOSED NIGHTTIME DIRECTIONAL ANTENNA RADIATION PATTERN ***** WOTT Watertown, New York ***** 6/69 θ° = 0.0	CALL WOTT FREQ 1410 KHz POWER 1.0 KW TYPE DA-N TIME NIGHT LAT. N-43-57-08 LONG. W-75-52-33 E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
	1	200		0.0	1.0		
	2	200		10.0	0.98		
	3	200		36.0	0.98		
	4	200		46.0	0.96		
	5						
	6						
	7						
	8						
	9						
	10						

Proposed Night
(10-28-69ct)

Station WOTT
Watertown, New York

WOTT
1kw, 5kw-LS, DA-N, U
1410 kc



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 8	STATION DATA																																																								
A diagram showing four towers labeled #1, #2, #3, and #4. Tower #1 is at the top left. Tower #2 is to its right, with an angle of 200° between them. Tower #3 is below tower #1, with an angle of 208° between them. Tower #4 is to the right of tower #3, with an angle of 122.96° between them. There is also an angle of 248.46° between tower #1 and tower #4. A reference angle of 69°T is shown for tower #2.	<table><tr><th>TOWER</th><th>ELECTRICAL HEIGHT</th><th>SPACING</th><th>PHASING</th><th>FIELD RATIO</th></tr><tr><td>No.</td><td>h'</td><td>s'</td><td>v'</td><td>f'</td></tr><tr><td>1</td><td>200</td><td></td><td>0.0</td><td>1.0</td></tr><tr><td>2</td><td>200</td><td></td><td>10.0</td><td>0.98</td></tr><tr><td>3</td><td>200</td><td></td><td>36.0</td><td>0.98</td></tr><tr><td>4</td><td>200</td><td></td><td>46.0</td><td>0.96</td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></table>	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	No.	h'	s'	v'	f'	1	200		0.0	1.0	2	200		10.0	0.98	3	200		36.0	0.98	4	200		46.0	0.96	5					6					7					8					9					10					PROPOSED NIGHTTIME DIRECTIONAL ANTENNA RADIATION PATTERN ***** WOTT Watertown, New York ***** 6/69	CALL WOTT FREQ 1410 KHz POWER 1.0 KW TYPE DA-N TIME NIGHT LAT. N-43-57-08 LONG. W-75-52-33 E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO																																																											
No.	h'	s'	v'	f'																																																											
1	200		0.0	1.0																																																											
2	200		10.0	0.98																																																											
3	200		36.0	0.98																																																											
4	200		46.0	0.96																																																											
5																																																															
6																																																															
7																																																															
8																																																															
9																																																															
10																																																															
	DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☒					θ° = 0.0																																																									

174°T
FCC File No. BP-18236
Accepted 10-3-69 Amended

Station WOTT
Watertown, New York

1410 kc





FIGURE 8
PAGE 2 OF 16

Proposed Night
(10-28-68ct)

Station WOTT
Watertown, New York

1kw, 5kw-LS, DA-N, U
1410 kc



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 7	STATION DATA	
NO. 1 O NO. 2 O NO. 3 O NO. 4 O NO. 5 O NO. 6 O	TOWER No.	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	WOTT WATERTOWN, NEW YORK ***** MAY - 1968 θ° = 0°	CALL WOTT FREQ 1410 KHz. POWER 1.0 Kw TYPE DA-N TIME UNLIMITED LAT. 43-57-08 LONG. 75-52-33 E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.	
	1	205.5	0	0	1.000			
	2	205.5	90	179.084	5.288			
	3	205.5	180	1.424	5.288			
	4	205.5	270	184.185	5.288			
	5	205.5	360	6.002	5.288			
	6	205.5	450	178.500	1.502			
	7							
	8							
	9							
	10							
DAYTIME OPERATION ☐					NIGHTTIME OPERATION ☒			

FCC File No. BP-18236
Accepted 9-30-68

Station WOTT
Watertown, New York

1410 kc

WOTT

Proposed Night Nulls
(10-28-68cc)

Station WOTT
Watertown, New York

1kw, 5kw-L, 5A-N, U
1410 Kc

1000 MW/M

PAGE 2 OF 15




FIGURE 7

FCC File No. BP-18236
Accepted 9-30-68

Station WOTT
Watertown New York

1410 Kc

136

WPOP

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WPOP

Main Studio: Hartford, Connecticut

Frequency: 1410 kHz

Power: 5 kW

Notification List No. 1676

Date: March 19, 1976

Class:

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 41' 35"
West Longitude: 72° 45' 30"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 2

Type of elements: Series-excited, uniform cross-section, guy
vertical steel towers.

TOWER:	NW(#1)	SE(#2)
HEIGHT ABOVE INSULATORS:	178'	178' (92°)
NIGHT PHASING:	0°	-17.5°
NIGHT FIELD RATIO:	1	0.96
DAY PHASING:	0°	-17.5°
DAY FIELD RATIO:	1.0	0.75

SPACING AND

ORIENTATION: Elements are spaced 447' (230°) on a line bearing 124° true.

GROUND SYSTEM: 120-285' equally spaced copper radials plus a 24' square ground screen about each tower. Radials are shortened to a transverse strap along intersections between towers. Centers of system are bonded together.


Predicted effective Night Field: 421 mv/m at rated power.

Predicted effective Day Field: 425 mv/m at rated power.


Note: Please retain the Daytime directional antenna radiation pattern notification for station WNBC (now WPOP) at New Britain, Connecticut, in the original 1941 notification and attach to this Revised Description Sheet and Nighttime patterns. This notification concerns only changes in the M.E.O.V.s of radiation in the nighttime pattern with daytime operation continued as previously notified.

CTR NO 30616A3

WPOP

Figure 1
Sheet 1 of 13

CALCULATED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN



GREATER CONNECTICUT
BROADCASTING, INC.
HARTFORD, CONNECTICUT

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION WPOP
1410 KHZ
5 KW U DA-2


WPOP

Proposed Day
(8-28-67ct)

Station WPOP
Hartford, Connecticut

5kw, DA-2, U
1410 kc

Figure 1




WPOP

Measured Day
(8-28-67ct)

Station WPOP
Hartford, Connecticut

5kw, DA-2, U
1410 kc

Figure 2




WPOP

Proposed Night
(8-28-67ct)

Station WPOP
Hartford, Connecticut

5kw, DA-2, U
1410 kc

Figure 3



FCC File No. BZ-6493
Accepted 8-15-67

Station WPOP
Hartford, Connecticut

1410 kc


WPOP

Measured Night
(8-28-67ct)

Station WPOP
Hartford, Connecticut

5kw, DA-2, U
1410 kc

Figure 4




WPOP

Measured Non-DA
(8-28-67ct)

Station WPOP
Hartford, Connecticut

5kw, DA-2, U
1410 kc

Figure 5



FCC File No. BZ-6493
Accepted 8-15-67

Station WPOP
Hartford, Connecticut


1410 kc

WPXC

Proposed Day
(9-28-67ct)


New; Prattville Radio, Inc.
Prattville, Alabama

1kw, 5kw-LS, DA-2, U
1410 kc



HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION



APPLICANT : RADIO PRATTVILLE, INC.

LOCATION : PRATTVILLE, ALABAMA

FREQUENCY : 1410 KC/S

POWER : 5 KW-LS, 1 KW-N (DA-2)

LATITUDE : 32 DEG 28 MIN 54.4 SEC

LONGITUDE : 86 DEG 31 MIN 53.3 SEC

WHEN USED : DAYTIME

R.M.S FIELD: 432.656 MV/M (CALCULATED)

DATE : JULY 1967

SILLIMAN, MOFFET & KOWALSKI


CONSULTING RADIO ENGINEERS

WASHINGTON, D.C.

Measured Day
(8-22-69ct)


Station WPXC
Prattville, Alabama

WPXC
1kw, 5kw-LS, DA- 2, U
1410 kc



North Latitude 30° 28' 54.4" NORTH
West Longitude 86° 31' 53.3"

MEASURED HORIZONTAL PLANE PATTERN
WPXC PRATTVILLE, ALABAMA
1410 KHz 5 KW DIRECTIONAL DAY



Engineer: Dwight M. Cleveland

FCC File No. BL-12424
Accepted 8-15-69


Station WPXC
Prattville, Alabama

1410 kc

Proposed Night
(9-28-67ct)


New; Prattville Radio, Inc.
Prattville, Alabama

WPXC
1kw, 5kw-LS, DA-2, U
1410 kc



HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION




APPLICANT :	RADIO PRATTVILLE, INC.
LOCATION :	PRATTVILLE, ALABAMA
FREQUENCY :	1410 KC/S
POWER :	5 KW-LS, 1 KW-N (DA-2)
LATITUDE :	32 DEG 28 MIN 54.4 SEC
LONGITUDE :	86 DEG 31 MIN 53.3 SEC
WHEN USED :	NIGHT-TIME
R.M.S. FIELD :	200,377 MV/M (CALCULATED)
DATE :	DECEMBER 1966

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

Measured Night
(8-22-69ct)

Station WPXC
Prattville, Alabama

WPXC
1kw, 5kw-LS, DA-2, U
1410 kc



FCC File No. BL-12424
Accepted 8-15-69

Station WPXC
Prattville, Alabama

1410 kc


L12424
 started
 1-24-69
 receive
 P for
 new AM
 broadcast
 station

Measured Non-DA
(8-22-69ct)

Station WPXC
Prattville, Alabama

WPXC
1kw, 5kw-LS, DA-2, U
1410 kc

3612424
started
-24-69
license
renewing
P for new
AP for
not
station



FCC File No. BL-12424
Accepted 8-15-69

Station WPXC
Prattville, Alabama

1410 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WRMN Main Studio: Elgin, Illinois
 Frequency : 1410 KHz Power : .5 kW Night 1 kW Day
 Notification: 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE
 DAYTIME AND NIGHTTIME ANTENNA SYSTEMS:

DAYTIME

North Latitude: 42° 02' 43"
 West Longitude: 88° 15' 35"

NIGHTTIME

North Latitude: 42° 00' 21"
 West Longitude: 88° 17' 55"

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 4

Type of elements : Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER	:	<u>S(#1)</u>	<u>SC(#2)</u>	<u>NC(#3)</u>	<u>N(#4)</u>	
HEIGHT ABOVE INSULATORS	:	<u>140'</u>	<u>140'</u>	<u>140'</u>	<u>140'(72°)</u>	
NIGHT PHASING	:	<u>-101°</u>	<u>85.62°</u>	<u>-85.62°</u>	<u>101°</u>	
NIGHT FIELD RATIO:		<u>1.0</u>	<u>2.498</u>	<u>2.498</u>	<u>1.0</u>	

SPACING AND

ORIENTATION: The towers in a row are spaced 174.52' (90°) on a line bearing 35° true.

GROUND SYSTEM: 120 - 150' equally spaced copper radials about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers. Centers of system are bonded together.

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (ND-D)

Number of elements: 1

Type of elements : Vertical steel tower, folded unipole.


HEIGHT ABOVE

INSULATORS

: 253'

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	RMS	RSS	RMS
Day	<u>189</u> mV/m	<u> </u> mV/m	<u> </u> mV/m
Night	<u>130</u> mV/m	<u>399</u> mV/m	<u>137</u> mV/m



Standard Pattern

HORIZONTAL RADIATION PATTERN		0° Standard Pattern	
Theoretical Pattern RMS - 130 MV/M Standard Pattern RMS - 137 MV/M RSS - 385 MV/M <i>this plot is accurate</i> A-140 (72°)		APPLICANT: WRMN LOCATION: Elgin, Illinois FREQUENCY: 1410 KC/S POWER: 500 Watts LATITUDE: 42 DEG 00 MIN 21 SEC LONGITUDE: 88 DEG 17 MIN 55 SEC WHEN USED: Nighttime RMS FIELD: 136.9 MV/M DATE: June 1st, 1976	
		RALPH J. BITZER CONSULTING RADIO ENGINEERS ST. LOUIS, MISSOURI	

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WSRC

Main Studio: Durham, North Carolina

Frequency : 1410 kHz

Power: 5 kW Day

Notification List No. 1776

Date : June 28, 1978

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: $\frac{36^{\circ}}{78^{\circ}}$ $\frac{01'}{51'}$ $\frac{46''}{03''}$
 West Longitude: $\frac{78^{\circ}}{78^{\circ}}$ $\frac{51'}{51'}$ $\frac{03''}{03''}$

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 3

Type of elements : Series excited, uniform cross-section, guyed,
 vertical
 steel towers.

TOWER :	S(#1)	NE(#2)	NW(#3)
HEIGHT ABOVE INSULATORS :	174'	174'	174' (89.8°)
PHASING:	0	+45.55	+82.25
FIELD RATIO:	1.000	0.703	0.820

SPACING AND

ORIENTATION: With the S(#1) tower as reference the NE(#2) tower is spaced
 410.08' (211.63°) on a line bearing 37.93° true and the NW(#3)
 tower is spaced 225.43' (116.34°) on a line bearing 312.97° true.

GROUND SYSTEM: 120-170' equally spaced copper radials about each tower. Radials
 are shortened and bonded to transverse straps along intersections
 between towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL RMS	RSS	STANDARD RMS
DAY	405.97 mV/m	495.17 mV/m	426.27 mV/m

NOTE:


This notification concerns an increase in the Daytime power of the station, a change in site and the use of a directional antenna system.

STANDARD THEORETICAL

JCI 318.938 495.173
 RMI 486.271 405.272
 RND RMI 1.220 1.220

PROPOSED COORDINATES:

N. LAT. 36° 01' 46"
 W. LONG. 78° 51' 03"



TOWER NUMBER	ORIENTATION DEGREES	SPACING DEGREES	FEET	FIELD RATIO	PHASING DEGREES	HEIGHT DEGREES
1	0.000	0.000	0.000	1.000	0.000	30.000
2	37.938	211.632	410.077	0.703	45.550	40.000
3	318.973	116.338	335.427	0.220	33.250	40.000

JOHN H. MULLANEY

CONSULTING
RADIO ENGINEER

RADIO STATION WSRC
 DURHAM, NORTH CAROLINA
 1410 KHz. 5 KW DA-D


FIGURE 3

PROPOSED
DAY

NEW, TAYLORVILLE, ILL.
(The Moyer Bg. Co.)

1kw, DA-D

W 71 M
TAYLORVILLE, ILL.
1410 kc




WTIM

MEASURED
DAY

WTIM, TAYLORVILLE, ILL.
2/7/52G

1 KW, DAY, DA-D

1410 KC



RECD FCC 1/14/52 ACC 1/29/52 BL-4655

WTIM, TAYLORVILLE, ILL.

1410 KC


WTIM

MEASURED
NON-DA

WTIM, TAYLORVILLE, ILL.
2/7/52G

1 KW, DAY, DA-D

1410 KC



RECD FCC 1/14/52 ACC 1/29/52 BL-4655

WTIM, TAYLORVILLE, ILL.

1410 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WPIM Main Studio: Taylorville, Illinois
 Frequency: 1410 kHz Power: 1 kw
 Notification List No. 1755 Date: November 2, 1977 Class: III

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 39° 32' 38"
 West Longitude: 89° 16' 36"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)
 Number of elements: 2
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	SW(#2)	NE(#1)
HEIGHT ABOVE INSULATORS:	174' (90°)	325' (167.7°)
PHASING:	0°	+90°
FIELD RATIO:	1	0.7
SPACING AND ORIENTATION:	Towers are spaced 174.4' (90°) on a line bearing 235° true.	
GROUND SYSTEM:	120-174' equally spaced copper radials plus a 24' square ground screen about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers. Centers of systems are bonded together.	


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL

RMS


Day 201.6 mv/m

Note: Please retain the Daytime directional antenna radiation pattern notified for a new station at Taylorville, Illinois in United States Change List Number 415 dated August 1, 1951 and attach to this Revised Description Sheet. This notification concerns changes in transmitter location, height of towers and ground system.



1410 30 ~~WALA~~ 1410
WONT

PAGE & DAVIS
Consulting Radio Engineers
WASHINGTON, D.C.



PATTERN No.: 410319
SUPERCEDES: 400218
REINSTATES:

W A L A, MOBILE, ALABAMA
PROPOSED DIRECTIVE ANTENNA
FOR NIGHTTIME OPERATION
HORIZONTAL PLANE PATTERN
UNATTENUATED FIELD AT ONE MILE
1410 KILOCYCLES - 5 KILOWATTS

NEW
1420

IFRB Serial No.
[] [] [] [] [] []

FORM FOR THE APPLICATION OF ARTICLE 4 OF THE AGREEMENT
CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

PART I GENERAL INFORMATION

(01) Administration CANADA Sheet No. 423 Date 830907

Assigned frequency (kHz)		(02)	1 4 2 0
Transmitting station	Name of the station	(03)	C A L G A R Y 3 B
	Call sign	(04)	
	Additional identification	(05)	
	Station class	(06)	B
	Operational Status	(07)	P
Country		(08)	CAN
Geographical coordinates of the transmitting station		(09)	1 1 3 W 5 0 1 9 . 5 0 N 5 8 1 1

(11) a) New assignment ☒ b) Modification of characteristic of an assignment recorded in the plan ☐ c) Cancellation of an assignment ☐

(12) Modification under Section 4.2.14 Yes ☐ No ☐

(13) Date of bringing into service or cessation of operation [] [] [] Year Month Day


STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	(21) 1 0 .	(31) 1 0 .
r.m.s. value of radiation for station power (mV/m at 1 km)	(25) 9 1 7 . 3 3	(35) 9 1 7 . 3 3
Antenna type	(26) B	(36) B
Simple vertical antenna electrical height (degrees)	(27) .	(37) .

(44) Remarks	COORDINATION UNDER ARTICLE 4:							
	COUNTRY	USA						
	IN PROGRESS	X						
	ACCEPTANCE OBTAINED							

Description of a directional antenna consisting of vertical conductors

17) SUPPLEMENTARY INFORMATION

NEW
1420



ANTENNA DESCRIPTION SHEET

CALL LETTERS:

(new station)

STATION:

Plessisville, Quebec.

FREQUENCY:

1420 KHz.

POWER:

1 KW D/0.5 KW N.

CLASS:

III (U)

NOTIFICATION LIST NO.

285

DATE: December 21, 1971.

COORDINATES:

North Latitude: $46^{\circ} 12' 47''$

West Longitude: $71^{\circ} 44' 28''$

ANTENNA SYSTEM:

a) Mode of Operation: DA-N

b) Type: two elements, guyed,
triangular cross-section,
series fed.


c) ground system: 120 No. 10 equally
spaced radials of a length of 277'
(0.4) with interconnected straps
buried approximately 8 inches.


ANTENNA MASTS:


	No. 1 South West	No. 2 North East
Orientation (Az)	Ref.	39°
Height above insulator	93.7°	93.7° (180')
Spacing:		208° (400')
Phase: Night	0°	$+22^{\circ}$
Night field ratio:	1.0	0.824

PREDICTED EFFECTIVE
FIELD:


Day: 188 mV/m
Night: 124 mV/m







ROE POLAR CO. MADE IN U.S.A. NEUFEL & ESSER CO.



$Z = 900$

$2390 + j51$

$2490 - j281$

FIGURE No. 5
ANTENNA DE RESECCION EN
FRECUENCIA
209025 209025
CONTRATANTE
RESECCION EN
CLASIFICACION 0.5 820 KHz
Rev. 2/1964

DESCRIPTION SHEET
(10/11/57g)

Station CJMT
Chicoutimi, Quebec, Canada

1kw, DA-1,U

1420 KC

DESCRIPTION OF ARRAY

STATION: C.J.M.T. MAIN STUDIO: Chicoutimi, Que.
POWER: 1 KW FREQUENCY: 1420 KC CLASS: 111
NOTIFICATION LIST NO: 114 DATE: AUGUST 28, 1957

LOCATION:

NORTH LATITUDE: 48° 24' 17"

WEST LONGITUDE: 71° 05' 55"

ANTENNA:

MODE OF OPERATION: Directional full time.
Same pattern day and night.

ELEMENTS: Two, guyed, uniform cross-section, series fed, no top loading.

<u>TOWER:</u>	#1 (N)	#2 (S)
<u>HEIGHT ABOVE INSULATORS:</u>	170' (88.3°)	170' (88.3°)
<u>SPACING:</u>	115.6' (60°)	
<u>PHASING:</u>	0	±132.5
<u>FIELD RATIO:</u>	1	1.6

GROUND SYSTEM: 120 equally spaced radials per mast extending to a maximum distance of 278' (0.4 w.l.), or to the limit of the property where applicable. In no case will the radials be less than 173.4' (0.25 w.l.). The radials will intersect and be bonded on a line equidistant between towers. Radials are No. 10 B & S bare copper wire buried 6 to 8 inches. The existing system will be extended as per Section 7.

PREDICTED EFFECTIVE FIELD: 195 mv/m at 1 mile for 1 KW.


ORIENTATION: Line of towers 15° East of True North.

PROPOSED DAY & NIGHT
(10/11/57g)

Station CJMT 1kw, DA-1, U
Chicoutimi, Quebec, Canada 1420 KC

CJMT

40°E ANTENNA CO-ORDINATE 339.31



Description Sheet
(8-28-67ct)

Station CJVR
Melfort, Saskatchewan

10kw, DA-N, U, Class III
1420 kc

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-N

STATION CALL: CJVR
MAIN STUDIO: Melfort, Saskatchewan
FREQUENCY: 1420 kc/s
POWER: 10 kw
CLASS: III
TIME: Unlimited
NOTIFICATION REFERENCE: #203 Dated: August 13, 1965.
GEOGRAPHICAL LOCATION: Lat 52°47'57", Lon 104°35'25"
ARRAY CHARACTERISTICS: Two elements, guyed, uniform cross section, base insulated, series feed. Height 346.6 feet or 180 degrees. No top loading

ELEMENT	SOUTH	NORTH
bearing	ref	08°
spacing	ref	120° (231.1')
ratio	1.00	0.86
phase	00°	-104°

Ground system 120 radials per tower, #10 AWG bare soft copper wire, spaced uniformly, depth approximately 8 inches. Radials bonded along line between towers and bonded to soft copper strap at tower base. Maximum radial length 277 feet.

Predicted R M S 235 mv/m at 1 mile for 1 kw
743 mv/m at 1 mile for 10 kw


Revised: November, 1965
Mar 1965

5

Proposed Night
(8-28-67ct)

Station CJVR
Melfort, Saskatchewan

10kw, DA-N, U, Class III
1420 kc



ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2

STATION CALL: C K P T
 LOCATION: Peterborough, Ontario.
 FREQUENCY: 1420 kc/s
 POWER: Day 10 kw, 5 kw Night
 CLASS: III
 TIME: Unlimited

NOTIFICATION REFERENCE List No. 342, Dated: July 8, 1975

GEOGRAPHICAL COORDINATES: Lat 44°16'13", Lon 78°17'23"

ARRAY CHARACTERISTICS: Four elements, guyed, uniform cross section, base insulated, series feed. Height 173 feet or 90 degrees. No top loading.

ELEMENT	ONE	TWO	THREE	FOUR
Bearing	ref	349°	343°	343°
Spacing	ref	174.26' 90.5°	346.6' 180°	519.9' 270°
Day R	1.400	1.380	0.600	
Ø	00°	-126.5°	+74°	
Night R	1.000	2.060	1.740	0.650
Ø	00°	-137°	+64°	-85°


Day RMS 585 mv/m at 1 mile for 10 kw
 185 mv/m at 1 mile for 1 kw

Night RMS 411 mv/m at 1 mile for 5 kw
 184 mv/m at 1 mile for 1 kw

Ground System 120 radials per tower, #10 AWG, bare, soft copper wire, spaced uniformly, depth 8 inches approximately. Radials bonded along lines between towers and bonded to soft copper straps at tower bases. Maximum radial length 277 feet

Feb 1975.

5





206
Description Sheet
(2-28-66ct)

Station CKPT
Peterborough, Ontario

CKPT
5kw, DA-2, U, Class III
1420 kc

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2

STATION CALL CKPT
MAIN STUDIO Peterborough, Ontario
FREQUENCY 1420 kc/s
POWER 5000 watts
CLASS III
TIME Unlimited
NOTIFICATION REFERENCE 206, December 14, 1965.
GEOGRAPHICAL LOCATION Lat 44°16'13", Lon 78°17'23"
ARRAY CHARACTERISTICS Four elements, guyed, uniform cross section, base insulated series feed. Height 173 feet or 90 degrees. No top loading.



ELEMENT	ONE	TWO	THREE	FOUR
Bearing	ref	349°	343°	343°
Spacing	ref	90.5° 174.26'	180° 346.6'	270° 519.9'
Day ratio	470	900	530	280
Day phase	00°	-111°	+122°	+03°
Night ratio	1000	2060	1740	650
Night phase	00°	-137°	+64°	-85°
Day RMS	414 mv/m at 1 mile for 5 kw 185 mv/m at 1 mile for 1 kw			
Night RMS	411 mv/m at 1 mile for 5 kw 184 mv/m at 1 mile for 1 kw			



Ground System 120 radials per tower, #10 AWG bare, soft copper wire, spaced uniformly, depth 8 in approximately. Radials bonded on a line between towers and bonded to soft copper strap at tower base. Maximum length 277 ft

NOTE: Please retain daytime radiation pattern notified for CKPT Peterborough in Canadian Change List No. 206 dated December 14, 1965 and attach to this description sheet and nighttime patterns. Dec. 23, 1965.
Spt 1965 # 5

206

Station CKPT
Petersborough

5kw, DA-2, U, Class III
1420 kc



4-06


CKPT

Proposed Night
(2-28-66ct)

Station CKPT
Peterborough, Ontario

5kw, DA-2, U, Class III
1420 kc

MSE POLAR COORDINATE 45 4413
MSE



#134

CKPT

PETERBOROUGH, ONTARIO

DESCRIPTION SHEET
(7-8-59g)New Station
Peterborough, Ontario, Canada500w, 1kw-LS, DA-2, U, Class III
1420 KC

Station: NEW

Main Studio: Peterborough

Frequency: 1420 Kc/s

Power: 1 KW D Class: III
0.5 KW N.

Notification List No: 134

Date: June 5, 1959

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM

North Latitude: 44° 16' 33"

West Longitude: 78° 17' 31"

ANTENNA CHARACTERISTICS

Mode of Operation: DA-2

Number of Elements: 3

Type of elements: Guyed, uniform cross-section,
base insulated, series fed.

TOWER #1 South #2 Centre #3 North

HEIGHT ABOVE INSULATORS: 174' 174' 174(90°)

OVERALL HEIGHT: 178' 178' 178'

SPACING: 331' (172°) 331' (172°)

PHASING: Day 0° 308° not used

Night 65° 0° -75°

FIELD RATIO: Day 1.0 0.6 not used

Night 1.0 1.4 0.6

ORIENTATION: Towers on a line bearing 13° east of true north.

GROUND SYSTEM: 120 radials #10 AWG copper wire spaced evenly around the base
of each tower and of maximum length of 276.5 ft. (0.4 A). Radials inter-
secting each other between towers are bonded to a #4 AWG copper bus.

Predicted effective field Day RMS 185 mv/m (185 mv/m for 1Kw)

Night RMS 129 mv/m (182 mv/m for 1 Kw)


#13A

CKPT

PROPOSED DAY
(7-8-59g)

New Station
Peterborough, Ontario, Canada

500w, 1kw-LS, DA-2, U, Class III
1420 KC




FGT Apr. 14. 1959 W.E. Wright, P. Eng.

TORONTO CANADA

#134

CRPT

PETERBORO, ONTARIO

PROPOSED NIGHT
(7-8-59g)New Station 500w, 1kw-LS, DA-2, U, Class III
Peterborough, Ontario, Canada 1420 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: (NEW) Main Studio: Trenton, Georgia
 Frequency: 1420 kHz Power: 0.5kw Day
 Notification List 1789 Date: September 12, 1980 Class: III
 GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 34° 51' 52"
 West Longitude: 85° 30' 00"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)
 Number of elements: 3
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.


TOWER:	S(#1)	NE(#2)
HEIGHT ABOVE INSULATORS	170'	170' (88.3°)
DAY PHASING:	0°	133°
DAY FIELD RATIO:	1.0	0.65

SPACING AND
 ORIENTATION: Towers in a row are spaced 173.3' (90°) on a line
 bearing 35° true.

GROUND SYSTEM: 120 - 173.3' equally spaced copper radials plus a 48'
 square ground screen about each tower. Radials are shortened
 and bonded to a transverse strap along intersection between
 towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	140.0 mv/m	166.6 mv/m	147.1 mv/m



STANDARD HORIZONTAL PLANE PATTERN

1420 kHz. 0.5 kW.

N. Lat. 34°51'52"

W. Lng. 85°30'00"

Theo. RMS 140.0

Theo. RSS 166.6

E₁ Theo. 139.7

Std. RMS 147.1

FCC 'Q' 6.000

Theo: N-35°-E

#2
0.65/133°

S=90°

#1 1/0°

G₁=G₂=88.3°

EXHIBIT E-1 FIGURE 3

RA-AD of TRENTON

PROPOSED DAYTIME PATTERN

TRENTON, GEORGIA

B. SCOTT BAXTER

AND ASSOCIATES

P. O. BOX 413

BRENTWOOD, TENN 37027

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : (NEW) Main Studio: Granbury, Texas
 Frequency : 1420 KHz Power: .5 kW Night 5 kW Day
 Notification: 1782 Date: October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 32° 27' 43"
 West Longitude: 97° 47' 19"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 4

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER	: <u>NE(#1)</u>	<u>EC(#2)</u>	<u>SE(#3)</u>	<u>W(#4)</u>		
HEIGHT ABOVE INSULATORS	: <u>145'</u>	<u>145'</u>	<u>145'</u>	<u>145' (75.3°)</u>		
NIGHT PHASING:	: <u>--</u>	<u>-16°</u>	<u>--</u>	<u>0°</u>		
NIGHT FIELD RATIO:	: <u>--</u>	<u>1.2</u>	<u>--</u>	<u>1.0</u>		
DAY PHASING	: <u>240°</u>	<u>120°</u>	<u>0°</u>	<u>--</u>		
DAY FIELD RATIO	: <u>1.0</u>	<u>1.56</u>	<u>1.0</u>	<u>--</u>		

SPACING AND ORIENTATION:


With the EC(#2) tower as reference, towers #1 and #3 are spaced 249 feet (145°) on bearing 347° true and 167° true respectively and tower #4 is spaced 456.2' (237°) on a bearing of 258° true.

GROUND SYSTEM: 120 - 173' equally spaced copper radials plus a 20x20' square ground screen about each tower. Radials are shortened and bonded to a transverse strap along inter-sections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL			STANDARD	
	<u>RMS</u>		<u>RSS</u>	<u>RMS</u>	
Day	<u>124.06</u>	mV/m	<u>117.40</u>	<u>131.05</u>	mV/m
Night	<u>125.7</u>	mV/m	<u>151.3</u>	<u>132.1</u>	mV/m

Note:




N. LAT. 32° 27' 43"
W. LNG. 97° 47' 19"


RMS (TH.) = 124.06 MV/M
RMS (ST.) = 131.05 MV/M
RSS (TH.) = 117.40 MV/M

NOT USED

G = 76° S1 = 237° S2 = 145°




STANDARD RADIATION PATTERN
GRANBURY RADIO COMPANY
GRANBURY, TEXAS
1420 KHZ. 0.5 KW, DA-2, U



N. LAT. $32^{\circ} 27' 43''$
W. LNG. $97^{\circ} 47' 19''$

RMS (TH.) 125.7 MV/M
RMS (ST.) 132.1 MV/M
RSS (TH.) 151.3 MV/M



G = 76° S1 = 237° S2 = 145°

STANDARD RADIATION PATTERN

GRANBURY RADIO COMPANY
GRANBURY, TEXAS

1420 KHZ. 0.5 KW, DA-2, U

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KBTN Main Studio: Neosho, Missouri
 Frequency : 1420 KHz Power : .5 kW Night .5 kW Day
 Notification: 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE
DAYTIME AND NIGHTTIME ANTENNA SYSTEMS:

DAYTIME			NIGHTTIME				
North Latitude:	<u>36°</u>	<u>52'</u>	<u>34"</u>	North Latitude:	<u>36°</u>	<u>50'</u>	<u>52"</u>
West Longitude:	<u>94°</u>	<u>23'</u>	<u>07"</u>	West Longitude:	<u>94°</u>	<u>19'</u>	<u>12"</u>

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for nighttime operation (DA-N)
 Number of elements: 2
 Type of elements : Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER.	:	<u>W(#1)</u>	<u>E(#2)</u>	_____	_____	_____
HEIGHT ABOVE INSULATORS	:	<u>173'</u>	<u>173(89.8')</u>	_____	_____	_____
NIGHT PHASING	:	<u>0°</u>	<u>154°</u>	_____	_____	_____
NIGHT FIELD RATIO:		<u>1.0</u>	<u>0.87</u>	_____	_____	_____

SPACING AND

ORIENTATION: Adjacent towers in a row are spaced 115.5' (60°) on a line bearing 86° true.

GROUND SYSTEM: 120 - 173' equally spaced copper radials plus 120 - 58' interspaced radials about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	134.4 mv/m		
Night	134.8 mv/m	231.9 mv/m	142.0 mv/m

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (ND-D)

Number of elements: 1


Type of elements : Series excited, uniform cross-section,
guyed, tapered, vertical steel towers.

HEIGHT ABOVE
INSULATORS

: 173' _____

GROUND SYSTEM: 120 - 170' equally spaced copper radials about the.
tower.

KBTN



$\theta = 60^\circ = 115.5 \text{ FT.}$

N. 86° E.

#1 WEST

S

#2 EAST

$.87 / 154^\circ$

$1 / 0^\circ$

KBTN NEQSHO MISSOURI

Station

1420 KHZ. 0.5 KW OA-N

Frequency Power

G1 = G2 = $90^\circ = 173.2 \text{ FT.}$

Height of Antennas

Location

N. LAT. $36^\circ 50' 52''$

W. LNG. $94^\circ 19' 12''$

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KITI Main Studio: Chehalis-Centralia, Washington
 Frequency: 1420 Power: 1 Kw Night 1 Kw Day
 Notification: 1778 Date: August 30, 1978 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 46° $41'$ $24''$
 West Longitude: 122° $57'$ $23''$

Predicted effective Daytime Field (omnidirectional) $190 \frac{\text{mv}}{\text{m}}$ at rated power.

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-N)
 Number of elements: 2
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER	:	NW (#1)	SE (#2)	_____	_____	_____	_____
HEIGHT ABOVE INSULATORS	:	<u>170'</u>	<u>170'</u>	_____	_____	_____	_____
PHASING	:	<u>0°</u>	<u>+38°</u>	_____	_____	_____	_____
FIELD RATIO	:	<u>1.0</u>	<u>1.0</u>	_____	_____	_____	_____
SPACING AND ORIENTATION	:	Towers in a row are spaced 308' (160°) on a line bearing 99.6° true.					

2.


GROUND SYSTEM: 120 - 180' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse strap along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
180.4 mv/m	194.93 mv/m	189.5 mv/m
_____ mv/m	_____ mv/m	_____ mv/m

Note: This notification concerns only an addition of Nighttime operation of the station with Daytime operation continued as previously notified.

PROPOSED: KITI 1420 Khz.
 Centralia--Chehalis, Washington
 1 Kw Day ND
 1 Kw DA-N



Tower Heights = G 170 Feet (88.42 Deg.)
 No. 1 tower inverse field in array = 137.837 Mv/m
 RSS value = 194.93 Mv/m
 RMS (Theo.) = 180.4 Mv/m
 RMS (Std.) = 189.5 Mv/m

CONSULTING ENGINEER KENNETH WILLIAMS, Jr. PE
 ELECTRICAL • AM/FM BROADCAST • TELEVISION
 321 SOUTH 11th. St. • TACOMA, WASHINGTON 98402

EXHIBIT No. 7

KITN - KITI Corporation • KITI 1420 Khz • CENTRALIA - CHEHALIS, Washington • June, 1976

SUPPLEMENTAL AND CORRECTED
DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KLFB

Main Studio: Lubbock, Texas

Frequency: 1420 kHz

Power: 0.5kw Night 0.5kw Day

Notification List No. 1788

Date: August 22, 1980, Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS OF
THE DAYTIME AND NIGHTTIME ANTENNA SYSTEMS:

DAYTIME

North Latitude: 33° 36' 49"
West Longitude: 101° 52' 30"

NIGHTTIME

North Latitude: 33° 31' 07"
West Longitude: 101° 49' 39"


Note: Please retain the description sheet and directional antenna radiation patterns notified for station KLFB in United States Change List Number 1782, dated October 26, 1979 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a change in the geographical coordinates of the center of the nighttime antenna system.

STANDARD
HORIZONTAL
PLANE PATTERN

EXHIBIT E - 1
1420 kHz
PAGE 6

INFORMATION
U.S.A.
GRAPH PAPER
DATE

NO 3



MEASURED KTRE, LUFKIN, TEX.
DAY (non-DA)

1kw, DAN


KLUF

2/8/50G

12-2-47

BL-2855

G 2/10/48



RMS = 200 MV/M

DAYTIME - ND - SW TOWER

$\phi = N 43^\circ E$

(2) $0.82 / +23^\circ$

S = 208°

G1 = G2 = 104°

(1) $1.0 / 0^\circ$

SITE: $31^\circ 22' 12'' N$
 $94^\circ 46' 19'' W$

PATTERN BASED ON
FIELD INTENSITY MEASUREMENTS

BROADCAST ENGINEERING SERVICE

Radio Engineering Consultants

SHREVEPORT, LA.

471124

RADIO STATION KTRE

1420 KC 1,000 WATTS DA-N

FIGURE


KTRE, Lufkin, Tex. 1420 kc

KLUF

Doc'd 12/1/47

9-2-48-GO

L-2855



E = N 43° E

(2) 0.82 / 23°

S = 208°

S GI = G2 = 104°

(1) 1.0 / 0°

PATTERN BASED ON
FIELD INTENSITY MEASUREMENTS

BROADCAST ENGINEERING SERVICE

Radio Engineering Consultants

SHREVEPORT, LA.

471124

RADIO STATION KTRE

1420 KC 1,000 WATTS DA-N

FIGURE 1A


LUFKIN, TEX.

KLUF

PROPOSED
NIGHT

KTRE, LUFKIN, TEXAS

11kw





KLUF

Measured Non-DA
(9-26-69ct)

Station KTRE
Lufkin, Texas

1kw, DA-N, U
1420 kc



G - 104°
S - 208°

RADIO STATION KTRE
LUFKIN, TEXAS

MEASURED NON-DIRECTIONAL
HORIZONTAL PLANE RADIATION PATTERN
1420 KHZ 1000 WATTS

102568-1

MERL SAXON

CONSULTING RADIO ENGINEER
LUFKIN, TEXAS

FIGURE 1
Station KTRE
Lufkin, Texas

FCC File No. BZ-7283
Accepted 9-18-69



1420 kc

KLUF

Measured Night
(9-26-69ct)

Station KTRE
Lufkin, Texas

1kw, DA-N, U
1420 kc



RADIO STATION KTRE
LUFKIN, TEXAS

MEASURED DIRECTIONAL
HORIZONTAL PLANE RADIATION PATTERN
1420 KHZ
1000 WATTS

102568-2

FIGURE 2

MERL SAXON
CONSULTING RADIO ENGINEER
LUFKIN, TEXAS

FCC File No. BZ-7283
Accepted 9-18-69

Station KTRE
Lufkin, Texas


1420 kc

K000

Measured Day
(12-27-68ct)

Station K000
Omaha, Nebraska

1kw, DA-D, D
1420 kc



FCC File No. BZ-7012
Accepted 12-3-68

Station K000
Omaha, Nebraska


1420 kc

K000

Measured Non-DA
(12-27-68ct)

Station K000
Omaha, Nebraska

1kw, DA-D, D
1420 kc



FCC File No. BZ-7012
Accepted 12-3-68

Station K000
Omaha, Nebraska

1420 kc


K000

PROPOSED DAY
(10/30/57g)

Station K000
Omaha, Nebraska

1kw, DA-D,D
1420 KC

*granted for increase in power
to 15-60*



FCC File No. BP-11,568-12,252
 Accepted 10-9-57

K000
Omaha, Nebraska


1420 KC

K000

MEASURED DAY
(7-7-60g)

Station K000
Omaha, Nebraska

1kw, DA-D,D
1420 KC



700 mV 100 mV minimum - power
8 25 60


K000

MEASURED NON - DA
(4/16/57g)

Station K000
Omaha, Nebraska

1420 KC

40



FCC File No. BL-6569
Accepted 4/1/57

K000
Omaha, Nebraska

1420 KC

KPAR
1420kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KPAR Main Studio: Granbury, Texas
 Frequency: 1420 kHz Power: 0.5kw Night 0.5kw Day
 Notification List No. 1789 Date: September 12, 1980 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 32° 27' 43"
 West Longitude: 97° 47' 19"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
 Number of elements: 4
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	NE(#1)	EC(#2)	SE(#3)	W(#4)
HEIGHT ABOVE INSULATORS:	145'	145'	145'	145' (75.4°)
NIGHT PHASING:	—	-16°	—	0°
NIGHT FIELD RATIO:	—	1.2	—	1.0
DAY PHASING:	+240°	+120°	0°	—
DAY FIELD RATIO:	1.0	1.56	1.0	—

SPACING AND ORIENTATION:

With Tower #2 as reference Tower #1 and Tower #3 are spaced
 249' (145°) on bearings of 347° true and 167° true
 respectively and Tower #4 is spaced 456' (237°) on a
 bearing 258° true.

GROUND SYSTEM: 120 - 173' equally spaced copper radials plus a 20'
 square ground screen about each tower. Radials bonded
 to a transverse strap along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL				STANDARD	
	RMS		RSS		RMS	
Day	124.06	mv/m	117.4	mv/m	131.05	mv/m
Night	125.7	mv/m	151.3	mv/m	132.1	mv/m


MODIFIED PATTERN AUGMENTATION

<u>Azimuth at Maximum Augmentation</u>	<u>Augmented Radiation E₂</u>	<u>Span of Augmentation From - To</u>	
34.0°	16	26°	42°
68.5°	16	60.5°	76.5°
265.5°	16	257.5°	273.5°
300.0°	16	292°	308°
347.0°	88	320°	14°

Note: Please retain the Nighttime directional antenna radiation pattern notified for a new station in Granbury, Texas on 1420 kHz in United States Change List Number 1782 dated October 26, 1979 and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in the Daytime operation of the station with Nighttime operation continued as previously notified.

KPAR 1420 kHz

C. P. CROSSNO & ASSOCIATES
BROADCAST CONSULTANTS, ENGINEERS




N. LAT. 32° 27' 43"
W. LNG. 97° 47' 19"

DAYTIME PATTERN

RMS (TH.) 124.06 MV/M
RMS (ST.) 131.05 MV/M
RSS (TH.) 117.40 MV/M

MODIFIED STANDARD RADIATION PATTERN

RADIO STATION KPAR
GRANBURY, TEXAS
1420 KHZ. 0.5KW, DA-2-U




AUGMENTATION DATA		
AZIMUTH	SPAN	MV/M
34.0°	16°	16
68.5°	16°	16
265.5°	16°	16
300.0°	16°	16
347.0°	54°	88

G=76° S1=237° S2=145°


FIG.

1



N. LAT. 32° 27' 43"
W. LNG. 97° 47' 19"

RMS (TH.) 125.7 MV/M
RMS (ST.) 132.1 MV/M
RSS (TH.) 151.3 MV/M



75.36 331.1
G = 76° S1 = 237° S2 = 145°

NIGHTTIME PATTERN

BL-800227A3

STANDARD RADIATION PATTERN

GRANBURY RADIO COMPANY
GRANBURY, TEXAS

1420 KHZ. 0.5 KW, DA-2, U

KPAR



KPEL

PROPOSED
NIGHT

KLFY, LAFAYETTE, LA.

500w, DA-N

1420 kc



KLFY Lafayette, La.		Location
Station	1420 kc	0.5 kw
Frequency	2	134 mv/m (190/2.7)
No. of Elements	MEASURED ☐ CALCULATED ☒	194 ft., 0.28 λ or 101°
Height of Antenna	50117.1 supercedes 500504.1	
Pattern	No.	
PROPOSED NIGHTTIME PATTERN		
Remarks		

AMENDMENT RECD 11/30/50 ACC 12/8/50 BP-7666

KLFY, Lafayette, La. 1420 kc

KFEL

MEASURED
NIGHT
9/19/51G

KLFY, LAFAYETTE, LA.

500W, 1KW-LS, U, DA-N

1420 KC

HORIZONTAL RADIATION PATTERN





EXHIBIT 2



L. J. N. du Treil & Associates
CONSULTING RADIO ENGINEERS
204 H. Melis's Avenue
NEW ORLEANS 13, LA


KLFY Lafayette, La.
1420 KC - 0.5 KW
2 Elements 194 ft
.28 λ or 101°
NIGHTTIME PATTERN

MEASURED
NON-DA
9/19/51G

KLFY, LAFAYETTE, LA.

500W, 1 KW-LS, U, DA-N

KFEL
1420 KC



RMS
200 MV/M
DAY TIME

L. J. N. du Trell & Associates
CONSULTING RADIO ENGINEERS
204 Homedale Avenue
NEW ORLEANS 19, LA.

KLFY Lafayette, La.
1420 KC — 1.0 KW
Non Directional —

APPL RECD 8/27/51

HL-4529

KLFY, LAFAYETTE, LA.

1420 KC

KREN


Proposed Day
(5-25-62ct)

New; Washington Broadcasting Co. 500w, DA-D, D
Renton, Washington 1420 kc

J. B. HATFIELD
CONSULTING RADIO ENGINEER
908 86TH AVENUE
SEATTLE 22, WASHINGTON

North Latitude $47^{\circ} 27' 17''$
West Longitude $122^{\circ} 12' 57''$

0-12-63
routed CP
to new station



FCC File No. BP-15448
Accepted 5-3-62

New; Washington Broadcasting Co.
Renton, Washington

1420 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KSCR Main Studio: Renton, Washington
 Frequency : 1420 KHz Power : _____ Night .5 kW Day
 Notification: 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE

CENTER OF THE ANTENNA SYSTEM: North Latitude: 47 ° 28 ' 37 "
 West Longitude: 122 ° 14 ' 30 "

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers..

TOWER : W(#1) E(#2) _____

HEIGHT ABOVE
 INSULATORS : 150' 150'(78.5°) _____

DAY PHASING: : 106.5° 0.0° _____

DAY FIELD RATIO: 1.0 1.0 _____

SPACING AND

ORIENTATION: Adjacent towers in a row are spaced 173.2' (90°) on a line
 bearing 70° true.


GROUND SYSTEM: 120 - 170 equally spaced copper radials about each tower.
 Radials are shortened and bonded to a transverse strap
 along intersections between towers. Centers of system
 are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	<u>RMS</u>	THEORETICAL	<u>RSS</u>	STANDARD	<u>RMS</u>
Day	<u>135</u>	mV/m	<u>145</u>	mV/m	<u>141.8</u>

Note:

KSCR



PATTERN NO.
SUPERSEDES:

NEW - 1420 KC

KSTN

330 340 350 0 10 20 STOCKTON 30
110° 80° T.
1.3/4 1.37



R & C-II/45




FIG. 1

PROPOSED HORIZONTAL
PLANE PATTERN

NEW STATION
STOCKTON — CALIF.
1420 KC — 1 KW — U — DA-N

RING & CLARK
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

KSTN

PROPOSED
DAY (8-2-56g)

STATION KSTN
STOCKTON, CALIF

1 KW - 5 KW
DA-2, U

1420 KC

KSTN Stockton 1420 K0


340-5 KW-D

GRANT R. WRATHALL

Consulting Radio Engineer

APTOS, CALIFORNIA

N 37°55'31.5", W 121°14'44.5"



KSTN

MEASURED DAY
(12-21-59g)


Station KSTN
Stockton, California

1kw, 5kw-LS, DA-2, U
1420 KC

8-18-60 granted & in Charge to
DA-2 operation.

CODEX ROCK COMPANY INC. NORWOOD MASSACHUSETTS

NO. 3124, POLAR CO-ORDINATE.



PROOF OF PERFORMANCE
KSTN STOCKTON, CALIF.
5 KW DA-D 1420 KC
Oct. 29, 1959

FCC File No. BL-7714
Accepted 11-18-59

KSTN
Stockton, California

1420 KC

KSTN

MEASURED NIGHT
(12-21-59g)Station KSTN
Stockton, California1kw, 5kw-LS, DA-2, U
1420 KC

0—95°—0—80.5 T.
1/2 0.82 / 42.2

NL 37° 55' 31.5"
WL 121° 14' 44.5"

Scale X .1

300
MV/M
200

Scale X .1

o = Radial Measurement

RMS = 210 mv/m

PROOF OF PERFORMANCE
KSTN STOCKTON, CALIF.
1 KW DA-N 1420 KC
Oct. 29, 1959

FCC File No. BL-7714
Accepted 11-18-59

KSTN
Stockton, California

1420 KC


8-18-60 Granted 1.70 change
to DA-2 operation.

KSTN

MEASURED NON-DA
(12-21-59g)Station KSTN
Stockton, California1kw, 5kw-LS, DA-2, U
1420 KC

CODEK BOOK COMPANY, INC. NORWOOD, MASSACHUSETTS

NO 3124 POLAR CO-ORDINATE.

FCC File No. BL-7714
Accepted 11-18-59KSTN
Stockton, California

1420 KC


Measured Non-DA
(10-26-64ct)

Station KHFH
Sierra Vista, Arizona

5C

KTAN

1420 kc



RMS = 186 MV/M

OSCAR LEON CUELLAR
AM - FM - TV
TUCSON, ARIZONA

RADIO STATION KHFH
1420 KC, 1KW-D, 500W-N, DA-N
SIERRA VISTA, ARIZONA
ESTHER MORRIS

FCC File No. BL-10644
Accepted 10-5-64

Station KHFH
Sierra Vista, Arizona

1420 kc

MAY 1964


KTAN

Measured Night
(10-26-64ct)

Station KHFH
Sierra Vista, Arizona

5.
1420 kc

F202-
0-9-64
printed L
a DA-N



OSCAR LEON CUELLAR
AM - FM - TV
TUCSON, ARIZONA

RADIO STATION KHFH
1420 KC, 1KW-D, 500W-N, DA-N
SIERRA VISTA, ARIZONA
ESTHER MORRIS

FCC File No. BL-10644
Accepted 10-5-64

Station KHFH
Sierra Vista, Arizona

MAY 1964
1420 kc


KTAN

PROPOSED NIGHT
(10-25-61ct)

Station KHFH
Sierra Vista, Arizona

500w, 1kw-LS, DA-N, U
1420 kc

PAGE 5



FCC File No. BP-14159
Accepted 10-17-61

Station KHFH
Sierra Vista, Arizona

1420 kc

KTOE


PROPOSED
NIGHT (8/19/54G)

KTOE
MANKATO, MINNESOTA

5KW DA-n UNLIMITED

1420kc

11 Lat. 44° 10' 06" N
Long. 93° 54' 37" W



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

PATTERN: PROPOSED NIGHTTIME
FOR: KTOE, MANKATO, MINN.

POWER: 5 KW

FREQ: 1420 KC

FCC FILE NO. BP-8702 (AMENDED)
DOCKET NO. 10592

DATE ACCEPTED 7-16-54

1420kc


1420k c

KTOE
MANKATO, MINNESOTA

5KW DA-N UNLIMITED

Long. 93° 54' 37" W

MAXIMUM EXPECTED
OPERATING VALUE



RMS = 398 MV/M

ALL $G'_{\text{a}} = 103.9^\circ$

EXPANDED MINIMA



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON, D. C.

PATTERN: PROPOSED NIGHTTIME

FOR: KTOE, MANKATO, MINN.

POWER: 5 KW

FREQ: 1420 KC

DATE:

FOC FILE NO. BP-8702 (AMENDED)
DOCKET NO. 10592

DATED ACCEPTED 7-16-54

1420 kc


KTOE

MEASURED
NIGHT (2/21/56G)

STATION KTOE
MANKATO, MINN.

5 KW
DA-N, U

1420 KC




KTOE

MEASURED
NON-DA (2/21/56G)

STATION KTOE
MANKATO, MINN.

5 KW
DA-N, U

1420 KC



KUJ
1420

340


NORTH

20

**NIGHT HORIZONTAL
PLANE RADIATION**
PROPOSED KUJ 5KW-1420KC.
WALLA WALLA, WASH.

PAUL GODLEY CO.
CONSULTING RADIO ENGINEERS
LABORATORIES: GREAT NOTCH, N.J. 5/46


FIG. 2




KUJ

1420

9/17/48 G



KUJ
1420



KULY

Proposed Day
(7-29-64ct)


New; Grant County B/cg Co., Inc.
Ulysses, Kansas

500w, 1kw-LS, DA-2, U
1420 kc

EXHIBIT NO. E-2

(Amended)

8-21-64
#200
granted CP
for new station



312° TRUE
NO.1 1/0°
G = 78°
RMS=187.5MV/M
NO.2 0.612/98.4°

COMMERCIAL RADIO EQUIPMENT CO.
Radio Engineering Consultants
WASHINGTON, D. C.
MAY 1964

PROPOSED DAYTIME
DIRECTIONAL PATTERN
ULYSSES, KANSAS
1420 KC, 1 KW-D, 500 W-N


Proposed Night
(7-29-64ct)

New; Grant County B/cg Co., Inc.
Ulysses, Kansas

500w, 1kw-LS, DA-2, U
1420 kc

EXHIBIT NO. E-4

(Amended)



COMMERCIAL RADIO EQUIPMENT CO.

Radio Engineering Consultants

WASHINGTON, D. C.

MAY 1964

PROPOSED NIGHTTIME
DIRECTIONAL PATTERN
ULYSSES, KANSAS

1420 KC, 1 KW-D, 500 W-N

FCC File No. BP-16076

New; Grant County B/cg Co., Inc.

Accepted 7-17-64 Amended Ulysses, Kansas

1420 kc

KULY

Measured Day
(5-27-65ct)


Station KULY
Ulysses, Kansas

500w, 1kw-LS, DA-2, U
1420 kc

N. Latitude 37° 32' 53"
W. Longitude 101° 21' 49"

Engineer: W. H. Bradley

LIC.
6-7-65



————— CALCULATED ——— RMS: 187.5 MV/M ----- MEASURED, MEAN OF VALUES DAY, ONE PW DIRECTIONAL PATTERN EXHIBIT # 1 DATED: JAN. 23, 1965 DAY .. 1000 WATTS	Figure 12-2 STATION K U L Y Ulysses, Kansas
--	--

FCC File No. BL-10877
Accepted 4-29-65

Station KULY
Ulysses, Kansas

1420 kc

KULY



Measured Night
(5-27-65ct)

Station KULY
Ulysses, Kansas

500w, 1kw-LS, DA-2, U
1420 kc

N. Latitude 37° 32' 53"
W. Longitude 101° 21' 49"

1420 KC, 5 KW



R X E 4 210.0 HVS
MEASURED

STATION KULY Ulysses, Kansas	
ENGINEER: H. H. Bradley	
DATE: JAN. 10, 1965	

FCC File No. BL-10877
Accepted 4-29-65

Station KULY
Ulysses, Kansas

1420 kc

10.
7-65

KULY


Measured Non-DA
(5-27-65ct)

Station KULY
Ulysses, Kansas

500W, 1kw-LS, DA-2, U
1420 kc

-10
-7-65

1420 KCS, 25KW



MON - DIRECTIONAL PATTERN MEASURED . .
POWER 250 WATTS

STATION : K U L Y
Ulysses, Kansas
1420 KC.

MEASURED VALUES

DATED: Jan. 23, 1965

Figure 121

EXHIBIT N I

FCC File No. BL-10877
Accepted 4-29-65

Station KULY
Ulysses, Kansas

1420 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: W A C K	Main Studio: Newark, New York
Frequency: 1420 KHZ	Power: 0.5 kW Night 0.5 kW Day
Notification List No. 1776	Date: June 28, 1978 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM: North Latitude: 43° 01' 08"
West Longitude: 77° 04' 41"

ANTENNA CHARACTERISTICS

PREDICTED EFFECTIVE DAY FIELD (OMINIDIRECTIONAL) 190 mV/m AT THE
RATED POWER

Authorized for Nighttime operation. (DA-N)
Number of elements: 4
Type of elements: Series excited, uniform cross-section,
guyed, Shunt excited, Self supporting,
tapered, vertical steel towers.

TOWER:	S (#3)	SC (#4)	NC (#1)	N (#2)
HEIGHT ABOVE INSULATORS:	173'	173'	173'	173' (90°)
NIGHT PHASING:	-20.5°	-177.2°	0°	-156.7°
NIGHT FIELD RATIO:	0.6689	0.6459	1.0000	0.9657


SPACING AND
ORIENTATION: With the NC(#1) tower the N(#2) tower is spaced 173.2' (90°) a line bearing 355° true; the S(#3) tower is spaced 483.1' (251°) on a line bearing 188.5° true, and the SC(#4) tower is spaced 317.3' (164.9°).

GROUND
SYSTEM: 120-173' equally spaced copper radials tower. Radials
are shortened and bonded to transverse along inter-
sections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Night	152.1 mV/m	267.2 mV/m	159.8 mV/m

Note: This notification concerns the addition of Nighttime operation to the station.



EDWARD F. LORENTZ & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

PROPOSED NIGHTTIME STANDARD
HORIZONTAL PLANE PATTERN
WACK, NEWARK, NEW YORK
1420 KHZ, 500 W-D, DA-N

WAMM

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WAMM

Main Studio: Flint, Michigan

Frequency: 1420 kHz

Power: 0.5 kW

Notification List No. 1652

Date: October 1, 1975

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 43° 01' 15"

West Longitude: 83° 38' 36"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER: NW(#2) SE(#1)

HEIGHT ABOVE

INSULATORS:

196'

196'

(103°)

PHASING:

-100°

0°

FIELD RATIO:

1

1

SPACING AND


ORIENTATION: Elements are spaced 171' (90°) on a line bearing 130° true.

GROUND SYSTEM: 120-200' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap along
intersections between towers.

Predicted effective Field: 147 mv/m at rated power.

Note: This notification concerns changes in means of radiation in the
directional antenna pattern.

WAMM



RMS = 147 mV/m


TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 3	STATION DATA
$G=103^\circ$ #2 $\frac{1}{-100^\circ}$ 90° #1 $\frac{1}{0^\circ}$ 130° T.	TOWER No.	ELECTRICAL HEIGHT G^*	SPACING S^*	PHASING ψ^*	FIELD RATIO F	PROPOSED CHANGES IN MEO VALUES WAMM FEBRUARY, 1975 6°	CALL WAMM FREQ 1420 kHz POWER 0.5 kW TYPE DA-D TIME DAY LAT. 43°01'15" LONG. 83°38'36"
	1						E. HAROLD MUNN, JR. & ASSOCIATES, INC. COLDWATER, MICH.
	2						
	3						
	4						
	5						
	6						
DAYTIME & NIGHTTIME OPERATION ☐							

WAMM

500w, DA-D, D
1420 kc

Measured Day
(12-22-64ct)

Station WAMM
Flint, Michigan



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS	FIGURE 1	STATION DATA																																																							
$G = 103^\circ$ $S = 90^\circ$ 310° T. No. 2 $0.967/-27.5^\circ$ S No. 1 $1/0^\circ$	<table border="1"> <thead> <tr> <th>TOWER No.</th> <th>ELECTRICAL HEIGHT C</th> <th>SPACING S</th> <th>PHASING P</th> <th>FIELD RATIO F</th> </tr> </thead> <tbody> <tr><td>1</td><td></td><td></td><td></td><td></td></tr> <tr><td>2</td><td></td><td></td><td></td><td></td></tr> <tr><td>3</td><td></td><td></td><td></td><td></td></tr> <tr><td>4</td><td></td><td></td><td></td><td></td></tr> <tr><td>5</td><td></td><td></td><td></td><td></td></tr> <tr><td>6</td><td></td><td></td><td></td><td></td></tr> <tr><td>7</td><td></td><td></td><td></td><td></td></tr> <tr><td>8</td><td></td><td></td><td></td><td></td></tr> <tr><td>9</td><td></td><td></td><td></td><td></td></tr> <tr><td>10</td><td></td><td></td><td></td><td></td></tr> </tbody> </table>	TOWER No.	ELECTRICAL HEIGHT C	SPACING S	PHASING P	FIELD RATIO F	1					2					3					4					5					6					7					8					9					10					MEASURED DAY DIRECTIONAL 5 - 64 $\theta^\circ 0^\circ$	CALL WAMM FREQ 1420 kc/s POWER 0.5 Kw TYPE DA-D TIME DAYTIME LAT. 43-01-15 LONG. 83-38-36 E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER No.	ELECTRICAL HEIGHT C	SPACING S	PHASING P	FIELD RATIO F																																																						
1																																																										
2																																																										
3																																																										
4																																																										
5																																																										
6																																																										
7																																																										
8																																																										
9																																																										
10																																																										

FCC File No. BZ-5318
Accepted 12-1-64

Station WAMM
Flint, Michigan


1420 kc

PROPOSED DAY
(10-21-56g)

Radio Station W A M M
Flint, Michigan

0.5 W A M M
XKW, DA-D, D 1420 KC

Number of towers: 2
Heights of towers: 196' 200' overall
Spacing between towers: 90*
Orientation: N 310*E
Field Ratios: 1.0
Phase Angles: #2 logs #1 by 100*



FCC File No.
BP-10,839

Accepted 10-15-56

Station W A M M
Flint, Michigan

1420 K C



POLAR CO. ORDINATE
MADE IN U.S.A.

NO. 10HP




CLEVELAND IN USE OF RADIO ELECTRONICS
CLEVELAND, OHIO



WAMM

Proposed
daytime



CARL E. SMITH
CONSULTING RADIO ENGINEERS
4900 Euclid Ave. Cleveland 3, Ohio

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
		TOWER	ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	PHASING	HORIZONTAL FIELD	FIELD RATIO	ELEV. ANGLE	ELEVATION RMS FIELD	CALL	
		No.	ft	°	ft	°	°			°	dBu	WAMM
		1	103	0	0	0	110	1.0	0	147	FREQUENCY	
		2	103	310	90	-100	110	1.0	10		1420	
		3							20		POWER	
		4							30		0.5	
		5							40		TIME OF OPERATION	
		6							50		D	
		7							60		TYPE OF OPERATION	
		8							70		DA-0	
		9					80		DAYTIME TOWERS			
		10					90		1 & 2			
							100		NIGHTTIME TOWERS			
							110		-0-			
							120		NO RADIALS PER TOWER			
							130		120			
							140		LENGTH OF RADIALS			
							150		105 - 200 //			
							160		GROUND SCREEN DIMENSION			
							170		-0-			
							180		LAT.			
							190		43° 01' 15"			
							200		LONG.			
							210		83° 38' 36"			
							220		SUPERSEDES			
							230		3/11/55G			
							240		PATTERN No.			
							250		551125			
							260					
							270					
							280					
							290					
							300					
							310					
							320					
							330					
							340					
							350					

DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐

BINDER - CARTER - DURHAM, INC.
3506 E. KEARSLEY ST.
FLINT, MICH

FIG. 7.10
EXPANDED
PROPOSED HORIZONTAL DAYTIME PATTERN

CORRECTED DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WAVO

Main Studio: Decatur, Georgia

Frequency: 1420 kHz

Power: 1 kW

Notification List No. 1655

Date: October 22, 1975 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 33° 47' 13"

West Longitude: 84° 14' 53"

Authorized for Daytime operation (DA-D).

Predicted effective Day Field: 198.8 mv/m at rated power.


Note: Please retain the description sheet and directional antenna radiation patterns notified for station WAVO in United States Change List Number 872, dated July 27, 1960 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a correction in the location of the main studio.

WAVO

Proposed Day
(12-22-64ct)

Station WAVO
Decatur, Georgia

1kw, DA-D, D
1420 kc



N: 33° 47' 13"
W: 84° 14' 53"

COMPUTED RMS = 198.8 MV/M

ANTENNA PARAMETERS		
0.683/-139°	1.0/0°	0.497/+139°
← 270°	→ 100°	→ 100° →
1	2	3
C=124.5°=240'		
S=100°=192.7'		

PALMER A. GREEN
GREENVILLE, S.C.

FIGURE 2	
BOB JONES UNIVERSITY INCORPORATED	
RADIO STATION WAVO	
DECATUR, GEORGIA,	
1420 KCS.	1.0 KW. DA-D.
COMPUTED HORIZONTAL RADIATION PATTERN.	

FCC File No. BZ-5311
Accepted 11-25-64

Station WAVO
Decatur, Georgia


1420 kc

WAVO

Measured Day
(12-22-64ct)


Station WAVO
Decatur, Georgia

1kw, DA-D, D
1420 kc



N: 33°47'13"
W: 84°14'53"

MEASURED RMS = 200 MV/M



PRIMER A. GREER
GREENVILLE, S.C.

FIGURE 3	
BOB JONES UNIVERSITY INCORPORATED	
RADIO STATION WAVO	
DECATUR, GEORGIA.	
1420 KCS.	1.0 KW. DA-D.
MEASURED HORIZONTAL RADIATION PATTERN	

FCC File No. BZ-5311
Accepted 11-25-64

Station WAVO
Decatur, Georgia


1420 kc

WAVO

Measured Non-DA
(12-22-64ct)

Station WAVO
Decatur, Georgia

1kw, DA-D, D
1420 kc



$G=124.5^\circ=240^\circ$

N: $33^\circ 47' 13''$
W: $84^\circ 14' 53''$



FCC File No. BZ-5311
Accepted 11-25-64

Station WAVO
Decatur, Georgia

1420 kc

FIGURE 1	
BOB JONES UNIVERSITY INCORPORATED	
RADIO STATION WAVO	
DECATUR, GEORGIA	
1420 KCS.	1.0 KW. DA-D.
MEASURED NON-DIRECTIONAL RADIATION PATTERN (EAST)	
3 ELEMENT, 1.0 KW.	

WBEC

PROPOSED NIGHT
(9/8/55G)

STATION WBEC
PITTSFIELD, MASSACHUSETTS

DA-2, U
1 KW

1420 KC

APP. ACC.
4-20-66
CHG TO DA-N


NIGHT HORIZONTAL PLANE RADIATION

PROPOSED 1KW., DA-2, 1420 KC.

WBEC - PITTSFIELD, MASS.

PAUL GODLEY CO.
CONSULTING RADIO ENGINEERS
LABORATORIES: GREAT NOTCH, N.J. 7/55

FIG. 2



FILE NO. BP-9653 (Amended) ACCEPTED FCC 8/10/55
BP 16265

WBEC, Pittsfield, Mass. 1420 KC


WBEC

MEASURED DAY
(2/11/57g)

Station WBEC
Pittsfield, Massachusetts

500W, 1KW-LS, DA-2, U
1420 KC

*measured license
4/3/57
PL ACC.
-20-66
HG TO DA-N*



North Lat : 42 - 26 - 40
West Long : 73 - 16 - 43

**MEASURED DAYTIME
HORIZONTAL PLANE RADIATION PATTERN**

WBEC - 1420 KC. 1KW, DA - 2
PITTSFIELD, MASS.

PAUL GODLEY CO.
CONSULTING RADIO ENGINEERS
LABORATORIES: GREAT NOTCH, N.J. 12/56

FCC File No. BL-6498
Accepted 1/29/57

WBEC
Pittsfield, Massachusetts

1420 KC

BP 16865


WBEC

MEASURED NIGHT
(2/11/57g)

Station WBEC
Pittsfield, Massachusetts

500W, 1KW-LS, DA-2, U
1420 KC

*revised license
4/3/57
APPL. ACC.
4-20-66
CHG TO DA-N*



FCC File No. BL-6498
Accepted 1/29/57
BP 16 865

WBEC
Pittsfield, Massachusetts

1420 KC

WBEC

Measured Non-DA
(4-28-67ct)


Station WBEC
Pittsfield, Massachusetts

1kw, DA-N, U
1420 kc

**MEASURED NON-DIRECTIONAL
HORIZONTAL PLANE RADIATION PATTERN**

WBEC - 1420 KHZ., 1 KW, DA-N
PITTSFIELD, MASS.

PAUL GOOLEY CO.
CONSULTING RADIO ENGINEERS
LITTLE FALLS, N.J. 1/67



Measured RMS (no loss) = 253 mv/m
Reduced to 210 mv/m with series
loss resistor, see Table I.

Note: EAST TOWER (NO. 2) EXCITED WITH
1000 WATTS. WEST TOWER DETUNED.

NORTH LATITUDE: 42° 26' 40"
WEST LONGITUDE: 73° 16' 43"

North Latitude 42° 26' 40"
West longitude 73° 16' 43"

FCC File No. BL-11600
Accepted 4-7-67

Station WBEC
Pittsfield, Massachusetts

1420 kc

EUGENE DIETZGEN CO.
MADE IN U. S. A.


NO. 341-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE

WBEC

MEASURED NON-DIRECTIONAL
(2/11/57g)

Station WBEC 500w, 1KW-LS, DA-2, U
Pittsfield, Massachusetts 1420 KC

*revised license
4/3/57
HPPL. ACC.
4-20-66
HG TO PA-N*



FCC File No. BL-6498

WBEC

Accepted 1/29/57

Pittsfield, Massachusetts

1420 KC

BP 16 865

(Per...)

PROPOSED
DAY (7-11-56g)


SUNSHINE STATE B/C CO.
BRADENTON, FLA.

1 KW
DA-D, D

BRADENTON, FLA
WBRD
1420 KC

*L.P. Granted
12/19/56*

82° 32' 10" N (Latitude)
27° 28' 32" W (Longitude)



SUNSHINE STATE BROADCASTING CO. INC. BRADENTON, FLORIDA DIRECTIONAL ANTENNA PATTERN	Figure 1
	1420 KC 500 WATTS DA-D
	FRANK H. McINTOSH & ASSOCIATES
	Consulting Radio Engineers Wyatt Building Washington, D. C.


WBRD

MEASURED DAY
(12-20-57g)

Station WBRD
Bradenton, Florida

1kw, DA-D,D
1420 KC

*Granted license
1/31/58 for new
station*



FCC File No. BL-6875
Accepted 11-29-57


WBRD
Bradenton, Florida

1420 KC

MEASURED NON-DA
(12-20-57g)

Station WBRD
Bradenton, Florida

1kw, DA-D,D
1420 KC



FCC File No. BL-6875
Accepted 11-29-57

WBRD
Bradenton, Florida

1420 KC

WBSM

PROPOSED DAY & NIGHT
(8/16/55G)

STATION WBSM
NEW BEDFORD, MASSACHUSETTS

1KW
DA-1, U

1420 KC

*granted for increase in day
power and DA-2 - 9-2-59*

GRANTED CP 6/4/56




FIGURE 5
HORIZONTAL RADIATION PATTERN
BAY STATE BROADCASTING COMPANY
WBSM 1 KW-U, DA-1 1420 KC
NEW BEDFORD, MASSACHUSETTS


Prepared by
Craven, Lohnes & Culver Washington 4, D. C.
July 1955

WBSM

MEASURED NIGHT &
DAY (1-29-57g)

Station W B S M 1 KW-D, 1KW-N, DA-1, U
New Bedford, Mass.

1420 K C



FCC File No.
BL-6481

Accepted 1-14-57

Station W B S M
New Bedford, Mass.

1420KC

WBSM

MEASURED NON-DA
(1-29-57g)

Station WBSM 1 KW-N, 1KW-D, DA-1, U
New Bedford, Mass.

1420 K C

*wanted license
4/1/57*

*increased for increase
in day power and DA 2
9-2-59*

NO. 340-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE
EUGENE DIETZEN CO.
PRINTED IN U.S.A.




FIGURE 4
WEST TOWER RADIATION PATTERN
(NON-DIRECTIONAL TEST)
BAY STATE BROADCASTING COMPANY
WBSM 1 KW-U, DA-1 1420 KC
NEW BEDFORD, MASSACHUSETTS

Prepared by
Lohnes and Culver Washington 4, D.C.
December 1956

FCC File No. Accepted 1-14-57
BL-6481


Station WBSM
New Bedford, Mass. 1420 KC

WBSM

PROPOSED DAY
(2-11-58g)

Station WBSM
New Bedford, Massachusetts

1kw,5kw-LS, DA-2,U
1420 KC



FCC File No. BP-11,766
Accepted 1-21-58

WBSM
New Bedford, Massachusetts


1420 KC

WBSM

MEASURED DAY
(2-26-60g)

Station WBSM
New Bedford, Massachusetts

1kw, 5kw-LS, DA-2, U
1420 KC



FCC File No. BL-7819
Accepted 2-11-60

WBSM
New Bedford, Massachusetts 1420 KC

WCED

PROPOSED
NIGHT (7/21/54G)

WCED
DuBois, Pa.

500W, 5KW-LS DA-2, U

1420kc


EXHIBIT NO. E-4

LAT. 41° 08' 31"
LONG. 78° 48' 07"

BP-17471
+ppl. accepted
1-3-67 to change from
500W, 5KW-LS
500W, 5KW-LS, DA-2, U
DA-N, U

8-14-67
GRANTED CP
change from
DA-2 to
DA-N

11-7-68
Granted license
covering
change from
DA-2 to
DA-N



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON, D. C.

PATTERN: PROPOSED NIGHTTIME

FOR: WCED, DuBois, Pa.

POWER: 500 W

FREQ: 1420 KC

DATE: 6/8/54

PROPOSED
NIGHT NULLS (7/21/54G)

WCED
DU BOIS, PA.


500W, 5KW-LS DA-2, U

1420kc

WCED

EXHIBIT NO. E-4A

BP-17471
App'l. accepted
to change
500W, 5KW-LS DA-2, U
500W, 5KW-LS DA-N, U
8-14-67
GRANTED CP
change from
DA-2
DA-N
11-7-68
Granted change
from DA-2
to DA-N



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON, D. C.

PATTERN: PROPOSED NIGHTTIME

FOR: WCED, Du Bois, Pa.

POWER: 500 W

FREQ: 1420 KC

DATE: 6/8/54

WCED

MEASURED
NIGHT (6-27-56g)

STATION WCED
DUBOIS, PENNSYLVANIA



500 W, 5 KW
DA-2, U

1420 KC

LAT. 41° 08' 31"
LONG. 78° 48' 07"

EXHIBIT NO. E-20
(Amended)

*1-3-67
wanted license
28/57 for
change from
DA-2 to DA-N
500W, 5KW-L5
DA-2, U
500W, 5KW-L5
DA-N, U
8-14-67
WANTED CP
change from
DA-2 to
DA-N
11-7-68
wanted license
reverting change
from DA-2
to DA-N.*



COMMERCIAL RADIO EQUIPMENT CO.
RADIO ENGINEERING CONSULTANTS
KANSAS CITY WASHINGTON, D. C.

PATTERN Measured Nighttime
FOR WCED, Du Bois, Pa.
POWER 500 Watts FREQ. 1420 Kc
DATE May 1956 BY CCW

WCED

MEASURED NON-
DIRECTIONAL (6-27-56g)

STATION WCED
DUBOIS, PENN.


500 W, 5 KW
DA-2, U

1420 KC

EXHIBIT NO. E-10

2
wanted license
12/8/57 for change
in freq., trans-
mission + to DA-2
BP-17471
ppe. accepted
a change from
20W, 5KW-LS,
DA-2, U
500W, 5KW-LS
DA-N U
8-14-67 CP
-RANTED
change from
DA-2 to
DA-N

11-7-68
wanted license
covering change
from DA-2 to
DA-N



RMS = 194 MV/M



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON, D. C.

PATTERN: Non-Directional	
F. R. WCED	
POWER: 1 KW	FREQ: 1420 Kc
DATE: MAY 4, 1956	BY: CCW


WCOJ

PROPOSED
NIGHT

(5/20/54G) WCOJ, Coatesville, Pa.

5KW, U, DA-N

1420 kc




WCOJ

MEASURED NIGHT
(11-26-55G)

STATION WCOJ
COATESVILLE, PENNSYLVANIA

5 KW
DA-N, U

1420 KC




WCOJ

MEASURED NON-DIRECTIONAL STATION WCOJ
(11-28-55G) COATESVILLE, PENNSYLVANIA

5 KW
DA-N, U

1420 KC




WDBF

Measured Day
(6-28-63ct)

Station WDBF
Delray Beach, Florida

500w, 5kw-LS, DA-2, U
1420 kc

8-15-63
Sounded
new change
from DA-2.



EUGENE DIETZEN CO.
PRINTED IN U.S.A.

NO. 340-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE

FCC File No. BL-10037
Accepted 6-17-63

Station WDBF
Delray Beach, Florida

1420 kc

1.0/0°

0.715 / 122.2°

90°

$$G = 104^{\circ} = 200'$$

MEOV \

五、

—

✱

1



68-13440

RM5: 130-144 M

NL 26° 27' 21.3"
ML 50° 05' 58"

NIGHTTIME HORIZONTAL RADIATION PATTERN
WDBF - DELRAY BEACH, FLORIDA
1420 KC - 500w/5kw-LS - DA-2
PATTERN NO. 610208

GAUTNEY & JONES
RADIO ENGINEERS WASHINGTON, D. C.
February, 1961

FCC File No. BP-14749
Accepted 4-25-61

WDBF
Delray Beach, Florida

1420 KC

WDBF


Measured Night
(6-28-63ct)

Station WDBF
Delray Beach, Florida

500w, 5kw-LS, DA-2, U
1420 kc

8-15-63
Liggett for
change in (theoretical)
* change from
DA-0 to DA-2.

1.0/0°	THEO.	0.716/122.2°
①	→ S →	② → 212° TRUE
1.0/0°	MEAS.	0.95/110°
S = 90° = 173'		G = 104° = 200'



EUDENE DIETZGEN CO.
MADE IN U.S.A.

NO. 340-P DIETZGEN GRAPH PAPER
POLAR CO-ORDIN.

FCC File No. BL-10037
Accepted 6-17-63

Station WDBF
Delray Beach, Florida

1420 kc

WDBF

Measured Non-DA
(6-28-63ct)


Station WDBF
Delray Beach, Florida

500w, 5kw-LS, DA-2, U
1420 kc

8-15-63
Shorted heater
for change in
from DA-0 to
DA-2

EUGENE DIEZGEN CO.
NEW YORK, N. Y.

NO. 340-P DIEZGEN GRAPH PAPER
"POLAR COORDINATE"



MEASURED 500 WATT NON-DA PATTERN
WDBF - DELRAY BEACH, FLORIDA
1420 KC - 0.5KW/5KW-LS - DA-2

GAUTNEY & JONES
RADIO ENGINEERS WASHINGTON, D. C.
October, 1962

FCC File No. BL-10037
Accepted 6-17-63

Station WDBF
Delray Beach, Florida

1420 kc

Station WHK
Cleveland, Ohio


WHK

9-25-63
Granted CPTC
make change
to DA-N

5kw, DA-N, U
1420 kc

Station WHK
Cleveland, Ohio

Proposed Night Nulls
(9-25-63ct)



1420 kc

Station WHK
Cleveland, Ohio

FCC File No. BP-15983
Accepted 8-28-63

φ = 0 at N°E

WHK

Measured Night
(12-22-64ct)

Station WHK
Cleveland, Ohio

5kw, DA-N, U
1420 kc

BL-10673
GRANTED
12-29-64
CHG, DA





FIGURE 9
MEASURED RADIATION PATTERN
DIRECTIONAL OPERATION
WHK 5 KW-U, DA-N 1420 KC
METROMEDIA, INC.
CLEVELAND, OHIO

Prepared by
Lohnes and Culver Washington, D. C.
June 1964
1420 kc

FCC File No. BL-10673
Accepted 11-25-64

Station WHK
Cleveland, Ohio


Measured Non-DA
(12-22-64ct)

Station WHK
Cleveland, Ohio

WHK

5kw, DA-N, U
1420 kc

3L-10673
GRANTED
12-29-64
CHG. PA



North Latitude 41° 21' 30"
West Longitude 81° 40' 03"

FIGURE 8
MEASURED RADIATION PATTERN
NON-DIRECTIONAL TOWER #1
WHK 5 KW-U, DA-N 1420 KC
METROMEDIA, INC.
CLEVELAND, OHIO

Prepared by
Lohnes and Culver Washington, D. C.
June 1964
1420 kc

FCC File No. BL-10673
Accepted 11-25-64

Station WHK
Cleveland, Ohio

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WIMS

Main Studio: Michigan City, Indiana

Frequency: 1420 kHz

Power: 5 kw Night 5 kw Day

Notification List No. 1778

Date: August 30, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 40' 26"

West Longitude: 86° 55' 58"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 6

Type of elements: Series excited, uniform cross-section
vertical steel towers. Towers #1, 2, 3
and 4 are guyed. Towers #5 and 6 are
self supporting.

TOWER:	#5(SSW)	#1(SW)	#2(C)	#3(NE)	#6(NNE)	#4(SE)
HEIGHT ABOVE INSULATORS:	195'(101.3°)	195'	195'	195'	195'	140'(72.8°)
NIGHT PHASING:	0°	-161.4°	+43.6°	-105.5°	+112.5°	---
NIGHT FIELD RATIO:	1.000	2.772	3.266	1.9294	0.582	---
DAY PHASING:	---	---	0°	---	---	-70°
DAY FIELD RATIO:	---	---	1.0	---	---	0.5

SPACING AND
ORIENTATION:Towers #1, #2, #3, #5, #6 spaced 172' (90°) on a
line bearing 16 true. Tower #4 is spaced 212' (110°)
on a line bearing 155° true.


GROUND SYSTEM: 120 - 275' equally spaced copper radials plus 120 - 75' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


	<u>RMS</u>	THEORETICAL <u>RSS</u>	STANDARD <u>RMS</u>
Day	415 mv/m		
Night	400 mv/m	1009.6 mv/m	420 mv/m

Note: Please retain the Daytime directional antenna radiation pattern notified for Station WIMS in United States Change List Number 812 dated May 27, 1959 and attach to this Revised Description Sheet and Nighttime pattern. This notification concerns only a change in the Nighttime operation of the station with Daytime operation continued as previously notified.

J. J. JONES CONSULTING ENGINEERS
 1000 N. W. 10th St., Miami, Fla. 33136



RMS (theor) = 400 mv/m
 RMS (std) = 420 mv/m
 RSS = 1009.6 mv/m



DIRECTIONAL RADIATION PATTERN

NORTHERN INDIANA BROADCASTERS, INC

☐ MEASURED ☒ PROPOSED

FREQ: 1420 kHz POWER: 5.0 kW ☐ DAY
 LAT: 41° 30' 26" ☐ NIGHT
 LONG: 86° 55' 58" ☐ W

LOCATION: Mishawaka City, Indiana

DATE: May 1976

ROBERT A. JONES
 CONSULTING ENGINEERS
 LA GRANGE, ILLINOIS

FIGURE 1

superceded 6/4/58

WIMS


PROPOSED DAY
(4-9-58g)

Station WIMS
Michigan City, Indiana

500w, 5kw-LS, DA-2, U

1420 KC

granted CP 9-16-57
to increase day power - 5KW



FCC File No. BP-11,285
Accepted 4-1-58

WIMS
Michigan City, Indiana


1420 KC

WIMS

MEASURED DAY
(9-13-60g)

Station WIMS
Michigan City, Indiana

500w, 5kw-LS, DA-2,U
1420 KC



FCC File No. BL-8028
Accepted 8-30-60


WIMS
Michigan City, Indiana

1420 KC

SITE:
~~41-40-00~~ 2-26-48
~~66-53-10~~

MICHIGAN CITY, IND.
 1420 KC 500 WATTS N

WIMS



NORTHERN INDIANA BROADCASTERS, INC. MICHIGAN CITY, INDIANA		Figure 1 Series 480127A
PROPOSED DIRECTIONAL ANTENNA PATTERN		1420 KC 500 WATTS NIGHT
SPACING 90° H=101°		FRANK H. McINTOSH Consulting Radio Engineer Washington, D.C.

2-26-48


WIMS

MEASURED
NIGHT

WIMS, MICHIGAN CITY, IND.
10/20/52G

500W, 1 KW-LS, U, DA-N

1420 KC



APPL RECD FCC 9/10/52 ACC 10/9/52 BL-4786

WIMS, MICHIGAN CITY, IND.

1420 KC

WIMS


MEASURED NON-DA
(9-13-60g)

Station WIMS
Michigan City, Indiana

500w, 5kw-LS, DA-2,U
1420 KC

EUGENE DIETZGEN CO
NEW YORK, N.Y.

NO 340 P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-8028
Accepted 8-30-60

WIMS
Michigan City, Indiana

1420 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WINI Main Studio: Murphyshore, Illinois
 Frequency: 1420 kHz Power: 0.5 kW
 Notification List No. 1739 Date: July 1, 1977 Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS OF THE DAY AND NIGHT ANTENNA SYSTEMS:

Daytime			Nighttime		
North Latitude:	37° 47' 20"		North Latitude:	37° 45' 30"	
West Longitude:	89° 20' 12"		West Longitude:	89° 14' 02"	

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 4

Type of elements: Series excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	NW(#1)	NE(#2)	SE(#3)	SW(#4)
HEIGHT ABOVE INSULATORS:	129'	129'	129'	129' (67°)
PHASING:	0°	+116.5°	+119.5°	-28.5
FIELD RATIO:	1	0.36	0.65	0.92

SPACING AND

ORIENTATION: From tower #1, tower #2 is located 134.77' (70°) in length on a line bearing 70.7° true, tower #3 is located 370.57' (140.5°) in length on a line bearing 168.5° true, and tower #4 is located 317.68' (165°) on a line bearing 192.9° true.

GROUND SYSTEM: 120-173' equally spaced copper radials plus 120-50' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation (DA)

Number of elements: 1

Height above insulator: 170'

Ground System: 120-170' equally spaced copper radials about the tower.

(Cont'd)

WINI

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	134.3 mv/m	- mv/m	- mv/m
Night	124.315 mv/m	169.79 mv/m	130.683 mv/m

Note: This notification concerns only a change to add new nighttime operation with Daytime operation continued as previously notified.

WINI

EXHIBIT E-5.2

Page 2



STANDARD

HORIZONTAL RADIATION PATTERN

EXPANDED SCALE

RADIO STATION WINI
1420 KHZ - 0.5 KW DA-N
MURPHYSBORO, ILLINOIS
DECEMBER 1975

ROBERT L. LUKS

REGISTERED RADIO ENGINEER

ILLINOIS PROFESSIONAL ENGINEERING BOARD




EXHIBIT E-5.3A

RADIO STATION WINT
1420 KHZ - 0.5 KW DA-N
WARRNSBORO, ILLINOIS
DECEMBER 1975

AZIMUTH, DEGREES FROM TRUE NORTH

VERTICAL ANGLE - 5°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

207001 L. JAMES
207001 L. JAMES
207001 L. JAMES
207001 L. JAMES

WINT




EXHIBIT E-5.38

RADIO STATION WENI
1420 KHZ - 0.5 KW DA-N
MURPHYSBORO, ILLINOIS
DECEMBER 1975

WATTAGE

VERTICAL ANGLE - 10°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

AZIMUTH, DEGREES FROM TRUE NORTH

WENI
1420 KHZ
0.5 KW
MURPHYSBORO, ILLINOIS
DECEMBER 1975

WENI




EXHIBIT E-5.30

RADIO STATION WINI
1420 KHZ - 0.5 KW DA-N
MURFESSBORO, ILLINOIS
DECEMBER 1975

VERTICAL ANGLE - 15°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

AZIMUTH, DEGREES FROM TRUE NORTH

WINI
1420 KHZ
0.5 KW
DA-N
MURFESSBORO, ILLINOIS
DECEMBER 1975
P.O. BOX 111 MURFESSBORO, TENNESSEE 37055




EXHIBIT E-5.3D

RADIO STATION WNI
1420 KHZ - 0.5 KW DA-N
MURPHYSBORO, ILLINOIS
DECEMBER 1975

AZIMUTH, DEGREES FROM TRUE NORTH

VERTICAL ANGLE - 20°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

ROBERT L. BARRS
FEDERAL BUREAU OF INVESTIGATION
U.S. DEPARTMENT OF JUSTICE
WASHINGTON, D.C. 20535

WNI




EXHIBIT E-5.3E

RADIO STATION WNI
1420 KHZ - 0.5 KW DA-N
MURPHYSBORO, ILLINOIS
DECEMBER 1975

AZIMUTH, DEGREES FROM TRUE NORTH

APPROVED FOR RELEASE
BY Robert L. Hanks
DATE 10/1/80
P.O. BOX 10000 WASHINGTON, D.C. 20540

VERTICAL ANGLE - 25°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

WNI




EXHIBIT E-5.3F

RADIO STATION WNI
1420 KHZ - 0.5 KW DA-N
MURPHYSBORO, ILLINOIS
OCTOBER 1975

AZIMUTH, DEGREES FROM TRUE NORTH

VERTICAL ANGLE - 30°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

STATION WNI
1420 KHZ
0.5 KW
DA-N
MURPHYSBORO, ILLINOIS
OCTOBER 1975
P. O. BOX 13 WOLA MISSOURI 64401 PHONE 814 289 3148

WNI




EXHIBIT E-5.3G

RADIO STATION WINI
1420 KHZ - 0.5 KW DA-N
NORTHSHORE, ILLINOIS
DECEMBER 1975

AZIMUTH, DEGREES FROM TRUE NORTH

VERTICAL ANGLE +35°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

WINI
1420 KHZ - 0.5 KW DA-N
NORTHSHORE, ILLINOIS
DECEMBER 1975
P.O. BOX 11 - MALLA, MISSOURI 64501 - PHONE 314 653 1148

WINI




EXHIBIT E-5.3H

RADIO STATION WENI
1420 KHZ - 0.5 KW DA-N
MURPHYSBORO, ILLINOIS
DECEMBER 1975

AZIMUTH, DEGREES FROM TRUE NORTH

VERTICAL ANGLE - 40°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

WENI
1420 KHZ
0.5 KW
DA-N
MURPHYSBORO, ILLINOIS
DECEMBER 1975




EXHIBIT E-5.31

RADIO STATION WINI
1470 KHZ - 0.5 KW DA-N
MURPHYSBORO, ILLINOIS
DECEMBER 1975

AZIMUTH, DEGREES FROM TRUE NORTH

VERTICAL ANGLE - 45°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

WINI
1470 KHZ
0.5 KW
DA-N
MURPHYSBORO, ILLINOIS
DECEMBER 1975




EXHIBIT E-5.3J

RADIO STATION WENT
1420 KHZ - 0.5 KW CA-N
W RHYNSBURG, ILLINOIS
DESIGNER 1975

VERTICAL ANGLE - 50°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

AZIMUTH, DEGREES FROM TRUE NORTH

DESIGNED BY
ROBERT L. BIRD
INCORPORATED
P.O. BOX 2, 401 N. HIGHWAY 100, RHYNSBURG, ILLINOIS 62450

PRINTED IN U.S.A.





EXHIBIT E-5.3K

RADIO STATION WINI
1920 KHZ - 0.5 KW DA-N
MURPHYSPRO, ILLINOIS
DECEMBER 1975

AZIMUTH, DEGREES FROM TRUE NORTH

VERTICAL ANGLE - 55°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

WINI
P.O. BOX 12
MURPHYSPRO, ILLINOIS 62450
PHONE 314 383 3144



RECEIVED
FEB 11 1976
FEDERAL BUREAU OF INVESTIGATION
U.S. DEPARTMENT OF JUSTICE
WASHINGTON, D.C. 20535


WINI

WKPR

PROPOSED DAY
(2/11/57g)

Kalamazoo B/C Co.
Kalamazoo, Michigan

1KW, DA-D, D
1420 KC



FCC File No BP-11,022
Accepted 1/28/57

Kalamazoo B/C Co.
Kalamazoo, Michigan

1420 KC

6.860 granted in

WKPR


MEASURED DAY
(12-15-60)

Station WKPR
Kalamazoo, Michigan

1kw, DA-D, D
1420 KC

12-15-61
printed for
new station

POLAR COORDINATE
359.31G
KALAMAZOO, MICHIGAN



FCC File No. BL-8165
Accepted 12-7-60

WKPR
Kalamazoo, Michigan
1420 KC


WKPR

MEASURED NON-DA
(12-15-60g)

Station WKPR
Kalamazoo, Michigan

1kw, DA-D, D
1420 KC

K&E POLAR CO-ORDINATE
KEUFFEL & ESSER CO.
359-316
MADE IN U.S.A.



NON-DIRECTIONAL PROOF OF PERFORMANCE
FOR RADIO STATION WKPR KALAMAZOO, MICH
ON 1420 KCS WITH 1000 WATTS DA-DAYTIME
USING NORTHEAST TOWER WITH 500 WATTS
BP-11,022
RALPH J. BITZER, CONSULTING RADIO ENGR


FCC File No. B1-8165
Accepted 12-7-60

WKPR
Kalamazoo, Michigan

1420 KC

1420 kc

• Prof



RMS = 181 MV/M

MEQV SHOWN ON VERTICALS


PATTERN NO. 050851

LATITUDE: 35°-11'-04"

LONGITUDE: 87°-03'-20"

JOHN H. MULLANEY

CONSULTING RADIO ENGINEER
WASHINGTON, D. C.



G • 100°

EXHIBIT NO. 2
NIGHT HORIZONTAL
RADIO STATION WKS
PULASKI BROADCASTING CO.
PULASKI, TENNESSEE

PRES. 730 KC 250W-D
PROP. 1420KC 1KW-DA-N-U


WKSJ

MEASURED
NIGHT (2/4/53G)

WKSJ, PULASKI, TENN.

1kw, U, DA-N

1420 kc




WKSr

MEASURED
~~SEE NOTE~~ (Dec 4/53G)

WKSr, PULASKI, TENN.

1kw, U, DA-N

1420 kc



WLNA
1420 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WLNA Main Studio: Peekskill, New York
Frequency: 1420 kHz Power: 1kw Night 5 kw Day
Notirication List No. 1783 Date: November 2, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 18' 31"
West Longitude: 73° 55' 00"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
Number of elements: 5
Type of elements: Series excited, unifor cross-section, guyed, vertical steel towers.

TOWER:	C(#1)	NE(#2)	SW(#3)	NW(#4)	SE(#5)
HEIGHT ABOVE INSULATORS	211.6' (110°)	211.6'	211.6'	150'	150' (78°)
NIGHT PHASING:	0°	+164°	-164°		
NIGHT FIELD RATIO:1		0.654	0.473		
DAY PHASING:	0°			-117.8°	+169.8°
DAY FIELD RATIO: 1				0.565	0.565

SPACING AND ORIENTATION:

With the center (#1) tower as reference the NE(#2) tower is spaced 173.2' (90°) on a line bearing 335° true, the South-west (#3) tower is spaced 173.2' (90°) on a line bearing 155° true, the northwest (#4) tower is spaced 173.2' (90°) on a line bearing 300° true and the Southeast (#5) tower is spaced 173.2' (90°) on a line bearing 120° true.

GROUND SYSTEM: 120-173' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

		THEORETICAL		STANDARD
		RMS	RSS	RMS
Day	462.59	mv/m	659.53	mv/m
Night	220.22	mv/m	413.19	mv/m

30°
330°

20°
340°

10°
350°

0°


350°
10°

340°
20°

WLNA
1420 KHz

330°
30°

DA-2



NO. 341-P DIETZGEN GRAPH PAPER
POLAR COORDINATE

STANDARD PATTERN RMS = 486.02 MV/M
NO. 760527
N. LAT. 41° 18' 31"
W. LON. 73° 55' 00"

FIG. 4

DAY HORIZONTAL PLANE RADIATION
PROPOSED IN/5D, DA-2, 1420 KHz.
WLNA - PEEKSKILL, NEW YORK

Paul Godley Co.
Consulting Communications Engineers
Little Falls, New Jersey 6/76

NIGHT HORIZONTAL PLANE RADIATION

PROPOSED 1N/5D, DA-2, 1420 kHz.

WLNA - PEEKSKILL, New York

Paul Godley Co.
Consulting Communications Engineers
Little Falls, New Jersey 6/76

FIG. 5

N. LAT. 41° 18' 31"
W. LON. 73° 55' 00"

G = 110°
#2 0.654 / 154°

#1 1.0 / 0°

#3 0.473 / -164°

WHK - CLEVELAND
402.0 MI

MGED - DU BOIS
254.1 MI

ENLARGED
DETAIL

WCOJ - COATESVILLE
133.3 MI

WBEC - PITTSFIELD
85.1 MI

WBSM - NEW BEDFORD
151.1 MI

STANDARD PATTERN RMS = 231.49 MV/M
NO 760518

150° 210° 160° 200° 170° 190° 180° 170° 200° 210° 150°

NO. 341-P DIETZEN GRAPH PAPER
POLAR COORDINATE
EUGENE DIETZEN CO.
IN U. S. A.


VOC

PROPOSED NIGHT
(3/22/55)

STATION VOC
DAVENPORT, IOWA

5KW
DA-2, U

1420 KC




WOC

MEASURED NIGHT
(10/18/54 G)

STATION WOC,
DAVENPORT, IOWA

5 KW
DA-2, U

1420 KC



A. D. RING & CO. - 1/52 - 1000

File No. BL--5472
(10/18/54 G)

Accepted 10/8/54

WOC, Davenport, Iowa

1420 KC


PROPOSED
DAY

(2/4/53G)

WOC, DAVENPORT, IOWA

5kw, U, DA-2

1420 kc



A. D. RING & CO. - 1/12 - 1000

WOC


MEASURED DAY
(10/18/54 G)

STATION WOC
DAVENPORT, IOWA

5 KB
DA-2, U

1420 KC

A. D. RING & CO. - 1/32 - 1000





ND

WOC

MEASURED NIGHT AND DAY
(10/18/ 54 G)STATION WOC,
DAVENPORT, IOWA5 KW
DA-2, U

1420 KC






WRBL
1420

JUN 3 1968 G

additions. Variation.

350 May 6-6




STILES & WARING—CONSULTING RADIO ENGINEERS—BOSTON & WASHINGTON

WRBL
1420

32-29-52
65-02-48

JUN 3 1948

additional information
May - 6-48



WVJS


PROPOSED DAY
(7-29-60g)

Station WVJS
Owensboro, Kentucky

1kw, 5kw-LS, DA-2,U
1420 kc

PAGE, CREUTZ, STEEL & WALDSCHMIDT
Consulting Engineers
1413 K STREET, NORTHWEST
WASHINGTON 5, D. C.

2-6-62
printed & for
new station



FCC File No. BP-14208
Accepted 7-14-60

WVJS
Owensboro, Kentucky

1420 kc

WVJS

Measured Day
(10-26-62ct)

Station WVJS
Owensboro, Kentucky

1kw, 5kw-LS, U
1420 kc

*1/2/63
fronted for
increase in day power*

Theoretical Parameters:

Tower #2 = $1/0^\circ$

Tower #4 = $0.85/+20^\circ$

Operating Parameters:


Tower #2 = $1/0^\circ$

Tower #4 = $0.65/+80^\circ$

DAVID BTEEL & ASSOCIATES
Communication Consulting Engineers
3312 M STREET, NORTHWEST
WASHINGTON 7, D. C.

EUGENE DIETZEN CO.
MADE IN U. S. A.


NO. 340R-P DIETZEN GRAPH PAPER
POLAR CO. ORIGINATE



FCC File No. BL-9602
Accepted 10-18-62

Station WVJS
Owensboro, Kentucky


1420 kc



Measured Night
(10-26-62ct)

Station WVJS
Owensboro, Kentucky

1kw, 5kw-LS, U
1420 kc




Measured Non-DA
(10-26-62ct)

Station WVJS
Owensboro, Kentucky


1kw, 5kw-LS, U
1420 kc

EUGENE DIETZGEN CO.
MADE IN U. S. A.

ND. 340R-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



2-28/5'




1420kc

Exhibit No. E-2

○ MAX PERMISSIBLE MW/M
MAX EXPECTED MW/M
(Base Scale)

● MAX PERMISSIBLE MW/M
MAX EXPECTED MW/M
(Enlarged Scale)



SITE: 35° 44' 37" N
77° 53' 36" W

PAT # 453N11

NO. TOWERS	2
------------	---

3° 150 3' 288.5

 $\theta = 47.5^\circ$ $r = 0.68$

1 KV RMS 179.6

.5 IV RMS	127.0
-----------	-------

TOWER LINE) °TRUE

VL Deg. $107^{\circ} - 90^{\circ}$

VL Pest 2061 - 1701

OA Feet	209' - 173'
---------	-------------

PAT.
UNIT rms: 1.17



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON, D. C. HOLLYWOOD

PATTERN: PROPOSED NIGHTTIME

FOR: WVOT, Wilson, North Carolina

POWER: 500W, 1KW-D FREQ: 1420KC

DATE: February 9, 1949

BY: ITN

X E E W

PROPOSED Station X E E W 1 KW, DA-1 Class III
DAY & NIGHT Matamoros, Tamaulipas
(9-21-56g)

1420
KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET 35615

Station: X E E W Main Studio: Matamoros, Tamaulipas
Frequency: 1420 KC Power: 1 KW
Mexican Change List No. 193 Date: June 29, 1956 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM: North Latitude: 25° 51' 38*
West Longitude: 97° 28' 29*

ANTENNA CHARACTERISTICS

Authorized for Day and Night Operation. (DA-1)
Number of elements: 2
Type of elements: Series-excited, uniform cross-section,

TOWER:	North	South
HEIGHT ABOVE INSULATORS:	90*	90* (53 meters)
PHASING:	160*	0*
FIELD RATIO:	1.0	1.0

SPACING AND
ORIENTATION: Adjacent elements are spaced 60* (35x21) meters) on a line
bearing 325* true.

GROUND
SYSTEM: 120-90* equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap
along intersections between towers. Centers of systems
are bonded together.

Predicted effective Field: 175 mv/m at rated power.

FCC FILE Station X E E W
LIST NO. 193 Matamoros, Tamaulipas
6-29-56


1420 KC

XEEW

1420 KC

PROPOSED Station X E E W 1 KW, Da-1
 DAY & NIGHT Matamoros, Tamaulipas Class III
 (9-21-56g)

25° 51' 38" N (Latitude)
 87° 28' 29" W (Longitude)




REVISE

APROBO:

PATRON DE RADIACION HORIZONTAL CALCULADO EN mv/M a 1609 MTS.

Esquema de las torres y su orientación respecto al Norte astronómico.



JORGE CARDENAS GONZALEZ.

Razon social o nombre del concesionario e indicativo de llamada.

XEEW

1420 KHz.

1000 Watts.

TECNICOS ASOCIADOS.

FCC FILE
 List No. 193
 6-29-56

Station X E E W
 Matamoros, Tamaulipas

1420 KC

Description Sheet
(9-26-68ct)

New Station
Digby, Nova Scotia

1kw, DA-1, U, Class III
1420 kc

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION CALL : New LOCATION : Digby N.S.
FREQUENCY : 1420 KHZ POWER : 1 KW CLASS : III

Notification List No : Date :

GEOGRAPHICAL LOCATION : 44° 38' 00" N 131°
OF THE ANTENNA SYSTEM : 65° 46' 40" W 130°

ANTENNA CHARACTERISTICS :

Mode of Operation : DA-1, full time

No. of Elements : 2 (two)

Type of Elements : Uniform cross-section, guyed,
base insulated, series fed,
no top loading

Power No. : #1 NE #1 SW

Height above
Insulator : 135 ft. (70) 135 ft

Spacing : 102 ft. (53)

Phasing : 134

Field Ratio : 1.0

Orientation : on a line bearing 50° E of T.N.

Ground System : 120 equidistantly spaced radials
per tower. No. 10 AWG soft-drawn
copper wire and buried approx. 6
inches in ground and extending
to the limits of the property in
order to cover an area equivalent
to 0.4 wavelength ground system

PREDICTED EFFECTIVE FIELD :

136 μ V/m at one mile for 1 KW radiated

NEW

Proposed Day & Night
(9-26-68ct)

New Station
Digby, Nova Scotia

1kw, DA-1, U, Class III
1420 kc

