

1430-1450

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
NEW	Grande Prairie, Alberta	1430	10 kW/DA-1	1/27/78
CKFH	Toronto, Ontario	1430	50 kW/DA-2	12/23/70
CKFH	Toronto, Ontario	1430	50 kW/DA-2	7/29/70
CKFH	Toronto, Ontario	1430	10 kW/DA-2	1/30/67
CKFH	Toronto, Ontario	1430	5/10 kW/DA-2	12/15/60
KALI	Pasadena, CA	1430	5 kW/DA-D	8/1/52
KALI	San Gabriel, CA	1430	5 kW/DA-2	12/12/58
KALV	Alva, OK	1430	0.5 kW/DA-1	5/12/76
KARM	Fresno, CA	1430	5 kW/DA-1	12/28/67
KBEV	Beaver Dam, WI	1430	1 kW	8/30/78
KBRC	Mt. Vernon, WA	1430	1 kW/DA-N	8/31/56
KNTA	Santa Clara, CA	1430	1 kW/DA-1	3/30/64
KEES	Gladewater, TX	1430	1 kW/DA-N	8/30/78
KELI	Tulsa, OK	1430	5 kW/DA-N	4/28/66
KJAY	Sacramento, CA	1430	5 kW/DA-D	7/24/63
KKAT	Roswell, NM	1430	1 kW/DA-N	12/21/59
KLO	Ogden, UT	1430	5 kW/DA-N	10/1/75
KOSI	Aurora, CO	1430	5 kWDA-N	10/26/79
KRGI	Grand Island, NE	1430	1 kW/DA-N	5/27/53
WBRB	Mt. Clemens, MI	1430	5 kW/DA-D	8/26/66
WBRB	Mt. Clemens, M	1430	0.5 kW/DA-2	10/5/76
WDEX	Monroe, NC			
WEEF	Highland Park, IL	1430	1 kW/DA-2	
WEIR	Weirton, WV	1430	1 kW/DA-2	1/22/71
WENE	Endicott, NY	1430	5 kW/DA-N	1/16/75
WENO	Madison, TN	1430	5 kW/ND/1 kW/DA-N	4/24/64
WFOB	Fostoria, OH	1430	1 kW/DA-2	5/29/56

1430-1450

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WHIL	Everett, WA	1430	5 kW/DA-N	12/9/60
WIL	St. Louis, MO	1430	5 kW/DA-2	6/28/43
WION	Ionia, MI	1430	5 kW/DA-D	7/27/62
WIRE	Indianapolis, IN	1430	5 kW/DA-N	5/28/64
WJRB	Madison, TN	1430	1 kW/DA-2	9/12/80
WMNC	Morganton, NC	1430	1/5 kW/DA-N	10/26/64
WNAV	Annapolis, MD	1430	1/5 kW/DA-N	2/21/74
WNJR	Newark, NJ	1430	5 kW/DA-N	2/9/73
WPCF	Panama City, FL	1430	5 kW/DA-2	7/12/55
WQDI	Homestead, FL	1430	0.5 kW/DA-N	10/26/79
WTTT	Amherst, MA	1430	5 kW/DA-D	6/28/63
WVAM	Altoona, PA	1430	1/5 kW/DA-N	9/68
WVVX	Highland Park, IL	1430	1 kW/DA-D	8/23/63
WWGS	Tifton, GA	1430	1/5 kW/DA-N	11/11/60
WYMC	Mayfield, KY	1430	1 kW/DA-D	11/16/79
NEW	Bathurst, NB	1430	10 kW/DA-1	5/12/72
CFGO	Ottawa, ON	1440	50 kW/DA-2	6/12/81
CJOI	Wetaskiwin, AL	1440	10 kW/DA-N	10/12/73
CJOI	Wetaskiwin, AL	1440	1 kW/DA-1	5/31/67
NEW	Courteney, BC	1440	1 kW/DA-N	9/24/58
CFGO	Ottawa, ON	1440	50 kW/DA-1	8/27/71
KDNT	Denton, TX	1440	0.5 kW/DA-N	7/27/65
KEWI	Topeka, KS	1440	1/5 kW/DA-2	2/28/69
KEYS	Corpus Christi, TX	1440	1 kW	9/8/70
KMLB	Monroe, LA	1440	1/5 kW/DA-N	11/17/61
KODL	The Dalles, OR	1440	1/5 kW/DA-N	3/8/77
KPUR	Lufkin, TX	1440	1/5 kW/DA-N	6/29/70

1430-1450

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
KEVE	Golden Valley, MN	1440	0.05/0.5 kW/DA-N	9/25/57
KUHL	Santa Maria, CA	1440	1/5 kW/DA-N	11/16/77
KVON	Napa, CA	1440	1/5 kW/DA-2	2/5/70
KVON	Napa, CA	1440	0.5/5 kW/DA-2	1/31/67
NEW	Martin, KY	1440	2.5 kW/DA-D	10/26/79
WAAB	Worcester, MA	1440	5 kW/DA-N	1/11/55
WAAB	Worcester, MA	1440	5 kW/DA-2	3/26/64
WAAB	Worcester, MA	1440	1 kW/ND	4/24/64
WAJR	Morgantown, WV	1440	0.5/5 kW/DA-2	11/9/56
WAKC	Normal, IL	1440	1 kW/DA-D	11/29/62
WAKC	Normal, IL	1440	0.5/1 kW/DA-N	6/29/64
WAYK	Lehigh Acres, FL	1440	1/5 kW/DA-2	4/10/61
WBCM	Bay City, MI	1440	5 kW/DA-2	
WBUY	Lexington, NC	1440	1/5 kW/DA-N	7/26/61
WCDS	Glasgow, KY	1440	5 kW/DA-D	6/28/78
WCHB	Inkster, MI	1440	1 kW/DA-D	5/31/79
WCHB	Inkster, MI	1440	0.5/1 kW/DA-2	5/27/65
WCHB	Inkster, MI	1440	1/5 kW/DA-2	2/28/69
WGEM	Quincy, IL	1440	1/5 kW/DA-2	10/25/61
WGIG	Brunswick, GA	1440	1 kW/DA-N	3/26/58
WGIG	Brunswick, GA	140	1/5 kW/DA-N	7/26/67
WHDM	McKenzie, TN	1440	5 kW/DA-D	12/4/80
WRRN	Warren, OH	1440	5 kW/DA-2	10/25/51
WHHY	Montgomery, AL	1440	1 kW/DA-N	12/26/46
WHHY	Montgomery, AL	1440	1/5 kW/DA-N	3/26/65
WHIS	Bluefield, WV	1440	5 kW/DA-N	2/8/49
WJBQ	Westbrook, ME	1440	5 kW/ND-D	5/31/78

1430-1450

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WJBQ	Westbrook, ME	1440	5 kW/DA-N	3/76
WKHJ	Holly Hill, SC	1440	1 kW/DA-N	9/27/78
WMVB	Millville, NJ	1440	1 kW/DA-D	4/29/70
WNBE	Winter Park, FL	1440	1/5 kW/DA-N	5/65
WNFL	Green Bay, WI	1440	1/5 kW/DA-2	3/50
WNFL	Green Bay, WI	1440	0.5/5 kW/DA-2	5/54
WNPV	Green Bay, WI	1440	0.5 kW/DA-2	10/1/80
WNPV	Green Bay, WI	1440	5 kW/DA-D	3/58
WOHN	Herndon, VA	1440	1 kW/DA-D	7/18/75
WPGW	Portland, IN	1440	5 kW/DA-D	9/49
WQOK	Greenville, SC	1440	5 kW/DA-N	6/17/66
WRDD	Bay City, MI	1440	2.5/5 kW/DA-2	8/30/78
WROK	Rockford, IL	1440	5 kW/DA-D	2/63
XERAL	Tonala, Jalisco	1440	5 kW	11/1/79
NEW	St. Eleuthere, PQ	1450	0.25/DA	8/26/66
CBG	Gander, Newfoundland	1450	0.25 kW	5/10/47
CFAB	Windsor, Nova Scotia	1450	0.25 kW	11/26/52
CFJR	Brockville, ON	1450	0.25/1 kW/DA-D, ND-N	5/28/59
CHEF	Granby, QU	1450	5/10 kW/DA-2	9/7/72
CHEF	Granby, QU	1450	0.25/10 kW/DA-D	6/27/69
CHRT	St. Eleuthere, PQ	1450	0.25 kW	4/29/69
CHUC	Cobourg, ON	1450	10 kW/DA-2	6/12/81
CJBM	Causapscal, QU	1450	0.25/1 kW	2/26/63
KVEN	Ventura, CA	1450	0.25/1 kW/DA-D	11/27/64
KYOR	Blythe, CA	1450	0.25/1 kW/DA-D	8/28/68
WKIP	Poughkeepsie, NY	1450	0.25/1 kW/DA-D	5/23/68
NEW	Jasper, AB	1450	1 kW	6/27/69

PROJECT #17601

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: NEW

MAIN STUDIO: Grande Prairie,
Alberta

FREQUENCY: 1430 kHz

POWER: 10 kW

NOTIFICATION LIST: 370

DATE: February 3, 1978

GEOGRAPHICAL LOCATION:

Latitude 55° 08' 11" North
Longitude 118° 45' 13" West

ANTENNA CHARACTERISTICS:

Mode of Operation:

DA-1

Number of Elements:

2 (Two)

Type of Elements:

Guyed steel towers, uniform
cross-section, base insulated
for series feed

TOWER:

#1 (South) #2 (North)

Height above base
insulator:

155' (81.2°) 155' (81.2°)

Overall height:

160' 160'

Ratio:

1.0 .87

Phasing:

0° -77

GROUND SYSTEM:

120 equally spaced radials per
tower of #10 B & S gauge bare
soft copper wire, buried approxi-
mately 8 inches.

The length of all radials, with
the exception of those joined
along the common chord is
275' (0.4 wavelength)

SPACING AND ORIENTATION:

Tower #2 is spaced 200.6' (105°)
along a line bearing 19.5° True
from Tower #1.


PREDICTED EFFECTIVE FIELD:


DAY AND NIGHT



574 mV/m at 1 mile for 10 kW
181 mV/m at 1 mile for 1 kW

July 5, 1977

Revised January 27, 1978







VERTICAL RADIATION PATTERNS



FIGURE 5

NEW AM
1430 kHz
PROJECT #17601

10 kW

GRANDE PRAIRIE, ALBERTA
DA-1 CLASS III
REVISED JANUARY 27, 1978

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS *BRH*



VERTICAL RADIATION PATTERNS

FIGURE 6



NEW AM
1430 kHz
PROJECT #17601

10 kW

GRANDE PRAIRIE, ALBERTA
DA-1 CLASS III
REVISED JANUARY 27, 1978

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

BRH



VERTICAL RADIATION PATTERNS

FIGURE 7

NEW AM
1430 kHz
PROJECT #17601

10 kW

GRANDE PRAIRIE, ALBERTA
DA-1 CLASS III
REVISED JANUARY 27, 1978

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

LGH

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: NEW

MAIN STUDIO: Grande Prairie,
Alberta

FREQUENCY: 1430 kHz

POWER: 10 kW

NOTIFICATION LIST: 370

DATE: February 3, 1978

GEOGRAPHICAL LOCATION:

Latitude 55° 08' 11" North

Longitude 118° 45' 13" West

ANTENNA CHARACTERISTICS:

Mode of Operation:

DA-1

Number of Elements:

2 (Two)

Type of Elements:

Guyed steel towers, uniform
cross-section, base insulated
for series feedTOWER:

#1 (South) #2 (North)

Height above base
insulator:

155' (81.2°)

155' (81.2°)

Overall height:

160'

160'

Ratio:

1.0

.87

Phasing:

0°

-77

GROUND SYSTEM:120 equally spaced radials per
tower of #10 B & S gauge bare
soft copper wire, buried approxi-
mately 8 inches.The length of all radials, with
the exception of those joined
along the common chord is
275' (0.4 wavelength)SPACING AND ORIENTATION:Tower #2 is spaced 200.6' (105°)
along a line bearing 19.5° True
from Tower #1.PREDICTED EFFECTIVE FIELD:DAY AND NIGHT

574 mV/m at 1 mile for 10 kW

181 mV/m at 1 mile for 1 kW

July 3, 1977

Revised January 27, 1978






FIGURE 3
HORIZONTAL RADIATION PATTERN
NEW AM GRANDE PRAIRIE, ALBERTA
1430 kHz 10 kW DA-1 CLASS III
PROJECT #17601 REV. JAN. 27, 1978
D.E.M. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS

150° 160° 170° 180° 190° 200° 210°
210° 200° 190° 180° 170° 160° 150°





VERTICAL RADIATION PATTERNS

FIGURE 5



NEW AM
1430 KHz
PROJECT #17501

10 KW

DA-1

GRANDE PRAIRIE, ALBERTA
CLASS III
REVISED JANUARY 27, 1973

D.F.M. ALLER & ASSOCIATES LTD., CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 6



NEW AM
1430 kHz
PROJECT #17691

10 kW

DA-1

GRANDE PRAIRIE, ALBERTA
CLASS III
REVISED JANUARY 27, 1978

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 7

NEW AM		GRANDE PRAIRIE, ALBERTA
1430 KHz	10 kW	DA-1 CLASS III
PROJECT #17601		REVISED JANUARY 27, 1978
D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS		6/24

CKFH

Description Sheet
(12-23-70ct)

Station CKFH
Toronto, Ontario
CORRECTED

50kw, DA-2, U, Class III
1430 kc

DESCRIPTION OF ARRAY

STATION: CKFH

MAIN STUDIO: Toronto, Ontario

FREQUENCY: 1430 Khz

POWER: 50 Kw CLASS: 111

NOTIFICATION LIST #: 265

DATE: January 21, 1970

GEOGRAPHICAL LOCATION
OF ANTENNA SYSTEM:

43° - 37' - 03" North Latitude
79° - 22' - 47" West Longitude

ANTENNA CHARACTERISTICS

Mode of operation: DA/2
Number of elements: 6
Type of elements:

Guyed, uniform cross-section
base insulated, top loading by
folded umbrella guy structure to
equivalent of 103 electrical degrees.

<u>TOWER:</u>	# 1 (N)	# 2 (NC)	# 3 (C)	# 4 (SC)	# 5 (S)	# 6 (SCE)
<u>HEIGHT OVER INSULATORS:</u>	150'	150'	150'	150'	150'	150'
<u>SPACING:</u>	140°	70°	0°	70°	140°	70°
	(267.2')	(133.6')	(Ref.)	(133.6')	(267.2')	(133.6')
<u>ORIENTATION:</u>	333.0°	333.0°	0°	153.0°	153.0°	150.1°
<u>PHASING:</u> Day:	+35.29°	-162.31°	0°	not used	-46.30°	+157.11°
Night:	+41.499°	-158.917°	0°	+156.566°	-50.101°	not used
<u>RATIO:</u> Day:	0.8000	2.40392	3.56839	not used	1.00000	2.80411
Night:	0.8000	2.72360	4.11909	3.12916	1.00000	not used

GROUND SYSTEM:

120 radials per tower # 10 AWG copper
0.4 wavelength long to property limits buried
to 8" depth or weighted in water surrounding the site.

PREDICTED EFF-
ECTIVE FIELD:

194.9 mv/m @ 1 mi. for 1 Kw. Day
1378 mv/m @ 1 mi. for 50 Kw. Day

189.8 mv/m @ 1 mi. for 1 Kw. Night
1342 mv/m @ 1 mi. for 50 Kw. Night

CONSULTANT:

D. B. Williamson, P. Eng.,
Consulting Engineer,
Radio CHUC Building,
Cobourg, Ontario.

NOTE: This refers to a change in night-time pattern only. To this corrected description sheet and night-time radiation patterns attach the day-time radiation patterns previously distributed with Canadian Change List # 265, dated January 1, 1970.


CKFH

Proposed Night
(12-23-70ct)

Station CKFH
Toronto, Ontario

50kw, DA-2, U, Class II
1430 kc

KE POLAR CO-ORDINATE 46 4413
KEUFFEL & ESSER CO.




Proposed Night Nulls
(12-23-70ct)

Station CKFH
Toronto, Ontario

50kw, DA-2, U, Class III
1430 kc

CKFH



Description Sheet
(7-29-70ct)

Station CKFH
Toronto, Ontario

CKFH
50kw, DA-2, U, Class III
1430 kc

DESCRIPTION OF ARRAY

STATION: CKFH

MAIN STUDIO: Toronto, Ontario

FREQUENCY: 1430 Khz

POWER: 50 Kw. Class: III

NOTIFICATION NO. 265

DATED: January 21, 1970

GEOGRAPHICAL LOCATION
OF ANTENNA SYSTEM:

43 - 37 - 03 North

79 - 22 - 47 West

ANTENNA CHARACTERISTICS

Mode of Operation: DA/2

Number of Elements: 6

Type of Elements:

Guyed, uniform cross section,
base insulated, top loading by
folded umbrella guy structure to
equivalent of 103 electrical degrees.

<u>TOWER:</u>	# 1(N)	# 2(NC)	# 3(C)	# 4(SC)	# 5(S)	# 6(SCE)
<u>HEIGHT OVER INSULATORS:</u>	150'	150'	150'	150'	150'	150'
<u>SPACING:</u>	140° (267.2')	70° (133.6')	0° (Ref.)	70° (133.6')	140° (267.2')	70° (133.6')
<u>ORIENTATION:</u>	333.0°	333.0°	0°	153.0°	153.0°	150.1°
<u>PHASING:</u> Day: +35.28°	-162.31°	0°	not used	-46.30°	+157.11°	
Night: +36.88	-162.28	0°	+159.79	-45.02	not used	
<u>RATIO:</u> Day: 0.8000	2.40392	3.56839	not used	1.00000	2.80411	
Night: 0.84000	2.68489	3.94065	3.02612	1.00000	not used	

GROUND SYSTEM:

120 radials per tower # 10 AWG copper.
0.4 wavelength long to property limits buried
to 8" depth or weighted in water surrounding the site.

PREDICTED EFFECTIVE

FIELD:

194.9 mv/m @ 1 mi. for 1 Kw. Day
1378 mv/m @ 1 mi. for 50 Kw. Day

189.8 mv/m @ 1 mi. for 1 Kw. Night
1342 mv/m @ 1 mi. for 50 Kw. Night

CONSULTANT:


D. B. Williamson, F. Eng.,
Consulting Engineer,
Radio CHUC Building,
Cobourg, Ontario.

Proposed Day
(7-29-70ct)

Station CKFH
Toronto, Ontario

CKFH
50kw, DA-2, U, Class III
1430 kc


K₀E POLAR COORDINATE 46 4413
KLOPFEL & ESSER CO.



Proposed Day Nulls
(7-29-70ct)

Station CKFH
Toronto, Ontario

CKFH
50kw, DA-2, U, Class III
1430 kc



10 X 10 TO THE CENTIMETER 40 15 13
KODAK SAFETY FILM


CKFH

Proposed Day Nulls
(7-29-70ct)

Station CKFH
Toronto, Ontario

50kw, DA-2, U, Class III
1430 kc

ME 10 X 10 TO THE CENTIMETER 46 1513
RELIFE 3 ESSER-00




CKFH Toronto, Ontario
50 Kw. DA/2 Class III
1430 Khz Unlimited
Horizontal Day Pattern
Linear scale expansion
D. B. Williamson, P. Eng.
Radio CHUC Bldg.
Cobourg, Ontario

Proposed Night
(7-29-70ct)

Station CKFH
Toronto, Ontario

~~CKFH~~ CKFH
50kw, DA-2, U, Class III
1430 kc

K0E POLAR COORDINATE 46 4413
NEUFFEL & ESSER CO.



CKFH

10 X 10 TO THE CENTIMETER 46 1513

SCOTT & SUTHERLAND


50kw, DA-2, U, Class III
1430 kc

Station CKFH
Toronto, Ontario

Proposed Night Nulls
(7-29-70ct)

Distance in Miles

CKFH Toronto, Ontario
1430 KHz Class III
50 Kw DA12 Unidirectional
Horizontal N-W-E Detail
D.B. Williamson, F. Eng.
Radio CHUC Building
Georgetown, Ontario 12/69



Description Sheet
(1-30-67ct)

Station CKFH
Toronto, Ontario

10kw, DA-2, U, Class III
1430 kc

d) DESCRIPTION OF ARRAY

STATION: CKFH

MAIN STUDIO: Toronto, Ontario

FREQUENCY: 1430 KHZ

POWER: 10 KW. Class III

Notification List No: 220

DATE: December 20, 1966

GEOGRAPHICAL LOC-

43° 37' 03" North

ATION OF ANTENNA SYSTEM

79° 22' 47" West

ANTENNA CHARACTERISTICS

Mode of Operation:

DA/2

Number of Elements:

4

Type of Elements:

Guyed, uniform cross section, base insulated, top loading by folded umbrella. Guy structure to 75° electrical height.

TOWER: #1(N)

#2(c)

#3(S)

#4(E)

HEIGHT OVER 100'

100'

100'

100'

INSULATORS:

OVERALL HEIGHT: 105'

105'

105'

105'

SPACING:

See Orientation Below

ORIENTATION: Towers #1, 2 & 3 are on a line bearing 345° true, spacing between adjacent towers is 129.8' (68°). Towers 2 & 4 are on a line bearing 114° true, spacing between towers #2 & 4 is 63' (33°).

PHASING: Day - 150°
Night - 139.30

not used
0°

+142°
+139.30

-27°
not used

RATIO: Day 1.000
Night 1.000

not used
1.919

1.080
1.000

1.900
not used

GROUND SYSTEM:

120 radials per tower #10AWG copper.
0.4 wavelength long to property limits buried to 8" depth or weighted in water surrounding the site.

PREDICTED EFFECTIVE
FIELD:

533 mv/m @ 1 mile for 10KW day
(175 mv/m @ 1 mile for 1KW)

592 mv/m @ 1 mile for 10KW night
(187 mv/m @ 1 mile for 1KW)

147
DESCRIPTION SHEET
(12-15-60g)

Station CKFH 5kw, 10kw-LS, DA-2, U, Class III
Toronto, Ontario, Canada 1430 KC

REVISED

ORIENT. OF ANTENNA

STATION: CKFH RATH PHOTO: TORONTO, CAN.
POWER: 10KW/5KW FREQ: 1430 KC CLASS: III

NOTIFICATION REFERENCE: List No. 147 DATE: May 24, 1960

LOCATION: NORTH LATITUDE: 43° 37' 03"
WEST LONGITUDE: 79° 22' 17"

ANTENNA:

MODE OF OPERATION: DA-2 (directional day and night with different patterns)

Four elements, uniform, cross section, guyed steel towers,
base insulated for series feed.

TOWER: North (#1) East Centre (#2) South (#3) Centre (East) (#4)

Height above insulators: 100' 100' 100' 100'

Spacing: See Orientation below

Phasing:

Day Operation:	-150	Not used	+142	-27
Night Operation:	-137° lag	0°	+137° lead	Not used

Field Ratio:

Day Operation	1.0	Not used	1.08	1.0
Night Operation:	.526	1	.526	Not used

Ground System: 120 equiangularly spaced radials extend from the base of each tower to a distance of 276 feet (.4 wavelength), with the exception of those joined along the common chords. Wires are continuous or bonded together at junction points and consist of solid copper wire #10 B & S gauge. The ground wires are buried to a depth of approximately eight inches with the exception of those radials which lie in water, these radials are weighted and lie on the bottom of the pond adjoining the property.

Predicted Effective Field:

Day Operation: 533 mv/m at 1 mile for 10 KW
(175 mv/m at 1 mile for 1 KW)
Night Operation: 118 mv/m at 1 mile for 5 KW
(187 mv/m at 1 mile for 1 KW)

Orientation: Towers #1, #2 and #3 are on a line bearing 345° true, spacing between adjacent towers is 129.8 ft. (68°). Towers #2 and #4 are on a line bearing 114° true, spacing between towers #2 and #4 is 63 feet (33°).


Note: The four towers are each top loaded by an 8' square grid which results in an overall equivalent electrical height of each tower of 61°.

Oficina Interamericana de Radio - PAU
OIR/NARBA 2389 Canada / C. 2454
La Habana 4. XI. 60. -

CKFH

PROPOSED DAY
(12-15-60g)

Station CKFH 5kw, 10kw-LS, DA-2, U, Class III
Toronto, Ontario, Canada 1430 KC




POLAR CO ORDINATE 059 31
KEUFFEL & ESSER CO

CKFH

PROPOSED DAY NULLS
(12-15-60g)

Station CKFH 5kw, 10kw-LS, DA-2, U, Class III
Toronto, Ontario, Canada 1430 KC




#147

CKFH

Proposed Night
(1-30-67ct)

Station CKFH
Toronto, Ontario

10kw, DA-2, U, Class III
1430 kc



Radio Station CKFH Toronto, Ont.
1430 KHz. 10 Kw. DA/2.
Class III. Nighttime Radiation
Pattern. Zenith 000°.
D.B. Williamson P.Eng.
Drawn: GJE.

POLAR CO-ORDINATE 359.31
MAGNETIC BEARING

MAR 57


CKFH

PROPOSED NIGHT
(3-23-59g)

Station CKFH
Toronto, Ontario, Canada

5kw, DA-2, U, Class III
1430 KC

259 31
POLAR COORDINATE
WIRE ANTENNA



1450-57

CKFH

PROPOSED NIGHT NULLS
(3-23-59g)

Station CKFH
Toronto, Ontario, Canada

5kw, DA-2,U, Class III
1430 KC




FIGURE 5
HORIZONTAL PATTERN DETAIL
(NIGHT TIME)
CKFH TORONTO, ONT.
1430 KC/S 5KW DA-2 CLASS III
PROJECT 2650-A MARCH 1957

REVISED

PROPOSED
DAY

(10/6/53G)

San Gabriel
KALI, PASADENA, CALIFORNIA

5KW, D, DA

1430 kc





FIGURE 2
HORIZONTAL PATTERN
CONSOLIDATED BROADCASTING CO.
KALI, PASADENA, CALIFORNIA
1430 KC - 5 KW - D - DA
AUGUST 1, 1952


BOND AND OAKLEY
Consulting Radio Engineers
LOS ANGELES, CALIFORNIA

KALI

MEASURED DAY
(12-12-58g)

Station KALI
San Gabriel, California

5kw, DA-2, U
1430 KC



FCC File No. BL-7280
Accepted 11-18-58

KALI
San Gabriel, California

1430 KC



granted 6.4.59

KALI

PROPOSED NIGHT
(3-12-58g)

Station KALI
San Gabriel, California

5kw, DA-2, U
1430 KC



FCC File No. BP-11,222


Accepted 3-4-58 (Amended)

KALI

San Gabriel, California

1430 KC

KALI

MEASURED NIGHT
(12-12-58g)Station KALI
San Gabriel, California5kw, DA-2, U
1430 KCFCC File No. BL-7280
Accepted 11-18-58KALI
San Gabriel, California

1430 KC


granted 6-4-59

KALI

MEASURED NON-DA
(12-12-58g)

Station KALI
San Gabriel, California

5kw, DA-2, U
1430 KC



FCC File No. BL-7280
Accepted 11-18-58

granted 6-4-59

KALI
San Gabriel, California

1430 KC

KALV

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KALV

Main Studio: Alva, Oklahoma

Frequency: 1430 kHz

Power: 0.5 kW

Notification List No. 1684

Date: May 12, 1976

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 36° 49' 06"

West Longitude: 98° 38' 38"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 4

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	SW(#3)	C(#2)	NE(#1)	E(#4)
HEIGHT ABOVE INSULATORS:	150'	150'	150' (78.5°)	120' (62.8°)
NIGHT PHASING:	-132°	0°	+132°	---
NIGHT FIELD RATIO:	1.0	1.85	1.0	---
DAY PHASING:	-123°	0°	---	+110°
DAY FIELD RATIO:	0.3	1	---	0.56

SPACING AND

ORIENTATION: Towers #1, #2 and #3 are spaced 153' (80°) on a line bearing 225° true. From tower #1, tower #4 is spaced 133.8' (70°) on a line bearing 89° true.

GROUND SYSTEM: 120-150' equally spaced copper radials plus 120-50' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	130.4 mv/m	164.3 mv/m	143.4 mv/m
Night	135 mv/m	---	---

(Cont'd.)

KALV

KALV
1430 kHz
Alva, Oklahoma

2.


Note: Please retain the directional antenna radiation pattern notified for a new station at Alva, Oklahoma in United States Change List Number 657 dated May 16, 1956, and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in the Daytime operation of the station with Nighttime operation continued as previously notified.

CTR NO 30376A3


KALV

Standard Pattern

EXHIBIT E-5.1



STANDARD HORIZONTAL RADIATION PATTERN



ELECTRICAL HEIGHT

#1	80°
#2	80°
#3	80°
#4	63°

APPLICANT	KALV
LOCATION	ALVA, OKLAHOMA
FREQUENCY	1430 KC/S
POWER	0.5 KW
LATITUDE	36 DEG 49 MIN 06 SEC
LONGITUDE	98 DEG 38 MIN 35 SEC
WHEN USED	Daytime
DATE	15 February 1975

ROBERT L. LINDS

KALV


PROPOSED NIGHT & DAY
(4-9-56G)

AUBREY D. CONROW
ALVA, OKLAHOMA

500W-N, 500W-D
DA-1, U

1430 KC

RECEIVED
10-5-64
APPL. FOR 5 H.




granted license 1/2/57

KALV

MEASURED NIGHT & Station K A L V
DAY (DA-1)(10-29-56g) Alva, Oklahoma

500 W, DA-1 U over

1430 K C



FCC FILE NO.
BL-6377

Accepted 10-22-56

Station KALV, Alva, Okla.


1430 KC

Granted license 1/2/51

KALV

MEASURED K A L V 500 W, DA-1, U
NON-DA(10-29-56g) Alva, Oklahoma Engr. - Benjamin O. Lange

1430 K C



LAT: 36° 49' 08"
LONG: 98° 38' 11"

Figure 2
MEASURED NON-DIRECTIONAL
HORIZONTAL RADIATION
KALV- 1430 KC - ALVA, OKLA
500 Watts DA-1

FCC File No.
BL-6377

Accepted 10-22-56

Station K A L V
Alva., Oklahoma

1430 K C


Proposed Day & Night
(12-28-67ct)

Station KARM
Fresno, California

KARM
5kw, DA-1, U
1430 kc

1-24-66
GRANTED
CP

10-17-68
Granted
license



Prop 4
MEASURED
NIGHT & DAY

KARM, FRESNO, CAL.

License 11-5-48

5kw, DA1

KARM - 1430 kc

3/10/49G130°


340°

350°

10°

20°

30°



KARM, Fresno, Cal. 1430 kc

KBEV

Station: WBEV

Main Studio: Beaver Dam, Wisconsin

Frequency: 1430 KHz

Power: 1 Kw Night 1 Kw Day

Notification: 1778

Date: August 30, 1978 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTERS OF DAYTIME AND
NIGHT ANTENNA SYSTEMS:

NIGHTTIME: North Latitude: 43° $25'$ $43''$
West Longitude: 88° $53'$ $33''$

DAYTIME: North Latitude: 43° $25'$ $40''$
West Longitude: 88° $54'$ $35''$

Predicted Effective Dayfield (omnidirectional): 195 $\frac{mv}{m}$ at rated power.

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 3

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.


TOWER	:	<u>S (#3)</u>	<u>C (#2)</u>	<u>N (#1)</u>	<u> </u>	<u> </u>	<u> </u>
HEIGHT ABOVE INSULATORS	:	<u>195'</u>	<u>195'</u>	<u>195'</u>	<u>(102°)</u>	<u> </u>	<u> </u>
NIGHT PHASING	:	<u>+94°</u>	<u>0</u>	<u>-94°</u>	<u> </u>	<u> </u>	<u> </u>
NIGHT FIELD RATIO:		<u>1</u>	<u>1.797</u>	<u>1</u>	<u> </u>	<u> </u>	<u> </u>
SPACING AND ORIENTATION	:	Towers in a row are spaced 229.4' (120°) on a line bearing 350° true.					

GROUND SYSTEM: 120 - 170' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	<u>RMS</u>	THEORETICAL <u>RSS</u>	STANDARD <u>RMS</u>
Night	<u>197.7</u> mv/m	<u>186.0</u> mv/m	<u>207.6</u> mv/m

Note: This notification concerns only the addition of operation of the station with Daytime operation continued as Nighttime directional antenna previously notified.



HORIZONTAL RADIATION PATTERN		0° Standard Pattern	
Theoretical RMS (1 ohm loss) -197.7 MV/M Standard Pattern RMS -207.6 MV/M RSS -186.0 MV/M		APPLICANT : WBEV LOCATION : Beaver Dam, Wisconsin FREQUENCY : 1430 KC/S POWER : 1000 Watts LATITUDE : 43 DEG 25 MIN 43 SEC. LONGITUDE : 88 DEG 53 MIN 33 SEC. WHEN USED: Nighttime R.M.S. FIELD: 207.6 MV/M DATE : June 5th, 1976	
A-195' 11027		RALPH J. BITZER CONSULTING RADIO ENGINEERS ST. LOUIS, MISSOURI	

PROPOSED
NIGHT (5/15/56g)

STATION KBRC
Mount Vernon, Wash.

1 KW
DA-N, U


1430 KC

K.F.N.C.

Granted CP
6/18/58 to increase
from 2A day
power from
1 KW to 5 KW
—
Granted license
11/14/58

SEE BALL FOR PARAMETERS & FORMULA JAN

1430 KC



KBRC

MEASURED
NIGHT (8-31-56g)


STATION KBRC
MOUNT VERNON, WASH.

DA-N, U
1 KW

1430 KC

Granted CP
12/18/58 to
increase then
day power
from 1 KW to 5 KW
—
Granted license
11/14/58

*Granted license
9/25/56*



FCC File No. BL-6249

Accepted 8-23-56

KBRC, Mount Vernon, Wash.

1430 KC

KNTA

KEGT


Measured Day & Night
(3-30-64ct)

Station KGBA
Santa Clara, California

1kw, DA-1, U
1430kc

EUGENE DIETZEN CO.
MADISON, U.S.A.

NO. 3408-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE




FCC File No. BL-10393
Accepted 2-25-64

Station KGBA
Santa Clara, California

1430kc

KNTA

KEGL

PROPOSED DAY & NIGHT
(8-22-61ct)New; George B. Bairey
Santa Clara, California1kw, DA-1, U
1430 KC3-8-63
painted CP
for new station

George B. Bairey
REGISTERED PROFESSIONAL ENGINEER
NUMBER 1188
DISTRICT OF COLUMBIA

EXHIBIT E-1-1
HORIZONTAL PLANE PATTERN

GEORGE B. BAIREY
PROPOSED 1430KC-1KW-U-DA1
SANTA CLARA, CALIFORNIA

FCC File No. BP-14934
Accepted 7-26-61

New; George B. Bairey
Santa Clara, California

1430 KC

74

KNTA

KEGL


Measured Non-DA
(3-30-64ct)

Station KGBA
Santa Clara, California

1kw, DA-1, U
1430kc

EUGENE DIETZGEN CO.
MADE IN U. S. A.

NO. 340R-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-10393
Accepted 2-25-64

Station KGBA
Santa Clara, California

1430kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KEES Main Studio: Gladewater, Texas
 Frequency: 1430 KHz Power: 1 Kw Night 5 Kw Day
 Notification: 1778 Date: August 30, 1978 Class: III

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 32° $31'$ $46''$
 West Longitude: 94° $52'$ $50''$

Predicted effective Daytime Field (omnidirectional) $420 \frac{\text{mv}}{\text{m}}$ at rated power.

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 2
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER	:	S (#2)	N (#1)	_____	_____	_____	_____
HEIGHT ABOVE INSULATORS	:	162.4'	162.4'	(85°)	_____	_____	_____
PHASING	:	-59.5°	0°	_____	_____	_____	_____
FIELD RATIO	:	0.93	1	_____	_____	_____	_____
SPACING AND ORIENTATION	:	Towers in a row are spaced 258' (135°) on a line bearing 0° true.					


2.

GROUND SYSTEM: 120 - 172' equally spaced copper radials plus 120 - 50' interspaced radials about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


	<u>RMS</u>	THEORETICAL <u>RSS</u>	STANDARD <u>RMS</u>
Night	184.8 mv/m	183.6 mv/m	194.1 mv/m

Note: This notification concerns a change in transmitter site; increase in daytime power and the addition of a directional antenna nighttime operation.



GUY C. HUTCHESON
 CONSULTING RADIO ENGINEER
 ARLINGTON, TEXAS

HORIZONTAL RADIATION PATTERN



K E E S GLADEWATER, TEXAS
 Station
 1430 KHZ. 1 KW. 5 KW-LS.OA-N
 Frequency Power
 G1 = G2 = 85° = 162.4 FT.
 Height of Antennas

32° 31' 46"
 94° 52' 50"

FIG. 36A

PROPOSED NIGHTTIME
 HORIZONTAL PATTERN

770705
 SUPERSEDES 760526

PROPOSED NIGHT

Station KTUL
Tulsa, Oklahoma

5kw, DA-N,U
1430 KC

KELI

NL 36° 14' 10"
WL 95° 56' 50"

Fig. 1

PROPOSED NIGHTTIME
HORIZONTAL RADIATION PATTERN


KTUL 1400 KC 5 KW
Tulsa, Okla.

Jansky and Bailey Washington, D. C.
July 1939

Parameters for 1430 kc

1/0° - 91.6°(175') - .856/137° -- 0°T

Height - 215'




KELI

Measured Night
(4-28-66ct)

Station KELI
Tulsa, Oklahoma

5kw, DA-N, U
1430 kc

W.D.LIC
3-24-66
REMOTE CONTROL



RMS
MEOV 476.3 mV/M

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE A	STATION DATA
G=110° 0° No.1 1.427/138° 90° No.2 1/0°	POWER No.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING P'	FIELD RATIO F	MEASURED NIGHT DIRECTIONAL PATTERN --- PATTERN CHECK FEBRUARY 1966	CALL KELI FREQ 1430 Kc/S POWER 5 Kw TYPE DA-N TIME NIGHT LAT. 36-14-10 N LONG. 95-56-50 W E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
	1						
	2						
	3						
	4						
	5						
	6						
	7						
	8						
	9						
	10					DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☒	0° 0°

FCC File No. BRC-2860
Accepted 4-8-66

Station KELI
Tulsa, Oklahoma

1430 kc

1450 KELI 1430





Fig. 14
 HORIZONTAL RADIATION PATTERN
 KTUL Tulsa, Okla.
 5000 W TA 1400 KC
 Jansky and Bailey Washington, D.C.
 Dec. 1938



EUGENE DIETZEN CO.

NO. 340-P DIETZEN GRAPH PAPER
 POLAR CO-ORDINATE


KJAY

Proposed Day
(10-26-62ct)

Station KJAY
Sacramento, California

500w, DA-D, D
1430 kc

11-20-62
printed map to
make changes in DA
atten + mbrx + ntr



$E_{RMS} = 124 \text{ MV/M}$

----- EXPANDED SCALE
..... M.E.O.V.

LATITUDE: N 38° 29' 34"
LONGITUDE: W 121° 32' 10"

ANTENNA PARAMETERS




FIGURE 4

DAYTIME DIRECTIONAL
HORIZONTAL PATTERN

RADIO CARMICHAEL
SACRAMENTO, CALIF.

JOHN H. MULLANEY
CONSULTING RADIO ENGINEER
WASHINGTON, D. C.

1430 KC

500 WATTS, DA-D

FCC File No. BMP-10595
Accepted 10-17-62

Station KJAY
Sacramento, California

1430 kc

KJAY

Measured Day
(7-24-63ct)

Station KJAY
Sacramento, California

500w, DA-D, D
1430 kc


North Latitude 38° 29' 39"
West Longitude 121° 32' 47"

Engineer: Fred W. Volken

GRAPH P

MEASURED DIRECTIONAL
HORIZONTAL RADIATION PATTERN

KJAY
1430 KC
SACRAMENTO, CALIFORNIA



	THEORETICAL	MEASURED
#1	1.00 / 0°	1.00 / 0°
#2	1.00 / +22°	0.98 / +25°
#3	1.00 / -96°	0.93 / -93.5°
#4	1.00 / -74°	0.94 / -74.5°

FCC File No. BL-10112
Accepted 7-2-63

Station KJAY
Sacramento, California

1430 kc

KJAY

Measured Non-DA
(7-24-63ct)


Station KJAY
Sacramento, California

500w, DA-D, D
1430 kc

GRAPH 0

MEASURED NON-DIRECTIONAL
HORIZONTAL RADIATION PATTERN
(TOWER #1)

KJAY
1430 kc
SACRAMENTO, CALIFORNIA



FCC File No. BL-10112
Accepted 7-2-63

Station KJAY
Sacramento, California

1430 kc

KKAT


MEASURED NON-DA
(12-21-59g)

Station KGFL
Roswell, New Mexico

1kw, 5kw-LS, DA-N, U
1430 KC

KGFL
KGFL, INCORPORATED
ROSWELL, NEW MEXICO
1430 KC 5 KW,LS 1 KW,N DA-N
OCTOBER 1959

MEASURED NON-DIRECTIONAL
HORIZONTAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE



LAT 33° 26' 11"
LONG 104° 36' 18"

RMS 434 MV/M
G 172° 90°

Vir N. James

CONSULTING RADIO ENGINEER

1316 S. KEARNEY, DENVER 22, COLORADO


FCC File No. BL-7711
Accepted 11-18-59

KGFL
Roswell, New Mexico

1430 KC

Handwritten note:
No. 12-21-59g
1430 KC
10-22-63

*Printed for Change of facilities
and station DA-N 6 22 00*



KKAT


MEASURED NIGHT
(12-21-59g)

Station KGFL
Roswell, New Mexico

1kw, 5kw-LS, DA-N, U
1430 KC

KGFL
KGFL INCORPORATED
ROSWELL, NEW MEXICO
1430 KC 5 KW,LS 1 KW,N DA-N
OCTOBER 1959

EXHIBIT E-804A



KKAT



PROPOSED NIGHT
(5/27/57g)

Station KGFL
Roswell, New Mexico

1kw,5kw-LS, DA-N,
1430 KC

LAT 33° 26' 11"
LONG 104° 36' 18"

*Granted CP 1/14/59 for
change in freq from
1400 KC, increase
power & for
DA system*



RADIO STATION KGFL
ROSWELL, NEW MEXICO
1430 KC 1KW 5KW-LS DA-N

TOWER	1	2	3	4
FIELD	1.00	1.95	1.95	1.00
PHASE	6200	-98.20	98.20	-62.00

A. EARL CULLUM, JR.
CONSULTING ENGINEERS
570408.2 FIGURE 7A

FCC File No. BP-11,273
Accepted 4/15/57

KGFL
Roswell, New Mexico

1430 KC

KLO

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KLO

Main Studio: Ogden, Utah

Frequency: 1430 kHz

Power: .5 kW

Notification List No. 1652

Date: October 1, 1975

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 10' 38"

West Longitude: 112° 04' 12"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 3

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	SW(#1)	C(#2)	NE(#3)	
HEIGHT ABOVE INSULATORS:	300'	300'	300'	(156.9°)
PHASING:	0°	+200°	+46°	
FIELD RATIO:	1.0	1.23	1.11	

SPACING AND

ORIENTATION: From reference tower #1; tower #2 is spaced 144.33' (75.49°) on
a line bearing 36.047° true, and tower #3 is spaced 305.95'
(160.025°) on a line bearing 38.994° true.

GROUND SYSTEM: 120-200' equally spaced copper radials plus a 48' square
ground screen about each tower. Radials are shortened and
bonded to transverse straps along intersections between towers.


Predicted effective Night Field: 499 mv/m at rated power.

Predicted effective Day Field: (omnidirectional) 493 mv/m at rated power.


Note: This notification concerns minor changes in the directional antenna
system and radiation pattern with Daytime operation continued as
previously notified.

CTR NO 30377A4

KLO




AMENDED COPY



STATION	KLO
LOCATION	OGDEN, UTAH
FREQUENCY	1430 Kcs
POWER	5KW U, DA-N
LATITUDE	41° 10' 36"
LONGITUDE	112° 04' 12"
RMS	499 mv/m
PATTERN	NIGHTTIME
DATE	MAY, 1975
ROBERT R. BLANCHARD LAKEWOOD, COLORADO	

KLO
1430



HORIZONTAL PLANE RADIATION
K L O - OGDEN, UTAH
PROPOSED 1430 KC. - 5 KW - DA
PATTERN NO. 470618
SUPERSEDES NO. 460620
REINSTATES NO. _____

JOHN BARRON
RADIO ENGINEERS WASHINGTON, D. C.

KLO

MEASURED
DAY & NIGHT


KLO OGDEN, UTAH

11/4/48

N
O

5kw, DA-1

1430kc



DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KOSI Main Studio: Aurora, Colorado
 Frequency : 1430 KHz Power : 5 kW Night 5 kW Day
 Notification: 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM:

North Latitude: 39 ° 33 ' 47 "
 West Longitude: 104 ° 55 ' 46 "

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 5

Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

(*) Center tower #3 is sectionalized. For nighttime operation, the top section of tower #3 is detuned for an effective electrical height of 136°. For daytime operation, the effective electrical height of tower #3 is 225°.

TOWER	:	<u>#1(N)</u>	<u>#2(NC)</u>	<u>#3(C)</u>	<u>#4(SC)</u>	<u>5(S)</u>
HEIGHT ABOVE INSULATORS	:	<u>260'</u>	<u>260'</u>	<u>429'*</u>	<u>260'</u>	<u>260'(136°)</u>
NIGHT PHASING	:	<u>65.9°</u>	<u>-136.9°</u>	<u>0°</u>	<u>142.7°</u>	<u>60.1°</u>
NIGHT FIELD RATIO:		<u>0.348</u>	<u>0.860</u>	<u>1.0</u>	<u>0.860</u>	<u>0.348</u>

SPACING AND
 ORIENTATION:

Adjacent towers in a row are spaced 191' (100°) on a line bearing 190° true.

GROUND SYSTEM:


120 - 240 equally spaced copper radials about tower #3
 plus 120 - 170' interspaced radials about the remaining
 towers plus 120-50' interspaced radials about each tower.
 Radials are shortened and bonded to transverse straps
 along intersections between towers. Centers of system
 are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD	
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>	
Day	<u>612.7</u>	<u> </u>	<u> </u>	mV/m
Night	<u>532</u>	<u> </u>	<u>558.6</u>	mV/m

Note:

JUNE 1977



PROPOSED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

S = 100°
G = 136°

#1: 0.348 / +65.9°
S
#2: 0.860 / -136.9°
S
#3: 1.00 / 0°
S
#4: 0.860 / 142.7°
S
#5: 0.348 / -60.1°
↓
190° TRUE

ARMSTRONG
BROADCASTING CORPORATION

AURORA, COLORADO

Jules Cohen & Associates
Consulting Electronics Engineers


RADIO STATION KOSI

1430 KHZ

5 KW U DA-N

Pattern No. 770621

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 5 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 10 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 15 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

EXIST.
R-1212-1977

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 20 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 25 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Conen & Associates Consulting Electronics Engineers

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 30 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 35 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 40 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

EXIST.
MAY 12 1977

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 45 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 50 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U D-A-N

Jules Cohen & Associates Consulting Electronics Engineers

JUNE 1977




PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 55 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N

Jules Cohen & Associates Consulting Electronics Engineers

EXISTING
JUN 12 1977

JUNE 1977



PROPOSED NIGHTTIME RADIATION PATTERN
AT VERTICAL ANGLE OF 60 DEGREES

ARMSTRONG BROADCASTING CORPORATION
RADIO STATION KOSI AURORA, COLORADO
1430 KHZ 5 KW U DA-N


Jules Cohen & Associates Consulting Electronics Engineers

KOSI

Measured Night
(6-29-70ct)

Station KOSI
Aurora, Colorado

5kw, DA-N, U
1430 kc
Figure 1



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

10° True (1) 0.348 / +65.9° (2) 0.86 / 136.2° (3) 0.160° (4) 0.86 / +142.7° (5) 0.348 / 60.1° S-100° (191°) G-136° (260°)	ARMSTRONG BROADCASTING CORPORATION AURORA, COLORADO	RADIO STATION KOSI 1430 KHZ
	Jules Cohen & Associates Consulting Electronics Engineers	5 KW U DA N JANUARY 1970

FCC File No. BZ-7509
Accepted 6-4-70

Station KOSI
Aurora, Colorado

1430 kc


KOSI

Proposed Night
(8-28-64ct)

Station KOSI
Aurora, Colorado

5kw, DA-N, U
1430 kc
EXHIBIT E-5.1

CP 6-14-65
CHG. PWR. 500W TO
5 KW. DA-N.
CHG. LOG
CHG. DA



FCC File No. BP-16253
Accepted 8-7-64

Station KOSI
Aurora, Colorado

1430 kc

KOSI

CP. 6-14-65
CHG. PWR.
LCC.
DA

5kw, DA-N, U
1430 kc

Station KOSI
Aurora, Colorado

Proposed Night Nulls
(8-28-64ct)

K O S I
ARMSTRONG BROADCASTING CORPORATION
1430 KC/S 5000 WATTS DA-N
AURORA, COLORADO
FEBRUARY 1964

Vir James
CONSULTING RADIO ENGINEERS
DENVER, COLORADO 3441 LOGAN BLVD. #1706
PHONE 161-333-5187

VERTICAL ANGLE - 0°
CONICAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

KELI 540 MI
KALV 390 MI
XELK 1610 MI
XELK 1230 MI
KELI 440 MI
XELK 890 MI
KALV 790 MI
KARM 830 MI
KLD 395 MI
KBRC 1085 MI

EXHIBIT E-5.2

— CALCULATED
--- M.E.O.V.

DEGREES FROM TOWER LINE

TRUE AZIMUTH

1430 kc

Station KOSI
Aurora, Colorado

FCC File No. BP-16253
Accepted 8-7-64

Measured Night
(9-28-67ct)

Station KOSI
Aurora, Colorado

KOSI
5kw, DA-N, U
1430 kc


K O S I
ARMSTRONG BROADCASTING CORPORATION
1430 KHZ 5000 WATTS DA-N
AURORA, COLORADO
MAY 1967

EXHIBIT E-8.04A

AMENDED

MEASURED NIGHTTIME DIRECTIONAL
HORIZONTAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

OVER



FCC File No. BL-11733
Accepted 8-20-67


Station KOSI
Aurora, Colorado

1430 kc

Measured Non-DA
(9-28-67ct)

Station KOSI
Aurora, Colorado

KOSI
5kw, DA-N, U
1430 kc.



FCC File No. BL-11733
Accepted 8-30-67

Station KOSI
Aurora, Colorado

1430 kc

Measured Non-DA
(9-28-67ct)

Station KOSI
Aurora, Colorado


KOSI
5kw, DA-N, U
1430 kc

K O S I
ARMSTRONG BROADCASTING CORPORATION
1430 KC/S 5000 WATTS DA-N
AURORA, COLORADO
OCTOBER 1966

MEASURED NON-DIRECTIONAL
HORIZONTAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE

PRE-SUNRISE OPERATION 5000 WATTS

EXHIBIT E-8.03B



FCC File No. BL-11733
Accepted 8-30-67

Station KOSI
Aurora, Colorado


1430 kc

PROPOSED
NIGHT

Station KRG1
NEW, GRAND ISLAND, NEB.
Grand Island B/cg Co.

1 KW, U, DA-N

1430 KC



AMD RECD 11/29/51 AGC 11/30/51 BP-8169 Amd.

NEW, GRAND ISLAND, NEB.
Grand Island B/cg Co.

1430 KC

KRGI


MEASURED
NIGHT

KRGI, GRAND ISLAND, NEBRASKA
(5/27/53G)

1kw, U, DA-N

1430 kc

11-7-62
granted up to
increase day ND
power to 5 kw
9-27-63
determined if
for increase
in 100 day
power and
if approved
increase
in 200 day



MEASURED
NON-DA


(5/27/53G)

KRGI, GRAND ISLAND, NEBRASKA

5 kw, U, DA-N

KRGI

1430 kc




WBRB

Proposed Day
(8-26-66ct)

Station WBRB
Mt. Clemens, Michigan

500w, DA-D, D
1430 kc

BP 17308
P 8-4-66



$E_{RMS} = 124.8$ (BY ADJUSTMENT)

PATTERN MINIMA: $100^\circ, 170^\circ, 210^\circ,$
AND 280°

LATITUDE: $42^\circ 32' 42''$

LONGITUDE: $82^\circ 54' 04''$

ANTENNA PARAMETERS

$G_2 = G_3 = 99.5^\circ$

$G_1 = 219^\circ$

$10^\circ T$

1 $\odot .535/-142.5^\circ$

2 $\odot 1.0/0^\circ$

3 $\odot .741/+142.5^\circ$

660325

FIGURE 4

PROPOSED DIRECTIONAL ANTENNA PATTERN

RADIO STATION WBRB
MOUNT CLEMENS, MICHIGAN

1430 KC

500 DA-D

CHARLES E. BRENNAN
CONSULTING RADIO ENGINEERS
MILWAUKEE, WISCONSIN

FCC File No. BP-17308
Accepted 8-3-66

Station WBRB
Mt. Clemens, Michigan

1430 kc

WBRB

PROPOSED DAY
(7-8-59g)


Station WBRB
Mt. Clemens, Michigan

500w, DA-D, D
1430 KC

*Granted CP for change in H
BP 17308
INC HT
8-4-66
APPL DA-1
DENIED
7-31-63*

7-29-59

*Application for MCP to increase
height 190 ft / 193 ft overall
BMP 8714
and add second FM antenna*



FCC File No. BP-11554
Accepted 4-23-59 (Amended)

WBRB
Mt. Clemens, Michigan

1430 KC


WBRB

Measured Day
(3-29-67ct)

Station WBRB
Mt. Clemens, Michigan

500w, DA-D, D
1430 kc

3-24-67
GRANTED
LICENSE
ON CHANGE
TO 24 SYSTEM



$E_{RMS} = 124 \text{ mV/m}$

LATITUDE: $42^{\circ} 32' 42''$
LONGITUDE: $82^{\circ} 54' 04''$

CHARLES E. BRENNAN
CONSULTING RADIO ENGINEERS
MILWAUKEE, WISCONSIN

ANTENNA PARAMETERS

$G_1 = G_2 = 99.5^{\circ}$
 $G_2 = 219^{\circ}$
 $S = 80^{\circ}$
 $1 \odot .535 / -142.5^{\circ}$
 S
 $2 \odot 1.0 / 0^{\circ}$
 S
 $3 \odot .741 / +142.5^{\circ}$

861129

FIGURE 4

MEASURED DAYTIME PATTERN
RADIO STATION WBRB
MOUNT CLEMENS, MICHIGAN

1430 KC

500 DA-D

FCC File No. BL-11582
Accepted 3-15-67

Station WBRB
Mt. Clemens, Michigan


1430 kc

Measured Non-DA
(3-29-67ct)

Station WBRB
Mt. Clemens, Michigan

500w, DA-D, D
1430 kc

1-4-7
PRINTED
1-3N-3
OV. HANSE
10 DA SYSTEM


$$E_{\text{RMS}} = 129 \text{ MV/V}$$

LATITUDE: 43° 30' 40" N LONGITUDE: 82° 54' 04" W	ANTENNA PARAMETERS	661129 FIGURE 3
CHARLES E. BRENNAN CONSULTING RADIO ENGINEERS MILWAUKEE, WISCONSIN	MEASURED WITH 250 WATTS INPUT TO TOWER 2. TOWER 2 = 219° 1 ○ 2 ○ 3 ○	MEASURED NON-DIRECTIONAL PATTERN RADIO STATION WBRB MOUNT CLEMENS, MICHIGAN

FCC File No. BL-11582
Accepted 3-15-67

Station WBRB
Mt. Clemens, Michigan

1430 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WBRB

Main Studio: Mt. Clemens, Michigan

Frequency: 1430 kHz

Power: 0.5 kW

Notification List No. 1704

Date: October 5, 1976

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:North Latitude: $42^{\circ} 32' 43''$ West Longitude: $82^{\circ} 54' 03''$

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 5

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	N(#1)	CW(#2)	SW(#3)	CE(#4)	SE(#5)
HEIGHT ABOVE INSULATORS:	190'	420' (219°)	190'	190'	190' (99.5°)
NIGHT PHASING:	-130.056°	-	-	0°	+136.468°
NIGHT FIELD RATIO:	0.3672	-	-	1	0.5827
DAY PHASING:	-142.5°	0°	+142.5°	-	-
DAY FIELD RATIO:	0.535	1.0	0.741	-	-

SPACING AND

ORIENTATION: Nighttime, from tower #4, tower #1 is spaced 171.7' (89.867°) on a line bearing 0° true, and tower #5 is spaced 164.9' (86.313°) on a line bearing 160.992° true. Daytime, towers #1, #2 and #3 are spaced 152.9' (80°) on a line bearing 10° true.

GROUND SYSTEM: 120-175' equally spaced copper radials about towers #1, #2 and #3 plus a 48' square ground screen about towers #4 and #5. Radials are shortened and bonded to transverse straps along intersections between towers #1, #2 and #3.

(Cont'd)

WBRB

WBRB

2.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

		THEORETICAL		STANDARD	
		<u>RMS</u>	<u>RSS</u>	<u>RMS</u>	
Day	<u>1/</u> 124.8	mv/m	-	mv/m	
Night	146.57	mv/m	195.49	mv/m	156.89 mv/m

1/ By adjustment of input power.

Note: Please retain the Daytime directional antenna radiation pattern notified for Station WBRB in United States Change List Number 1176 dated August 10, 1966 and attach to this Revised Description Sheet and Nighttime pattern. This notification concerns the addition of a new Nighttime operation for the station with Daytime operation continued as previously notified.

CTR NO: 31124A3





FIGURE 1-2

STANDARD HORIZONTAL PLANE PATTERN

SPACING AND ORIENTATION




APPLICANT	WALSH BROADCASTING CO.
LOCATION	1 MT. CLEMENS, MICHIGAN (WBRB)
FREQUENCY	1430 KC/S
POWER	0.5 KW - U DA-2
LATITUDE	42 DEG 32 MIN 53 SEC
LONGITUDE	82 DEG 55 MIN 00 SEC
WHEN USED	NIGHTTIME
RMS FIELD	150.89 Mv/m (STANDARD)
DATE	AUGUST 1958

SILLIMAN, MOFFET & KOWALSKI
 CONSULTING RADIO ENGINEERS
 WASHINGTON, D.C.

INDEX MONROE
NC

MEASURED PATTERN
Mv/M IN KILOMETERS



MEASURED NIGHTTIME OPERATING PARAMETERS


TOWER	FIELD	PHASE	SPACING	ORIENTATION
# 1	1	0	0	0
# 2	1.051	72.1	100	279
# 3	1.322	96.4	190.56	343.5
# 4	1.218	10.8	173	15

FIGURE 14 B

MEASURED
NIGHT-TIME DIRECTIONAL


W. LEE SIMMONS, INC.
BROADCAST CONSULTANTS
MONROE, LOUISIANA

WEEF - HIGHLAND PARK IL.



SPECIFIED
 $RMS_{theo} = 182.500 \text{ mV/m}$
 $RMS_{std} = 191.655 \text{ mV/m}$
 $RSS_{theo} = 154.215 \text{ mV/m}$ } AT 1 Mi


10X EXPANSION

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 7	STATION DATA
● = Unused towers 	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	PROPOSED HORIZONTAL PLANE STANDARD PATTERN HIGHLAND PARK, ILL. "NIGHTTIME" $\theta^\circ = 0$	WEEF WOVQ CALL 1430 kHz FREQ 1 kW POWER DA-2 TYPE UNLIMITED TIME N 42°09'26" LAT. W 87°51'02" LONG. E. HAROLD MUNN, JR & ASSOCIATES, INC. COLDWATER, MICH.
	No.	6°	5°	6°	F		
	1	78°		65°	0.90		
	2	78°		---	---		
	3	78°		---	---		
	4	78°		0°	1.00		
	5	78°		87°	0.90		
	6	78°		152°	0.81		
DAYTIME OPERATION ☐ NIGHT-TIME OPERATION ☒							

(Measured Non-DA
(1-22-71ct)

Station WEIR
Weirton, West Virginia

WEIR
1kw, DA-2, U
1430 kc



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
357° ↑ ○ No. 3 ○ No. 2 ○ No. 1		TOWER	ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	PHASING	HORIZONTAL FIELD ANGLE	P.F.D. PAT. D	ELEV. ANGLE	ELEVATION PHASE FIELD	CALL	WEIR
		No.	0	0	0	0	0	1.0	0	130	FREQUENCY	1430 kc
		1	90	0	0	0	0	1.0	0	130	POWER	1 kw
		2									TIME OF OPERATION	U
		3									TYPE OF OPERATION	DA-2
		4									EXISTING TOWERS	
		5									NIGHTTIME TOWERS	
		6									NO. HANDS PER TOWER	120
		7									LENGTH OF BASIS	90 - 170 ft
		8									LENGTH OF SCREEN DIVISION	48x48
9									DAY	40 26 45		
10									NIGHT	80 37 36		
		DATE/TIME OF OPERATION								PATTERN No. 701121		

Carl E. Smith
Consulting Radio Engineers

FIG. 7.14
ND HORIZONTAL PATTERN
Radio Station WEIR
Weirton, W. Virginia

FCC File No. BRC-3486
Accepted 12-30-70


Station WEIR
Weirton, West Virginia

1430 kc

Measured Night
(1-22-71ct)

Station WEIR
Weirton, West Virginia

WEIR
1kw, DA-2, U
1430 kc



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
357° ↑ ○ No. 3 ○ No. 2 ○ No. 1		TOWER	ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	FLAS NO.	HORIZONTAL FIELD	FIELD RATIO	FLEV ANGLE	ELEVATION	CALL
		No.	ft.	°	ft.	ft.	ft.	ft.	ft.	ft.	FREQUENCY
		1	90	0	0	0		1.0	0	160	WEIR
		2	90	357	110	163		1.889	10		1430
		3	90	357	220	308		0.957	20		POWER
		4							30		1
		5							40		TIME OF OPERATION
		6							50		U
		7							60		DA-2
		8							70		DAYTIME TOWERS
		9							80		NIGHTTIME TOWERS
		10							90		1, 2, 3
		DAYTIME OPERATION		NIGHTTIME OPERATION						NO. TOWERS PER TOWER	
										120	
										LENGTH OF PATTERN	
										90 - 170	
										GROUND SCREEN DIMENSIONS	
										48x48	
										DATE	
										40 26 45	
										LONG	
										80 37 36	
										SUPERSEDES	
										500918	
										PATTERN NO.	
										701121	

Carl E. Smith
Consulting Radio Engineers

FIG. 7.42
NIGHTTIME HORIZONTAL PATTERN
Radio Station WEIR
Weirton, W. Virginia


FIG. 7.42
NIGHTTIME HORIZONTAL PATTERN
Radio Station WEIR
Weirton, W. Virginia



Measured Day
(1-22-71ct)

Station WEIR
Weirton, West Virginia

WEIR
1kw, DA-2, U
1430 kc



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA			
357° No. 3 No. 2 No. 1		TOWER No.	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION °	SPACING ft	PHASING °	HORIZONTAL FIELD mV/m	FIELD RATIO	ELEV. ANGLE °	ELEVATION RMS FIELD mV/m	CALL WEIR	FREQUENCY 1430	
		1	90	0	0	0	1.0	C	181	POWER 1	TIME OF OPERATION U		
		2	90	357	110	128	0.58	D		TYPE OF OPERATION DA-2			
		3	90	357	220	263	0.563	D		DAYTIME TOWERS 1, 2, 3			
		4								NIGHTTIME TOWERS ---			
		5								NO. RADIALS PER TOWER 120			
		6								LENGTH OF RADIALS 90 * 170 ft			
		7								GROUND SCREEN DIMENSION 48x48			
		8								LAT. 40° 26' 45"			
		9								LONG 80° 37' 36"			
10								SUPERSEDES 500918					
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐										PATTERN No 701121			

Carl E. Smith
Consulting Radio Engineers

FIG. 7.28
DAYTIME HORIZONTAL PATTERN
Radio Station WEIR
Weirton, W. Virginia

FCC File No. BRC-3486
Accepted 12-30-70

Station WEIR
Weirton, West Virginia

1430 kc

PROPOSED
DAY

NEW, WEIRTON, W. VA.
(Weirton Bg. Co.)

WEIR

WEIRTON, W. VA.


1kv, DA2

1430 kc
FIGURE 18

5/26/49G

TRUE NORTH

1430 KC 1 KW U DA-2



SITE: 40° 26' 45" N
80° 37' 36" W

CALCULATED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

357° TRUE 3 0.67 / 135° 110° 209.84' 2 0.71 / 0° 110° 209.84' 1 1.0 / -135° G = 90° = 170°	WEIRTON BROADCASTING COMPANY WEIRTON WEST VIRGINIA	WEIRTON BROADCASTING COMPANY WEIRTON WEST VIRGINIA
	WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON D.C. DALLAS TEXAS	1430 KC 1 KW U DA-2 W 490412C

AMENDMENT RECD 5-9-49 to BP-6788

New, Weirton, W. Va. 1430 kc


WEIR

MEASURED
DAY


WEIR, WEIRTON, W. VA.

1kw, DA-2

1430 kc



MEASURED DAYTIME HORIZONTAL PLANE RADIATION PATTERN



WEIR, Weirton, W. Va. 1430 kc

PROPOSED
NIGHT

NEW, WEIRTON, W. VA.
(Weirton Bg. Co.)

WEIR


WEIRTON, W. VA.

1kw, DA2

1430 kc


FIGURE 10.0

5/26/49G



SITE: 40° 26' 45" N
80° 37' 36" W

CALCULATED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN



WEIRTON BROADCASTING COMPANY
WEIRTON WEST VIRGINIA

WELDON & CARR
CONSULTING RADIO ENGINEERS
WASHINGTON D.C. DALLAS TEXAS

WEIRTON BROADCASTING COMPANY
WEIRTON WEST VIRGINIA

1430 KC 1 KW U DA-2
W 4904128


PROPOSED
NIGHT NULLS

NEW, WEIRTON, W. VA.
(Weirton Bg. Co.)

WEIR
1kw, DA2

WEIRTON, W.VA.
1430 kc
FIGURE 10.1

5/26/49G



CALCULATED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

SITE: 40° 26' 45" N
80° 37' 36" W

DETAIL IN NULLS

WEIRTON BROADCASTING COMPANY
WEIRTON WEST VIRGINIA

WELDON & CARR
CONSULTING RADIO ENGINEERS
WASHINGTON D.C. DALLAS TEXAS

WEIRTON BROADCASTING COMPANY
WEIRTON WEST VIRGINIA


1430 KC 1 KW U DA-2
W 490412A

MEASURED
NIGHT


WEIR, WEIRTON, W. VA.

1kw, DA-2

1430 kc



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN



WEIR, Weirton, W. Va. 1430 kc


WEIR

MEASURED
NIGHT NULLS

WEIR, WEIRTON, W. VA.

1kw, DA-2

1430 kc



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

Details in Nulls

THE TRI-STATE BROADCASTING COMPANY

WELDON & CARR CONSULTING RADIO ENGINEERS

DALLAS ● WASHINGTON ● SEATTLE

Figure 10

WEIR

Weirton

West Virginia

1430 KC

1 KW

U DA-2

WEIR, Weirton, W. Va. 1430 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

WENE

Station: WENE

Main Studio: Endicott, New York

Frequency: 1430 kHz

Power: 5 kW

Notification List No. 1615

Date: January 16, 1975

Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 04' 56"
West Longitude: 76° 01' 53"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 5

Type of elements: Series-excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	NW(#3)	NC(#2)	NE(#1)	SW(#5)	SE(#4)
HEIGHT ABOVE INSULATORS:	200'	200'	200'	200'	200' (104.5°)
PHASING:	+4°	-140°	+80°	-80°	+140°
FIELD RATIO:	1.0	0.685	0.26	0.26	0.685

SPACING AND

ORIENTATION: From a reference point in the center of the array,
Tower #1 is located 344' (180°) on a line bearing 52° true,
Tower #2 is located 172' (90°) on a line bearing 50° true,
Tower #3 is located 11.5' (6°) on a line bearing 345° true,
Tower #4 is located 172' (90°) on a line bearing 230° true,
Tower #5 is located 344' (180°) on a line bearing 232° true.

GROUND SYSTEM: 120-172' equally spaced copper radials plus a 32' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

Predicted effective Night Field: 485 mv/m at rated power.


Predicted effective Day Field: (omnidirectional) 439 mv/m at rated power.

Note: Please retain the Nighttime verticle angle directional antenna radiation patterns notified for Station WENE in United States Change List Number 360, dated May 12, 1950, and attach to this Revised Description Sheet and Nighttime horizontal and vertical patterns. This notification concerns only a change in the meovs of radiation in the nighttime directional antenna pattern with daytime operation continued as previously notified.

CTR NO 31130A6

WENE





Figure 1A



WENE

AUGUST 1974

Figure 2



— Theoretical pattern

--- MEOV


⌊ Vertical departure bracket angle

NIGHTTIME VERTICAL PLANE RADIATION PATTERNS WENE, ENDICOTT, NEW YORK TOWARD WNJR

JANUARY ENTERPRISES, INC.
STATION WENE ENDICOTT, NEW YORK
1430 KHZ 5 KW U DA-N


Jules Cohen & Associates

Consulting Electronics Engineers




5kw, DA-N, U
1430 kc

figure 11



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN



JANUARY ENTERPRISES, INC.

ENDICOTT, NEW YORK

Jules Cohen & Associates
Consulting Electronics Engineers

WENZ.

1430 KHZ

5 KW U D.A.N

Pattern 700320

FCC File No. BZ-7741
Accepted 1-27-71

Station WENE
Endicott, New York

1430 kc


WENE

Measured Non-DA
(2-22-71ct)

Station WENE
Endicott, New York

5kw, DA-N, U
1430 kc

Figure 9



FCC File No. BZ-7741
Accepted 1-27-71

Station WENE
Endicott, New York

1430 kc

WENE

MEASURED
NIGHT & 


WENE, ENDICOTT, N. Y.

5kw, DA-N

1430 kc


*Grant's line, 9/27/58
to change to DA-N only*

Change chart 6/21/58 to DA-N



1430 kc

Granted Memo 9/27/5
to change to D. A. House 50



AMENDMENT RECD 2-27-50 BP-7413

WENE, Endicott, N. Y. 1430 kc


WENO

Measured Night
(4-24-64ct)

Station WENO
Madison, Tennessee

1kw, 5kw-LS, DA-N, U.
1430 kc

7/14/64
1430 to 2:00 AM
measured & plotted
L.A.



File No. BL-10528
cepted 4-21-64

Station WENO
Madison, Tennessee



1430 kc

Proposed Night
(12-19-61ct)

Station WENO
Madison, Tennessee

1kw, 5kw-LS, DA-N, U
1430 kc

2-7-63
center CP
change to
measured
A-N



HORIZONTAL PLANE PATTERN	
WENO MADISON, TENNESSEE	
1430 KC 1430 KC	PRESENT PROPOSED
5 KW-D ; 1 KW N-DA FEBRUARY 1, 1961	
— COMPUTED	M. LATI. 36° 16' 19"
--- MEQV	W. LONG. 86° 42' 53"
RMS = 177 mV/m	
LYNNE C. SNEYD, CONSULTING RADIO ENGINEER WASHINGTON 15, D. C.	
FIGURE 1	

FCC File No. BP-15188
Accepted 12-13-61

Station WENO
Madison, Tennessee

1430 kc


WENO

Measured Non-DA
(4-24-64ct)

Station WENO
Madison, Tennessee

1kw, 5kw-LS, DA-N, U
1430 kc

MEASURED NON DIRECTIONAL PATTERN
W E N O 5 KW-ND-1 / 1 KW-DA-N 1430 KC
MADISON TENNESSEE
JANUARY 1964



Broadcast Maintenance Service

Pea Bowman Route 5, Topeka, Kansas 66608
MUrdock 8-1872

File No. BL-10528
Accepted 4-21-64

Station WENO
Madison, Tennessee

1430 kc


MEASURED
DAY (6/6/56)

STATION WFOB
FOSTORIA, OHIO

1 KW
DA-2,U

1430 KC

WFOB




WFOB

PROPOSED DAY
(9/8/55G)

STATION WFOB
FOSTORIA, OHIO

1 KW
DA-2, U

1430 KC




WFOB

PROPOSED
NIGHT

NEW, FOSTORIA, OHIO
(Seneca Radio Corp.)

1kw, DA-2

FOSTORIA, OHIO - 1430 KC




WFOB

MEASURED
NIGHT

WFOB, POSTORIA, OHIO

1kw, U, DA-2

1430 kc




WFOB

MEASURED NON-DIRECTIONAL
(6/6/56G) STATION WFOB
FOSTORIA, OHIO

1 KW
DA-2, U

1430 KC




WHIL

PROPOSED NIGHT
(9-20-61ct)

Station WHIL
Everett, Massachusetts

5kw, DA-N, U
1430 kc

11



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

WASHINGTON, D. C.

PATTERN Proposed Nighttime Horizontal

FOR: WHIL, Everett, Mass.

POWER: 5 KW

FREQ: 1430 KC

DATE: 12/9/60


FCC File No. BP-15030
Accepted 8-30-61

Station WHIL
Everett, Massachusetts

1430 kc

JUN 28 12 MG

WIL
ST. LOUIS, MO.
1430 KC 5 KW-DA 2



MISSOURI BROADCASTING CORP. ST. LOUIS, MISSOURI		Figure 3 Series 480419C
		1430 KC 5000 WATTS DAY
		FRANK H. McINTOSH <i>Consulting Radio Engineer</i> Washington, D.C.

PROPOSED
DIRECTIONAL ANTENNA PATTERN

WIL

MEASURED
DAY

WIL, ST. LOUIS, MO.


License 3-11-49

5kw, DA2

1430kc

1430 KC 5 KW-DA 2

3/17/49G



SITE: 38° 32' 47" N
90° 11' 34" W


STATION WIL ST. LOUIS, MISSOURI		FIGURE 6A SERIES W490310
		1430 KC 5000 WATTS DAY
0.5 L-1100 1200 SPACING 90° H = 101°	MEASURED DIRECTIONAL ANTENNA PATTERN	FRANK H. McINTOSH <i>Consulting Radio Engineer</i> Washington, D.C.

WIL, St. Louis, Mo. 1430 kc

ST. LOUIS, MO
1430

WIL

1430 KC
5 KW
DA 2



MISSOURI BROADCASTING CORP. ST. LOUIS, MISSOURI		Figure 1 Series 480419W
PROPOSED DIRECTIONAL ANTENNA PATTERN		1430 KC 5000 WATTS NIGHT
1.02/146° 2.53/-23.2° 2.53/169.2° H=101° 1.020° SPACING 90° 3.40°		FRANK H. McINTOSH Consulting Radio Engineer Washington, D.C.

WIL

MEASURED
NIGHT

WIL, ST. LOUIS, MO.


License 3-11-49

5kw, DA2

1430kc

3/17/49G

1430 KC
5 KW
DA 2



SITE: 38° 32' 47" N
90° 11' 34" W

STATION WIL ST. LOUIS, MISSOURI		FIGURE 6B SERIES W490310
		1430 KC 5000 WATTS NIGHT
MEASURED		FRANK H. McINTOSH <i>Consulting Radio Engineer</i>
DIRECTIONAL ANTENNA PATTERN		Washington, D.C.

1.02146°
2.534-23.2°
2.534169.2°
H=101° 1.020°
SPACING 90°
340°

WIL, St. Louis, Mo. 1430 kc

PROPOSED DAY
(11-17-58g)

Station WION
Ionia, Michigan

5kw, DA-D, D
1430 KC

12-14 to
intercept
to 1430 KC
to 1430 KC
to 1430 KC




FIGURE 1B

FCC File No. BP-12,445
Accepted 10-29-58


WION
Ionia, Michigan

1430 KC

WION

Measured Day
(7-27-62ct)Station WION
Ionia, Michigan5kw, DA-D, D
1430 kc

4/28/62
until L for
change in day power
not DA-D

RMS 413.5 MV/M
MEOVMEAS. ———
PROP. - - - -N. L. 43° 00' 16"
W. L. 85° 05' 09"

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 2	STATION DATA
G = 102° 345° T. No. 3 .379/46P No. 2 1.0/0° No. 1 .807/+149° S = 80°	TOWER NO.	ELECTRICAL HEIGHT FT.	SPACING S	PHASING P	FEED MAX P	MEASURED WION DAYTIME PATTERN - - - MAY, 1962	CALL WION FREQ 1430 KC POWER 5 KW TYPE DA TIME DAY LAT. LONG.
	1						

FCC File No. BL-9442
Accepted 7-13-62Station WION
Ionia, Michigan


1430 kc

WION

Measured Non-DA
(7-27-62ct)

Station WION
Ionia, Michigan

5kw, DA-D, D
1430 kc



RMS MEQV 134.6 mV/m



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS				FIGURE 1	STATION DATA	
345° T. NON-DA TOWER 80° 80°	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	WION MEASURED NON-DIRECTIONAL FIELD FROM THE NORTH TOWER AT 0.5 KW POWER	CALL WION FREQ 1430 KC POWER 0.5 KW TYPE NON-DA TIME DAY LAT. LONG.
	1	6"	5'	4"	2"		
	2						
	3						
	4						
	5						
	6						
	7						
	8						
	9						
	10						
DAYTIME OPERATION ☐					NIGHTTIME OPERATION ☐	θ°	E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.

FCC File No. BL-9442
Accepted 7-13-62

Station WION
Ionia, Michigan

1430 kc

WIRE



BZ-7922

FIGURE 5 - REVISED
HORIZONTAL RADIATION PA
(DA-N OPERATION)
WIRE 5KW-U, DA-N 1430
MID AMERICA RADIO, IN
INDIANAPOLIS, INDIAN


Prepared by
Lohnes and Culver Washington

WIRE

Measured Non-DA
(5-28-64ct)

Station WIRE
Indianapolis, Indiana

5kw, DA-N, U
1430 kc
EXHIBIT NO. E-7



COMMERCIAL RADIO EQUIPMENT CO.
Radio Engineering Consultants

WASHINGTON, D. C.

MEASURED DAYTIME NON-DIRECTIONAL
WIRE INDIANAPOLIS, INDIANA
1430 KC, 5 KW-U, DA-N
DECEMBER 1963

FCC File No. BZ-5203
Accepted 4-28-64

Station WIRE
Indianapolis, Indiana

1430 kc

FIG. 4
HORIZONTAL RADIATION PATTERN
WIRE 1430 NO. 5 KW
INDIANAPOLIS, IND.

Jansky & Bailey, Washington, D.C.
Jan. 1940

RMS of measured
pattern = 547 MV/M

Brooklyn, N.Y.
500 m.


800 MV/M

Computed Pattern

Measured Pattern

$$\frac{k_1 I_1}{k_2 I_2} = 1.23$$

$$\alpha_{1,2} = 165^\circ$$



409130

1430

WJRB
1430KHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WJRB

Main Studio: Madison, Tennessee

Frequency: 1430 kHz

Power: 1kw Night 5kw Day

Notification List No. 1789

Date: September 12, 1980 Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS OF DAYTIME AND NIGHTTIME ANTENNA SYSTEMS:

DAYTIME

North Latitude: 36° 16' 17"
West Longitude: 86° 42' 57"

NIGHTTIME

North Latitude: 36° 16' 19"
West Longitude: 86° 42' 56"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 6

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	SE(#1)	NE(#2)	SW(#3)	NW(#4)	SW(#5)	NW(#6)
HEIGHT ABOVE INSULATORS:	420.62'	420.62'	172.07'	172.07'(90°)	420.62'	420.62'(220°)
NIGHT PHASING:	0°	+111°	—	—	+340°	+85°
NIGHT FIELD RATIO:	1	1	—	—	0.7822	0.7822
DAY PHASING:	0°	+130°	+339°	+107°	—	—
DAY FIELD RATIO:	1	0.43	0.37	0.35	—	—

SPACING AND ORIENTATION:

The towers #1, #2, #5 and #6 are located at the vertices of a parallelogram the long sides of which are 430.2' (225°) in length on a line bearing 116° true. The short sides are 153' (80°) in length on a line bearing 0° true. The towers #1, #2, #3 and #4 are located at the vertices of a parallelogram the long sides of which are 451.2' (236°) in length on a line bearing 261.5° true. The short sides are 153' (80°) in length on a line bearing 0° true.

GROUND SYSTEM: 120 - 172' equally spaced copper radials plus 120 - 35' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL					STANDARD
	<u>RMS</u>		<u>RSS</u>			<u>RMS</u>
Day	570.98	mv/m	753.27	mv/m		599.85 mv/m
Night	269.14	mv/m	356.02	mv/m		282.75 mv/m

330°

N

30°


Theo. RMS = 269.14 mv/m
Std. RMS = 282.75 mv/m
Theo. RSS = 356.02 mv/m
N 36°16'19" W 86°42'56"

NIGHTTIME STANDARD
HORIZONTAL PLANE PATTERN

RADIO STATION WJRB

1430 kHz 021079 1000 W (DA-2)

Standard Pattern



JOHN B. HEFFELFINGER
Consulting Communications Engineer
2808 WYOMING PLACE
KANSAS CITY, MISSOURI 64114

210°

180°

150°


Proposed Night
(10-26-64ct)

Station WMNC
Morganton, North Carolina

1kw, 5kw-LS, DA-N, U
1430 kc

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

V=0°



0 4884 / +66
110° No 4
12174 / +285.73
110° No 3
13532 / +144.45
110° No 2
1070
110° No 1

WEST LONGITUDE 81° 43' 03"
NORTH LATITUDE 35° 45' 08.5"

**COMPUTED HORIZONTAL
PLANE RADIATION PATTERN
FOR PROPOSED NIGHTTIME OPERATION AT
WMNC, MORGANTON, NORTH CAROLINA
1430 KC 1/5 KW DA-N U
AUGUST 1964**

FCC File No. BP-16328
Accepted 10-22-64

Station WMNC
Morganton, North Carolina

1430 kc

WMNC

Measured Night
(8-28-67ct)


Station WMNC
Morganton, North Carolina

1kw, 5kw-LS, DA-N, U
1430 kc

9-7-67
GRANTED
FOR DA-N

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

V=0°



MEASURED PARAMETERS

H - 104.7° = 205°
S - 110° = 210°

MEASURED HORIZONTAL
PLANE RADIATION PATTERN
FOR PROPOSED OPERATION OF
WMNC, MORGANTON, NORTH CAROLINA
1430 KC- 1/5 KW- DA-N U
JUNE 1967

NORTH LATITUDE 35° 45' 08.5"
WEST LONGITUDE 81° 45' 05"

FCC File No. BL-11716
Accepted 8-22-67

Station WMNC
Morganton, North Carolina

1430 kc


WMNC

Measured Non-DA
(8-28-67ct)

Station WMNC
Morganton, North Carolina

1kw, 5kw-LS, DA-N, U
1430 kc

9-7-67
GRANTED FOR
LICENSE FOR
DA-N



FCC File No. BL-11716
Accepted 8-22-67

Station WMNC
Morganton, North Carolina

1430 kc

CORRECTED DIRECTIONAL
ANTENNA DESCRIPTION SHEET

Station: WNAV

Main Studio: Annapolis, Maryland

Frequency: 1430 kHz

Power: 1 kW Night 5 kW Day

Notification List No. 1568

Date: February 21, 1974 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 38° 59' 00"

West Longitude: 76° 31' 21"

Authorized for Nighttime operation (DA-N)

Predicted effective Day Field: (omnidirectional) 195 mv/m at rated power,
by adjustment of input power.

Predicted effective Night Field: 245 mv/m at rated power.

*Note: Please retain the description sheet and directional antenna radiation patterns notified for station WNAV in United States Change List Number 381, dated November 14, 1950 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only corrections in the Predicted Day and Night effective fields.

CTR NO 31125A4

WNAV

MEASURED
NIGHT

WNAV, ANNAPOLIS, MD.

350°
10°

1kw, DA-N

1430 kc

Latitude 38° 59' 00"
Longitude 76° 31' 21"

$G_1 = G_2 = 215^\circ$ Elec.

$\theta_2 = 344^\circ$ T $S_2 = 90^\circ$

$E_1 = 0.825$ $\psi_1 = 0^\circ$

$E_2 = 1.0$ $\psi_2 = +140^\circ$

Measured RMS 240 mv/m

WNAV
1 kw DA-N 1430 kc
Annapolis, Maryland


Measured Nighttime DA
Horizontal Radiation Pattern

500112

GLENN D. GILLET & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON 4, D.C.

2/7/51G

1-31-51



WNAV, Annapolis, Md. 1430 kc

Yanner 45 KW 1-20-60
ND power

45 KW 6-27-60

WNAV

MEASURED NON-DA
(5-27-60g)

Station WNAV
Annapolis, Maryland

1kw, 5kw-LS, DA-N.U
1430 KC

Latitude 38° 59' 00"
Longitude 76° 31' 21"

Tower No. 1 with Tower
No. 2 Grounded

Measured RMS 396 mv/a

MEASURED DAYTIME RADIATION PATTERN

TOWER I


CAPITAL B/CING. CO.

ANNAPOLIS, MD.

1430 KC. 5KW-D, 1KW-DA-N

PREPARED BY: LLOYD S. SMITH

RMS = 396



FCC File No. BL-7916
Accepted 5-10-60

WNAV
Annapolis, Maryland

1430 KC

*Plotted on Wednesday, ND
from 15:00 to 6:27-00*

RMS 574.5 MV/M

Diagram showing a line segment with points #1 and #2. The segment is divided into two parts by a point. The first part is labeled 140° and the second part is labeled 118° . The total length of the segment is labeled 0.6120 .



GATEWAY TO THE
GARDEN OF EDEN


FIG. 4 (Rev.)
BROWN BROADCASTING CORPORATION
NEWARK, NEW JERSEY
1495 Rm 2 L.C. Rm 10-5
HORIZONTAL RADIATION PATTERN

SEP 9, 72

DIFFERENTIAL RECEIVED FOR NEW YORK DA 11,0 Page 40

WNJR





MEASURED
NIGHT

WNJR, NEWARK, N. J.


5kw, U, DA-N

1430kc

(1/9/580)

340° **FIG. II** NORTH**NIGHT HORIZONTAL
PLANE RADIATION**1430 KC 5 KW D.A.-N.
WNJR, NEWARK, N.J.

SHOWING TOLERANCE (FROM E.P. 3/45)

PAUL GODLEY CO.
CONSULTING RADIO ENGINEERS
LABORATORIES: GREAT NOTCH, N.J. 11/47

measured day mon DA

WNJR

MEASURED
DAY

(1/9/53G)

WNJR, NEWARK, N. J.

5kw, U, DA-N


1430 kc

FIG. 12₀

DAY HORIZONTAL
PLANE RADIATION

1430 KC 5 KW DA - N
WNJR, NEWARK, N.J.

PAUL GODLEY CO.
CONSULTING RADIO ENGINEERS
LABORATORIES: GREAT NOTCH, N.J. 11/47




5 KW
74-2, 11

POLAR CO-ORDINATE
MADE IN U.S.A.

NO. 10 HP

CLEVELAND INSTITUTE OF RADIO ELECTRONICS
CLEVELAND, OHIO



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS							STATION DATA			
		TOWER NO.	TOWER HEIGHT	RWG. TOWER ORIENTATION	STACK	SPACING	HORIZONTAL FIELD PAIR	FIELD PATTERN	ELEV. ANGLE	ELEVATION	CALL	FREQ.
		1	600	000	000	000	000	000	000	1430	1430	
		2	90	041	135	000	1	1	1	5	5	
		3	90	041	135	000	1	1	1	5	5	
		4	90	041	135	000	1	1	1	5	5	
		5	90	041	135	000	1	1	1	5	5	
		6	90	041	135	000	1	1	1	5	5	
		7	90	041	135	000	1	1	1	5	5	
		8	90	041	135	000	1	1	1	5	5	
		9	90	041	135	000	1	1	1	5	5	
		10	90	041	135	000	1	1	1	5	5	
		DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY ☐ NIGHT ☐								CALL ☐ FREQ. ☐		
		TYPE OF OPERATION ☐ DAY <										

1. *Chlorophyll a* (Chl *a*)

DATE : 06/6/98


DOI: 10.1002/for

WPCF

MEASURED DAY
(5-29-58g)Station WPCF
Panama City, Florida

5kw, DA-2, U

1430 KC



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS							STATION DATA		
		TOWER No.	ELECTRICAL HEIGHT G	TRUE TOWER ORIENTATION Z	SPACING S	PHASING V	HORIZONTAL FIELD ANGLE E	FIELD RATIO F	ELEV. ANGLE P	ELEVATION RMS FIELD dBm Eg	CALL W P C F
1										FREQUENCY 1430	
2	90°	041°	135°	-70°		.900		10		POWER 5.0	
3										TIME OF OPERATION Day	
4	90°	000°	000°	000°		1.00		20		TYPE OF OPERATION DA	
5								30		DAYTIME TOWERS 2 - 4	
6								40		NIGHTTIME TOWERS 1 - 2 - 3	
7								50		NO. RADIALS PER TOWER 120	
8								60		LENGTH OF RADIALS 104.5' 200'	
9								70		GROUND SCREEN DIMENSION 24 x 24	
10								80		LAT. 30° 09' 38"	
								RMS 426		LONG 85° 43' 43"	
		DAYTIME OPERATION ☒		NIGHTTIME OPERATION ☐				P ₁		SUPERSEDES	
								P ₂		PATTERN No. 589201A	
CLAUDE M. GRAY CONSULTING RADIO ENGINEER BIRMINGHAM, ALA.		MEASURED HORIZONTAL RADIATION PATTERN BAY COUNTY BROADCASTING COMPANY PANAMA CITY, FLORIDA									

FCC File No. B1-7110
Accepted 5-19-58WPCF
Panama City, Florida


1430 KC

granted 5-27-59

PROPOSED NIGHT
(6-16-58)

Station WPCF
Panama City, Florida

Ww, DA-2, C
1430 KC




TOWER PLACEMENT SKETCH		PATTERN PARAMETERS										STATION DATA	
N 350° E #3 0.609/-19.45 240° NO 41° E #2 1/000° 216° #1 0.677/14.55		TOWER No	ELECTRIC HEIGHT ft	TRUE TOWER ORIENTATION °	SPACING ft	PHASING °	HORIZONTAL FIELD ANGLE °	FIELD RATIO F	ELEV ANGLE °	ELEVATION HEIGHT ft	CALL	WPCF	
1	90	170	246	14.55		0.677				FREQUENCY	1430		
2	90	000	000	000		1				POWER	5.0		
3	90	350	246	-19.45		0.609				TIME OF OPERATION	Night		
4										TYPE OF OPERATION	DA		
5										DAYTIME TOWERS	2, 6, 4		
6										NIGHTTIME TOWERS	1, 2, 6, 3		
7										NO. RADIALS PER TOWER	120		
8										LENGTH OF RADIAL	201.5 - 200		
9										SPACING SCREEN DIMENSIONS	24" x 24"		
10										LONG	30" 09" 30"		
										SUPERSEDED	550520		
										SERIAL NO	551010		
										NIGHTTIME			
										PROPOSED HORIZONTAL RADIATION PATTERNS			
										W P C F PANAMA CITY, FLORIDA			
										5.0 KW-U DA-2 1430 KC			
										0° ELEVATION GROUND			

CLAUDE M. GRAY
CONSULTING RADIO ENGINEER
BIRMINGHAM, ALA.

EXHIBIT
1-A-II

PROPOSED HORIZONTAL RADIATION PATTERNS
W P C F PANAMA CITY, FLORIDA
5.0 KW-U DA-2 1430 KC
0° ELEVATION GROUND

MEASURED NIGHT
(5-29-58g)Station WPCF
Panama City, Florida5kw. DA-2.U
1430 KC

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
		TOWER No	ELECTRICAL HEIGHT G'	TRUE TOWER ORIENTATION θ	SPACING S'	PHASING φ	HORIZONTAL FIELD mV/m E	FIELD RATIO F	ELEV ANGLE θ°	ELEVATION RMS FIELD mV/m E _g	CALL # P C F
1	90°	178°	246°	+19.45°	0.609	0				FREQUENCY 1430 kc	
2	90°	000°	000°	000°	1.000	10				POWER 5.0 kw	
3	90°	358°	246°	-14.55°	0.677	20				TIME OF OPERATION Night	
4						30				TYPE OF OPERATION DA	
5						40				DAYTIME TOWERS 2 - 4	
6						50				NIGHTTIME TOWERS 1 - 2 - 3	
7						60				NO RADIALS PER TOWER 120	
8						70				LENGTH OF RADIALS 104.5' 200 //	
9						80				GROUND SCREEN DIMENSION 24' x 24'	
10						90				LAT. 30° 09' 38"	
										LONG 85° 43' 43"	
										SUPERSEDES	
										PATTERN No 580202A	
CLAUDE M. GRAY CONSULTING RADIO ENGINEER BIRMINGHAM ALA		MEASURED HORIZONTAL RADIATION PATTERN DAY COUNTY BROADCASTING COMPANY PANAMA CITY, FLORIDA									

FCC File No. HL-7119
Accepted 5-19-58WPCF
Panama City, Florida

1430 KC


granted 5-21-59

WPCF

MEASURED NON-DA
Accepted 5-19-58

WPCF
Panama City, Florida

1430 KC



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS										STATION DATA	
		TOWER No.	ELECTRICAL HEIGHT G	TRUE TOWER ORIENTATION P	SPACING S	PHASING Y	HORIZONTAL FIELD PATTERN E	FIELD PATTERN F	ELEV. ANGLE B	ELEVATION ANGLE F _h	CALL SIGNATURE WPCF	FREQUENCY 1430 Kc	
1										POWER 5.0 kw			
2	90°	000°	000°	000°			1.0			TIME OF OPERATION ND (Proof)			
3										TYPE OF OPERATION ND			
4										DAYTIME TOWERS 2			
5										NIGHTTIME TOWERS XX			
6										NO RADIALS PER TOWER 120			
7										LENGTH OF RADIALS 04.5' 200 ft			
8										GROUND SCREEN DIMENSION 24 x 24			
9										WAVELENGTH 30' 09" 38"			
10										LONG 85' 43' 43"			
DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☐										RMS 429 mV	SUPERSEDES		
										PATTERN No.	580203A		

CLAUDE M. GRAY
CONSULTING RADIO ENGINEER
BIRMINGHAM ALA

MEASURED HORIZONTAL RADIATION PATTERN

BAY COUNTY BROADCASTING COMPANY

PANAMA CITY, FLORIDA

FCC File No. BL-7110
Accepted 5-19-58

WPCF
Panama City, Florida

1430 KC

Granted 5-27-59

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WQDI Main Studio: Homestead, Florida
 Frequency : 1430 KHz Power : .5 kW Night .5 kW Day
 Notification No. 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 25 ° 27 ' 09 "
 West Longitude: 80 ° 30 ' 57 "

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER	:	<u>SW(31)</u>	<u>NE(#2)</u>	_____	_____	_____	_____
HEIGHT ABOVE INSULATORS	:	<u>200'</u>	<u>200' (104.6°)</u>	_____	_____	_____	_____
NIGHT PHASING	:	<u>0°</u>	<u>175°</u>	_____	_____	_____	_____
NIGHT FIELD RATIO:		<u>1.0</u>	<u>0.40</u>	_____	_____	_____	_____

SPACING AND

ORIENTATION: Adjacent towers in a row are spaced 305.7' (160°) on a line bearing 60° true.

GROUND SYSTEM: 120-172' equally spaced copper radials about each tower.
 Radials are shortened and bonded to a transverse strap
 along intersections between towers. Centers of system
 are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


	<u>RMS</u>	THEORETICAL	<u>RSS</u>		STANDARD	
					<u>RMS</u>	
Day	<u>138.6</u>	mV/m		mV/m		mV/m
Night	<u>145.14</u>	mV/m	<u>136.83</u>	mV/m	<u>152.52</u>	mV/m

Note:

WQDI


LOCATION:

N 25° 27' 00"
W 80° 30' 37"



RSS = 126.83 MV/M
RMS = 152.52 (STANDARD)
RMS = 145.14 (THEORETICAL)

HORIZONTAL RADIATION PATTERN



$\phi = 104.7^\circ$

FIG. 4 (REV.)
RADIO SOUTH DADE INC.
RADIO STATION WQDI
HOMESTEAD, FLORIDA
1430 KHz 0.5 KW's DA-N
HORIZONTAL RADIATION PATTERN


WTTT

Measured Non-DA
(6-28-63ct)

Station WTTT
Amherst, Massachusetts

5kw, DA-D, D
1430 kc

-6-63
measured
w new
station



FCC File No. BL-10034
Accepted 6-17-63

Station WTTT
Amherst, Massachusetts

1430 kc


WTTT

Measured Day
(6-28-63ct)

Station WTTT
Amherst, Massachusetts

5kw, DA-D, D
1430 kc

8-6-63
granted license
for new A-M station.



N 42° 21' 25"
W 72° 29' 13"

1.0/0.0
160° 75/430°
WEST EAST N 98° E
Q = 78.6°

DREUTZ & SNOWBERGER
Consulting Engineers
724 - 14TH STREET, NORTHWEST
WASHINGTON 5, D. C.

FCC File No. BL-10034
Accepted 6-17-63

WTTT

Station WTTT
Amherst, Massachusetts

FIGURE 21
MEASURED DIRECTIONAL PATTERN
RADIO STATION WTTT
AMHERST, MASSACHUSETTS
1430 KC 5KW DA-D
MARCH 1963

1430 kc

1430 KC

WVAM 1430 ALTOONA, PA. 1430

$G = 215^\circ$

$17-118^\circ$
 $0.96/11.4^\circ$
 $17-118^\circ$

90°
 90°
 355° True

GENERAL BROADCASTING CORPORATION

Altoona, Pennsylvania.

PROPOSED 1430 kc — 1 kw — U-DA

NIGHTTIME **WVAM**

HORIZONTAL PLANE RADIATION


MAY and BOND

CONSULTING RADIO ENGINEERS

WASHINGTON 4 D C

RMS = 253

FIG. NO. 3B



APPL. FOR CP ACCEPTED
 GRANTED CP from 1kw to 5kw
 changes in Antenna System

BP-17469

EUGENE DIETZEN CO

NO 340 P DIETZEN WASH D.C. LIT

N. LAT 40° 29' 18"
W. LONG 78° 24' 04"

JUNE 1948

AMENDED FIG. NO. 3B

1430.

150°

160²170³

180

190°

260°

210

 $G = 180^\circ$

$\bullet \xrightarrow{90^\circ} \bullet \xrightarrow{90^\circ} \bullet \xrightarrow{355^\circ} \bullet$
 $\downarrow \angle 118^\circ \quad .96 \downarrow 11.4^\circ \quad \downarrow \angle 118^\circ$

NIGHTTIME

**CALCULATED
RMS = 253**

----- MEASURED
RMS = 256

W V A M

ALTOONA, PA.


1430 Kc

1 KW DA-2

HORIZONTAL PATTERN

JOHN BARRON

CONSULTING RADIO ENGINEERS
Warner Bldg., Washington, D. C.



WVAM

Measured Night
(11-29-68ct)

Station WVAM
Altoona, Pennsylvania

1kw, 5kw-LS, DA-N, U
1430 kc

BL-12172
WANTED 2-14-69
LICENSE COVERING
INCREASE IN
DAYTIME POWER
& CHANGE
IN DAYTIME
ANTENNA
SYSTEM





FIGURE 4-B

HORIZONTAL RADIATION PATTERN



APPLICANT	WVAM
LOCATION	ALTOONA, PA.
FREQUENCY	1430 KC/S
POWER	1 KW. DA-N
LATITUDE	40 DEG 29' N 42' SEC
LONGITUDE	78 DEG 24' W 06' SEC
WHEN USED	NIGHTTIME
RMS FIELD	240.8 MV/M
DATE	SEPT. 1968

RAYMOND E. ROHRER & ASSOCIATES

CONSULTING RADIO ENGINEERS

WASHINGTON D. C.

FCC File No. BL-12172
Accepted 11-15-68

Station WVAM
Altoona, Pennsylvania

1430 kc

WVAM

Measured Non-DA
(11-29-68ct)

Station WVAM
Altoona, Pennsylvania

1kw, 5kw-LS, DA-N, U
1430 kc

BL12172
Granted
2-14-67
license
increased
in daytime
power
to 5 kw
in
daytime
antenna
system




FIGURE 4-A

HORIZONTAL RADIATION PATTERN

APPLICANT	WVAM
LOCATION	ALTOONA, PA.
FREQUENCY	1430 KC/S
POWER	5 KW. ND-D
LATITUDE	40° 29' 42" SEC
LONGITUDE	78° 24' 06" SEC
WHEN USED	DAYTIME
RMS FIELD	-----
DATE	SEPT 1968

RAYMOND E. ROHRER & ASSOCIATES
CONSULTING RADIO ENGINEERS

FCC File No. BL-12172
Accepted 11-15-68

Station WVAM
Altoona, Pennsylvania

1430 kc


WVXX

Measured Day
(8-23-63ct)


Station WEEF
Highland Park, Illinois

1kw, DA-D, D
1430 kc

2-20-64
revised
series for
new station



DESIGN PARAMETERS



S = 125° = 239'
H = 78° = 150'

42 09 26
87 51 02

HORIZONTAL RADIATION
PATTERN
WEEF 1KW 1430 KC
HIGHLAND PARK, ILL
JUNE 1963

ROBERT A. JONES
CONSULTING ENGINEER
LA GRANGE, ILLINOIS

FCC File No. BL-10179
Accepted 8-5-63

Station WEEF
Highland Park, Illinois

1430 kc


WVVX

Measured Non-DA
(8-23-63ct)

Station WEEF
Highland Park, Illinois

1kw, DA-D, D
1430 kc

2-20-64
granted
license for new
station



FCC File No. BL-10179
Accepted 8-5-63

Station WEEF
Highland Park, Illinois

1430 kc


WVX

Proposed Day
(10-26-62ct)


Station WNSH
Highland Park, Illinois

1kw, DA-D, D
1430 kc

11-20-62
granted map to
have change in D & P.



DESIGN PARAMETERS



S = 125° = 239'

N LAT 42 09 26

H = 78° = 150'

W LONG. 87 51 02

HORIZONTAL RADIATION PATTERN

WNSH 1 KW 1430 KC
HIGHLAND PARK, ILL.
SEPT. 1962

ROBERT A. JONES
CONSULTING ENGINEER
LA GRANGE, ILLINOIS

FCC File No. BMP-10583
Accepted 10-8-62

Station WNSH
Highland Park, Illinois

1430 kc


WWG

PROPOSED NIGHT
(6-16-59g)

Station WWGS
Tifton, Georgia

500w, DA-N, U
1430 KC

*granted MCP to move nighttime
x mtr location.*



1430 KC WWGS - Tifton, Georgia; BMP-8795. An application to modify CP by moving nighttime transmitter location was accepted by the FCC. Proposed nighttime coordinates are:

North Latitude 31° 27' 29"
West Longitude 83° 33' 39"

Make notation on Proposed Night pattern dated 6-16-59g.

FCC File NO. BP-11788
Accepted 5-18-59 (Amended)

WWGS
Tifton, Georgia

1430 KC

granted CP DA-N-6-17-59


WWGS

MEASURED NIGHT
(11-11-60g)

Station WWGS
Tifton, Georgia

1kw, 5kw-LS, DA-N, U
1430 KC

1-22-61
measured for
DA-N



FCC File No. BL-8143
Accepted 10-20-60

WWGS
Tifton, Georgia

1430 KC

PAGE, GERTZ, STEEL & WALSHMUTT
Consulting Engineers
1413 K STREET, NORTHWEST
WASHINGTON, D. C.

WWGS

MEASURED NON-DA
(11-11-60g)

Station WWGS
Tifton, Georgia

1kw, 5kw-LS, DA-N, U
1430 KC




Figure 8
Non-directional (test) Horizontal Radiation Pattern
Using Southeast Tower 3
WWGS Tifton, Georgia
1430 Kc 1/5 kw-LS DA-N
September, 1960

PAGE, CREUTZ, STEEL & WALDSCHMITT
Consulting Engineers
1412 K STREET, NORTHWEST
WASHINGTON 5, D. C.

FCC File No. BL-8143
Accepted, 10-20-60

WWGS
Tifton, Georgia

1430 KC

WYMC
1430 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WYMC

Main Studio: Mayfield, Kentucky

Frequency: 1430 kHz

Power: 1kw Night 1kw Day

Notification List No. 1785

Date: November 16, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 36° 47' 12"

West Longitude: 88° 39' 16"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-D)

Number of elements: 4

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	#1 (N)	#2 (NC)	#3 (SC)	#4 (S)
HEIGHT ABOVE INSULATORS:	140'	140'	140'	140' (73°)
NIGHT PHASING:	0°	-144.8	64.75	-76.0°
NIGHT FIELD RATIO:	1.000	1.63608	1.4355	0.6055

SPACING AND
ORIENTATION:

The towers are spaced 172' (90°) on a line bearing 195° true.

GROUND SYSTEM:

120 - 175' equally spaced copper radials about each tower.
Radials are shortened and bonded to transverse straps along
intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Night	177.99 mv/m	327.5 mv/m	186.93 mv/m

PREDICTED EFFECTIVE DAY FIELD: (Omnidirectional) 183 mv/m at rated power.

Note: Please retain directional antenna radiation pattern notified for a new Station in United States Change List Number 1682 dated April 27, 1976 and attach to this Revised Description Sheet. This notification concerns only a change in the Daytime operation of the station with Nighttime operation continued as previously notified.

WYMC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: (New)

Main Studio: Mayfield, Kentucky

Frequency: 1430 kHz

Power: 1 kW

Notification List No. 1682

Date: April 27, 1976

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 36° 47' 12"

West Longitude: 88° 39' 16"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-1)

Number of elements: 4

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	N(#1)	NC(#2)	SC(#3)	S(#4)
HEIGHT ABOVE INSULATORS:	140'	140'	140'	140' (73°)
PHASING:	0°	-144.8°	64.75°	-76.0°
FIELD RATIO:	1	1.636	1.436	0.606

SPACING AND


ORIENTATION: Adjacent towers in a row are spaced 172' (90°) on a line
bearing 195° true.GROUND SYSTEM: 120-175' equally spaced copper radials about each tower.
Radials are shortened and bonded to transverse straps
along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL RMS	RSS	STANDARD RMS
	177.99 mv/m	327.5 mv/m	186.93 mv/m

CTR NO 30459A3

STANDARD HORIZONTAL PLANE PATTERN



RSS = 327.5 mv/m

PATTERN PARAMETERS

1. 1.000 / 0°

2. 1.63608 / -144.8°

3. 1.4355 / 64.75°

4. 0.6055 / -76.0°

195° True S = 90° H = 73°

DIRECTIONAL RADIATION PATTERN

PURCHASE SOUND, INC

☐ MEASURED ☒ PROPOSED

FREQ: 1430 (KHZ) POWER: 1.0 (KW) ☒ DA-D

N. LAT. 36° 47' 12" ☒ DA-N

W. LONG. 88° 39' 16" ☐ N-D

LOCATION: MAYFIELD, KENTUCKY

DATE: DECEMBER 1974

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

DIRECTIONAL ANTENNA DESCRIPTION SHEET

STATION: New

MAIN STUDIO: Bathurst, N.B.

POWER: 10 kW

FREQUENCY: 1430 kHz, CLASS: III

NOTIFICATION LIST NO: 291

DATE: May 12, 1972

GEOGRAPHICAL LOCATION: North Latitude 47° 39' 20"
West Longitude 65° 40' 25"

ANTENNA CHARACTERISTICS

MODE OF OPERATION:

DA-1, Unlimited

ANTENNA CHARACTERISTICS:

Two elements, uniform cross-section guyed steel tower, base insulated for series feed, no top loading.

TOWERS:

No. 1

No. 2

HEIGHT ABOVE INSULATORS:

115' (60°)

115'

OVERALL HEIGHT:

120'

120'

FIELD RATIOS:

1.0

.85

PHASING:

0°

-60°

SPACING:

0°

230' (120°)

ORIENTATION:

Ref.

45°

GROUND SYSTEM:

120 equiangularly spaced radials extend from the base of each tower to a maximum distance of 275 ft. (0.4 wavelength) and bonded along the common chord. Ground wires are No. 10 B & S soft drawn copper wire, buried 8" in the ground.

PREDICTED FIELD:

570 mV/m for 10 kW

RCA LIMITED
APRIL 1972

PROJECT 5121-A-1




FIGURE 2
HORIZONTAL RADIATION PATTERN
NEW BRATBURST, N.B.
1430 KHZ 10 KW DA-1 CLASS III
PROJECT 5121-A1 APRIL 1972
RCA LIMITED MONTREAL, QUE.

PROJECT # 20404

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CFCO
FREQUENCY: 1440 kHz
NOTIFICATION LIST NO: 405

MAIN STUDIO: Ottawa, Ontario
POWER: 50 kW CLASS: III
DATE: June 12, 1981

GEOGRAPHICAL LOCATION:

Latitude	45° 16' 59" North
Longitude	75° 44' 31" West

ANTENNA CHARACTERISTICS:

```
Mode of Operation:      DA-2
Number of Elements:     6 (Six)
Type of Elements:       Guyed steel towers, uniform
                        cross-section, base insulated
                        for series feed.
```

Tower	#1	#2	#3	#4	#5	#6
Height above Base Insulator:	170' (90°)	170' (90°)	170' (90°)	170' (90°)	170' (90°)	170' (90°)
Overall Height:	175'	175'	175'	175'	175'	175'
Day Field Ratio:	-	-	2.0	-	1.0	0.83
Day Phasing:	-	-	-70.5°	-	0	-141.1°
Night Field Ratio:	1.0	2.6	2.6	.94	-	-
Night Phasing:	0°	-113°	-235°	-2°	-	-
Spacing:	341.4' (179.82°)	170.9' (90°)	Ref.	170.9' (90°)	208.8' (110°)	208.8' (110°)
Orientation:	197.5°	200°	Ref.	20°	174°	354°


GROUND SYSTEM: 120 equally spaced radials per tower of No. 10 B & S gauge bare soft copper wire, buried approximately 8". Length of radials is 273.4' (0.4 wavelength) with the exception of those joined along the common chords. Size limitations of the transmitter site do not allow a standard ground system. This will be offset by installation of extra long radials in other directions.

PREDICTED EFFECTIVE FIELD:

Nighttime:	1393	mV/m	at 1 mile	for 50 kW
	197	mV/m	at 1 mile	for 1 kW
Daytime:	1292	mV/m	at 1 mile	for 50 kW
	183	mV/m	at 1 mile	for 1 kW


December 3, 1980

Revised May 27, 1981



IN STOCK DIRECT FROM CODED BOOK CO., NORWOOD, MASS. 02062
PRINTED IN U.S.A.
GRAPH PAPER

NO. 3124. POLAR CO-ORDINATE.



CJOI
1440

PROJECT #11606

OK
APR 22, 73
PMB

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CJOI MAIN STUDIO: WETASKIWIN, ALBERTA

FREQUENCY: 1440 kHz POWER: 10 kW

NOTIFICATION LIST: 315 DATE: October 12, 1973

GEOGRAPHICAL LOCATION: Latitude 52° 57' 30" North
Longitude 113° 27' 00" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-N
Number of Elements: 3 (Three)
Type of Elements: Guyed steel towers, uniform cross-section, base insulated for series feed

TOWER:	#1(South)	#2(Centre)	#3(North)
Height above base insulator:	171' (90°)	171' (90°)	171' (90°)
Overall Height:	174'	174'	174'
Field Ratio:	.515	1.0	.361
Phasing:	+151°	0°	-149°
Orientation:	Ref.	350°T	350°T
Spacing:	Ref.	114' (60°)	228' (120°)


GROUND SYSTEM:



120 equally spaced radials per tower of #10 bare soft copper wire, buried approximately 8". The radials extend to a length of 191' (0.4 wavelength), with the exception of those joined along the common chords.

PREDICTED EFFECTIVE FIELDS:


Day	Night
601 mV/m at 1 mile for 10 kW	634 mV/m at 1 mile for 10 kW
190 mV/m at 1 mile for 1 kW	201 mV/m at 1 mile for 1 kW

March 30, 1973





UNATTENUATED (MV/M) 1 MILE FIELD





UNATTENUATED (MV/M) 1 MILE FIELD


VERTICAL RADIATION PATTERNS

FIGURE 4

CJ01
1440 kHz
PROJECT #11606
10 kW
DA-N
WETASKIWIN, ALBERTA
CLASS III
MARCH 30, 1973
D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS



UNATTENUATED (MV/M) 1 MILE FIELD



UNATTENUATED (MV/M) 1 MILE FIELD

VERTICAL RADIATION PATTERNS

FIGURE 5

CJOI
1440 kHz

10 kW

DA-II

NETASKIWIN, ALBERTA

CLASS III



MARCH 30, 1973

PROJECT #11606


D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

G9-10159 (NO 10LV)

POLAR - ORDINATE
MADE IN CANADA



UNATTENUATED (MV/M) 1 MILE FIELD



UNATTENUATED (MV/M) 1 MILE FIELD



VERTICAL RADIATION PATTERNS

FIGURE 6

CJ01 1440 kHz 10 kW DA-N WETASKIWIN, ALBERTA CLASS III
PROJECT #11606 MARCH 30, 1973
D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

G9-10159 (NO 101V)

POLAR CO-ORDINATE
MADE IN CANADA





VERTICAL RADIATION PATTERNS

FIGURE 7

CJOI 10 kW DA-II NETASKININ, ALBERTA
 1440 KHZ CLASS 11
 PROJECT #11006 MARCH 30, 197
 D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

G9-10159 (NO 10LV)

POLAR CO-ORDINATE
MADE IN CANADA



VERTICAL RADIATION PATTERNS

FIGURE 8

CJ01
1440 kHz
PROJECT #11606

10 kW

DA-II

WETASKIWIN, ALBERTA
CLASS III
MARCH 30, 1973

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

Description Sheet
(7-26-67ct)

New Station
Wetaskiwin, Alberta

CJOI
1kw, DA-1, U, Class III
1440 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: NEW

Main Studio: Wetaskiwin, Alberta.

Frequency: 1440 KHz

Power: 1 KW, DA-1 Class III

Notification List No. 227

Date: May 31, 1967

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM:

North Latitude: 52° 57' 30"

West Longitude: 113° 27' 00"

ANTENNA CHARACTERISTICS:

Mode of Operation:

DA-1

Number of Elements:

2

Type of Elements:

guyed, base insulated,
series fed, uniform
cross section.

TOWER: NO. 1 SOUTH

NO. 2 NORTH

HEIGHT ABOVE
INSULATORS: 171' (90°)

171' (90°)

OVERALL HEIGHT: 174'

174'

SPACING: 228' (120°)

PHASING: 0

-108°

FIELD RADIO: 1

.24

ORIENTATION: Towers on a line bearing 10° West of True North.


GROUND SYSTEM: 120 radials No. 10 AWG copper wire per tower.
Radials from each tower bonded to No. 4 AWG bus at right angles
midway between towers. Effective radial length. .4λ (191').

Predicted Effective Field (191 mv/m for 1 Kw).

Proposed Day & Night
(7-26-67ct)

New Station
Wetaskewin, Alberta

CJOI
1kw, DA-1, U, Class III
1440 kc



#125
AK
July 22, 78
PWS

Courtenay, B.C., Canada

CFOP

DESCRIPTION SHEET
(11-17-58g)

New Station
Courtenay, British Columbia, Canada

1kw, DA-N, U

1440 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: NEW

Main Studio: Courtenay, B.C.

Frequency: 1440 kcs.

Power: 1000 watts

Class: III

Notification List No. 125

Date: September 24, 1958

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM:

North Latitude: $49^{\circ} 41' 05''$

West Longitude: $124^{\circ} 58' 30''$



ANTENNA CHARACTERISTICS

Mode of Operation: DA/N

Number of elements: 2

Type of elements: guyed, uniform cross-section,
series fed, no top loading.

TOWERS:

North Tower

South Tower

HEIGHT OVER INSULATORS:

170' (90°)

170' (90°)

OVERALL HEIGHT:

179'

179'

SPACING:

170' (90°)

PHASING:

-85°

0

FIELD RATIO:


1.0

1.0

GROUND SYSTEM: 120 radials per tower 0.4 wavelength long.

PREDICTED EFFECTIVE FIELD: 187 mv/m at 1 mile for 1 kw.

ORIENTATION: Towers due North-South.



#125

Courtenay, B.C., Canada

CTCP

PROPOSED NIGHT
(11-17-58g)


New Station
Courtenay, British Columbia, Canada

1kw, DA-N, U

1440 KC

G9-31
POLAR CO-ORDINATE

STANDARD TIME INDICATING, LTD.



CK
Aug-22-78
P.204

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station Call : CKPM Main Studio : Ottawa, Ont.
 Frequency : 1440 kHz Power : 50 kW
 Time : Unlimited Class : III

Notification List No. : 282 Date : August 27, 1971.

Geographical Location : 45° 16' 59" N. Latitude
 of the Antenna System : 75° 44' 31" W. Longitude.

Antenna Characteristics -

Mode of Operation : DA-1


No. of Elements : 4 (Four)

Type of Elements : Uniform cross-section, guyed,
 base insulated, series fed,
 no top loading.

Tower No.	1(S)	2	3	4(N)
Height above Insulator	171' (90°)	171'	171'	171'
Overall Height	175'	175'	175'	175'
Spacing	Ref.	90°	180°	270°
Phasing	0°	-121°	+118°	-3°
Field Ratio	1	3.16	3.56	1.47
Orientation (E of True)	20°	20°	20°	20°
Ground System	120 radials per tower, No. 10 AWG bare, soft copper wire, buried approx. 8" in ground. Radials bonded along line between towers and bonded to 4" copper strap at tower base. Average length of radial : 274 ft. (= 0.4λ).			

Predicted Effective Field : 1350 mV/m at 1 mile for 50 kW, or
 190.9 mV/m at 1 mile for 1 kW radiated.

C/PM



July 19~~th~~, 1971

Paton, Colvin & Associates

KDNT


Measured Night
(7-27-65ct)

Station KDNT
Denton, Texas

500w, 5kw-LS, DA-N, U
1440 kc

N. Latitude 33° 09' 45"
W. Longitude 97° 06' 18"

-101.8-11-65
CHG. LOC.



FCC File No. BL-10961
Accepted 7-22-65

Station KDNT
Denton, Texas

1440 kc

JUL 18 1975


KDNT

Measured Non-DA
(7-27-65ct)

Station KDNT
Denton, Texas

500w, 5kw-LS, DA-N, U
1440 kc

10.8-11-65
CHG LOC.



FCC File No. BL-10961
Accepted 7-22-65

Station KDNT
Denton, Texas

1440 kc



*Granted Mexican
Daytime ND power
to S 1CW 11-19-51*

KDNT

PROPOSED KDNT, DENTON, TEXAS
NIGHT 1/21/52G

500W, 1 KW-LS, U, DA-N

1440 KC



Station	KDNT DENTON, TEXAS	
Frequency	1440 kc	Location
Power	0.5 kw	131 mV/m (135/kw)
No. of Elements	2	R-M-S Field
MEASURED ☐	CALCULATED ☒	192 ft. = 0.25 λ = 101°
Pattern	Height of Antenna	
HORIZONTAL PATTERN	520104.1 supersedes 510-17.1	
Remarks	GUY C. HUTCHESON CONSULTING RADIO ENGINEER ARLINGTON TEXAS	

AMD RECD 1/9/52 ACC 1/11/52 BP-8120 Amd.

KDNT, DENTON, TEXAS

1440 KC


JUL 1 1975

KEWI

Measured Day
(2-28-69ct)

Station KEWI
Topeka, Kansas

1kw, 5kw-LS, DA-2, U
1440 kc



FCC File No. BZ-7073
Accepted 1-29-69

Station KEWI
Topeka, Kansas

1440 kc


JUL 1975 6K

KEW 1

Measured Night
(2-28-69ct)

Station KEWI
Topeka, Kansas

1kw, 5kw-LS, DA-2, U
1440 kc



FCC File No. BZ-7073
Accepted 1-29-69

Station KEWI
Topeka, Kansas

1440 kc

JUL 18 1975 cK

KEWI



Measured Non-DA
(2-28-69ct)

Station KEWI
Topeka, Kansas

1kw, 5kw-LS, DA-2, U
1440 kc

EUGENE DIETZGEN CO.
MADE IN U. S. A.

NO. 341-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



Broadcast Maintenance Service

OFFICE:

2715 N. Topeka Ave.
Topeka, Kansas 66608
Phone 232-3712

RESIDENCE:

Route 5,
Topeka, Kansas 66608
Phone MU 8-1235

FCC File No. BZ-7073
Accepted 1-29-69

Station KEWI
Topeka, Kansas

1440 kc

KEWI

Proposed Day
(4-27-62ct)

Station KEWI
Topeka, Kansas

1kw, 5kw-LS, DA-2, U
1440 kc

10-24-62
granted CPO
make changes in
DA patterns.





FIGURE 1

HORIZONTAL RADIATION PATTERN



APPLICANT :	KJAY, INC.
LOCATION :	TOPEKA, KANSAS
FREQUENCY :	1440 KC/S
POWER :	5 KW DA
LATITUDE :	39 DEG 01 MIN. 17 SEC.
LONGITUDE :	95 DEG 34 MIN. 15 SEC.
WHEN USED :	DAYTIME
R.M.S. FIELD :	393.5 MV/M
DATE :	FEBRUARY 1962
SILLIMAN, MOFFET & KOWALSKI	
CONSULTING RADIO ENGINEERS	
WASHINGTON, D.C.	

FCC File No. BP-15216
Accepted 4-10-62

Station KEWI
Topeka, Kansas


1440 kc

KEWI

Proposed Day Nulls
(4-27-62ct)

Station KEWI
Topeka, Kansas

1kw, 5kw-LS, DA-2, U
1440 kc



EXPANDED VIEW

5 KW DAYTIME

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FCC File No. BP-15216
Accepted 4-10-62

Station KEWI
Topeka, Kansas

1440 kc


KEWI

Proposed Night
(4-27-62ct)


Station KEWI
Topeka, Kansas

1kw, 5kw-LS, DA-2, U
1440 kc

10-24-62
granted CP to change
DA pattern



HORIZONTAL RADIATION PATTERN



FCC File No. BP-15216
Accepted 4-10-62

Station KEWI
Topeka, Kansas


1440 kc

KEWI

Proposed Night Nulls
(4-27-62ct)

Station KEWI
Topeka, Kansas

1kw, 5kw-LS, DA-2, U
1440 kc



EXPANDED VIEW

1 KW NIGHTTIME


SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-15216
Accepted 4-10-62

Station KEWI
Topeka, Kansas

1440 kc


KEYS
1440 kc



1440 kc

KEYS

106




DL-13, 614

FIGURE 1-B

HORIZONTAL RADIATION PATTERN

KEYS

G #1,3,4 = 106.5°
G #2 = 146°



THEORETICAL PARAMETERS

JUL 15 1975

APPLICANT :	RADIO CORPUS CHRISTI, INC.
LOCATION :	CORPUS CHRISTI, TEXAS
FREQUENCY :	1440 KC/S
POWER :	1 KW
LATITUDE :	27 DEG 47 MIN. 02 SEC.
LONGITUDE :	97 DEG 27 MIN. 29 SEC.
WHEN USED :	NIGHTTIME
R.M.S. FIELD :	204.8
DATE :	SEPTEMBER 1973


SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

KMLB

Proposed Night
(11-30-61ct)

Station KMLB
Monroe, Louisiana

1kw, 5kw-LS, DA-N, U
1440 kc



FCC File No. BP-15175
Accepted 11-17-61

Station KMLB
Monroe, Louisiana

1440 kc


KMLB

Measured Night
(2-26-63ct)

Station KMLB
Monroe, Louisiana

1kw, 5kw-LS, DA-N, U
1440 kc

5-1-63
renewed
license code
change in antenna
transmitter location



$E_{RMS} = 177.3$

- MEASURED RADIALS
- ✕ CROSS RADIALS
- MEASURED PATTERN
- CALCULATED PATTERN

LATITUDE **N 32° 33' 10"**
LONGITUDE **W 92° 04' 24.5"**

ANTENNA PARAMETERS

W — 150° — E — N 85° E
1.15 / -30° 1.0 / 0°
G = 105.3°

FIGURE-15A
HORIZONTAL POLAR
PATTERN

KMLB MONROE
1440 kcs. 5.0KW LS
1.0KW DA N

AMBROSE W. KRAMER
CONSULTING RADIO ENGINEER

FCC File No. BL-9744
Accepted 2-18-63

Station KMLB
Monroe, Louisiana

1440 kc


KMLB

Measured Non-DA
(2-26-63ct)

Station KMLB
Monroe, Louisiana

1kw, 5kw-LS, DA-N, U
1440 kc

5-1-63
parted by
overing change
in antenna
position



FCC File No. BL-9744
Accepted 2-18-63

Station KMLB
Monroe, Louisiana

1440 kc


KODL

PROPOSED
NIGHT

KODL, THE DALLES, OREGON
(7/10/53G)

1kw, U, DA-N

1440 kc




KODL

MEASURED NIGHT (CORRECTED)
(8/16/55G)

STATION KODL
THE DALLES, OREGON

1 KW
DA-N, 11


1440 KC



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS										STATION DATA	
1	ELECTRICAL HEIGHT 92'	TRUE TOWER ORIENTATION 92°	SPACING 0'	HEIGHT 0'	HORIZONTAL FIELD 116.5°	FIELD STRENGTH 190	ELEV. ANGLE 0°	ELEV. ANGLE 0°	ELEV. ANGLE 0°	ELEV. ANGLE 0°	ELEV. ANGLE 0°	DALL KODL	
2	92'	92°	0'	0'	116.5°	190	0°	0°	0°	0°	0°	FREQUENCY 1440 KC	
3												POWER 1 KW	
4												TIME OF OPERATION UNLIMITED	
5												TYPE OF OPERATION	
6												DAYTIME TOWERS 2	
7												NIGHTTIME TOWERS 2	
8												NO RADIALS PER TOWER 120	
9												LENGTH OF RADIALS	
10												GROUND SCREEN DIMENSION	
11												LAT 45° 55' 51"	
12												LONG 121° 11' 57"	
13												SUPERSEDES	
14												PATTERN NO	

DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☐


CORRECTED MEASURED PATTERN
7/18/55



Theoretical ① 0.567/-166° ② 1.37/0° ③ 1.00/166° ① — ② — ③ → 145°T	RADIO STATION <u>KPUR</u> <u>AMARILLO, TEXAS</u> MEASURED DIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN 1440 KHZ 1000 WATTS	
G₁ - 362' - 191° G₂ = G₃ - 171' - 90° S - 114' - 60°	090672 FIGURE 2	MERL SAXON CONSULTING RADIO ENGINEER LUFKIN, TEXAS BL 13482

KQRS

GOLDEN VALLEY

MEASURED NIGHT
(5-28-59g)Station KEVE
~~Minneapolis~~, Minnesota500w, 5kw-LS, DA-N,U
1440 KCFCC File No. BL-7457
Accepted 5-12-59KEVE
Minneapolis, Minnesota


1440 KC

KQRS

MEASURED NON-DA
(5-28-59g)

GOLDEN VALLEY
Station KEVE
Minneapolis, Minnesota

500w, 5kw-LS, DA-N,U
1440 KC



$E_{RMS} = 472 \text{ MV/M}$

O = MEASURED RADIALS

LATITUDE: $44^{\circ} 59' 20''$
LONGITUDE: $93^{\circ} 21' 05.8''$

ANTENNA PARAMETERS

JOHN H. MULLANEY
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FIGURE 17

HORIZONTAL POLAR PATTERN
(NON-DIRECTIONAL)

KQRS
RADIO STATION KEVE
MINNEAPOLIS, MINNESOTA

1440 KC 0.5KW, 5KW-LS, DA-N,U

FCC File No. BL-7457
Accepted 5-12-59

KEVE
Minneapolis, Minnesota

1440 KC

*granted lic for DA-N
7-17-59*

SUPPLEMENTAL
DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KUHL

Main Studio: Santa Maria, California

Frequency: 1440 kHz

Power: 1kw Night 5kw Day

Notification List No. 1757

Date: November 16, 1977 Class III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: $34^{\circ} 59' 02''$

West Longitude: $120^{\circ} 27' 10''$

Authorized for Nighttime operation (DA-N)

Predicted effective Day Field: (omnidirectional) 427 mv/m at rated power.


Note: Please retain the corrected description sheet and directional antenna radiation patterns notified for station KDOY (now KUHL) in United States Change List Number 784, dated November 12, 1958 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating an increase in daytime power from 1 kw with no changes in the nighttime operation.

KUHL

PROPOSED NIGHT
(3-3-58g)

Station KCOY
Santa Maria, California

1kw, DA-N,U
1440 KC



FCC File No. BP-11,805
Accepted 2-12-58

KCOY
Santa Maria, California

1440 KC

granted for change of freq
increase power and install
DAN 5-3-60

KUHL

MEASURED NIGHT
(7-8-59g)

Station KCOY
Santa Maria, California


1kw, DA-N, U
1440 KC



1.0 $\angle 0^\circ$ $\nearrow$ 52°T
S = 80°, 152'
G = 90°, 172'

Lat. 34° 59' 02"
Long. 120° 27' 10"

.85 $\angle -140^\circ$ ○




granted K for change in freq
increase of power + install DA-N
5-3-60

KUHL

MEASURED NON -DA
(7-8-59g)

Station KCOY
Santa Maria, California

1kw, DA-N, U
1440 KC



FCC File No. BL-7886
Accepted 6-16-59

KCOY
Santa Maria, California

1440 KC

granted & for change in reg.
increase power and install DA-N
5-3-60

Measured Day
(2-28-70ct)

Station KVON
Napa, California

1kw, 5kw-LS, DA-2, U
1440 kc




FIG. 2

MEASURED DAYTIME HORIZONTAL RADIATION
KVON 1440 KC 5.0 KW-D, 1.0 KW-N, DA-2
NAPA, CALIFORNIA

A.E.Towne Associates Inc., Radio Engineering Consultants, San Carlos, Calif.

BL 12493
GR. (2-13-70) Lic. Covering CP for Changes

KVON

Measured Night
(2-28-70oct)

Station KVON
Napa, California

1kw, 5kw-LS, DA-2, U
1440 kc




FIG. 3

MEASURED NIGHTTIME HORIZONTAL RADIATION
KVON 1440 KC 5.0 KW-D, 1.0 KW-N DA-2
NAPA, CALIFORNIA

A.E.Towne Associates Inc., Radio Engineering Consultants, San Carlos, Calif.

FCC File No. BL-12493
Accepted 2-5-70

Station KVON
Napa, California

1440 kc


DL 12475
GR(2-13-70) LIC, covering CP for changes

KVON

Measured Non-DA
(2-28-70ct)

Station KVON
Napa, California

1kw, 5kw-LS, DA-2, U
1440 kc



FCC File No. BL-12493
Accepted 2-5-70

Station KVON
Napa, California

1440 kc

KVON

Proposed Day
(2-28-67ct)

Station KVON
Napa, California

500w, 5kw-LS, DA-2, U
1440 kc

7-11-67
2-DAY
C.P.
JAG:SES
W4 SYST.

EUGENE ORTIZ (EN)
KAP: N.D. 5.5

40 50 P. ORTIZ (EN)
KAP: N.D. 5.5




Fig. 1

PROPOSED HORIZONTAL RADIATION
KVON 1440 KC .5 KW-N 5.0 KW-D DA-2
NAPA, CALIFORNIA

A.E.Towne Associates Inc., Consulting Engineers, San Carlos, Calif.

FCC File No. BP-17295
Accepted 1-31-67

Station KVON
Napa, California

1440 kc

KVON

Proposed Night
(4-29-68ct)

Station KVON
Napa, California

1kw, 5kw-LS, DA-2, U
1440 kc

2/23/68
RADIATED CP
FOR MAKE CHANGES
IN NIGHT DA-
PATTERN




Fig. 1

PROPOSED NIGHTTIME HORIZONTAL RADIATION
KVON 1440 KC 5.0 KW LS 1.0 KW N DA-2
NAPA, CALIFORNIA

A.E.Towne Associates Inc., Radio Engineering Consultants, San Carlos, Calif.

FCC File No. BMP-12359
Accepted 4-5-68

Station KVON
Napa, California

1440 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: (NEW)

Main Studio: Martin, Kentucky

Frequency: 1440 kHz

Power: 2.5kw Day

Notification List No. 1782

Date: October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 37° 35' 33"
West Longitude: 82° 43' 43"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation (DA-D)

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	#1 (NW)	#2 (SE)
HEIGHT ABOVE INSULATORS:	171'	171' (90°)
DAY PHASING:	0°	3°
DAY FIELD RATIO:	1	0.55

SPACING AND
ORIENTATION:

Adjacent towers in a row are spaced 341.6' (180°) on a line
bearing 104° true.


GROUND SYSTEM: 120 - 171' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap along
intersections between towers. Centers of system are bonded
together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	282.79 mv/m	327.981 mv/m	297.06 mv/m

Standard Pattern

Standard Pattern



$RMS_{theo} = 282.790 \text{ mV/m}$

$RMS_{std} = 297.096 \text{ mV/m}$

$RSS_{theo} = 327.981 \text{ mV/m}$

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 4	STATION DATA
G's = 90° #1 — 180° — #2 — 104° T.	TOWER No.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING V'	FIELD RATIO F'	PROPOSED DAYTIME STANDARD PATTERN MAY - 1977 MARTIN, KENTUCKY $\theta^\circ = 0$	CALL NEW FREQ 1440 KHz POWER 2.5 kW TYPE DA-D TIME DAYTIME LAT. N 37°35'33" LONG. W 82°43'43" E. HAROLD MUNN, JR. & ASSOCIATES, INC. COLDWATER, MICH.
	1			0°	1.00		
	2			3°	0.55		
	3						
	4						
	5						
	6						
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐							


OVER WAAB

PROPOSED DAY
(2/4/55G)

STATION WAAB
WORCESTER, MASSACHUSETTS

5 KW
DA-2, U

1440 KC



WAAB


Measured Day
(4-24-64ct)

Station WAAB
Worcester, Massachusetts

5kw, DA-2, U
1440 kc

*4/24/64
JG
antenna
etc*

K-E POLAR CO-ORDINATE 358-31
KUPPEL & EBBEN CO. MADE IN U.S.A.



North Latitude 42° 17' 25"
West Longitude 71° 50' 47"
Engineer: George J. Capalbo

MEASURED
HORIZONTAL RADIATION
PATTERN
WAAB 1440 kc
5kw DA-2
4/24/64

FCC File No. BL-10460
Accepted 3-26-64

Station WAAB
Worcester, Massachusetts

1440 kc

JUL 15 1975

30° 20°
330° 340°

10° 7/19/46
350° 0

350° 10°

340° P-3174
20° 330°

WAAB

True Bearings
WBOM 282.5 Deg.
WHIS 238.0 "
WRCK 275.0 "
WSFA 235.0 "

North

MV/M
700

LINE OF TOWERS

WBOM 605 MI.

WRCK 975 MI.

MV/M 75

WHIS 595 MI.
WSFA 1010 MI.

Pattern At Nela

Calculated Unabsorbed Field Intensity at One Mile in the Horizontal Plane
Proposed Station at Worcester, Mass.
Frequency 1440 KCS. — Power 3,000 Watts
Day and Night Operation

The Yankee Network Inc.

South

150 210 160 200 170 190 180 180° 190° 170° 200° 210 150


REVISED EXHIBIT D

WAAB

Measured Night
(4-24-64ct)

Station WAAB
Worcester, Massachusetts

5kw, DA-2, U
1440 kc



FCC File No. BL-10460
Accepted 3-26-64

Station WAAB
Worcester, Massachusetts

1440 kc

JUL 18 1975

WAA B


Measured Non-DA
(4-24-64ct)

Station WAA B
Worcester, Massachusetts

5kw, DA-2, U
1440 kc

*6/30/64
17.6
non-symmetry
with*

1000 POLAR CO ORDINATE 35-131
1000 1000 1000 1000



FCC File No. BL-10460
Accepted 3-26-64

Station WAA B
Worcester, Massachusetts


1440 kc

WAJR

PROPOSED
DAY(11-9-56g)

WAJR
Morgantown, West Virginia

1440 KC
re 88



FCC File No.
BMP-7421

Accepted 11-2-56

WAJR
Morgantown, West Virginia 1440 KC


WAJR

MEASURED DAY
(9/25/57g)

Station WAJR
Morgantown, West Virginia

500w, 5kw-LS, DA-2, U
1440 KC

*Granted license
12/15/58 for
change in facility
& install of DA-2
operation*




MEASURED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

G=105 (2) 170° 130° (4) 0.8/-60° 183° TRUE	THE WEST VIRGINIA RADIO CORPORATION MORGANTOWN, WEST VIRGINIA	RADIO STATION WAJR 1440 KC
	VANDIVERE, COHEN and WEARN CONSULTING ELECTRONIC ENGINEERS	0.5 KW, 5 KW-LS DA-2 JULY 1957


FCC File No. BL-6750
Accepted 9/11/57

WAJR
Morgantown, West Virginia

1440 KC



PROPOSED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN



THE WEST VIRGINIA RADIO CORPORATION

MORGANTOWN, WEST VIRGINIA

VANDIVERE, COHEN and WEARN
CONSULTING ELECTRONIC ENGINEERS

PROPOSED OPERATION

WJ R

1440 KC

5 KW-LS, 0.5 KW-N, DA-2

OCTOBER 1956

-FCC File No.
BMP-7421

Accepted 11-2-56

W A J R

Morgantown, West Virginia

1440 KC


WAJR

MEASURED NIGHT
(9/25/57g)

Station WAJR
Morgantown, West Virginia

500w, 5kw-LS, DA-2, U
1440 KC

*Granted license
12/15/58 for
change in facilities
& for DA-2 operation*



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

(1) 1.0/0° G=105° (2) 1.31/202.9° (3) 1.0/45.9° 134° TRUE	THE WEST VIRGINIA RADIO CORPORATION MORGANTOWN, WEST VIRGINIA	RADIO STATION WAJR 1440 KC
	VANDIVERE, COHEN and WEARN CONSULTING ELECTRONIC ENGINEERS	0.5 KW, 5 KW-LS DA-2 JULY 1957

FCC File No. BL-6750
Accepted 9/11/57

WAJR
Morgantown, West Virginia

1440 KC

JUL 18 1975


WAJR

MEASURED NON-DA
(9/25/57g)

Station WAJR
Morgantown, West Virginia

500w, 5kw-LS, DA-2, U
1440 KC

*Granted license
12/15/58 for
change in facilities
& install of PA-2
system*



MEASURED NONDIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN

G=10%	THE WEST VIRGINIA RADIO CORPORATION MORGANTOWN, WEST VIRGINIA VANDIVERE, GOREN and WEARN CONSULTING ELECTRONIC ENGINEERS	RADIO STATION WAJR 1440 KC 0.5 KW, 5 KW-LS DA-2 JULY 1957
--------------	--	---

FCC File No. BL-6740
Accepted 9/11/57



WAJR
Morgantown, West Virginia

1440 KC

Measured Day
(11-29-62ct)

Station W1OK
Normal, Illinois

1kw, DA-D, D
1440 kc



W1OK RADIATION PATTERN
1440 KC 1.0 KW
NORMAL, ILLINOIS
AUG. 1962

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

FCC File No. BL-9611
Accepted 11-18-62



Station W1OK
Normal, Illinois

1440 kc

Proposed Night
(6-29-64ct)

Station WIOK
Normal, Illinois

500w, 1kw-LS, DA-N, U
1440 kc



HORIZONTAL
PLANE RADIATION PATTERN
1440 KC 0.5 KW NIGHT
MCLEAN COUNTY B/C
NORMAL, ILLINOIS
APRIL, 1964

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

FCC File No. BMP-10066
Accepted 5-26-64

Station WIOK
Normal, Illinois



1440 kc

WAKC —

Measured Night
(12-29-65ct)

Station W10K
Normal, Illinois

500w, 1kw-LS, DA-2, U
1440 kc



W10K
MEASURED RAD. PATTERN
0.5 KW(NIGHT) 1440 KC
NORMAL, ILLINOIS
OCT. 1965

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

FCC File No. BL-11128
Accepted 11-26-65

Station W10K
Normal, Illinois


1440 kc

—WAKC

Measured Non-DA
(12-29-65ct)

Station W1OK
Normal, Illinois

500w, 1kw-LS, DA-2, U
1440 kc



FCC File No. BL-11128
Accepted 11-26-65

Station W1OK
Normal, Illinois

1440 kc

WAYK

PROPOSED DAY
(4-10-61g)

New; Southern Radio & TV Co.
Lehigh Acres, Florida

1kw, 5kw-LS, DA-2, U
1440 KC


GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 2, D. C.

OVER
12-12-66
GRANTED APPL.
FOR CP AM
A NEW STATION

BP 18383
AN APPLICATION
FOR CP WAS
ACCEPTED 11-27-66
BY THE F.C.C.
TO REPLACE
EXPIRED CON-
STRUCTION
PERMIT BP 14297
AS MODIFIED
WHICH
AUTHORIZED

A NEW AM
BROADCAST
STATION

NO. 341-B DIETZEN GRAPH P. 1
POLAR CO-ORDINATE



FCC File No. BP-14297
Accepted 3-17-61 (Amended)

Southern Radio & Television Company
Lehigh Acres, Florida
1440 KC

WAYK

PROPOSED NIGHT
(4-10-61g)

New; Southern Radio & TV Co.
Lehigh Acres, Florida


1kw, 5kw-LS, DA-2, U
1440 KC

12-12-66

GRANTED APPL. FOR CP
FOR A NEW AM STATION.

BP 18383 AN APPLICATION
FOR CP WAS ACCEPTED
11-27-68 BY THE
F.C.C. TO REPLACE
~~MODIFIED EXPIRED~~
~~CONSTRUCTION~~
PERMIT (BP-14297
AS MODIFIED)
WHICH
AUTHORIZED
A NEW AM
BROADCAST
STATION

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.




COMPUTED HORIZONTAL
PLANE RADIATION PATTERN
FOR PROPOSED NIGHTTIME OPERATION
AT LEHIGH ACRES, FLORIDA
1 KW NIGHT, 5 KW DAY - 1440 KC
JANUARY 1961

NORTH LATITUDE: 26° 36' 44"
WEST LONGITUDE: 81° 33' 52.5"

FCC File No. BP-14297
Accepted 3-17-61 (Amended)

Southern Radio & Television Company
Lehigh Acres, Florida 1440 KC

WBCM - 1440 kHz




$S_{theo} = 471.292 \text{ mV/m}$

$S_{std} = 495.109 \text{ mV/m}$

$S_{theo} = 606.825 \text{ mV/m}$

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 4	STATION DATA	
All G's = 115° 17.5° #3 3.076/-268.899° 90° #2 3.074/221.252° 90° #1 1.000/0°	TOWER	ELECTRICAL	SPACING	PHASING	FIELD	PROPOSED DAYTIME STANDARD PATTERN BAY CITY, MICHIGAN	CALL	WBCM
	No.	HEIGHT			RATIO		FREQ	1440 kHz.
		G's	S'	V'	F		POWER	5.0 kw
	1						TIME	DA-2
	2						LAT.	N 43-31-27
	3						LONG.	W 83-57-58
	4						E. HAROLD MUNN, JR. & ASSOCIATES, INC. COLUMBIA, MICH.	
5								
6								
DAYTIME OPERATION		NIGHTTIME OPERATION		θ° = 0				

WBCM - 1440 kHz



$E = 280.000 \text{ mV/m}$

$E = 294.241 \text{ mV/m}$

$E = 457.398 \text{ mV/m}$

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 17	STATION DATA
15° 17.5° T. #3 0.49/56.5° 90° #2 1.06/208.25° 90° #1 1.0/0°	TOWER No.	ELECTRICAL HEIGHT G	SPACING S	PHASING P	FIELD RATIO F	PROPOSED NIGHTTIME STANDARD PATTERN BAY CITY, MICHIGAN $\theta = 0^\circ$	CALL WBCM FREQ 1440 kHz. POWER 2.5 kW TYPE DA-2 TIME Unlimited LAT. N 43-31-27 LONG. W 83-57-58 E. HAROLD MUNN, JR. & ASSOCIATES, INC. COLDWATER, MICH.
	1						
	2						
	3						
	4						
	5						
	6						
DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☒							

$$= 457.398 \text{ mV/m}$$

ANTENNA PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 17A	STATION DATA
15° 17.5° T. #3 ϕ 0.49/56.5° 90° #2 ϕ 1.06/208.25° 90° #1 ϕ 1.0/0°	TOWER No.	ELECTRICAL HEIGHT G ²	SPACING S ²	PHASING P ²	FIELD RATIO F	PROPOSED NIGHTTIME STANDARD PATTERN BAY CITY, MICHIGAN	CALL <u>WBCY</u> FREQ <u>1440 kHz.</u> POWER <u>2.5 kw</u> TYPE <u>DA-2</u> TIME <u>Unlimited</u> LAT. <u>N 43-31-27</u> LONG. <u>W 83-57-58</u> E. HAROLD MUNN, JR. & ASSOCIATES, INC. COLDWATER, MICH.
	1						
	2						
	3						
	4						
	5						
	6						
	DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☒					$\theta^\circ = 0^\circ$	


WBUY

PROPOSED NIGHT
(8-22-61ct)

Station WBUY
Lexington, North Carolina

1kw, 5kw-LS, DA-N, U
1440 KC

*1/6/63
printed CP for
DA-N & unlimited*




E_{RMS} 196 MV/M

---MEOV

LATITUDE 35° 49' 55"
LONGITUDE 80° 17' 12.5"

ANTENNA PARAMETERS



S = 90° ± 171°
G = 95° ± 180°

FIGURE 4
PLOT OF NIGHTTIME HORIZONTAL
POLAR PATTERN

RADIO STATION
LEXINGTON, N.C.

1440 KC 10/50 KW-LS, DA-N, U

FCC File No. BP-14938
Accepted 7-26-61

Station WBUY
Lexington, North Carolina


1440 KC

WBUY

Measured Night
(3-30-64ct)

Station WBUY
Lexington, North Carolina

1kw, 5kw-LS, DA-N, U
1440kc



◻ RADIAL VALUES
MEASURED RMS
(98 MV/M)



ANTENNA PARAMETERS	
1	50.8 155°
	N. 35° 49' 55"
	W. 80° 17' 12.5"
2	84.2 0°
3	63.5 -152.5°
	N-118.5°E
S=90°	=171°
G=95°	=180°

FIG. 3
MEASURED NIGHTTIME HORIZONTAL RADIATION PATTERN
RADIO STATION WBUY
LEXINGTON, N.C.
1440 KCS. 1.0 KW, 5 KW, LS, DA-N

FCC File No. BL-10424
Accepted 3-11-64

Station WBUY
Lexington, North Carolina

1440kc

JUL 19 1975

Measured Non-DA
(3-30-64ct)

Station WBUY
Lexington, North Carolina

1kw, 5kw-LS, DA-N, U
1440kc

WBUY




FIG. 1
MEASURED NON-DIRECTIONAL PATTERN, #2, CENTRAL TOWER
RADIO STATION WBUY
LEXINGTON, N.C.
1440 KCS. 1.0 KW, 5 KW, LS. DA-N

FCC File No. BL-10424
Accepted 3-11-64

Station WBUY
Lexington, North Carolina

1440kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: W C D S

Main Studio: Glasgow, Kentucky

Frequency: 1440 kHz

Power: 5 kW Day

Notification List No.: 1776

Date: June 28, 1978 Class: III

GEORGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude:	<u>36 °</u>	<u>58 '</u>	<u>10 "</u>
West Longitude:	<u>85 °</u>	<u>56 '</u>	<u>24 "</u>

ANTENNA CHARACTERISTIC

Authorized for Daytime operation. (DA-D)

Number of elements: 3Type of elements : Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER	SW (#1)	E (#2)	NE (#3)
HEIGHT ABOVE INSULATORS :	359.9'	359.9'	359.9' (189.7°)
PHASING:	0	+101.8	+6.0
FIELD RATIO:	1.00	0.60	0.68

SPACING AND
ORIENTATION:

With the SW(#1) tower as reference the E(#2) tower is spaced 219.9' (115.9°) on a line bearing 82° true, and the NW(#3) tower is spaced 345.9' (182.3°) on a line bearing 46.3° true.

GROUND
SYSTEM:

120-170' equally spaced copper radials a 24' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL RMS	<u>RSS</u>	STANDARD <u>RMS</u>
Day	533.90 mV/m	626.66 mV/m	560.84 mV/m

Note: This notification concerns a daytime in power increase with a direction antenna system.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station WCHB Main Studio: Inkster, Michigan
 Frequency: 1440 kHz Power: 1kw Night 1kw Day
 Notification List No. 1775 Date: May 31, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 15' 22"
 West Longitude: 83° 21' 48"

DAYTIME ANTENNA CHARACTERISTICS

Authorized for daytime operation. (DA-D)

Number of elements: 6

Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers. Top loaded
 by top 28.5' section of guy wires to an
 effective electrical height of 90°.

TOWER:	SW(#5)	CW(#3)	NW(#1)	SE(#6)	CE(#4)	NE(2)
HEIGHT ABOVE INSULATORS:	143'	143'	143'	143'	143'	143' (75.4°)
DAY PHASING:	+130°	+130°	+130°	0°	0°	0°
DAY FIELD RATIO:	1.0	2.0	1.0	1.0	2.0	1.0

SPACING AND
ORIENTATION:

The towers are located at the vertices of a rectangle long
 sides of which are 493' (260°) in length on a line bearing
 316° true. The short sides are 171' (90°) in length on a line
 bearing 46° true.

GROUND SYSTEM: 120 - 180' equally spaced copper radials plus a 40' square
 ground screen about each tower. Radials are shortened and
 bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL	
	RMS	RSS
Day	178 mV/m	

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 6
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	W(#1)	NW(#3)	N(#5)	E(#6)	SE(#4)	S(#2)
HEIGHT ABOVE INSULATORS:	143'	143'	143'	143'	143'	143' (75.4°)
NIGHT PHASING:	0	+212.5	-295	-297	+210.5	-2.0
NIGHT FIELD RATIO:	1.000	2.220	1.234	1.371	2.466	1.111

SPACING AND
ORIENTATION:

The towers are located in two parallel rows with 3 towers per row. Adjacent towers in a row are spaced 170.8' (90°) on a line bearing 46° true. End towers forming a side of the parallelogram are spaced 493.5' (260°) on a line bearing 136° true.


GROUND SYSTEM: 120 - 230' equally spaced copper radials plus a 40' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL	STANDARD
	<u>RMS</u>	<u>RMS</u>
Night	175.000 mv/m	183.896 mv/m

Note: Please retain the Daytime directional antenna radiation pattern notified for Station WCHB in United States Change List Number 1066 dated June 24, 1964 and attach to this Revised Description Sheet and Nighttime patterns. This notification concerns only a change in Nighttime operation of the station with Daytime operation continued as previously notified.

WCHB



$RMS_{theo} = 175.000 \text{ mV/m}$

$RMS_{std} = 183.896 \text{ mV/m}$

$RSS_{theo} = 281.918 \text{ mV/m}$

10X EXPANSION

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 3	STATION DATA
S = 90° S = 260°	TOWER No.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING V'	FIELD RATIO F'	PROPOSED NIGHTTIME STANDARD PATTERN INKSTER, MICHIGAN $\theta^\circ = 0^\circ$	CALL WCHB
	1	75.4		0°	1.000		FREQ 1440 kHz
	2	75.4		-2.0	1.111		POWER 1.0 kW
	3	75.4		212.5	2.220		TYPE DA-2
	4	75.4		210.5	2.466		TIME Unlimite
	5	75.4		-295	1.234		LAT. N 42-15-
	6	75.4		-297	1.371		LONG. W 83-21-
DAYTIME OPERATION ☐					NIGHTTIME OPERATION ☒	E. HAROLD MUNN, & ASSOCIATES, INC COLDWATER, MICH.	


WCHB

Measured Day
(5-27-65ct)

Station WCHB
Inkster, Michigan

500w, 1kw-LS, DA-2, U
1440 kc

LIC. 5-27-65
DA-2, U



RMS MEOW 177.5 MV/M

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 7	STATION DATA
	TOWER No	ELECTRICAL HEIGHT Ft	SPACING Ft	PHASING K°	FIELD RATIO F	MEASURED DAYTIME DIRECTIONAL PATTERN FEBRUARY - 1965	CALL WCHB FREQ 1440 Kc/S POWER 1 Kw TYPE DA-2 TIME DAY LAT. 42°15'22" LONG. 83°21'47.5"
	1	75.4	-	0°	1.0		
	2	75.4	-	+60°	1.375		
	3	75.4	-	+158°	1.625		
	4	75.4	-	+39.8°	2.25		
	5	75.4	-	+148°	1.069		
	6	75.4	-	+167°	0.957		
	7						
	8	ALL	±	TOP	LOAD		
	9						
	10						
	DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐					0° 0°	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.

FCC File No. BL-10883
Accepted 4-29-65

Station WCHB
Inkster, Michigan

1440 kc

JUL 18 1975


WCHB

Measured Night
(5-27-65ct)

Station WCHB
Inkster, Michigan

500w, 1kw-LS, DA-2, U
1440 kc


LIC. 5-27-65
DA-2, U



RMS
MEOV

125.1 mv/m

TOWER PLACEMENT SKETCH



PATTERN PARAMETERS

TOWER No.	ELECTRICAL HEIGHT ft	SPACING ft	PHASING °	FIELD RATIO
1	75.4	-	0°	1.0
2	75.4	-	-152°	1.057
3	75.4	-	+3°	0.922
4	75.4	-	-175°	1.109
5				
6				
7	NO	TOP	LOAD	
8				
9				
10				

FIGURE 8

MEASURED NIGHTTIME
RADIATION PATTERN

FEBRUARY - 1965

STATION DATA

CALL WCHB
FREQ 1440 Kc/S.
POWER 0.5 Kw, 1 LS
TYPE DA-2
TIME NIGHT
LAT. 42°15'22"
LONG. 83°21'47.5"

E.H. MUNN, JR.
RADIO ENGINEER
COLDWATER, MICH.

FCC File No. BL-10883
Accepted 4-29-65

Station WCHB
Inkster, Michigan

1440 kc

JUL 1 1975


WCHB

Measured Non-DA
(5-27-65ct)

Station WCHB
Inkster, Michigan

500w, 1kw-LS, DA-2, U
1440 kc

LIC. 5-27-65
DA-2, U.



RMS
MEOV 132.5 MV/M

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS	FIGURE 6	STATION DATA																																																												
337° T. #2 #1 S1 S2 67° T. #4 S1=90° #3 S1 S2 S2=215° #5 S2 S1 #6	<table><thead><tr><th>TOWER</th><th>ELECTRICAL HEIGHT</th><th>SPACING</th><th>PHASING</th><th>FIELD RATIO</th></tr><tr><th>NO.</th><th>H'</th><th>S'</th><th>φ'</th><th>F</th></tr></thead><tbody><tr><td>1</td><td></td><td></td><td></td><td></td></tr><tr><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>3</td><td></td><td></td><td></td><td></td></tr><tr><td>4</td><td></td><td></td><td></td><td></td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></tbody></table> DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	NO.	H'	S'	φ'	F	1					2					3					4					5					6					7					8					9					10					MEASURED DAYTIME NON-DIRECTIONAL RADIATION - 1965 TOWER NO. 6 75.4° + TOP LOAD 6° 0"	CALL WCHB FREQ 1440 Kc/S POWER 0.5 Kw TYPE TIME LAT. LONG. E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO																																																											
NO.	H'	S'	φ'	F																																																											
1																																																															
2																																																															
3																																																															
4																																																															
5																																																															
6																																																															
7																																																															
8																																																															
9																																																															
10																																																															

FCC File No. BL-10883
Accepted 4-29-65

Station WCHB
Inkster, Michigan


1440 kc

WCHB

Measured Night
(9-26-69ct)

Station WCHB
Inkster, Michigan

500w, 1kw-LS, DA-2, U
1440 kc



RMS
MEOV 123.9 Mv/M

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 6	STATION DATA
G's 75.4	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	MEASURED NIGHTTIME RADIATION PATTERN RADIO STATION WCHB READJUSTMENT 1968	CALL WCHB FREQ 1440 kHz POWER 0.5 Kw, 1 Kw LS TYPE DA-2 TIME NIGHT LAT. 42°15'22" LONG. 83°21'47.5"
	No.	ft.	ft.	deg.			
	1			0	1.0		
	2			154°	954		
	3			45°	972		
	4			173°	1.1		
	5						
	6						
	7						
	8						
	9						
	10						
DAYTIME OPERATION ☐					NIGHTTIME OPERATION ☒	6° 0°	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.

FCC File No. BZ-7281
Accepted 9-18-69

Station WCHB
Inkster, Michigan


1440 kc


WCHB

Measured Day
(9-26-69ct)

Station WCHB
Inkster, Michigan

500w, 1kw-LS, DA-2, U
1440 kc



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 5	STATION DATA
G's 75.4" S ₁ 90° S ₂ 215° 337° T. 	TOWER No.	ELECTRICAL HEIGHT — G' —	SPACING — F' —	PHASING — ° —	FIELD RATIO — F —	MEASURED DAYTIME DIRECTIONAL PATTERN WCHB, INKSTER, MICH 1968 READJUSTMENT	CALL WCHB FREQ 1440 kHz POWER .5Kw, 1 Kw LS TYPE DA-2 TIME DAYTIME LAT. 42°15'22" LONG. 83°21'47.5"
	1			0	1.0		
	2			+57	1.535		
	3			+149	1.684		
	4			+34	2.258		
	5			+145	0.974		
	6			+165	0.948		
	7						
	8						
	9						
	10						
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐						θ°	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.



FCC File No. BZ-7281
Accepted 9-18-69

Station WCHB
Inkster, Michigan

1440 kc

1440 kc

WGEN
1kw. 5kw-LS, DA-2, U
1440 kc



Prepared by
Lohnes and Culver Washington 4, D.C.
July 1961
1440 kc

Station WGEM
Quincy, Illinois


WGEM

Measured Day
(5-28-63ct)


Station WGEM
Quincy, Illinois

1kw, 5kw-LS, DA-2, U
1440 kc

*8-1-63 granted
license covering
an increase in day
power and change
in night DA pattern*



North Latitude 39° 58' 47"
West Longitude 91° 19' 27"



FCC File No. BL-9964
Accepted 5-1-63

Station WGEM
Quincy, Illinois

JUL 13 1975 OK

FIGURE 8

HORIZONTAL RADIATION PATTERN
DAYTIME OPERATION

QUINCY BROADCASTING COMPANY

WGEM 1 KW, 5 KW-LS, DA-2 1440 KC
QUINCY, ILLINOIS

Prepared by

Lohnes and Culver

Washington 6, D.C.

December 1962 1440 kc


WGEM

Measured Night
(5-28-63ct)

Station WGEM
Quincy, Illinois

1kw, 5kw-LS, DA-2, U
1440 kc

*8-1-63
granted license
covering an increase
in daytime power
and change in nighttime
DA pattern.*



North Latitude 39° 58' 47"
North Longitude 91° 19' 27"

FIGURE 9
HORIZONTAL RADIATION PATTERN
NIGHTTIME OPERATION
QUINCY BROADCASTING COMPANY
WGEM 1 KW, 5 KW-LS, DA-2 1440 KC
QUINCY, ILLINOIS

Prepared by
Lohnes and Culver Washington 4, D.C.
December 1962 1440 kc

FCC File No. BL-9964
Accepted 5-1-63

Station WGEM
Quincy, Illinois


JR 10 1975 6 11

WGEM

Measured Non-DA
(5-28-63ct)

Station WGEM
Quincy, Illinois

1kw, 5kw-LS, DA-2, U
1440 kc



North Latitude 39° 58' 47"
West Longitude 91° 19' 27"

FCC File No. BL-9964
Accepted 5-1-63

Station WGEM
Quincy, Illinois

FIGURE 7
HORIZONTAL RADIATION PATTERN
NON-DA TEST OPERATION
QUINCY BROADCASTING COMPANY
WGEM 1 KW, 5 KW-LS, DA-2 1440 KC
QUINCY, ILLINOIS

Prepared by
Lohnes and Culver Washington 4, D.C.
December 1962 1440 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

1 6 0 1 5

1/48

Station: W G E M Main Studio: Quincy, Illinois

Frequency: 1440 kc Power: 1kw

Notification List No. 225 Date: May 2, 1947 Class: III-B

Location: North Latitude: 39° 59' 20"
 West Longitude: 91° 19' 15"

Antenna: Authorized for Day and Night operation (DA-2)
 Two elements Day, Four elements Night, Series-fed,
 uniform cross-section, guyed vertical steel towers.

Towers:	North East	South East	South West	North West
Height above Insulators	192'	192'	192'	192' (101.5°)

Spacing: See "Orientation" below.

Night Phasing:	4289°	+109°	0°	+180°
Night Field Ratio:	1.0 Not	1.0	1.0	1.0 Not
Day Phasing:	Used Not	460°	0°	Used Not
Day Field Ratio:	Used	1.0	1.0	Used

Ground System: 120 - 170' equally spaced radials plus 120 - 50' interspaced radials about each tower base. Radials shortened and bonded by transverse bonding straps along intersections between towers. Centers of systems bonded together.

Orientation: The towers are mounted on the four vertices of a parallelogram, the long sides of which are 703' (370°) long and are on a line bearing 346° true. The short sides are 171' (90°) and are on a line bearing 67° true.

Predicted effective Night Field: 180 mv/m (at rated power)

Predicted effective Day Field: 187 mv/m (at rated power)

WGEM



Proposed Night
(2-26-63ct)

Station WGEM
Quincy, Illinois

1kw, 5kw-LS, DA-2, U
1440 kc

North Latitude 39° 58' 47"
West Longitude 91° 19' 27"

2-13-63
granted MCP
for changes in night DA.




SPACING
1-2 370°
2-3 90°

FIGURE 9
HORIZONTAL RADIATION PATTERN
NIGHTTIME OPERATION
QUINCY BROADCASTING COMPANY
WGEM 1 KW, 5 KW-LS, DA-2 1440 KC
QUINCY, ILLINOIS
Prepared by
Lohrey and Culver
Washington, D.C.
December 1962

FCC File No. BMP-10780
Accepted 2-14-63

Station WGEM
Quincy, Illinois

BRUNSWICK, GA.
PATTERN NO. 470919
012
051 1440




1 KW-DA-N-U

WGIG

Measured Night
(7-26-67ct)

Station WGIG
Brunswick, Georgia

1kw, 5kw-LS, DA-N, U
1440 kc




North Latitude $31^{\circ} 10' 07''$
West Longitude $81^{\circ} 32' 14''$

MEASURED DIRECTIONAL PATTERN
WGIG - BRUNSWICK, GEORGIA
1440 KC - 5.0 KW-LS/1.0 KW - DA-N
APRIL, 1967



GAUTREY & JONES
CONSULTING RADIO ENGINEERS

FCC File No. BZ-6465
Accepted 6-30-67




WGIG

Measured Non-DA
(7-26-67ct)

Station WGIG
Brunswick, Georgia

1kw, 5kw-LS, DA-N, U
1440 kc



MEASURED NON-DIRECTIONAL PATTERN
WGIG - BRUNSWICK, GEORGIA
1440 KC - 5.0 KW-LS/1.0 KW - DA-N
APRIL, 1967



Gauthrey & Jones
CONSULTING RADIO ENGINEERS

FCC File No. BZ-6465
Accepted 6-30-67

Station WGIG
Brunswick, Georgia

1440 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WHDM Main Studio: McKenzie, Tennessee
 Frequency: 1440 kHz Power 5kw Day
 Notification List No. 1790 Date: December 4, 1980 Class: III
 GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM North Latitude: 36° 07' 45"
 West Longitude: 88° 29' 50"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)
 Number of elements: 3
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	NW(#1)	NE(#2)	S(#3)
HEIGHT ABOVE INSULATORS:	132.81'	132.81'	132.81' (70°)
DAY PHASING:	0°	-139.87°	+42.53°
DAY FIELD RATIO:	1	1.561	0.818


SPACING AND
 ORIENTATION: With the NW(#1) tower as the reference, the NE(#2)
 tower is spaced 181.536' (95.68°) on a bearing 117.91°
 true, and the South #3 tower is spaced 264.411' (139.37°)
 on a bearing of 138.58° true.

GROUND SYSTEM: 120 - 170' equally spaced copper radials about each tower.
 Radials are shortened and bonded to transverse straps
 along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	415.352 mv/m	767.349 mv/m	436.12 mv/m

WHDN
1440 kHz



RSS= 767.349
RMS= 415.352
RSS/RMS RATIO=1.847
STANDARD RADIATION RMS=436.12

N. LAT. 36° 07' 45"
W. LONG. 88° 29' 49.5"

PETER V. GURECKIS & ASSOC.
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.




FIGURE 4
PROPOSED DIRECTIONAL
DAYTIME PATTERN


RADIO STATION WHDM
MCKENZIE, TENNESSEE

1440 KHz 5 KW, DA-2

Prop. Day

W/HHH

1440




WHHH

MEASURED
NIGHT-
DAY

WHHH, WARREN, OHIO
10/25/51G
340°

5 KW, U, DA-2

1440 KC




APPL RECD 8/24/51 BZ-3328

WHHH, WARREN, OHIO

1440 KC

JUL 18 1975 GL 3479




W H H H

Proposed Night Nulls
(2-28-62ct)

Station W H H H
Warren, Ohio

5kw, DA-2, U
1440 kc

NO 341.0 DIETZEN, GRAHAM, DAVIS
POLAR COORDINATE



FCC File No. BP-15300
Accepted 1-22-62

Station W H H H
Warren, Ohio

1440 kc


1440 kc

W A H H

Measured Night Nulls
(8-24-62ct)

Station W H H H
Warren, Ohio

5kw, DA-2, U
1440 kc




ENLARGED DETAIL
NIGHT HORIZONTAL PLANE RADIATION

5 kw., DA-2., 1440 kc.

W H H H - WARREN, OHIO

PAUL GODLEY CO.
CONSULTING RADIO ENGINEERS
LABORATORIES: GREAT NOTCH, N.J. 3/62

WHHY
OVER



NL 32° 18' 29"
WL 86° 16' 39"

.7/ 80° — 220° — 1/ 0° — 147°T —→
(417')

HORIZONTAL PLANE RADIATION PATTERN

WHPA - MONTGOMERY, ALA.

1440 KC. - 1 KW. U. D.A. - N.

HOLLEY & HILLEGAS
NOV. 1945

Prop Nite

MONTGOMERY, ALABAMA

WHHY

~~WSTH~~


1440 KC

1KW-L


DA-N

12/26/46

A.F.B.



$$E = 175 [1.064 + \cos(220 \cos A \cos V + 80)]^{1/2} f(V)$$



(Prepared by L.J.N. du Treil & Assoc.
 from data submitted by WHHY)


WHHY

Measured Non-DA
(3-26-65ct)

Station WHHY
Montgomery, Alabama

1kw, 5kw-LS, DA-N, U
1440 kc

BL-10807
3-1-65
-HG. ANT. LNC



[Prepared by L.J.M. du Toit & Assoc.
From data submitted by WHHY]

FIGURE 61
HORIZONTAL PLANE PATTERN
NON-DIRECTIONAL
WHHY

FCC File No. BL-10807
Accepted 3-17-65

Station WHHY
Montgomery, Alabama

1440 kc

MEASURED
DAY (non-DA)

WHIS, BLUEFIELD, W. VA.


License 2-2-49

5kw. DAN

1440 kc

WHIS

*Granted license 10/9/54
for 5-Kw DA-N
was 5 DA-N*



DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WJBQ

Main Studio: Westbrook, Maine

Frequency: 1440 kHz

Power: 5kw Night 5kw Day

Notification List No. 1775

Date: May 31, 1978 Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS OF THE
DAYTIME AND NIGHTTIME ANTENNA SYSTEMS:

DAYTIME

NIGHTTIME

North Latitude: 43° 41' 16"
West Longitude: 70° 19' 24"North Latitude: 43° 40' 51"
West Longitude: 70° 23' 06"

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation (ND-D-191)
Number of elements: 1
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.HEIGHT ABOVE
INSULATORS:

175' (92.2°)

GROUND SYSTEM:

120 - 175' equally spaced copper radials plus a 24' square
ground screen about the tower.

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
Number of elements: 3
Type of elements: Series excited, uniform cross-section,
guyed, Shunt excited, self supporting, tapered, vertical
steel towers.

TOWER:

SW(#3)

C(#2)

NE(#1)

HEIGHT ABOVE
INSULATORS:

171'

171'

171' (90.1°)

NIGHT PHASING:

+208°

+104°

1.000

NIGHT FIELD RATIO: 1.877

2.690

SPACING AND
ORIENTATION:Adjacent towers in a row are spaced 189.67' (99.97°) on a line
bearing 256° true.

GROUND SYSTEM: 120 - 171' equatly spaced copper radials plus a 48' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	<u>RMS</u>	THEORETICAL <u>RSS</u>	STANDARD <u>RMS</u>
Night	443.8 mv/m	446.4 mv/m	466.2 mv/m

Note: This notification concerns only an addition of the Nighttime operation of the station at a new nighttime directional antenna site, with Daytime operation continued as previously notified.

WJISQ

COHEN AND DIPPELL, P.C.
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D. C. 20004



RSS/RMS = 1.01
RSS_{th} = 446.4
RMS_{th} = 443.8 MV/M
RMS_{std} = 466.2 MV/M


N. LAT: 43° 40' 51"
W. LONG: 70° 23' 06"

2.690/104° #2
1.877/208°
N 235°E
H=90°-171 FEET
100°-189.67 FEET

STANDARD RADIATION PATTERN
HORIZONTAL PLANE
FOR THE PROPOSED NIGHTTIME OPERATION OF
WJBQ, WESTBROOK, MAINE
1440 kHz 5 KW DA-N

Standard Pattern

Standard Form W3BQ



DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WKHJ

Main Studio: Holly Hill, South Carolina

Frequency : 1440 KHz

Power : 1 KW Night 1 KW Day

Notification List No.: 1779

Date : Sept 27, 1978

Class: III

GEORGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude:	<u>33°</u>	<u>20'</u>	<u>23"</u>
West Longitude:	<u>80°</u>	<u>26'</u>	<u>18"</u>

Predicted Daytime effective Field at rated power: $186 \frac{\text{mV}}{\text{m}}$

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 3
 Type of elements : uniform cross section, guyed,
 Shunt excited, vertical steel towers.

TOWER:	West(#3)	Center(#2)	East(#1)
HEIGHT ABOVE INSULATORS	190'	150' (79°)	114' (60°)
PHASING:	+138°	0°	-154°
FIELD RATIO:	0.574	1.0	0.563

SPACING AND

ORIENTATION: Adjacent towers in a row are spaced 171' (90°) on a line bearing 107° true.

GROUND SYSTEM: 120- 170' equally spaced copper radials about the West and east towers. 120-200' equally spaced copper radials about the center tower. A 24' square ground screen at the base of each tower. Radials are shortened and bonded to transverse straps along intersections between towers.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL <u>RMS</u>	<u>RSS</u>	STANDARD <u>RMS</u>
NIGHT	200.414 mv/m	309.073 mv/m	210.435 mv/m

NOTE: This notification concerns only a change in the addition of Nighttime operation of the station with Daytime operation continued as previously notified.


CTR NO

(REV. 3-78)



DISTANCES IN MILES


LATITUDE: 41° 50' N
LONGITUDE: 87° 10' W



LBA

LAWRENCE TECH ASSOCIATES, INC.
GREENVILLE, S.C. 29615

ANTENNA PARAMETERS



$G_1 = 50^\circ$
 $G_2 = 79^\circ$
 $G_3 = 100^\circ$ $S_1 = S_2 = 90^\circ$

$R_{20} = 1.0$
 $R_{50} = 1.0$
 $R_{70} = 1.0$
 $R_{90} = 1.0$
 $R_{110} = 1.0$
 $R_{130} = 1.0$

FIGURE 1A
PROPOSED STANDARD NIGHTTIME
HORIZONTAL PATTERN

1440 KHZ, 1 KW, ENF

Measured Day
(4-29-70ct)


Station WMVB
Millville, New Jersey
NORTH

WMVB

1kw, DA-D, D

1440 kc

U U U U



FCC File No. BZ-7468
Accepted 4-9-70

Station WMVB
Millville, New Jersey

1440 kc


PROPOSED
DAY (2/4/53G)

NEW, MILLVILLE, N. J.

1kw, D, DA-D

1440 kc

MILLVILLE, N.J.




MEASURED
NON-DA

WMLV, Millville, New Jersey
(5/4/54G)

1KW, D, DA-D

WMLV WMLV
1440 kc




1976 ~~WBJW~~
WNBE

Proposed Night
(11-30-61ct)

Station WABR
Winter Park, Florida

1kw, 5kw-LS, DA-N, U
1440 kc

12-15-63
Winter Park, FL
1kw, 5kw-LS
DA-N



FCC File No. BP-15168
Accepted 11-9-61-

Station WABR
Winter Park, Florida

1440 kc


WNBEI -

Measured Night
(11-29-65ct)

Station WABR
Winter Park, Florida

1kw, 5kw-LS, DA-N, U
1440 kc

10 3-28-66



EUGENE DIETZEN CO.
MADE IN U.S.A.

NO. 340-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE

FCC File No. BL-11116
Accepted 11-8-65

Station WABR
Winter Park, Florida

1440 kc

Measured Non-DA
(11-29-65ct)


Station WABR
Winter Park, Florida

WNBE —
1kw, 5... LS, DA-N, U
1440 kc

10-3-28-66

EUGENE DIETZEN CO.
MADE IN U. S. A.

NO. 340-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-11116
Accepted 11-8-65

Station WABR
Winter Park, Florida

1440 kc


WNFL ~~WJPG~~

PROPOSED
NIGHT

WJPG, GREEN BAY, WISC.

500w, 1kw-LS, DA-2

1440 kc



AMENDMENT RECD 4-3-50 BP-7422

WJPG, Green Bay, Wisc. 1440 kc

~~WJPS~~

1440 kc



WJPG, Green Bay, Wis. 1440 kc

WNFL WJPG


MEASURED
DAY (7/13/54G)

WJPG, Green Bay, Wisc.

500W, 5KW-LS, U, DA-2

1440 kc

GEORGE C. DAVIS
CONSULTING RADIO ENGINEER
WASHINGTON 4, D. C.



MEASURED HORIZONTAL PLANE PATTERN
FOR 5 KW DAYTIME OPERATION
UNATTENUATED FIELD AT ONE MILE
WJPG - 1440 KC - 0.5 KW - 5 KW - DA-2
GREEN BAY, WISCONSIN
MAY 1954

WNPV

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WNPV Main Studio: Lansdale, Pennsylvania
 Frequency : 1440 KHz Power : .5 kW Night .5 kW Day
 Notification No.: 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 40° 14' 18"
 West Longitude: 75° 19' 00"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 5

Type of elements: Series excited, uniform cross-section, guyed, vertical steel towers.

TOWER	:	N	S	W	C	E	
HEIGHT ABOVE INSULATORS	:	<u>171'</u>	<u>171'</u>	<u>171'</u>	<u>171'</u>	<u>171'</u>	
NIGHT PHASING	:	<u>--</u>	<u>--</u>	<u>0</u>	<u>183.66</u>	<u>26</u>	
NIGHT FIELD RATIO:		<u>--</u>	<u>--</u>	<u>1.0</u>	<u>0.728</u>	<u>1.0</u>	
DAY PHASING	:	<u>0°</u>	<u>+60.</u>				
DAY FIELD RATIO	:	<u>1.0</u>	<u>0.78</u>				

SPACING AND

ORIENTATION: DAYTIME: Spaced 322 feet (170°) on a bearing of 206° true.

NIGHTTIME: Adjacent towers in a row are spaced 189.7 (100°) on a line bearing 101° true.

GROUND SYSTEM: 120 - 171' equally spaced copper radials plus 120 - 50' interspaced radials and a 48' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD	
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>	
Night	<u>138.7</u> mV/m	<u>245.5</u> mV/m	<u>145.8</u> mV/m	

Note: Please retain the nighttime directional antenna radiation pattern notified for Station (NEW) in United States Change List Number 843 dated December 29, 1959 and attach to this supplemental Description Sheet and Nighttime pattern. This notification concerns only a change in the Nighttime operation of the station with Daytime operation continued as previously notified.


OCT

COHEN AND DIPPPELL

TRUE NORTH

COHEN AND DIPPPELL, P.C.
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D. C. 20004

WNPV



RSS/RMS = 1.77
RSS_{th} = 245.5
RMS_{th} = 138.7
RMS_{std} = 145.8
N. LAT: 40° 14' 18"
W. LONG: 75° 19' 00"


W(#3) 1/0°
C(#4) 0.728/183.66°
E(#5) 1/26°
N 101°E
H=90°=171 FEET
100°=189.7 FEET

STANDARD RADIATION PATTERN
HORIZONTAL PLANE
FOR THE PROPOSED NIGHTTIME OPERATION OF
WNPV, LANSDALE, PENNSYLVANIA
1440 kHz 0.5 KW DA-2
MAY 1976

COHEN AND DIPPILL, P.C.
CONSULTING ENGINEERS
RADIO TELEVISION
WASHINGTON, D. C. 20044

$\psi = 0^\circ$

STANDARD RADIATION PATTERN
VERTICAL PLANE
FOR THE PROPOSED NIGHTTIME OPERATION OF
WNPV, LANSDALE, PENNSYLVANIA
1440 kHz 0.5 KW DA-2
MAY 1976



Standard Pattern

WNPV


Lansdale, Pa.

WNPV

PROPOSED DAY
(7-25-58g)

New; Equitable Publishing Co.
Lansdale, Pennsylvania

500w, DA-D,D
1440 KC



FCC File No. BP-11,934
Accepted March, 1958

Equitable Publishing Co.
Lansdale, Pennsylvania

1440 KC

WNPV

MEASURED DAY
(12-15-60g)


Station WNPV
Lansdale, Pennsylvania

500w, DA-D, D
1440 KC

NORTH LATITUDE 40° 14' 18"
WEST LONGITUDE 75° 19' 00"

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

1-31-62
granted L for
new station



FCC File No. BL-8156
Accepted 11-17-60

WNPV
Lansdale, Pennsylvania

1440 KC


WNPV

MEASURED NON-DA
(12-15-60g)

Station WNPV
Lansdale, Pennsylvania

500w, DA-D, D
1440 KC

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 25 D. C.



FCC File No. BL-8156
Accepted 11-17-60

WNPV
Lansdale, Pennsylvania

1440 KC

WOHN


Proposed Day
(3-26-65ct)

Station WHRN
Herndon, Virginia

1kw, DA-D, D
1440 kc

EXHIBIT NO. E-1

BMP-11460
3-17-65 MCP
CHG. DA.



COMMERCIAL RADIO EQUIPMENT CO.
RADIO ENGINEERING CONSULTANTS
WASHINGTON, D. C. 2/65

PATTERN: Proposed Daytime
FOR: Herndon, Virginia
POWER: 1KW-D FREQ: 1440 KC

FCC File No. BMP-11460
Accepted 3-16-65

Station WHRN
Herndon, Virginia

1440 kc

Measured Day
(11-29-65ct)

Station WHRN
Herndon, Virginia


1kw,
1440 kc

WOHN

N 77° 23' 06"
W 38° 56' 32"

$S_1 = S_2 = 120^\circ$

0.5 / $\angle 78.1^\circ$
#1 S_1 $G=70^\circ$
0.982 / 0°
#2 S_2 $G=103^\circ$
0.5 / $\angle 78.1^\circ$
#3 $G=70^\circ$ 101° True
 $E_{rms} = 186 \text{ mv/m}$
Theoretical Parameters



COMMERCIAL RADIO EQUIPMENT CO.
Radio Engineering Consultants

WASHINGTON, D C

7/65

MEASURED HORIZONTAL DIRECTIONAL
RADIATION PATTERN
RADIO STATION WHRN
HERNDON, VIRGINIA

1440 KC

1 KW, DA-D

FCC File No. BL-11091
Accepted 11-1-65

Station WHRN
Herndon, Virginia

1440 kc

1975

Measured Non-DA
(11-29-65ct)


Station WHRN
Herndon, Virginia

1k

WOHN

N 77° 23' 06"
W 38° 56' 32"
SITE

TOWER NO. 2
30° (Centre)



COMMERCIAL RADIO EQUIPMENT CO.
Radio Engineering Consultants

WASHINGTON, D. C.

MEASURED HORIZONTAL NON-DIRECTIONAL
RADIATION PATTERN
RADIO STATION WHRN
HERNDON, VIRGINIA

1440 KC

250 WATTS

FCC File No. BL-11091
Accepted 11-1-65

7/65
Station WHRN
Herndon, Virginia

1440 kc

WPGW

PROPOSED
DAYTIME

NEW, PORTLAND, IND.
(Glenn West)


500W, DA, D

PORTLAND, IN

PORTLAND, IND. 1440KC

330°
11/10/49G

GEORGE C. DAVIS
CONSULTING RADIO ENGINEER
WASHINGTON 4 D. C.



AMENDMENT RECD 10-25-49 BP-6785

New, Portland, Ind. 1440 kc


WPGW

MEASURED
DAY

WPGW, PORTLAND, IND.

500w, DA


1440 kc



WPGW, Portland, Ind. 1440 kc

WQOK

82 7998



RMS 438 MV/M

MEASURED

#1 0.45 / 146.5°

90°

#2 1.0 / 0°

90°

#3 0.772 / 151.8°

90°

82 7998

FIG. 5
WQOK, INC.
RADIO STATION WQOK
GREENVILLE, S.C.
MEASURED NIGHTTIME HORIZONTAL
RADIATION PATTERN.

1440 KHz

WQOK

Measured Night
(6-28-66ct)

Station WQOK
Greenville, South Carolina

5kw, DA-N, U
1440 kc





Fig. 5		
RADIO STATION WQOK		
GREENVILLE, S.C.		
1440 KCS.	5.0 KW.	DA-N.
MEASURED NIGHTTIME HORIZONTAL		
RADIATION PATTERN.		

FCC File No. BZ-6017
Accepted 6-17-66


Station WQOK
Greenville, South Carolina

1440 kc

Measured Non-DA
(6-28-66ct)

Station WQOK
Greenville, South Carolina

WQOK
5kw, DA-N, U
1440 kc



WQOK
5kw, DA-N, U
1440 kc
THE NON-DESTRUCTIVE MEASURED
RADIATION PATTERN, #2

FCC File No. BZ-6017
Accepted 6-17-66

Station WQOK
Greenville, South Carolina

1440 kc

WQOK


Station WQOK - Greenville, South Carolina

5kw, DA-2, U

1440 KC

Proposed Night Pattern

9/2/48 GO



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS										STATION DATA			
		POWER	ELECTRIC FIELD	TIME PERIOD	SPACING	PHASE	HORIZONTAL FIELD	FIELD GAIN	SLIP ANGLE	ELEVATION	REAR FIELD	CALL	WQOK		
		dBm	V/m	hr	m	deg	dBm	dB	deg	deg	dBm	Frequency	1440		
		1	102		20	-58.74	59.74	1	0	45		Power	5		
		2	103		20	-100.77	2.458	10				Time of operation	U		
		3	102		20	-100.33	2.557	20				Type of operation	DA-2		
		4	102		20	-58.74	67.74	1	30			Softtime towers	1		
		5										Softtime towers	4		
		6										No signals per tower	100		
		7										Length of signal on S	100		
		8										Ground screen diameter	40' x 40'		
9										LAT	34° 52' 15"				
10										LONG	82° 28' 22"				
												Superfines	47HII-B		
												Pattern No.	47G15-B		
TEXTILE BROADCASTING COMPANY GREENVILLE, S. C. 1440 KC 5KW DA-2 GEORGE P. ADAIR Radio Engineering Consultant Fig. 1A															

WKDD
1440 KHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WRDD

Main Studio: Bay City, Michigan

Frequency: 1440 KHz

Power: 2.5 Kw Night 5 Kw Day

Notification: 1778

Date: August 30, 1978 Class: III

GEOGRAPHICAL LOCATION OF THE

CENTER OF THE ANTENNA SYSTEMS:

North Latitude: 43° 31' 27"
West Longitude: 83° 57' 58"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 3

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER	:	<u>S (#1)</u>	<u>C (#2)</u>	<u>N (#3)</u>	<u> </u>	<u> </u>	<u> </u>
HEIGHT ABOVE INSULATORS	:	<u>218.3'</u>	<u>218.3'</u>	<u>218.3'</u>	<u>(115°)</u>	<u> </u>	<u> </u>
NIGHT PHASING	:	<u>0°</u>	<u>+206.°</u>	<u>+51°</u>	<u> </u>	<u> </u>	<u> </u>
NIGHT FIELD RATIO:		<u>1.0</u>	<u>1.15</u>	<u>0.58</u>	<u> </u>	<u> </u>	<u> </u>
DAY PHASING	:	<u>0°</u>	<u>-139.5°</u>	<u>+80°</u>	<u> </u>	<u> </u>	<u> </u>
DAY FIELD RATIO	:	<u>1.000</u>	<u>3.02</u>	<u>2.98</u>	<u> </u>	<u> </u>	<u> </u>
SPACING AND ORIENTATION	:	Towers in a row are spaced 170.8' (90°) on a line bearing 21.5° true.					

GROUND SYSTEM: 120 - 170.8' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of system are bonded together.



PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	<u>RMS</u>	THEORETICAL <u>RSS</u>	STANDARD <u>RMS</u>
Day	469.3 mv/m	649.9 mv/m	493.1 mv/m
Night	280 mv/m	483.9 mv/m	294.3 mv/m

Note: This notification concerns a change in the Daytime operation of the station and Nighttime to use a directional antenna daytime and nighttime and increase daytime and nighttime power.

WRDD
1440 kHz

NORTH



NORTH LATITUDE: 43° 31' 27"
WEST LONGITUDE: 83° 57' 58"


BL-790810AC

FIGURE 3
PROPOSED DAYTIME HORIZONTAL PLANE
STANDARD RADIATION PATTERN

WRDD 2.5 kW-N, 5 kW-LS, DA-2 1440 kHz
BAY CITY, MICHIGAN

Prepared by
Lohnes and Culver Washington, D. C.
April, 1979

WRDD
1440 kHz



$RMS_{Th} = 280 \text{ mV/m}$
 $RSS_{Th} = 483.9 \text{ mV/m}$
 $RMS_{Std} = 294.3 \text{ mV/m}$


NORTH LATITUDE: $43^{\circ} 31' 27''$
 WEST LONGITUDE: $83^{\circ} 57' 58''$

BL-790810 AC

FIGURE 5
 PROPOSED NIGHTTIME HORIZONTAL PLANE
 STANDARD RADIATION PATTERN

WRDD 2.5 kW-N, 5 kW-LS, DA-2 1440 kHz
 BAY CITY, MICHIGAN

Prepared by
 Lohnes and Culver Washington, D. C.
 April, 1979



WROK

Proposed Day
(12-19-61ct)

Station WROK
Rockford, Illinois

500w, 5kw-LS, DA-D, U
1440 kc

North 42° 16' 50"
West 61° 52' 16"

3-28-62
printed CP for
increase in Day power
5 KW-DA-D





FIGURE 4
HORIZONTAL RADIATION PATTERN
ROCKFORD BROADCASTERS, INC.
WROK 500W, 5KW-LS DA-D 1440 KC
ROCKFORD, ILLINOIS

Prepared by
Lohmes and Culver Washington 6, D. C.
July 1961

FCC File No. BP-13422
Accepted 11-9-61

Station WROK
Rockford, Illinois 1440 kc

WROK

Measured Day
(5-28-63ct)

Station WROK
Rockford, Illinois

500w, 5kw-LS, DA-D, U
1440 kc

North Latitude 42°16'50"
West Longitude 89°02'16"

6-21-63
granted 2. covering
increase in day power
and install DA-D





FIGURE 7
HORIZONTAL RADIATION PATTERN
(DA-DAY)

ROCKFORD BROADCASTERS, INCORPORATED
WROK 0.5 KW, 5 KW-LS, DA-D 1440 KC
ROCKFORD, ILLINOIS

Prepared by
Lahnes and Culver Washington 4, D.C.
February 1963 1440 kc

FCC File No. BL-9883
Accepted 5-9-63

Station WROK
Rockford, Illinois

WROK

Measured Non-DA
(5-28-63ct)

Station WROK
Rockford, Illinois

500w, 5kw-LS, DA-D, U.

1440 kc

North Latitude 42° 16' 50"

West Longitude 89° 02' 16"

6-21-63
granted L. covering
increase in day power
and install DA-D.




FIGURE 6
HORIZONTAL RADIATION PATTERN
(NON-DIRECTIONAL)

ROCKFORD BROADCASTERS, INCORPORATED
WROK 0.5 KW, 5 KW-LS, DA-D 1440 KC
ROCKFORD, ILLINOIS

Prepared by
Lohnes and Culver Washington 4, D.C.
February 1963

1440 kc

FCC File No. BL-9883
Accepted 5-9-63

Station WROK
Rockford, Illinois

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: XERAL Main Studio: Tonala, Jalisco
Frequency: 1440 kHz Power: 5kw
Notification List No. 292 Date: November 1, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 20° 37' 25"
West Longitude: 103° 15' 49"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)
Number of elements: 2
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	#1 (N)	#2 (S)
HEIGHT ABOVE INSULATORS:	498.7	498.7'
DAY PHASING:	0°	135°
DAY FIELD RATIO:	1	1

SPACING AND
ORIENTATION: The towers are spaced 132.9' (70°) on a line bearing
166° true.

GROUND SYSTEM: 90 - 498.7' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap along
intersections between towers. Centers of system are bonded
together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL

RMS

Day 416.76 mv/m

XERAL

XERAL

1440 KHz.

5 KW. AD .

PATRON DE RADIACION


AUGUSTO


TONALA, JAL.

SEPTIEMBRE DE 1979

REVISOR

REVISOR

REVISOR


REVISOR

DESCRIPCION DEL SISTEMA RADIADOR DIRECCIONAL XERAL

1. LISTA DE CAMBIOS _____
 2. FECHA SEPTIEMBRE DE 1979
 3. FRECUENCIA 1440 KHz
 4. DISTINTIVO XERAL
 5. POBLACION TONALA JALISCO
 6. UBICACION _____
 7. POTENCIA 5000 AD-D
 8. CLASE III

LAT. NORTE 20°-37'-25"
 LONG. OESTE 103°-15'-49"

CARACTERISTICAS TECNICAS DEL RADIADOR


9. TIEMPO DE OPERACION DIURNO
 10. SISTEMA DEL RADIADOR DIRECCIONAL - DIURNO
 11. NUMERO DE ELEMENTOS DOS

TIPO DE ELEMENTOS RADIADORES

12. TIPO DE ALIMENTACION SERIE
 13. SECCION TRANSVERSAL FORMA TRIANGULAR DIMENSIONES 45 CMS. POR LADO
 14. TIPO DE ELEMENTO RADIADOR VERTICAL
 15. TIPO DE SOPORTE CON RETENIDAS TIPO DE RETENES CABLE ACE-
RO DE 6.3 mm. DE DIAM.
 16. LONGITUD DE TOPETE CAPACITIVO _____
 17. IMPEDANCIA MUTUA $Z_{12} = 26.15 - j 8.50$ IMPEDANCIA PROPIA $45 + j 30 = Z_{11} = Z_{22}$
 18. NUMERO DE ELEMENTOS 1 2
 19. ALTURA SOBRE EL AISLADOR 52 M. 52 M.
 20. DEFASAMIENTO 0° 135°
 21. RELACION DE CAMPO 1 1
 22. DESCRIPCION DE LA ORIENTACION DEL SISTEMA RADIADOR EL EJE DE LAS
TORRES SE ENCUENTRA A 166° RESPECTO DEL NORTE GEOGRAFICO, LA
SEPARACION ENTRE TORRES ES DE 70° Y LA FASE DE LAS CORRIENTES
ES DE 1350 Y EN RELACION ES LA UNIDAD.

SISTEMA DE TIERRA

23. NUMERO DE RADIALES POR ELEMENTO 90
 24. LONGITUD DE LOS RADIALES 52
 25. TIPO DEL RADIAL ALAMBRE DE COBRE No. 10



RADIACION DEL SISTEMA

26. INTENSIDAD DE CAMPO EFECTIVO TEORICO (OMNIDIRECCIONAL) DE LA POTENCIA RADIADA (RCM) 416.76
 27. INTENSIDAD DE CAMPO EFECTIVO TEORICO A 1609 mts POR KW DE POTENCIA RADIADA 190 MV/M

28. NOTA PATRON NUEVO

[Handwritten signature]

[Handwritten signature]

PATRON DE RADIACION HORIZONTAL TABULADO

OPERACION DIURNA

XERAL

1440 KHZ

$$E_{\theta} = 2E \cos \left[\frac{s}{2} \cos(166 - \theta) + \frac{\psi}{2} \right]$$

5,000 WATTS

TONALA JAL.


$$E_1 = 403.61$$

$$s = 70^{\circ}$$

$$\psi = 135^{\circ}$$


AZIMUT	A	B	C	D	F	E (mV./M)
θ	$\cos(166 - \theta)$	$\frac{s}{2} A$	$B + \frac{\psi}{2}$	$\cos C$	2D	F
0	-0.9702	-33.9603	33.5396	0.8335	1.6670	672.8208
10	-0.9135	-31.9740	35.5259	0.8138	1.6277	656.9582
20	-0.8290	-29.0163	38.4836	0.7827	1.5655	631.8800
30	-0.7193	-25.1768	42.3231	0.7393	1.4787	596.8258
40	-0.5877	-20.5724	46.9275	0.6829	1.3658	551.2691
50	-0.4383	-15.3429	52.1570	0.6134	1.2269	495.2292
60	-0.2756	-9.6473	57.8526	0.5320	1.0641	429.5200
70	-0.1045	-3.6584	63.8415	0.4408	0.8817	355.8676
80	0.0697	2.4414	69.9414	0.3429	0.6859	276.8601
90	0.2419	8.4672	75.9672	0.2424	0.4849	195.7316
100	0.4067	14.2357	81.7357	0.1437	0.2874	116.0283
110	0.5591	19.5717	87.0717	0.0510	0.1021	41.2371
120	0.6947	24.3130	91.8130	-0.0316	-0.0632	-25.5390
130	0.8090	28.3155	95.8155	-0.1013	-0.2026	-81.7932
140	0.8987	31.4577	98.9577	-0.1557	-0.3114	-125.689
150	0.9612	33.6441	101.1441	-0.1932	-0.3865	-156.018
160	0.9945	34.8082	102.3082	-0.2131	-0.4263	-172.076
170	0.9975	34.9147	102.4147	-0.2149	-0.4299	-173.541
180	0.9702	33.9603	101.4603	-0.1986	-0.3973	-160.386
190	0.9135	31.9740	99.4740	-0.1646	-0.3292	-132.869
200	0.8290	29.0163	96.5163	-0.1134	-0.2269	-91.6082
210	0.7193	25.1768	92.6768	-0.0467	-0.0934	-37.7000
220	0.5877	20.5724	88.0724	0.0336	0.0672	27.1509
230	0.4383	15.3429	82.8429	0.1245	0.2491	100.5705
240	0.2756	9.6473	77.1473	0.2224	0.4448	179.5622
250	0.1045	3.6584	71.1584	0.3229	0.6459	260.6927
260	-0.0697	-2.4414	65.0585	0.4216	0.8433	340.3984
270	-0.2419	-8.4672	59.0327	0.5145	1.0290	415.3536
280	-0.4067	-14.2357	53.2642	0.5981	1.1962	482.8190
290	-0.5591	-19.5717	47.9282	0.6700	1.3401	540.8864
300	-0.6946	-24.3130	43.1869	0.7291	1.4582	588.5638
310	-0.8090	-28.3155	39.1844	0.7751	1.5502	625.6895
320	-0.8987	-31.4577	36.0422	0.8085	1.6170	652.7049
330	-0.9612	-33.6441	33.0558	0.8304	1.6634	670.3493
340	-0.9945	-34.8082	32.6917	0.8415	1.6851	679.3472
350	-0.9975	-34.9147	32.5852	0.8425	1.6851	680.1563

XERAL



PATRON DE RADIACION HORIZONTAL CALCULADO

ESQUEMA DE LAS TORRES Y SU ORIENTACION CON RESPECTO AL NORTE ASTRONOMICO



SARA CABAÑAS RODRIGUEZ

XERAL

1440 KHz


5,000 WATTS

REL: 2

ING. ANTONIO DE AVILA S

SEPTIEMBRE DE 1979

APROBADO



EN TODAS LAS UNIONES SE UTILIZA SOLDADURA DE COBRE APLICADA CON ACETILENO



ESCALA: 1:1250

SISTEMA DE TIERRA

DESCRIPCION DEL MATERIAL

120 RADIALES POR TORRE
IGUALMENTE ESPACIADAS
PARTIENDO DE LA BASE
DE CADA TORRE 53 m DE
LONGITUD DE ALAMBRE-
No. 10 ENTERRADOS A 10
cm. DE PROFUNDIDAD

IDENTIFICADOR DE LLAMADA

XERAL

COORDENADAS GEOGRAFICAS

LN 20° 37' 25"
LW 103° 15' 49"



FRECUENCIA

1440 KHz.

CERTIFICADO EN TELECOMUNICACIONES
ING. ANTONIO DE AVILA - S.
REGISTRO No. 7

FECHA

SEPTIEMBRE DE 1979



SECCION TRANSVERSAL
ESCALA 1 : 20

LARGUEROS = tubo $1\frac{1}{2}$ " Cal. 13 redondo
ESCALONES = tubo $1\frac{3}{4}$ " x $\frac{3}{4}$ " Cal. 13 ovalado


TIPO T-60
SECCION TRIANGULAR
GALVANIZADO EN CALIENTE
ESCALA 1 : 20

UNION = bridas $\frac{1}{4}$ "

DETALLE SECCION DE TORRE — ANTENA

FRECUENCIA: 1440 KHz.	SARA CABAÑAS RDGZ.	RESPONSABLE TECNICO: ING. ANTONIO DE AVILA SERAFIN
POTENCIA: 5,000 WATTS.	XERAL TONALA, JAL.	FECHA: SEPTIEMBRE DE 1979

ESCALA 1:500



DETALLE DE LA TORRE Y RETENIDAS

FRECUENCIA

1440 KHz.

POTENCIA

5,000 WATTS.

SARA CABAÑAS RDGZ.

XERAL

TONALA JAL.



RESPONSABLE TECNICO

ING.

ANTONIO DE AVILA

FECHA

SEPTIEMBRE DE 1979



SISTEMA DE ALIMENTACION DE 120 V.A.C.
PARA EL ALUMBRADO DE LA TORRE.

XERAL
1440 KHZ.

216

Description Sheet
(8-26-66ct)

New Station
St. Eleuthere, P. Q.

250w, U, Class IV
1450 kc



DESCRIPTION SHEET - OMNIDIRECTIONAL ANTENNA

STATION CALL: New
MAIN BUILDING: Ville la Pocatière, Qué.
STATION LOCATION: St. Eleuthere, P. Q.
FREQUENCY: 1450 KHz
POWER: 0.25 KW
CLASS: IV
TIME: Day and Night Operation

NOTIFICATION LIST NO.: 216 DATE: July 26, 1966

GEOGRAPHICAL LOCATION: 47° 28' 45" N. Lat.
OF THE ANTENNA SYSTEM: 69° 16' 35" W. Long.

ANTENNA CHARACTERISTICS:

HEIGHT: 142 ft. (75°)

TYPE OF ELEMENT: Triangular, uniform
cross-section, guyed,
base insulated, series
fed, no top loading.

GROUND SYSTEM: 120 equally spaced radials
consisting of #10 B&S bare
soft-drawn copper wire buried
approx. 8" in ground. The ra-
dials extend to a length of
at least 275 ft. (equivalent
to 0.4)

EXPECTED EFFICIENCY: 92.5 mV/m @ 1 mile for 0.25 KW
or
185 mV/m @ 1 mile for 1 KW.

AIR SERVICES
TELECOMMUNICATIONS DIVISION



REFER TO FILE NUMBER

5-10-47

DEPARTMENT OF TRANSPORT

(REVISED)

DESCRIPTIVE SHEET - OMNIDIRECTIONAL ANTENNA

Station Call: CBG
Main Studio: Gander, Newfoundland
Frequency: 1450 Kc/s.
Power: 250 watts
Class: IV
Time: U

Geographical Location:

North Latitude: 48° 57' 19"
West Longitude: 54° 36' 48"

Antenna Characteristics:

Height: 110 ft. 72 degrees electrical including top loading.

Expected efficiency: 75 mv/m at 1 mi. for 0.25 KW.

or: 150 mv/m at 1 mi. for 1 KW.

Ground System: Rods driven into ground, connected to tower base by radials and a ground lead bonded to the water system.

Type of Element: Constant triangular cross-section tower, guyed, base insulated for series feed. Top loading employed.

Nov 26 '52

CFAB
1450

AIR SERVICES
TELECOMMUNICATIONS DIVISION
(5-10-99)



DEPARTMENT OF TRANSPORT

DESCRIPTIVE SHEET - OMNIDIRECTIONAL ANTENNA

Station Call: CFAB
Main Studio: Windsor, Nova Scotia
Frequency: 1450 Kc/s.
Power: 0.25 Kw.
Class: IV
Time: U

Notification Reference: NARBA Annex 3

Geographical Location:

North Latitude: 44° 59' 52"
West Longitude: 64° 09' 45"

Antenna Characteristics:

Height: 90 ft. 52 degrees
Expected Efficiency: 90 mv/m at 1 mi. for 0.25 Kw.
or: 180 mv/m at 1 mi. for 1 Kw.

Ground System:

120 radial ground wires approximately 230 feet long.

Type of Element:

One radiator, guyed, insulated, series-fed; top loading is a "capacity hat", 4-foot diameter wheel with 16 spokes.

November 26, 1952

#132
DESCRIPTION SHEET
(5-28-59g)

Station CFJR 250w, 1kw-LS, DA-D,U, Class IV
Brockville, Ontario, Canada 1450 KC

CFJR

Description of Array

<u>Station</u>	CFJR	<u>Main Studio</u>	Brockville, Ontario
<u>Frequency</u>	1450 kc	<u>Power</u>	1 kw D/0.25 kw N <u>Class</u> IV
<u>Notification List No.</u>	132	<u>Date</u>	April 9, 1959

Geographical Location
of Antenna System

North Latitude 44° 36' 22"
West Longitude 75° 43' 09"

Antenna Characteristics

Mode of Operation: DA-D, ND-N
Number of Elements: 2
Type of Elements: guyed, uniform cross section,
no top loading.

	<u>North Tower</u>	<u>South Tower</u>
Height above Insulators	170'	100'
Overall Height	175'	103'
Spacing	141'	
<u>Phasing</u>	0°	+85.5°
<u>Field Ratio</u>	1.0	0.193
Orientation	Line through towers in Azimuth 173°.	
Ground System	Around each tower base, 120 radials spaced 30° to limit of property approximately 400' from base, plus 120 radials interspaced, each 40' long.	
Predicted Effective Field	190 mv/m at 1 mile (190 per kw)	

150 160 170 180 190 200 210

220° 140°
230° 130°
240° 120°
250° 110°
260° 100°
270° 90°
280° 80°
290° 70°
300° 60°
310° 50°
320° 40°

NORTH

110°
75°
0.193 +05.5°

CHEF 155 MI
WPOM 134 MI 1470 K
MYIM AT 1 MILE

300 100 100 200 300

RMS - 100

WKAL 97 MI

FIG. 1

KEITH A. MACKINNON
CONDUCTING RADIO ENGINEER
OTTAWA CANADA
CFJR - Brockville, Ont
1450 KC. 11W0 KEAW N. DA-D
DAYTIME HOURS
PATTERNS
JAN. 28, 1933

330° 30°
340° 20°
350° 10°
0
10° 350°
20° 340°
30° 330°


ANTENNA DESCRIPTION SHEET


1. Call Letters: CHEF
2. Station: Granby, Quebec.
3. Frequency: 1450 kHz
4. Power: 10 Kw D/5 Kw N
5. Class: IV (U)
6. Notification No.: 296 Date: September 7, 1972.
7. Co-ordinates: North Latitude: $45^{\circ} 19' 03''$
West Longitude: $72^{\circ} 41' 43''$
8. Antenna System: a) Mode of Operation: DA-2
b) Type: four elements, guyed triangular and series fed.
c) ground system: 120 No. 10 equally spaced radials of a length 271' (0.49) with interconnected straps buried approximately 8 inches.

9. Antenna Characteristics:	No. 1 South	No. 2	No. 3	No. 4 North
Orientation (Az.)	166.5°	Ref.	346.5°	346.5°
Height above insulator:	165'	165'	165'	165' (87.8°)
Spacing:	80°	Ref.	80°	160°
Phasing:	Day: $+140^{\circ}$ Night: $+160^{\circ}$	$+10^{\circ}$ $+0.5^{\circ}$	-140° -160°	- $+42^{\circ}$
Field intensity ratio:	Day: 0.9672 Night: 0.4516	1.0 1.0	0.6393 0.9677	- 0.4194

10. Predicted efficiency: Day: 597 mVm
Night: 382 mVm


Yves R. Hamel
Consulting Engineer
3772 Kent Avenue
Montreal 249, P.Q.




150
740

CHEF

210° 150° 230° 160° 190° 180° 170° 190° 160° 150° 210°





CHEF




FIGURE NO. 5
RANGE EXTENSION LIAISON UNIT
FIVE MILES
AZ 250° 22.5', 255° 00' 162.5'
RANGE CO. T-141 INDICATION 12 M
CLASS IV 10-141 / 5 M-17 AD-2 1450 KHz
10/4/74 T-141 12-10-11
Y-15 12-10-11
Y-16 12-10-11

CHEF

Description Sheet
(2-28-69ct)

Station CHEF
Granby, P.Q.

5kw, 10kw-LS, DA-2, U, Class IV
1450 kc

DESCRIPTION OF THE DIRECTIONAL ANTENNA SYSTEM

CALL SIGN: CHEF

LOCATION: Granby, P.Q.

FREQUENCY: 1450 kHz

POWER: 10 kW D/5 kW N

CLASS: IV, (U)

NOTIFICATION NO. 251 DATE: January 28, 1969

COORDINATES: Latitude North: 45° 19' 03"
Longitude West: 72° 41' 43"

ANTENNA SYSTEM: Mode of Operation: DA-2

Type: three triangular section elements and one square section element (No. 4), guyed and series fed.

Ground system: 120 No. 10 wires per element, evenly spaced and 0.4 in length, approximately 8 inches underground.

ANTENNA MASTS:	No. 1 South	No. 2	No. 3	No. 4 North
Orientation (in line)	Az 166.5°	Ref.	Az 346.5°	Az 346.5°
Height above insulator:	165' (87.8°)	165' (87.8°)	165' (87.8°)	154' (82°)
Spacing:	80°	Ref.	80°	160°
Phasing:	Day: +140°	+10°	-140°	-
	Night: +160°	+0.5°	-160°	+42°
Field ratio:	Day: 0.9672	1.0	0.6393	-
	Night: 0.4516	1.0	0.9677	0.4194
EXPECTED EFFICIENCY:	Day: 597 mV/m			
	Night: 382 mV/m			

CHEF

Description Sheet
(6-27-69ct)

Station CHEF
Granby, Quebec

250w, 10kw-LS, DA-D, U, Class IV
1450 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Call Sign: CHEF

Location: Granby, Quebec

Frequency: 1450 kc/s

Power: 10 kw Day 0.25 kw Night

Notification List No. 257

Date: June 5, 1969 Class: IV (u)

GEOGRAPHICAL LOCATION OF THE DAY AND NIGHT ANTENNA SYSTEMS:

DAY
North Latitude: 45° 19' 03"
West Longitude: 72° 41' 43"

NIGHT
North Latitude: 45° 24' 58"
West Longitude: 72° 45' 13"

Description of the Day Antenna System. (DA-D)

Number of elements: 3

Type of elements: Triangular section, guyed and series fed.

ANTENNA CHARACTERISTICS:	NO.1 SOUTH	NO.2 CENTRE	NO.3 NORTH
ORIENTATION (IN LINE)	Az 166.5°	REF.	Az 346.5°
HEIGHT ABOVE	165'	165'	165' (87.8°)
INSULATOR SPACING:	80°	REF.	80°
PHASING:	+140°	+10°	-140°
FIELD RATIO:	0.9672	1.0	0.6393

GROUND SYSTEM: 120 radials of No. 10 solid copper wire per tower, evenly spaced and 0.4 in length, approximately 8 inches underground.

EXPECTED EFFICI-
ENCY:

597 mv/m

Description of the Night Antenna System (omnidirectional)

Number of elements: 1

Type of elements: Guyed, square section tower, series fed.

ANTENNA CHARACT-
ERISTICS:

HEIGHT: 154' (82°)

GROUND SYSTEM: 120 radials of No. 10 solid copper wire, evenly spaced and approximately 350' in length, buried 6 inches deep.

EXPECTED

EFFICIENCY: (omnidirectional) 91 mv/m


NOTE: Please retain the daytime directional antenna radiation pattern notified in Canadian change List No. 251, dated January 29, 1969 and attach to this Description Sheet.

CHEF

Proposed Day
(2-28-69ct)

Station CHEF
Granby, P.Q.

5kw, 10kw-LS, DA-2, U, Class IV
1450 kc




46 4413
POLAR CO ORDINATE
46 4413
46 4413

CHEF

Proposed Night
(2-28-69ct)

Station CHEF
Granby, P.Q.

5kw, 10kw-LS, DA-2, U, Class IV
1450 kc



CHEF

Proposed Day Nulls
(2-28-69ct)

Station CHEF
Granby, P.Q.

5kw, 10kw-LS, DA-2, U, Class IV
1450 kc




FIGURE #3

LIMITES DE RADIATION DE JOUR

POSTE COMMERCIAL RADIOPHONIQUE MA

CHEF, GRANBY, QUE.

CLASSE IV 10 kW J / 5 kW N AD-2 1450 kHz

YVES R. HAMEL

INGENIEUR-CONSULT

15/2/68

J.R.H.

#131

CHEF

DESCRIPTION SHEET
(5-28-59g)Station CHEF 250w, 1kw-LS, U, Class IV
Granby, Quebec, Canada 1450 KCDESCRIPTIVE SHEET - OMNIDIRECTIONAL ANTENNA

STATION CALL: CHEF
MAIN STUDIO: GRANBY, QUE.
FREQUENCY: 1450 KC
POWER: 1 KW DAY/250 W NIGHT
CLASS: IV
TIME: U
GEOGRAPHICAL LOCATION: NORTH LATITUDE 45° 24' 58"
WEST LONGITUDE 72° 45' 13"
ANTENNA CHARACTERISTICS: HEIGHT: 154 FEET (82°)
EXPECTED EFFICIENCY: 182 MV/M AT 1 MILE FOR 1 KW
GROUND SYSTEM: 120 RADIALS, MOST ABOUT 300 FEET LONG.
SOME RADIALS ON SOUTH SIDE 350 TO 400 FEET LONG BURIED
6 INCHES DEEP
TYPE OF ELEMENT: UNIFORM, BASE INSULATED, SQUARE CROSS-
SECTION, SERIES FED, GUYED.

NOTIFICATION LIST NO. 131

DATE: February 27, 1959

Description Sheet
(4-29-69ct)

Station CHRT
St. Eleuthere, P. Q.
CORRECTED

CHRT
250w, U, Class IV
1450 kc

DESCRIPTION SHEET - OMNIDIRECTIONAL ANTENNA

STATION CALL: CHRT
MAIN STUDIO Ville la Pocatiere, Que.
STATION LOCATION: St. Eleuthere, P. Q.
FREQUENCY: 1450 kHz
POWER: 0.25 KW
CLASS: IV
TIME: Day and Night Operation
NOTIFICATION LIST NO. 216 DATE: July 26, 1966
GEOGRAPHICAL LOCATION 47° 28' 36" N. Lat.
OF THE ANTENNA SYSTEM: 69° 16' 14" W. Long.
ANTENNA CHARACTERISTICS:

HEIGHT: 142 ft. (759)

TYPE OF ELEMENT: Triangular, uniform
cross-section, guyed,
base insulated, series
fed, top loaded to an
effective electrical
height of 82° (42)

GROUND SYSTEM: 120 equally spaced radials
consisting of #10 B&S bare
soft-drawn copper wire buried
approx. 8" in ground. The ra-
dials extend to a length of
at least 275 ft. (equivalent
to 0.4λ)

EXPECTED EFFICIENCY: 92.5 mV/m @ 1 mile for 0.25 KW
or
185 mV/m @ 1 mile for 1 KW.

NOTE: This notification concerns only a correction to
geographical coordinates and to provide details
of top loading.

Revised: December 31, 1968.

210° 150° 200° 160° 190° 170° 180° 160° 200° 150° 210° 1450 KHZ

DA-D

N A

220°
140°

230°
130°

240°
120°

250°
110°

260°
100°

270°
90°

280°
80°

290°
70°

300°
60°

310°
50°

320°
40°

140°
220°

130°
230°

120°
240°

110°
250°

100°
260°

90°
270°

80°
280°

70°
290°


60°
300°

50°
310°

40°
320°

200 600 MV/M 900

RMS 600 MV/M



CHUC COBOURG ONTARIO
HORIZONTAL DAYTIME
RADIATION PATTERN.


1450 KHZ. 10 KW. DA/2.
CLASS IV UNLIMITED.

D.B. Williamson P. Eng.
Consulting Engineer.
Calgary, Alberta.
20/1/81.

330° 30° 340° 20° 350° 10° 0 10° 350° 20° 340° 30° 330°

KEUFFEL & ESSER CO.

CHUC
1450KHz
DA-N



NIGHTIME RADIATION PATTERN

CHUC COBOURG, ONTARIO.

1450 Khz. 10 Kw. DA/2.

Class IV-U.

D.B. Williamson P. Eng.
Consulting Engineer.
Calgary, Alta. 3/3/81.

#175
Description Sheet
(2-26-63ct)

New Station
Causapsca1, Quebec

PM
250w, 1kw-LS, U, Class IV
1450 kc

Description Sheet - Omni-directional Antenna

Station Call : ~~WJ~~ CQBM

Main Studio : Transmitter at Causapsca1, Que., to be programmed
from CMA studios in Rimouski.

Frequency : 1450 kc

Power : 1 kw Day, 0.5 kw Night

Class : IV

Time : Day and Night

Identification List : 175

Date : December 21, 1963

Geographical Location
of Antenna System :

48 21 53
North Lat. 48° 1' 53"
West Long. 67° 14' 17"
67 14 17

Antenna Characteristics :

Height : 175 feet (5.3)

Type of Element : horizontal
cross-section

Ground System : 10 parallel wires,
each 175' (5.3 m) long,
in length,
No. 10 wire, twisted 1/2".

Expected Efficiency :

100 mV/m (all) - 100 mV
95 for 0.5 m


KVEN

PROPOSED DAY
(9-13-60g)

Station KVEN
Ventura, California


250w, 1kw-LS, DA-D,U
1450 KC

4-26-61
planed up to
increase power
initially
over
H 203
10-30-60
planed 2 for
DAD and 1 KW



S = 110° = 208'
G = 122° = 230'
RMS = 200 MV/M

N. LAT. 34° 14' 50"
W. LONG. 119° 15' 45"



HORIZONTAL RADIATION PATTERN DAYTIME

UNATTENUATED FIELD INTENSITY
AT ONE MILE

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION KVEN
1450 KC, 0.25 KW, 1 KW-LS, DA-D, U
VENTURA, CALIFORNIA

600526

FIGURE 3

FCC File No. BP-13279
Accepted 9-7-60 (Amended)


KVEN
Ventura, California

1450 KC

Measured Day
(11-27-64ct)

Station KVEN
Ventura, California

KVEN
250w, 1kw-LS, DA-D, U
1450 kc



FCC File No. BL-10660
Accepted 10-27-64


Station KVEN
Ventura, California

1450 kc

Measured Non-DA
(11-27-64ct)

Station KVEN
Ventura, California

KVEN
250w, 1kw-LS, DA-D, U
1450 kc



FCC File No. BL-10660
Accepted 10-27-64

Station KVEN
Ventura, California

1450 kc

KYOR


Proposed Day
(7-28-66ct)

Station KYOR
Blythe, California

250w, 1kw-LS, DA-D, U
1450 kc

N 33° 37' 16"
W 114° 35' 28"

BP-17195
various
IP to include
day to date
power
4-14-67



MARCH 1966

OSCAR LEON CUELLAR, P.E.
CONSULTING ENGINEER
TUCSON, ARIZONA

PROPOSED KYOR OPERATION
1450 KC, 1 KW-D, 0.25 KW-N, DA-D
BLYTHE, CALIFORNIA
KYOR, INC.

FCC File No. BP-17195
Accepted 7-18-66

Station KYOR
Blythe, California

1450 kc


KYOR

Measured Day
(8-28-68ct)

Station KYOR
Blythe, California

250w, 1kw-LS, DA-D, U
1450 kc

BL 12034
Handed
131/69
license
looking
changes



FCC File No. BL-12034
Accepted 7-29-68

Station KYOR
Blythe, California

1450 kc


Measured Non-DA
(8-28-68ct)

Station KYOR
Blythe, California

250w, 1kw-LS, DA-D, U
1450 kc

KYOR

BL 12034
granted
1/31/67
license
covering
changes



FCC File No. BL-12034
Accepted 7-29-68

Station KYOR
Blythe, California

1450 kc

WKIP

Proposed Day
(5-28-68ct)


Station WKIP
Poughkeepsie, New York

250w, 1kw-LS, DA-D, U
1450 kc

*BP 18122
Amended
8/1/69
to change
to NON-DA*

LUCENE DIETZGEN CO.
MADE IN U. S. A.

NO. 341 P. DIETZGEN GRAPH PAPER
POLAR CO. COORDINATE



FCC File No. BP-18122
Accepted 5-23-68

Station WKIP
Poughkeepsie, New York

1450 kc

WKIP

Mesured Day
(4-20-66ct)

Station WKIP
Poughkeepsie, New York


250w, 1kw-LS, DA-D, U
1450 kc

LIC-5-23-66

1 USONE 1 7 DEN. CO.

APLH

NO. 341 P DIETZEN GRAY
POLAR CO-ORDINATE



FCC File No. BL-11241
Accepted 3-28-66

Station WKIP
Poughkeepsie, New York

1450 kc

WKIP

Measured Non-DA
(4-28-66ct)


Station WKIP
Poughkeepsie, New York
NORTH

250w, 1kw-LS, DA=D, U
1450 kc

4105-23-66

EUGENE J. ZIGEN CO.
NEW YORK, N.Y.

NO. 341-P DIETZEN DRAI
APER POLAR CO-ORDINATE



FCC File No. BL-11241
Accepted 3-28-66

Station WKIP
poughkeepsie, New York

1450 kc

Description Sheet
(6-27-69ct)

New Station
Jasper, Alberta

100w, U, Class IV
1450 kc

PROJECT #5907

DESCRIPTION SHEET - OMNIDIRECTIONAL ANTENNA

STATION CALL: NEW
TRANSMITTER SITE: JASPER, ALBERTA
MAIN STUDIO: EDSON, ALBERTA
FREQUENCY: 1450 kHz
POWER: 100 Watts
TIME: U
NOTIFICATION LIST: #256 DATE: May 16, 1969

GEOGRAPHICAL LOCATION:

Latitude: 52° 52' 51" North
Longitude: 118° 04' 26" West

ANTENNA CHARACTERISTICS:

Height above the base insulator: 80 feet, top-loaded
to an equivalent electrical height of 60°

Height above ground: 83 feet

Type of Element: A guyed steel tower, uniform
cross-section, base insulated for series feed

Ground System: 120 equally spaced radials of
#10 B & S gauge bare soft copper wire buried approx-
imately 8", extend from the base of the tower to the
property boundary. The radial lengths vary from 60'
to 160' in length.

EXPECTED EFFICIENCY: 47.5 mV/m at 1 mile for 100 Watts

D. E. M. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS