

1480-1500

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
NEW	Edmonton, AB	1480	10 kW/DA-1	12/27/79
CHRD	Drummondville, QU	1480	10 kW/DA-2	6/24/76
CHRD	Drummondville, QU	1480	50/35 kW/DA-2	7/10/79
CKAN	Newmarket, ON	1480	10 kW/DA-N	9/23/77
KAPE	San Antonio, TX	1480	0.5 kW/DA-D	7/1/77
KAUS	Austin, MN	1480	1 kW/DA-2	4/29/70
KHEA	Mission, KS	1480	1 kW/DA-D	5/29/58
KHEA	Mission, KS	1480	0.5/1 kW/DA-2	6/14/61
KMEZ	Dallas, TX	1480	1/5 kW/DA-2	4/9/75
KEHG	Fosston, MN	1480	2.5/5 kW/DA-N	10/26/79
KG CX	Sidney, MT	1480	5 kW/DA-1	7/11/49
KLEO	Wichita, KS	1480	1/5 kW/DA-2	6/29/70
KLMS	Lincoln, NE	1480	1 kW/DA-2	6/14/61
KLMS	Lincoln, NE	1480	1/2.5 kW/DA-D	10/26/79
KLMS	Lincoln, NE	1480	0.5/1 kW/DA-N	10/1/52
KOOD	Lakewood, WA	1480	1 kW/DA-D	3/23/59
KPIA	Ironton, MO	1480	5 kW/DA-D	3/14/74
KPUB	Pueblo, CO	1480	1 kW/DA-D	2/11/58
KVAN	Vancouver, WA	1480	5/1 kW/DA-N	8/24/76
KWEW	Hobbs, NM	1480	1 kW/DA-N	1/21/55
KWEW	Hobbs, NM	1480	1/5 kW/DA-N	8/24/76
KWIZ	Santa Ana, CA	1480	5 kW/DA-2	11/16/79
KWIZ	Santa Ana, CA	1480	1/5 kW/DA-2	1/24/62
KWUN	Concord, CA	1480	0.5 kW/DA-2	11/16/79
KYOS	Merced, CA	1480	5 kW/DA-N	4/1/48
WABB	Mobile, AL	1480	5 kW/DA-N	7/16/75
WAME	Charlotte, NC	1480	5 kW/DA-2	5/27/60

1480-1500

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WCIN	Cincinnati, OH	1480	0.5/5 kW/DA-2	11/27/74
WDAS	Philadelphia, PA	1480	1/5 kW/DA-2	7/26/61
WGSB	Geneva, IL	1480	0.5/1 kW/DA-2	6/14/61
WHBC	Canton, OH	1480	5 kW/DA-N	4/25/46
WHOM	New York, NY	1480	5 kW/DA-2	12/28/67
WIOS	Tawas City-E.Tawas, MI	1480	1/5 kW/DA-2	12/27/68
WISL	Shamokin, PA	1480	1 kW/DA-N	2/10/48
WISM	Madison, WI	1480	5 kW/DA-2	5/8/74
WISM	Madison, WI	1480	1/5 kW/DA-2	7/19/57
WJBM	Jerseyville, IL	1480	0.5 kW/DA-D	4/29/69
WKND	Windsor, CT	1480	0.5 kW/DA-D	7/26/61
WLEE	Richmond, VA	1480	5 kW/DA-2	6/12/74
WRDW	Augusta, GA	1480	5 kW/DA-N	11/42
WRSW	Warsaw, IN	1480	0.5/1 kW/DA-2	5/8/61
WSAR	Fall River, MA	1480	5 kW/DA-1	7/20/77
WSDS	Ypsilanti, MI	1480	0.5 kW/DA-D	8/24/62
WTHI	Terre Haute, IN	1480	1/5 kW/DA-2	1/22/71
WVCF	Windermere, FL	1480	5 kW/DA-D	4/28/65
WYDK	Yadkinville, NC	1480	1 kW/DA-D	12/29/66
NEW	Winchester, VA	1480	0.5 kW/DA-D	6/14/61
NEW	Gravehurst, ON	1490	1/0.25 kW	7/5/83
CBAM	Edmundston, NB	1490	0.10 kW	12/29/52
CFRC	Kingston, ON	1490	0.10 kW	12/18/52
CFWB	Campbell River, BC	1490	1/0.25 kW	9/28/67
CHYM	Kitchener, ON	1490	5/10 kW/DA-2	7/27/65
CKAD	Wilmot Station, NS	1490	1/0.25 kW	1/5/62

1480-1500

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
CKBM	Montmagny, QU	1490	0.25/1 kW	10/28/53
CKEN	Kentville, NS	1490	1/0.5 kW/DA-1	8/23/68
WNUS	West Springfield, MA	1490	0.25/1 kW/DA-D	4/22/59
WOHI	Easter Liverpool, OH	1490	0.25/0.5 kW/DA-D	2/2/59
WOLF	Syracuse, NY	1490	0.25/1 kW/DA-D	4/30/63
WVEC	Hampton, VA	1490	0.25 kW	8/16/55
NEW	St. Catherines, ON	1500	1 kW/DA-D	1/28/65
CKAY	Duncan, BC	1500	5/1 kW/DA-2	8/8/72
CKAY	Duncan, BC	1500	10/1 kW/DA-2	3/28/79
NEW	Dallas, GA	1500	1/0.5 kW/DA-D	11/2/79
KANI	Wharton, TX	1500	0.5 kW/DA-1	8/8/59
KOKN	Pawhuska, OK	1500	5 kW/DA-D	11/29/65
KROQ	Burbank, CA	1500	1/10 kW/DA-2	2/28/68
KSTP	St. Paul, MN	1500	50 kW/DA-2	8/27/65
KTXO	Sherman, TX	1500	1 kW/DA-D	6/28/67
KXRX	San Jose, CA	1500	5/10 kW/DA-2	6/28/65
KXRX	San Jose, CA	1500	1/10 kW/DA-2	3/26/58
WAKE	Valparaiso, IN	1500	1 kW/DA-D	8/28/68
WBRI	Indianapolis, IN	1500	10 kW/DA-D	3/28/60
WBRI	Indianapolis, IN	1500	5 kW/DA-D	10/26/62
WDEE	Detroit, MI	1500	5/50 kW/DA-2	8/29/60
WDEE	Detroit, MI	1500	1/10 kW/DA-2	3/30/63
WFIF	Milford, CT	1500	5 kW/DA-D	2/28/69
WGFT	Youngstown, OH	1500	0.5 kW/DA-D	10/29/75
WGFT	Youngstown, OH	1500	0.5/0.25 kW/DA-2	2/28/67
WKAX	Russellville, AL	1500	1 kW/DA-D	7/29/68
WKBX	Winston-Salem, NC	1500	10/1 kW/DA-2	2/22/71

1480-1500

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WKBX	Winston-Salem, NC	1500	1 kW/DA-D	7/26/61
WKER	Pompton Lakes, NJ	1500	1 kW/DA-D	2/22/71
WKER	Pompton Lakes, NJ	1500	0.5 kW/DA-D	3/30/63
WKIZ	Key West, FL	1500	0.25 kW/DA-1	1/30/67
WTOP	Washington, DC	1500	50 kW/DA-2	2/7/57
WVOC	Battle Creek, MI	1500	1 kW/DA-D	1/28/66
WZBN	Zion, IL	1500	0.25 kW/DA-D	5/25/62
NEW	Ellwood City, PA	1500	0.25 kW/DA-D	6/28/67
NEW	Marion-Jonesboro, IN	1500	5/0.5 kW/DA-2	7/12/61
XEMS	Matamoros, Tamaulipas	1500	1 kW/DA-1	8/27/65
XERH	Mexico, DF	1500	20 kW/DA-N	4/15/53

TABLE 1

ANTENNA DESCRIPTION SHEET

STATION CALL: NEW
 STUDIO LOCATION: EDMONTON, ALBERTA
 FREQUENCY: 1480 kHz
 POWER: 10 kW
 CLASS: III
 MODE: DA-1
 TIME: UNLIMITED

NOTIFICATION LIST NO.: 293.. DATE: ..December, 27, 1979

GEOGRAPHICAL LOCATION: Latitude: 53° 23' 40" North
 Longitude: 113° 26' 08" West

ARRAY CHARACTERISTICS: Three guyed steel towers of uniform cross section; base insulated; series fed; no top loading.

	TOWER NUMBER: 1 NORTH	2 CENTRE	3 SOUTH
OVERALL HEIGHT:	185'	385'	185'
HEIGHT ABOVE BASE INSULATOR:	97.5° (180')	205.9° (380')	97.5° (180')
SPACING:	reference	150° (276.9')	301.6° (556.6')
TRUE BEARING:	reference	170°	172.8°
FIELD RATIO:	0.43	1	0.47
PHASE ANGLE	-67°	0°	79°


GROUND SYSTEM: 120 equally spaced radials per tower of #10 AWG soft drawn bare copper buried 6" to 18" deep where possible, of length 266' (0.4λ) excluding those along common chord.

PREDICTED EFFICIENCY: 717.09 mV/m (226.76 mV/m for 1 kW)
 (UNATTENUATED FIELD AT ONE MILE)

NEW



UNITED STATES OF AMERICA
FEDERAL BUREAU OF INVESTIGATION

UNITED STATES OF AMERICA
FEDERAL BUREAU OF INVESTIGATION



NEW-AM EDMONTON, ALBERTA
PROPOSED
10 kW DA-1 1480 kHz
HORIZONTAL RADIATION PATTERN
E.E.L. Rev. DECEMBER 1979

FIGURE 2-1



VERTICAL RADIATION PATTERNS



NEW EDMONTON, ALBERTA
 10 kW DA-1 1480 kHz Class III
 E.E.L. DEC. 1979

CLEVELAND INSTITUTE OF RADIO ELECTRONICS
 CLEVELAND, OHIO

NO. 10 LV

POLAR CO-ORDINATE
 MADE IN U.S.A.

FIGURE 2-2



VERTICAL RADIATION PATTERNS

NEW EDMONTON, ALBERTA

10 KW DA-1 1480 kHz Class III

E.E.L.

DEC. 1979


CLEVELAND INSTITUTE OF RADIO ELECTRONICS
CLEVELAND, OHIO

NO. 10 LV

POLAR CO-ORDINATE
MADE IN U.S.A.

NEW

FIGURE 2-3



CLEVELAND INSTITUTE OF RADIO ELECTRONICS
CLEVELAND, OHIO

NO. 10 LV

POLAR CO-ORDINATE
MADE IN U.S.A.

CHRD

SUPPLEMENTAL DIRECTIONAL

ANTENNA DESCRIPTION SHEET

Station: CHRD

Location: Drummondville, Quebec

Frequency: 1480 kHz

Power: 10 kw, Class: 111

Notification List No: 357

Date: June 24, 1976

Geographical Location of the
Center of the Antenna System:

North Latitude: 45° 47' 47"

West Longitude: 72° 29' 04"

Mode of Operation - DA-2

Note: Please retain the description sheet and directional antenna radiation patterns notified for station CHRD in Canadian Change List Number 215 dated July 8, 1966 and attached to this supplemental description sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates.

Description Sheet
(1-30-67ct)

Station CHRD
Drummondville, Quebec

10kw, DA-2, U, Class III.
1480 kc

DESCRIPTION OF ARRAY

ATTN: CHFD

STUDIO: DRUMMONDVILLE, QUE.

FREQUENCY: 1480 KHz

POWER: 10Kw - DA-2

CLASSIFICATION LIST NO: 215

CLASS: III

Date: **July 8, 1966**

GEOGRAPHICAL COORDINATES OF ARRAY:

North Latitude	45°	47'	08"
West Longitude	72°	29'	12"

CHARACTERISTICS OF ARRAY

Mode of operation: 100W, Different patterns day and night

Number of elements: Four (4)

Type of Radiators: Guyed steel towers, uniform cross section base insulated for series feed, no top loading.

ATTENZIONE No.1 (c) No.2(n) No.3 (s) No.4 (w)

HEIGHT ABOVE INSULATOR 90° 90° 90° 90° (166')

OVERALL HEIGHT	169'	169'	169'	169'
----------------	------	------	------	------

FIELD RATIO	Day	reference	.5	.5
	Night	reference	.5	0

PLANNING	Day	reference	+155°	+69°
	Night	reference -103°	+103°	

SP. 1010 reference 90° 90° 90° (166°)

ORIENTATION reference 205° 265°

GROUND SYSTEM Equiangularly spaced radials of solid no.10
B & S copper wire extending from the base
of each tower to a common chord or to 0.4
wavelength

PREDICTED EFFECTIVE FIELD


600 MV/M at 1 mile for 10KW
190 MV/M at 1 mile for 1 KW

CHRD

Proposed Day
(1-30-67ct)

Station CHRD
Drummondville, Quebec

10kw, DA-2, U, Class III
1480 kc




CHRD

Proposed Night
(8-26-66ct)

Station CHRD
Drummondville, Quebec,

10kw, DA-2, U, Class III
1480 kc



359-31
POLAR CO-ORDINATE
KUPPERS & PERRY CO.
30

PROJET D'INSTALLATION D'UNE STATION RADIO AM

1. LETTRES D'ADRESSE: CHRD.
2. EMPLACEMENT: Orionville, Q.6.
3. FREQUENCE: 1430 KHz.
4. PUISSANCE: 50 KW de jour et 35 KW de nuit.
5. CLASSE: III (U).
6. NOTIFICATION NO: 387 DATE: July 10, 1979
7. COORDONNEES: Latitude nord: $45^{\circ} 47' 47''$
Longitude ouest: $72^{\circ} 29' 04''$
8. SYSTEME D'ANTENNE:
 - a) Fonctionnement: directionnel AD-2.
 - b) Type: quatre (4) éléments à section uniforme, haubanés et alimentés en série.
 - c) Mise à la terre: 120 fils #10 par élément, espacés également, d'une longueur max. de 266' (0.4A) avec courroies d'interconnexion, le tout enfoui à environ 3 pouces sous la surface.
9. DATS D'ANTENNE:

	#1 (C)	#2 (H)	#3 (S)	#4 (O)
Orientation (Az):	Ref.	25°	205°	265°
Hauteur au-dessus de l'isolateur:	166'	166'	166'	166' (90')
Espacement:	Ref.	166' (90')	166' (90')	166' (90')
Phasage:				
Jour:	0.0	-	+134.0	+71.0
Nuit:	0.0	-105.0	+105.0	-
Rapport l'intensité de champ:				
Jour:	1.000	-	0.510	0.410
Nuit:	1.000	0.501	0.501	-
10. EFFICACITE PREVUE:
 - a) Jour: 1343.3 mV/m à 1 mille pour 50 kW.
199.0 mV/m à 1 mille pour 1 kW.
 - b) Nuit: 1124.1 mV/m à 1 mille pour 35 kW.
199.0 mV/m à 1 mille pour 1 kW.

Q = 10 mV/m

YVES R. HAMEL
INGENIEUR-CONSEIL

22/7/77

22/7/77

Please retain the radiation patterns notified for CHRD Drumondville, Quebec on Canadian Change List No. 379 dated December 8, 1978. This notification involves only a change to the reduced quadrature factor Q associated with the night-time radiation pattern. The change is consistent with the control system which has been designed for optimum pattern stability.


I - DESCRIPTION DU SYSTEME A ANTENNE DIRECTIONNELLE


1. LETTRES D'APPEL: CHRD.
2. EMPLACEMENT: Drummondville, Qué.
3. FREQUENCE: 1480 KHz.
4. PUISSANCE: 50 KW de jour et 35 KI de nuit.
5. CLASSE: III (U).
6. NOTIFICATION NO: 379 DATE: December 8, 1978
7. COORDONNEES: Latitude nord: 45° 47' 47"
Longitude ouest: 72° 29' 04"
8. SYSTEME D'ANTENNE:
 - a) Fonctionnement: directionnel AD-2.
 - b) Type: quatre (4) éléments à section uniforme, haubanés et alimentés en série.
 - c) Mise à la terre: 120 fils #10 par élément, espacés également, d'une longueur max. de 266' (0.4λ) avec courroies d'interconnexion, le tout enfoui à environ 3 pouces sous la surface.
9. DATS D'ANTENNE:

	#1 (C)	#2 (H)	#3 (S)	#4 (O)
Orientation (Az):	Réf.	25°	205°	265°
Hauteur au-dessus de l'isolateur:	166'	166'	166'	166' (90°)
Espacement:	Réf.	166' (90°)	166' (90°)	166' (90°)
Phasage:				
Jour:	0.0°	-	+134.0°	+71.0°
Nuit:	0.0°	-195.0°	+195.0°	-
Rapport d'intensité de champ:				
Jour:	1.000	-	0.510	0.410
Nuit:	1.000	0.501	0.501	-
10. EFFICACITE PREVUE:
 - a) Jour: 1343.3 mV/m à 1 mille pour 50 KI.
199.3 mV/m à 1 mille pour 1 KI.
 - b) Nuit: 1124.1 mV/m à 1 mille pour 35 KI.
199.0 mV/m à 1 mille pour 1 KI.
Q= 18 mV/m

YVES R. HAMEL
INGENIEUR-CONSEIL

YRH








FIGURE #3
 PATRON DIRECTIONNEL DE NUIT - PLAN VERTICAL
 Az 163.55°, 163.71°, 164.09° et 164.61°

POSTE COMMERCIAL RADIOPHONIQUE 12A
 CHRD, DRUMMONDVILLE, QUE.
 CLASSE III 50 KW J / 35 KW N AD-2 1400 KHz

RADIO DRUMMOND LTEE

YVES R. HAVEL
 INGÉNIEUR-CONSEIL

CHP




FIGURE #4
PATRON DIRECTIONNEL DE NUIT - PLAN VERTICAL
Az 191.79°, 193.39°, 194.25° et 194.96°

POSTE COMMERCIAL RADIO-TELEPHONIQUE HA
CHRO. DEPUY-BOUVILLE, QUE.
CLASSE III 50 KI J / 35 KW H AD-2 1400 KHz

1947

130

120

110

100

90

80

70

60

50

40

30

20

10

Az 199.95°

Az 211.69°

Az 270.31°

Az 235.41°

WQAS

WASL

WQAS

WQBC

40

30

20

10

0

10

20

30

40

50

600

400

200

100

50

25

12.5

6.25

3.125

1.5625

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

600

400

200

100

50

25

12.5

6.25

1000

800

Az 25.00°
Max.

500 1000 1500 2000 mV/m

FIGURE #7
PATRON DIRECTIONNEL DE NUIT - PLAN VERTICAL
Az 25.00° (max.)

POSTE COMMERCIAL RADIOPHONIQUE N°

CHRD, DRETONVILLE, QUE.

CLASSE III 50 kW J / 35 kW N A2-2 1480 KHZ

RADIO DROMOND LTÉE

YVES R. HAMEL

INGENIEUR-CONSEIL

22/9/81

Y.R.H.

140°
120°

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2

STATION CALL: CKAN

LOCATION:

Newmarket, Ontario.

FREQUENCY:

1480 kc/s

POWER:

10,000 watts

CLASS:

III

TIME:

Unlimited

NOTIFICATION REFERENCE: 367

DATE: September 23, 1977

GEOGRAPHICAL COORDINATES:

Lat 43°57'28", Lon 79°26'44"

ARRAY CHARACTERISTICS:

Six elements, guyed, uniform
cross section, base insulated,
series feed, no top loading,
Height 166.3 feet or 90 degrees

Spacing	1-2, 2-3, 4-5, 5-6, =	90 degrees or 166.3'
	1-6, 2-5, 3-4, =	176 degrees or 325.1'
Bearing	1-2-3, 6-5-4, =	00 degrees
	1-6, 2-5, 3-4, =	95 degrees


ELEMENT	Day R	Day ϕ	Night R	Night ϕ
One	1.000	00.00°	0.800.	00.00°
Two	1.178	-101.0	1.310	-113.36
Three	0.360	+158.0	0.540	+132.00
Four	0.306	+168.0	0.675	+137.00
Five	1.001	-91.0	1.638	-108.36
Six	0.850	+10.0	1.000	+05.00

Ground System 120 radials per tower, #10 AWG bare, soft
copper wire, spaced uniformly, depth 8
inches approximately. Radials bonded on
lines between towers and bonded to soft
copper strap at towers bases. Maximum
length 266 feet.

Predicted RMS 600.8 mv/m at 1 mile for 10 kw
190.0 mv/m at 1 mile for 1 kw

NO. 340-B DITZEL'S GRAPH PAPER
POLAR CO-ORDINATE
MADE IN U.S.A.


RYAN





HORIZONTAL DAYTIME PATTERN
 10 km DA-2 1480 kc III
 George Nathan, P. Eng
 Jan 1976 # 6-1

MADE IN U. S. A.

POLAR CO-ORDINATE



HORIZONTAL NIGHT PATTERN
NEWMARKET, ONTARIO
10 Kw. DA-2 1480. Kc III
George Hather, P. Eng
Jan 1976 # 6-2




VERTICAL RADIATION PATTERNS

NEWMARKET, ONTARIO
10 kw DA-2 1480 kc III
George Mather, P.Eng.

Jan 1976

7-1

359.91
SEMI-LOGARITHMIC
NEWELL ESSER CO. MADE IN U.S.A.



NIGHTTIME PATTERN SECTIONS
NEWMARKET, ONTARIO
10 kw DA-2 1480 kc III
George Mather, P.Eng.
Jan 1976 # 7-2

CRAN

mV/m

25°

30°

35°

40°

NIGHTTIME PATTERN SECTIONS
 BEXMARKE, CRANIO
 10 kw DA-2 1430 No III
 George Rother, P.Eng
 Jan 1976 # 7-3

Bearing

125° 150° 175° 200° 225° 250°

1005 SEMI-LOGARTHMIC 359-91
 KROFFTS & CO. LTD.
 1005 SEMI-LOGARTHMIC 359-91

CKAN ✓

SUPPLEMENTAL DIRECTIONAL
ANTENNA DESCRIPTION SHEET

Station: CKAN

Main Studio: Newmarket, Ontario

Frequency: 1480 kHz

Power: 10 kW Class: TXX

Notification List No.: 380

Date: December 27, 1978

Geographical Location of the
Center of the Antenna System:

North Latitude: 43° 57' 28"

West Longitude: 79° 26' 53"

Mode of Operation: DA-2

Note: Please retain the description sheet and directional antenna radiation patterns notified for station CKAN. In Canadian Change List Number 367 dated September 23, 1977 and attach to this supplemental description sheet. This notification is for the purpose of indicating only a correction in the geographical co-ordinates.

SUPPLEMENTAL DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KAPE

Main Studio: San Antonio, Texas

Frequency: 1480 kHz

Power: 0.5 kW

Notification List No. 1739

Date: July 1, 1977

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM

North Latitude: 29° 24' 43"

West Longitude: 98° 24' 50"

Authorized for Daytime operation (DA-D).

Towers are top loaded by uppermost 40' sections of guy wires to an effective electrical height of 80 degrees.

Note: Please retain the description sheet and directional antenna radiation patterns notified for a new station at San Antonio, Texas in United States Change List Number 822, dated August 3, 1959, and attach to this supplemental Description Sheet. This notification is for the purpose of indicating changes in the geographical coordinates of the center of the antenna system and to add top loading.

San Antonio, Texas


KAPE

PROPOSED DAY
(10-24-58g)

New; Top Broadcasters, Inc.
San Antonio, Texas

500w, DA-D,D
1480 KC

*granted up for new station
9-2-59*



HORIZONTAL RADIATION PATTERN

NL 29° 04' 42"
WL 98° 24' 51"

ANTENNA PLACEMENT SKETCH

DIRECTIONAL ANTENNA PARAMETERS

STATION New
FREQUENCY 1480 KC

LOCATION San Antonio, Texas
RATED POWER 0.5 KW

Antenna No.	True Bearing	Spacing	Phasing	Field Ratio	Horizontal Field Intensity	Electrical Height
1	61°	80°	0°	1.00	127 MV/M	65°
2	241°	80°	-103°	0.95	120.6 MV/M	65°

KENNETH R HYMAN
RADIO ENGINEER

PATTERN NO 580805.1

EXHIBIT NO 11-B

FCC File No. BP-12,321
Accepted 9-29-58

Top Broadcasters, Incorporated
San Antonio, Texas

1480 KC

*11/24/58 to make changes in
antenna system
height 121' / 126' small*


11-4-60 granted
 for new station
 MEASURED DAY
 (7-7-60g)

KAPE

Station KAPE
 San Antonio, Texas

500w., DA-D,D

1480 KC



HORIZONTAL RADIATION PATTERN

ANTENNA PLACEMENT SKETCH PATTERN NO. 600526	DIRECTIONAL ANTENNA PARAMETERS						
	STATION <u>New</u>			LOCATION <u>San Antonio, Texas</u>			
	FREQUENCY <u>1480 KC</u>			RATED POWER <u>0.5 KW</u>			
	Antenna No.	True Bearing	Spacing	Phasing	Field Ratio	Horizontal Field Intensity	Electrical Height
1	61°	80°	0	1.00	126 MV/M	60°	
2	241°	80°	180°	.92		Plus 15° Top Load	

PATTERN NO. 600526


KENNETH A HYMAN
 RADIO ENGINEER
 SAN ANTONIO, TEXA

FCC File No. BL-7955
 Accepted 7-1-60

KAPE
 San Antonio, Texas

1480 KC

KAPE

MEASURED NON-DA
(7-7-60g)Station KAPE
San Antonio, Texas500w, DA-D,D
1480 KC


NON-DIRECTIONAL HORIZONTAL RADIATION PATTERN

ANTENNA PLACEMENT SKETCH	DIRECTIONAL ANTENNA PARAMETERS						
	STATION <u>New</u>			LOCATION <u>San Antonio, Texas</u>			
	FREQUENCY <u>1480 KC</u>			RATED POWER <u>0.5 KW</u>			
	Antenna No.	True Bearing	Spacing	Phasing	Field Ratio	Horizontal Field Intensity	Electrical Height
	1	61°	90°	0	1.00	126 MV/M	60°
	2	241°	80°	-22°	.92		Plus 15° Top Loading

KENNETH A HYMAN
RADIO ENGINEER
SAN ANTONIO, TEXAFCC File No. BL-7955
Accepted 7-1-60KAPE
San Antonio, Texas

1480 KC


RAYMOND M. WILMOTTE INC.
Engineers and Consultants
Washington, D.C.



KAUS

1kw, DA-2, U


1480 kc

Measured Day
(4-29-70ct)Station KAUS
Austin, Minnesota

PATTERN NO. 470424
SUPERSEDES 460606
REINSTATES:

RAYMOND M. WILMOTTE INC
Engineers and Consultants
Washington, D.C.

NL 43° 37' 20"
WL 92° 59' 22"




KAUS

Measured Night
(4-29-70ct)

Station KAUS
Austin, Minnesota

1kw, DA-2, U
1480 kc



FCC File No. BL-12568
Accepted 4-2-70

Station KAUS
Austin, Minnesota


1480 kc

KAUS

Measured Non-DA
(4-29-70ct)

Station KAUS
Austin, Minnesota

1kw, DA-2, U
1480 kc



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT: FEDERAL BROADCASTING COMMISSION
 LOCATION: AUSTIN, MINN. STATION KAUS
 FREQUENCY: 1480 KC/S
 POWER: 1 KW
 LATITUDE: 43° 05' N
 LONGITUDE: 93° 05' W
 WHEN USED: FOR FIELD SURVEY
 RMS FIELD: 200 M/M
 DATE: 4-29-70

SILLIMAN, MOFFET & KOWALSKI
 CONSULTING RADIO ENGINEERS
 WASHINGTON, D.C.

FCC File No. BL-12568
 Accepted 4-2-70

Station KAUS
 Austin, Minnesota

1480 kc


PROPOSED DAY
(5-29-58g)

Station KBKC
Mission, Kansas

1kw, DA-D,D
1480 KC

KFEA
KHEA

granted CP
12/17/58 for
increase in
power
granted 10-2-59
for increase in power




FCC File No. BP-11,984
Accepted 5-20-58

KBKC
Mission, Kansas

1480 KC

KBEA

MEASURED
DAYTIME HORIZONTAL PLANE PATTERN
RADIO STATION KBEA
MISSION, KANSAS
1440 KHZ. 1 M.-D, 500 W.-N, DA-2





~~KBEA~~
KHEA

PROPOSED NIGHT
(6-14-61g)

Station KBEA
Mission, Kansas

500w, 1kw-LS, DA-2, U
1480 KC

162
Ed CP to
to DA-2



CREUTZ, STEEL & SNOWBERGER
Consulting Engineers
1111 K STREET, N.W.
WASHINGTON, D. C.

FIGURE 7
CALCULATED NIGHTTIME HORIZONTAL
PLANE PATTERN
RADIO STATION KBKC, INC.
KBEA MISSION, KANSAS
1480KC, 0.5KW, 1KW-LS, U, DA-2
JANUARY 1961

FCC File No. BP-14854
Accepted 6-13-61


KBEA
Mission, Kansas

1480 KC

BZ-9568

JOHN B. THEFFELFINGER
Consulting Communications Engineer
9208 WYOMING PLACE
KANSAS CITY, MISSOURI 64114

MEASURED
NIGHTTIME HORIZONTAL PLANE PATTERN
RADIO STATION KBFA
MISSION, KANSAS
14.1 MHz 1 kW-D, 50.0 W-E, DA-2



~~KBOX~~
RINEZ

Main Studio: Dallas, Texas

Power: 1 kW Night 5 kW Day

Date: April 9, 1975

Class: III

North Latitude: 32° 52' 15"
West Longitude: 96° 42' 54"

Authorized for Daytime and Nighttime operation. (DA-2)

Type of elements: Series-excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	NW(#1)	N(#2)	SW(#3)	SE(#4)	C(#5)	E(#6)
HEIGHT ABOVE INSULATORS:	120'	120'	120'	120' (65°)	128'	128' (69.3°)
NIGHT PHASING:	0°	+135°	+94°	+209°	---	---
NIGHT FIELD RATIO:	1	1.45	0.642	0.9	---	---
DAY PHASING:	---	---	---	---	-100°	0°
DAY FIELD RATIO	---	---	---	---	0.8	1

ORIENTATION: Nighttime towers #1 through #4 are located at the vertices of a parallelogram the long sides of which are 688.6' (373°) in length on a line bearing 129° true. The short sides are 166' (90°) in length on a line bearing 84° true.

Daytime towers #5 and #6 are spaced 184.6' (100°) on a line bearing 60° true.

GROUND SYSTEM: 120-166' equally spaced copper radials plus a 24' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

THEORETICAL

	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Daytime	413 mv/m	---	---
Nighttime	184.4 mv/m	224.2 mv/m	193.9 mv/m

STANDARD

RMS

193.9 mV/m

(Cont'd.)

KBOX

2.


KBOX

Note: Please retain the Nighttime directional antenna radiation patterns notified for Station KBOX in United States Change List Number 1619, dated February 12, 1975, and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a correction to the orientation from tower #1 to tower #4 from 119.71° true to 120.71° true.


CTR NO 31197A6

KBOX
KMEZ

COHEN AND DIPPELL, P.
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D. C. 20004





32° 52' 15"
96° 42' 54"



HORIZONTAL PLANE RADIATION PATTERN
FOR THE PROPOSED DAYTIME OPERATION OF
KBOX, DALLAS, TEXAS
1480 KHz - 1/5 KW - DA-2 U
APRIL 1975

KBOX
KMEZ

COHEN AND DIPPELL, P.C.
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D. C. 20004



RSS /RMS = 1.22
th th
RSS = 224.2 MV/M
th
RMS = 184.4 MV/M
th
RMS = 193.9 MV/M
std
2 OHM LOSS USED

STANDARD RADIATION PATTERN
HORIZONTAL PLANE
FOR THE PROPOSED NIGHTTIME OPERATION
KBOX, DALLAS, TEXAS
1480 KHz 1/5 KW DA-2 U
AUGUST 1974

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KEHG Main Studio: Fosston, Minnesota
 Frequency : 1480 KHz Power : 2.5 kW Night 5 kW Day
 Notification: 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE

CENTER OF THE ANTENNA SYSTEM: North Latitude: 47 ° 33 ' 44 "
 West Longitude: 95 ° 43 ' 30 "

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 3

Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER : N(#1) C(#2) S(#3)

HEIGHT ABOVE
 INSULATORS : 160(86.7°) 197'(106.7°) 160'(86.7°)

NIGHT PHASING : 0° 130° -99°

NIGHT FIELD RATIO: 1.0 1.84 0.9

SPACING AND
ORIENTATION:

Adjacent towers in a row are spaced 156.9 (85°) on a line
 bearing 203° true.

GROUND SYSTEM: 120 - 164' equally spaced copper radials plus 120 - 50'
 interspaced radials about each tower. Radials are
 shortened and bonded to transverse strap along intersec-
 tions between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD	
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>	
Day	440.5 mV/m			mV/m
Night	328.8 mV/m	439.9 mV/m	345.4 mV/m	

Note:

KEHG
KEHG RADIO, INC.
1480 kHz 5 kW-D 2.5 kW-N DA-N
FOSSTON, MINNESOTA
JUNE 1976

EXHIBIT E-6.01A

PROPOSED NIGHTTIME DIRECTIONAL
HORIZONTAL RADIATION PATTERN


UNATTENUATED FIELD AT 1000 WATTS

NIGHTTIME STANDARD PATTERN

ELECTRICAL DESCRIPTION

Power = 2500 Watts
 $G_{1,3} = 86.7^\circ$
 $G_2 = 106.7^\circ$
K = 193 mV/m
Th. RMS = 328.8 mV/m
RSS = 439.9 mV/m
 $Q(\theta) = 10.998 \text{ mV/m}$
Std. RMS = 345.4 mV/m

760617




NL: 47° 33' 44"
WL: 95° 43' 30"

1/0° 1.84/130° 0.9/-99°
#1 — S — #2 — S — #3 — 203°T
S = 85° $G_2 = 106.7^\circ$ $G_{1,3} = 86.7^\circ$

VIR JAMES
CONSULTING RADIO ENGINEERS
345 COLORADO BLVD • DENVER, CO • 80206
Phone: (303) 333-3562



EXHIBIT E-602A



PROPOSED NIGHTTIME DIRECTIONAL
EXPANDED HORIZONTAL PATTERN
UNATTENUATED FIELD AT ONE MILE

NIGHTTIME STANDARD PATTERN

K E H G
KEHG RADIO, INC.
1480 KHz 5 kW-D 2.5 kW-N DA-N
FOSSTON, MINNESOTA
JUNE 1976

KGCK

KLMs

KAUS

WISM

WHBC

WGSB

TOWER LINE

TOWER LINE

VIR JAMES
CONSULTING RADIO ENGINEERS
345 COLORADO BLVD - DENVER, CO - 80206
PHONE (303) 323-5562



KGCX


PROPOSED
NIGHT & DAY

KGCX, SIDNEY, MONT.

5kw, DA-1

1480 kc

7/11/49G



RMS = 450 MV/M

CALCULATED

MAXIMUM EXPECTED

PATTERN NO. 490603

LATITUDE: 47° 46' 26"

LONGITUDE: 104° 6' 54"

ROTHROCK & BAIREY

Consulting Radio Engineers
WASHINGTON, D. C.

S = 80° G = 175° - 95°

1 182° TRUE 2

TOWER	FIELD	ψ
1	.8	0°
2	1.0	+135°

FIGURE No. 2A
(Revised)

RADIO STATION KGCX
E. E. KRESSBACH
SIDNEY, MONTANA

Proposed 1480KC - 5KW - DA-1

HORIZONTAL PLANE PATTERN


KGCX

PROPOSED
NIGHT&DAY NULLS

KGCX, SIDNEY, MONT.

5kw, DA-1

1480 kc



AMENDMENT FILED 7-1-49 BMP-4239

KGCX, Sidney, Mont. 1480 kc


KGCX

MEASURED
NIGHT & DAY

KGCX, SIDNEY, MONT.

5kw, DA-1

1480 kc



PATTERN NO. 491206 DP
 LATITUDE: 47° 46' 26"
 LONGITUDE: 104° 06' 54"

GEORGE B. BAIREY
 CONSULTING RADIO ENGINEER
 WASHINGTON, D. C.

TOWER	CURRENT	PHASE
1	5.7	0°
2	8.1	+139°

EXHIBIT NO 18

RADIO STATION KGCX
 SIDNEY, MONTANA
 1480 KC - 5 KW - DA-1

MEASURED DIRECTIONAL
 PATTERN



KGCX, Sidney, Mont. 1480 kc

SEE
REVERSE
SIDE

Proposed Day
(6-29-70ct)

Station KLEO
Wichita, Kansas

KLEO
1kw, 5kw-LS, DA-2, U
1480 kc



THEORETICAL PARAMETERS

TOWER	FIELD	PHASE
1	1.000	0.00°
2	0.600	-100.00°
3	0.400	50.00°
4	0.240	-50.00°
5	—	—

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KLEO
1480 KC 1 KW 5 KW-LS DA-2
660420.2A FIGURE 4B

FCC File No. BMP-13000
Accepted 6-1-70

Station KLEO
Wichita, Kansas



1480 kc

SEE
REVERSE
SIDE

Proposed Night
(6-29-70ct)

Station KLEO
Wichita, Kansas

KLEO
1kw, 5kw-LS, DA-2, U
1480 kc



THEORETICAL PARAMETERS

TOWER	FIELD	PHASE
1	1.000	0.00°
2	0.800	-111.00°
3	—	—
4	0.500	-4.00°
5	0.400	-115.00°

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS


RADIO STATION KLEO
1480 KC 1 KW 5 KW-LS DA-2
660420.3A
FIGURE 4B

FCC File No. BMP-13000
Accepted 6-1-70


Station KLEO
Wichita, Kansas

1480 kc

NIGHTTIME
DIRECTIONAL PATTERN
RMS = 182 mV/M



AT. $37^{\circ} 44' 21''$
LONG. $97^{\circ} 16' 14''$



$S_1 = 166.0' = 90^{\circ}$
 $S_2 = 394.8' = 214^{\circ}$
 $G = 166.0' = 90^{\circ}$


ANTENNA PARAMETERS

TOWER	THEORETICAL		INDICATED	
	FIELD	PHASE	FIELD	PHASE
1	1.000	0.00°	1.299	114.00°
2	0.800	-111.00°	1.000	0.00°
3	—	—	—	—
4	0.500	-4.00°	0.696	112.00°
5	0.400	-115.00°	0.537	-2.00°


PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KLEO
1480 kHz 1 kW 5 kW-LS DA-2
701220
FIGURE 2C

NON-DIRECTIONAL
PATTERN
RMS = 426 MV/M



LAT. $37^{\circ} 44' 21''$
LONG. $97^{\circ} 16' 14''$



TOWER

1
2
3
4
5


TEST OPERATION

DETUNED
DETUNED
SERIES FED
DETUNED
DETUNED


PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KLEO
1480 kHz 1 kW 5 kW-LS DA-2
701220
FIGURE 2A

DAYTIME
DIRECTIONAL PATTERN
RMS = 408 MV/M



LAT. $37^{\circ} 44' 21''$
LONG. $97^{\circ} 16' 14''$



$S_1 = 166.0' = 90^{\circ}$
 $S_2 = 245.5' = 133^{\circ}$
 $G = 166.0' = 90^{\circ}$

ANTENNA PARAMETERS

TOWER	THEORETICAL		INDICATED	
	FIELD	PHASE	FIELD	PHASE
1	1.000	0.00°	1.000	0.00°
2	0.600	-100.00°	0.537	-103.00°
3	0.400	50.00°	0.394	50.00°
4	0.240	-50.00°	0.254	-48.00°
5	—	—	—	—

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KLEO
1480 KHZ 1 KW 5 KW-LS DA-2
701220
FIGURE 2B


KLMS

LINCOLN, NEB

1480

9/7/48-60

P-4985



NO 140° DIEZSEN (MAGNETIC)
POLAR COORDINATE

PROPOSED DAY NULLS
(6-14-61g)

Station KLMS
Lincoln, Nebraska

1kw, DA-2, U
1480 KC




FIGURE 1-B

EXPANDED VIEW OF
KLMS HORIZONTAL PATTERN
WITH
AGREED UPON MEOV

SILLIMAN, MOFFET & COMPANY
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

KLMS

Measured Day
(12-19-61ct)

Station KLMS
Lincoln, Nebraska

1kw, DA-2, U
1480 kc

1-24-62
painted
overing changes
in daytime
directional
pattern.





FIGURE 1-C

HORIZONTAL RADIATION PATTERN



APPLICANT	KLMS RADIO TOWER CO.
LOCATION	LINCOLN, NEBRASKA
FREQUENCY	1480 KC
POWER	1 KW - STATION
LATITUDE	41 DEG 08 MIN 22 SEC
LONGITUDE	96 DEG 58 MIN 21 SEC
WHEN USED	(DATE)
R.M.S. FIELD	100 MV/M
DATE	SEPTEMBER 1961

SILLIMAN, MOFFET & ROHRER
CONSULTING ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-8835
Accepted 11-29-61

Station KLMS
Lincoln, Nebraska


1480 kc

KLMS

LINCOLN, NEBR.

9/7/4860

P-340 4985 330 1480



A=0 at 64°

Rotation clockwise $E = 206.5 \text{ f(v)} \sqrt{[1.031 + \cos(340 \cos A \cos V - 120)] \times [1 + \cos(90 \sin A \cos V + 130)]}$

Measured Night
(12-19-61ct)

Station KLMS
Lincoln, Nebraska

1kw, DA-2, U
1480 kc





FIGURE 1-B

HORIZONTAL RADIATION PATTERN



APPLICANT	LINCOLN BROADCASTING CORP.
LOCATION	LINCOLN, NEBRASKA
FREQUENCY	1480 KC/S
POWER	1 KW-DA-2
LATITUDE	40 DEG 45 MIN 27 SEC
LONGITUDE	96 DEG 36 MIN 27 SEC
WHEN USED	NIGHT ME
R.M.S. FIELD	176.0 MV/M
DATE	SEPTEMBER 1961

SILLIMAN, MOFFET & ROHRER
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-8835
Accepted 11-29-61


Station KLMS
Lincoln, Nebraska

1480 kc

Measured Non-DA
(12-19-61ct)

Station KLMS
Lincoln, Nebraska

1kw, DA-2, U
1480 kc



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT	LINCOLN BROADCAST NG CORP.
LOCATION	L. NEOLN, NEBRASKA
FREQUENCY	1480 KC/S
POWER	500 WATTS
LATITUDE	40 DEG 48 MIN 21 SEC
LONGITUDE	95 DEG 36 MIN 27 SEC
WHEN USED	NON-DIRECTIONAL SURVEY ONLY
RMS FIELD	134.1 MV/M
DATE	SEPTEMBER 1961

SILLIMAN, MOFFET & ROHRER
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-8835
Accepted 11-29-61

Station KLMS
Lincoln, Nebraska

1480 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KLMS Main Studio: Lincoln, Nebraska
 Frequency : 1480 KHz Power : 1 kW Night 2.5 kW Day
 Notification: 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE
 DAYTIME AND NIGHTTIME ANTENNA SYSTEMS:

DAYTIME			NIGHTTIME				
North Latitude:	<u>40°</u>	<u>47'</u>	<u>47"</u>	North Latitude:	<u>40°</u>	<u>48'</u>	<u>27"</u>
West Longitude:	<u>96°</u>	<u>34'</u>	<u>56"</u>	West Longitude:	<u>96°</u>	<u>36'</u>	<u>27"</u>

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 4

Type of elements : Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER	:	<u>E(#1)</u>	<u>EC(#2)</u>	<u>WC(#3)</u>	<u>W(#4)</u>	<u> </u>	<u> </u>
HEIGHT ABOVE INSULATORS	:	<u>190'</u>	<u>190'</u>	<u>190'</u>	<u>190'(105°)</u>	<u> </u>	<u> </u>
DAY PHASING	:	<u>0°</u>	<u>214°</u>	<u>68.5°</u>	<u>283.5°</u>	<u> </u>	<u> </u>
DAY FIELD RATIO:		<u>1</u>	<u>2.49</u>	<u>2.48</u>	<u>1.035</u>	<u> </u>	<u> </u>

SPACING AND

ORIENTATION: Adjacent towers in a row are spaced 166.14' (90°) on a line bearing 280° true.

GROUND SYSTEM: 120 - 166' equally spaced copper radials about each tower
 Radials are shortened and bonded to a transverse strap
 along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day 308.2 mv/m	534.84 mv/m	324.56 mv/m
Night 175 mv/m		

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 4

Type of elements : Series excited, uniform cross-section,
guyed, Shunt excited, Self supporting,
tapered, vertical steel towers.

TOWER	:	<u>SW(#1)</u>	<u>NW (#2)</u>	<u>NE(#3)</u>	<u>SE(#4)</u>		
HEIGHT ABOVE INSULATORS	:	<u>190'</u>	<u>190'</u>	<u>190'</u>	<u>190'</u>		
NIGHT PHASING	:	<u>+130°</u>	<u>0°</u>	<u>-120°</u>	<u>10°</u>		
NIGHT FIELD RATIO:		<u>1.00</u>	<u>1.00</u>	<u>1.28</u>	<u>1.28</u>		

SPACING AND

ORIENTATION: The towers are located at the vertices of a rectangle the long sides of which are 628.8' (340°) in length on a line bearing 64° true. The short sides are 166.3' (154°) true.


GROUND SYSTEM: 120 - 190' equally spaced copper radials about each tower
Radials are shortened and bonded to transverse straps
along intersections between towers.

Note: Please retain the nighttime directional antenna radiation pattern notified for Station KLMS in United States Change List Number 248 dated October 16, 1947 and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in the Daytime operation of the station with nighttime operation continued as previously notified.

RMS (theo) = 308.3 mv/m

RMS (std) = 324.6 mv/m

KLMS



STANDARD

HORIZONTAL RADIATION PATTERN

280° ← #4
1.035/283.5 #3
2.48/68.5 #2
2.49/214 #1
1/0

All G's = 103°

Spacing
= 90° Between
Adjacent Elements
For Day Array

○ #5

#7 ○

#6 ○

APPLICANT : RADIO STATION KLMS

LOCATION : LINCOLN, NEBRASKA

FREQUENCY : 1430 KC/S

POWER : 2500 WATTS

LATITUDE : 40 DEG 48 MIN 27 SEC

LONGITUDE : 96 DEG 36 MIN 27 SEC

WHEN USED : Daytime

R.M.S. FIELD:

DATE : June, 1976


RALPH E. EVANS ASSOCIATES

Consulting Radio Engineers

3500 North Sherman Boulevard
Milwaukee, Wisconsin 53216

Telephone: 442-4210 (Area Code 414)

14.80 KC




KLVL

MEASURED KLVL, Pasadena, Texas
NIGHT (7/13/54G)

500W, 1KW-LS, U, DA-N

1480 kc



PROPOSED DAY
(3-23-59g)


Station KFHA
Lakewood, Washington

1kw, DA-D,D

1480 KC

KOOD

Granted Mod.
of CP (2/9/59)
to change
PA pattern



FCC File No. BMP-8403
Accepted 2-10-59

KFHA
Lakewood, Washington

1480 KC

*granted
license 7-16-59*

KOOD


MEASURED DAY
(4-22-59g)

Station KFHA
Lakewood, Washington

1kw, DA-D,D
1480 KC

MEASURED H.P. RADIATION
KFHA (CP) 1480 kc 1kw D (DA)
LAKEWOOD, WASHINGTON
JANUARY, 1959

1000 watt DA



FCC File No. BL-7387
Accepted 3-26-59

KFHA
Lakewood, Washington

1480 KC

ARCHER S. TAYLOR
Consulting Radio Engineer
Post Office Box 1479
MISSOULA - MONTANA

granted license
7-16-59.

K00D

MEASURED NON-DA
(4-22-59g)

Station KFHA
Lakewood, Washington

1kw, DA-D, D
1480 KC

MEASURED H.P. RADIATION
KFHA (GP) 1480 kc 1 kw D(DA)
LAKEWOOD, WASHINGTON


JANUARY, 1959

500 watt non-DA

IONIC
DIP
TUBE
CLEAN AND DRY
LAW

W. L. L.

POLAR COORDINATE
MADE IN U.S.A.



FCC File No. BL-7387
Accepted 3-26-59

KFHA
Lakewood, Washington

1480 KC

ARCHER S. TAYLOR
Consulting Radio Engineer
Post Office Box 1479
MISSOULA - MONTANA

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : K00D Main Studio: Lakewood, Washington
 Frequency : 1480 kHz Power : 1kw
 Notification List No.: 1751 Date : September 28, 1977 Class: 1

GEOSPGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 47° 09' 56"
 West Longitude: 122° 34' 32"

authorized for daytime operation (DA-D)

PREDICTED EFFECTIVE FIELD: 175 mv/m at rated power.

 Note: Please retain the description sheet and directional antenna radiation pattern notified for Station KTEA (now K00D) in United States Change List Number 774, dated September 3, 1958 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a change or correction in the geographical coordinates of the center of the antenna system and to supply additional information concerning the predicted effective field of the omnidirectional antenna employed daytime.

KPIA

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KPIA

Main Studio: Ironton, Missouri

Frequency: 1480 kHz

Power: 5 kW

Notification List No. 1571

Date: March 14, 1974

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:North Latitude: 37° 37' 18"
West Longitude: 90° 38' 46"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D) STANDARD PATTERN
Number of elements: 2Type of elements: Series-excited, uniform cross-section, guyed
vertical steel towers.

TOWER: SW(#1) NE(#2)

HEIGHT ABOVE

INSULATORS: 162.9' 162.9' (88.2°)

PHASING: 0° +130°

FIELD RATIO: 1.0 0.64

SPACING AND


ORIENTATION: Elements are spaced 162.9' (88.2°) on a line bearing 54° true.

GROUND SYSTEM: 120-162.9' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap along
intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
441.210 mv/m	522.101 mv/m	463.481 mv/m

Standard Pattern



$S = 403.451 \text{ MW/M}$
 $G = 441.210 \text{ MW/M}$
 $E = 522.101 \text{ MW/M}$

BL-13,741

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS					FIGURE 3		STATION DATA	
S = 48.2° G = 68.2° 48.2° = 102.0° 410 ← S → G → 540 0.64/1300		TOWER	HEIGHT	SPACING	PHASING	FIELD RATIO	PROPOSED DAYTIME DIRECTIONAL RADIATION PATTERN ***** JULY - 1973 E.C. = 0	CALL KPIA FREQ 1480 KHZ POWER 5.0 KW TYPE DA-11 TIME DAYTIME LAT. N 31-37-13 LONG. W 91-34-13	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.	
		1								
		2								
		3								
		4								
		5								
		6								
		STATION DATA								PATTERN PARAMETERS

Pueblo, Colo.


~~KPUB~~

KPUB

PROPOSED DAY
(2-11-58g)

New; Steel City B/Cstng. Co., Inc.
Pueblo, Colorado

1kw, DA-D,D
1480 KC



FCC File No. BP-11,778
Accepted 1-24-58


New; Steel City Broadcasting Co., Inc.
Pueblo, Colorado
1480 KC

KPUB

MEASURED DAY
(12-21-59g)

Station KTUX
Pueblo, Colorado

1kw, DA-D,D
1480 KC



Granted L 4-14-60

FCC File No. BL-7660
Accepted 11-10-59

KTUX
Pueblo, Colorado


1480 KC

~~KPUB~~
KPUB

MEASURED NON-DA
(12-21-59g)

Station KTUX
Pueblo, Colorado

1kw, DA-D,D
1480 KC



FCC File No. BL-7660
Accepted 11-10-59

KTUX
Pueblo, Colorado


1480 KC

Granted L-4-14-60

KVAN



JAN. 1976



ERMS (Standard) = 520.44 mV/m
 ERMS (Theoretical) = 494.83 mV/m
 ERSS (Theoretical) = 1142.03 mV/m

Standard Pattern
BL-14,411

N. Lat: 45° 38' 46.5"

W. Long: 122° 30' 46.5"




FIG. 4A-R (2)
 PROPOSED NIGHTTIME
 STANDARD HORIZONTAL
 PLANE PATTERN

KVAN 5/1 (LS), DA-N 1480 kHz
 THE NEW BROADCASTING CORPORATION
 VANCOUVER, WASHINGTON

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KVAN

Main Studio: Vancouver, Washington

Frequency: 1480 kHz

Power: 5 kW Night 1 kW Day

Notification List No. 1699

Date: August 24, 1976 Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS OF THE DAY AND NIGHT ANTENNA SYSTEMS:

Daytime
 North Latitude: 45° 36' 06"
 West Longitude: 122° 43' 06"

Nighttime
 North Latitude: 45° 38' 46"
 West Longitude: 122° 30' 46"

Authorized for Night operation (DA-N).

NIGHTTIME ANTENNA CHARACTERISTICS

Number of elements: 4

Type of elements: Series excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	W(#4)	WC(#3)	EC(#2)	E(#1)
HEIGHT ABOVE INSULATORS:	199.0' (107.8°)	202.0' (109.4°)	203.1'	203.1' (110°)
NIGHT PHASING:	-113.99°	+44.78°	-163.47°	0
NIGHT FIELD RATIO:	0.90	2.0876	2.2199	1

SPACING AND

ORIENTATION: The towers are located in a row with adjacent towers spaced 166.26' (90°) on a line bearing 280° true.

GROUND SYSTEM: 120-166' equally spaced copper radials plus a 24' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of system are bonded together.

DAYTIME ANTENNA CHARACTERISTICS

Number of elements: 1

HEIGHT ABOVE INSULATORS: 200'

(Cont'd)

KVAN

GROUND SYSTEM: 120-150' to 200' equally spaced copper radials about the tower.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	197 mv/m	- mv/m	- mv/m
Night	494.83 mv/m	1142.03 mv/m	520.44 mv/m

Note: This notification concerns a change to add new nighttime operation with
Daytime operation continued as previously notified.

CTR NO 31181A3



JAN. 1976



Standard Pattern

ERMS (Standard) = 520.44 mV/m

ERMS (Theoretical) = 494.83 mV/m

ERSS (Theoretical) = 1142.03 mV/m

N. Lat: 45° 38' 46.5"

W. Long: 122° 30' 46.5"




FIG. 4A-R (2)
PROPOSED NIGHTTIME
STANDARD HORIZONTAL
PLANE PATTERN

KVAN 5/1 (LS), DA-N 1480 kHz

THE NEW BROADCASTING CORPORATION
VANCOUVER, WASHINGTON

1480 KC
NIGHT


MEASURED NIGHT(CORRECTED)
(2-21-56G) Not on Press Release

STATION KWEW
HOBBS, NEW MEXICO

1 KW
DA-N, U

~~KWEW~~
KWEW
1480 KC

N LAT 32° 42' 54"
W LONG 103° 07' 30"



①—S—②—S—③—S—④— N 80° E

S = 203 FEET = 110 DEGREES

TOWER	(1)	(2)	(3)	(4)
TOWER HEIGHT	108°	90°	90°	90°

RADIO STATION KWEW
HOBBS, NEW MEXICO
1480 KC 1 KW DA-N

THEORETICAL PHASING	0.0°	137.1°	256°	153.6°
PHASE MONITOR READING	0°	123°	27°	154°
THEORETICAL FIELD RATIO	1.000	0.498	0.631	0.686
LOOP CURRENT RATIO	1.000	0.667	0.804	0.914

A. EARL CULLUM, JR.
CONSULTING RADIO ENGINEERS
551202.1
FIGURE 4A


quartz 10-6-57 for increase in power to 5 KW

~~KNEW~~
KNEW
1480 KC

MEASURED NON-DIRECTIONAL STATION KNEW
(2-21-56G) HOBBS, NEW MEXICO

1KW
DA-N, U

*granted for increase in N/D power
to 5 kW 11-6-53*



1

S

2

S

3

S

4

→

N 80° E

S = 203 FEET = 110 DEGREES

TOWER	(1)	(2)	(3)	(4)
TOWER HEIGHT	108°	90°	90°	90°

RADIO STATION KNEW
HOBBS, NEW MEXICO
1480 KC 1KW DA-N

NUMBER 1 TOWER USED FOR
NONDIRECTIONAL OPERATION
NUMBER 2, 3, AND 4 TOWERS DETUNED

A. EARL CULLUM, JR.
CONSULTING RADIO ENGINEERS
551202
FIGURE 4A

KWEW

SUPPLEMENTAL DIRECTIONAL ANTENNA
DESCRIPTION SHEET

Station: KWEW

Main Studio: Hobbs, New Mexico

Frequency: 1480 kHz

Power: 1kW Night 5 kW Day

Notification List No. 1699

Date: August 24, 1976 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 32° 42' 57"

West Longitude: 103° 07' 28"

Authorized for Nighttime operation (DA-N).

Predicted effective Day Field: (omnidirectional) 449 mV/m at rated power.

Note: Please retain the directional antenna radiation patterns notified for station KWEW in United States Change List Number 603, dated March 30, 1955, and retain the description sheet notified for KWEW in change List No. 802 dated March 20, 1959, and attached to this supplemental Description Sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates of the center of the antenna system.

CTR NO 31192A4

NOTE: Please retain the Daytime directional antenna radiation pattern notified for Station KWIZ in United States Change List Number 751 dated March 21, 1962 and attach to this Revised Description Sheet and Nighttime pattern. This notification concerns only a change in the Nighttime operation of the station with Daytime operation continued as previously notified.

KWIZ
1480 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KWIZ Main Studio: Santa Ana, California
 Frequency: 1480 kHz Power: 5kw Night 5kw Day
 Notification List No. 1785 Date: November 16, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 33° 45' 06"
 West Longitude: 117° 54' 36"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation (DA-2)
 Number of elements: 5
 Type of elements: Series excited, uniform cross section, guyed,
 Shunt excited, Self supporting, tapered,
 vertical steel towers.

TOWER:	#1(SW)	#2(NW)	#3(SE)	#4(NE)	#5(SC)
HEIGHT ABOVE INSULATORS:	175	175	175	175	175 (94.75°)
NIGHT PHASING:	0°	+110°	+155°	+265°	---
NIGHT FIELD RATIO:	1.0	1.40	1.70	2.40	---
DAY PHASING:	0°	---	---	---	-150°
DAY FIELD RATIO:	1.0	---	---	---	0.67

SPACING AND ORIENTATION:


With tower #1 as reference, tower #2(NW) is spaced 276.9' (150°)
 on a line bearing 30.75° true, tower #3(SE) is spaced 166.1' (90°)
 on a line bearing 65.1° true, tower #4(NE) is spaced 424.6'
 (230°) on a line bearing 43.19° true, and tower #5(SC) is spaced
 112.7' (61°) on a line bearing 65.1° true.

GROUND SYSTEM: 120 - 200' equally spaced copper radials plus a 24' square ground
 screen about each tower. Radials are shortened and bonded to a
 transverse strap along intersections between towers. Centers of
 system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	428 mv/m		
Night	456.89 mv/m	508.55 mv/m	479.95 mv/m

KWIZ
49 1480KHz




HATFIELD & DAWSON
CONSULTING ELECTRICAL ENGINEERS
3525 STONE WAY N.
SEATTLE, WASHINGTON 98103

RADIO STATION KWIZ
SANTA ANA, CA.

9/78

FIGURE 2



PROPOSED NIGHTTIME DIRECTIONAL ANTENNA

5 KW HORIZONTAL PLANE STANDARD PATTERN

RMS THED = 456.8988 MV/M STD = 479.9506 MV/M
RCS = 508.5527 MV/M K = 149.2519

#	F	θ	S	θ
1	1.0	0°	0°	0°
2	1.40	110°	150°	30.75°
3	1.70	155°	90°	65.1°
4	2.40	265°	230°	43.19°

G OF ALL ELEMENTS = 175' (94.75°)


KWIZ

Proposed Day
(1-24-62ct)

Station KWIZ
Santa Ana, California

1kw, 5kw-LS, DA-2, U
1480 kc

3-9-62
printed MCP
changes in
orig DA pattern



LAT. 33° 45' 6.4"

LONG. 117° 54' 36"

RON OAKLEY
Consulting Radio Engineer




FIGURE 3a

PROPOSED DAYTIME
HORIZONTAL PATTERN

RADIO STATION KWIZ
SANTA ANA, CALIF

1480 KC -- 1/5 KW -- U -- DA-2

(AMENDED NOV. 1961)

FCC File No. BMP-10021
Accepted 1-5-62

Station KWIZ
Santa Ana, California

1480 kc


KWIZ

Measured Day
(6-22-62ct)

Station KWIZ
Santa Ana, California

1kw, 5kw-LS, DA-2, U
1480 kc

5-13-62
granted L for increase
in day power and DA-2



SITE:

117° 54' 36" W.
33° 45' 6.4" N.

$E_{RMS} = 433 \text{ MV/M}$




FIGURE 5
MEASURED DAYTIME
DIRECTIONAL FIELD INTENSITY AT ONE MILE
KWIZ, SANTA ANA, CALIFORNIA
1480 KC - 1 KW, 5 KW LS - U - DA-2
JANUARY, 1962

RON OAKLEY
Consulting Radio Engineer

FCC File No. BL-9337
Accepted 6-15-62

Station KWIZ
Santa Ana, California


1480 kc

KWIZ

Measured Non-DA
(6-22-62ct)

Station KWIZ
Santa Ana, California

1kw, 5kw-LS, DA-2, U
1480 kc



SITE:
117° 54' 36" W.
33° 45' 6.4" N.

$E_{RMS} = 192 \text{ MV/M}$


FIGURE 4

NON-DIRECTIONAL FIELD INTENSITY AT ONE MILE

KWIZ, SANTA ANA, CAL

JANUARY, 1962

RON OAKLEY
Consulting Radio Engineer



KWIZ

KWIZ

1480

10/21/48G

340°

0°

20°

320°

40°

300°

60°

280°

80°

270°

90°

260°

100°


240°

120°

220°

140°

1-7-60 pattern of station
w/ D.A. axis into secondary power



HORIZONTAL RADIATION PATTERN

STATION KVOE, SANTA ANA, CALIF.

GRAPH No. 9

PREPARED BY: Jay E. Japp

200°

180°

160°

1480 kc

L-2340

6.7 c/s 67°

KWUN
1480kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KWUN Main Studio: Concord, California
 Frequency: 1480 kHz Power: 0.5kw Night 0.5kw Day
 Notification list No. 1785 Date: November 16, 1979 Class: 1B1

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTIENNA SYSTEM:

North Latitude: 37° 57' 45"
 West Longitude: 121° 56' 43"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 5

Type of elements: Series excited, uniform cross-section, guyed, vertical steel towers.

TOWERS:	NE(#4)	NC(#2)	C(#1)	SC(#3)	SW(#5)
HEIGHT ABOVE INSULATORS:	203'	203'	203'	203'	203' (110°)
DAY AND NIGHT PHASING:	-99°	+132°	0°	-132°	+99°
DAY AND NIGHT FIELD RATIO:	0.190	0.685	1.0	0.685	0.190

SPACING AND ORIENTATION: Adjacent towers in a row are spaced 184' (100°) on a line bearing 60° true.

GROUND SYSTEM: 120 - 90' to 165' equally spaced copper radials plus 240 - 50' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL RMS	RSS	STANDARD RMS
Day	129.5 mv/m		
Night	152.80 mv/m		160.6 mv/m
Azimuth Maximum Augmentation	341°	Augmented Radiation E ₂	Span of Augmentation From - To
		23.4 $\frac{mv}{m}$	319° 161°

KWUN
1480 kHz

DA-2


SW(#5) S SC(#3) S C(#1) S NC(#2) S NE(#4) 500
0.19/-99° 0.685/-132° 1.0/0° 0.685/+132° 0.19/+99° true

S = spacing = 100° (184')

G = height = 110° (203')

Lat. = 37° 57' 45"

Long. = 121° 56' 43"




RMS(th) = 152.8 mv/m
RMS(stc) = 160.8 mv/m
RSS(th) = 196.0 mv/m

FIGURE 18

MODIFIED STANDARD
HORIZONTAL RADIATION PATTERN
NIGHTTIME

RADIO STATION KWUN
1480 KHZ, 0.5 KW, DA-2
CONCORD, CALIF.

SEPT. 1967



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
	TOWER	ELECTRICAL HEIGHT	TOWER ORIENTATION	SPACING	PHASING	HORIZONTAL FIELD	FIELD RATIO	ELEV. ANGLE	ELEVATION	CALL	KAJA
	AZ	GT	°	S	F	°	F	°	°	FREQUENCY	1480
	1	110	0	0	0	0	0	0	0	POWER	0.5
	2	110	60	100	132	685	685	0	0	TIME OF OPERATION (DAYTIME)	
	3	110	240	100	132	685	685	0	0	TYPE OF OPERATION (JA-U)	
	4	110	60	200	49	19	19	0	0	DAYTIME TOWERS	5
	5	110	240	200	92	19	19	0	0	NIGHTTIME TOWERS	
	6							0	0	NO. RADIALS PER TOWER	
	7							0	0	LENGTH OF RADIALS	
	8							0	0	GROUND SCREEN DIMENSION	
S-184	9							0	0	JA	37 57 45.5
	10							0	0	GN	121 56 43.7
S-184		AMENDED MEIN SPECIFICATIONS (Superheater Pattern of April, 1971)								FIGURE I	
CECIL LYNCH, CONSULTING ENGINEER MOORESTOWN, CALIFORNIA		RADIO STATION KWUN <> CONCORD, CALIFORNIA May, 1971									

FCC File Number BP-19027
July 7, 1971 K & E


KWUN


PROPOSED DAY
(9-20-61ct)

Station KWUN
Concord, California

500w, DA-D, D
1480 kc

10-13-61
granted MOP to
be changes in DA system
3-15-61 - granted
3p for new station



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS									STATION DATA	
		TOWER #	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION deg	SPACING ft	PHASING deg	HORIZONTAL FIELD dBu	FIELD RATIO f	ELEV. ANGLE deg	ELEVATION RMS FIELD dBu	CALL KWUN	FREQUENCY 1480
		1	110	0	0	0		1.0	0	129.5	POWER 0.5	TIME OF OPERATION DAYTIME
		2	110	60	100	132		.685	10		TYPE OF OPERATION DA-D	
		3	110	240	100	-132		.685	20		DAYTIME TOWERS 5	
		4	110	60	200	-99		.19	30		NIGHTTIME TOWERS -	
		5	110	240	200	99		.19	40		NO RADIALS PER TOWER 120	
		6							50		LENGTH OF RADIALS 90° approx.	
		7							60		GROUND SCREEN DIMENSION	
		8							70		LAT 37° 57' 45.5"	
		9							80		LONG 121° 56' 43.7"	
		10								EP	SUPRESEDES	
		DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☐									PA	PATTERN NO 080761
CECA LYNCH, CONSULTING ENGINEER MODESTO, CALIFORNIA		SERVICE BROADCASTING COMPANY RADIO STATION KWUN CONCORD, CALIFORNIA									FIGURE NO. 1	

FCC File No. BMP-9714
Accepted 8-30-61

Station KWUN
Concord, California

1480 kc


KWUN

Measured Day
(3-30-62ct)

Station KWUN
Concord, California

500w, DA-D, D
1480 kc

10-16-63
Semi-annual
from station



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS						STATION DATA		
		TOWER NO	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION °	SPACING ft	PHASING Calculated °	FIELD RATIO Calculated %	PHASING Machinery °	FIELD RATIO Machinery %	CALL KWUN
		1	110	0	0	0	1.0	0	1.0	FREQUENCY 1480
		2	110	60	100	+132	.685	+132	.786	POWER 0.5
		3	110	240	100	-132	.685	-132	.501	TIME OF OPERATION DAY
		4	110	60	200	-99	.19	-80.2	.276	TYPE OF OPERATION DA-D
		5	110	240	200	+99	.19	+62	.133	DAYTIME TOWERS 5
		6								NIGHTTIME TOWERS 0
		7								NO RADIALS PER TOWER 120
		8								LENGTH OF RADIALS 90° approx.
		9								GROUND SCREEN DIMENSION AT 37' 57' 63.5'
		10							LONG 121' 56' 63.7'	
		DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐						PATTERN NO.		
DECAL LYNN, CONSULTING ENGINEER MODESTO, CALIFORNIA		SERVICE BROADCASTING COMPANY RADIO STATION KWUN CONCORD, CALIFORNIA						FIGURE NO. 6-A		

FCC File No. BL-8934
Accepted 3-6-62

Station KWUN
Concord, California

1480 kc


KWUN


Measured Non-DA
(3-30-62ct)

Station KWUN
Concord, California

500w, DA-D, D
1480 kc

*10-14-63
checked
for non direction*



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS	STATION DATA																												
	NON-DIRECTIONAL OPERATION ANTENNA PROOF OF PERFORMANCE TOWER NO 1 USED AS RADIATING ELEMENT • • • • • NOVEMBER, 1961	<table><tr><td>CALL</td><td>KWUN</td></tr><tr><td>FREQUENCY</td><td>1480</td></tr><tr><td>POWER</td><td>0.5</td></tr><tr><td>TIME OF OPERATION</td><td>Day</td></tr><tr><td>TYPE OF OPERATION</td><td>DA-D</td></tr><tr><td>DAYTIME TOWERS</td><td>5</td></tr><tr><td>NIGHTTIME TOWERS</td><td>-</td></tr><tr><td>NO. RADIALS PER TOWER</td><td>120</td></tr><tr><td>LENGTH OF RADIAL</td><td>90' 183"</td></tr><tr><td>GROUND SCREEN DIMENSIONS</td><td>00' 0"</td></tr><tr><td>LAT</td><td>37° 57' 45.8"</td></tr><tr><td>LONG</td><td>121° 56' 43.7"</td></tr><tr><td>SUPERSEDES</td><td></td></tr><tr><td>PATTERN NO</td><td></td></tr></table>	CALL	KWUN	FREQUENCY	1480	POWER	0.5	TIME OF OPERATION	Day	TYPE OF OPERATION	DA-D	DAYTIME TOWERS	5	NIGHTTIME TOWERS	-	NO. RADIALS PER TOWER	120	LENGTH OF RADIAL	90' 183"	GROUND SCREEN DIMENSIONS	00' 0"	LAT	37° 57' 45.8"	LONG	121° 56' 43.7"	SUPERSEDES		PATTERN NO	
CALL	KWUN																													
FREQUENCY	1480																													
POWER	0.5																													
TIME OF OPERATION	Day																													
TYPE OF OPERATION	DA-D																													
DAYTIME TOWERS	5																													
NIGHTTIME TOWERS	-																													
NO. RADIALS PER TOWER	120																													
LENGTH OF RADIAL	90' 183"																													
GROUND SCREEN DIMENSIONS	00' 0"																													
LAT	37° 57' 45.8"																													
LONG	121° 56' 43.7"																													
SUPERSEDES																														
PATTERN NO																														
GEO. LYNCH, CONSULTING ENGINEER MODESTO, CALIFORNIA	SERVICE BROADCASTING COMPANY RADIO STATION KWUN CONCORD, CALIFORNIA	FIGURE NO 3																												

FCC File No. BL-8934
Accepted 3-6-62

Station KWUN
Concord, California

1480 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KWUN

Main Studio: Concord, California

Frequency : 1480 KHz

Power : 0.5KW Night 0.5KW Day

Notification List No.: 1779

Date : Sept. 27, 1978

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude:	<u>37°</u>	<u>57'</u>	<u>46"</u>
West Longitude:	<u>121°</u>	<u>56'</u>	<u>44"</u>

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 5Type of elements : Series excited, uniform cross-section, guyed,
vertical steel towers.

TOWER	SW(#5)	SC(#3)	C(#1)	NC(#2)	NE(#4)
HEIGHT ABOVE INSULATORS :	203'	203'	203'	203'	203' (110°)
Day and Night PHASING:	+99	-132°	0°	+132°	-99°
Day and Night FIELD RATIO	0.190	0.685	1.0	0.685	0.190

SPACING AND
ORIENTATION: Adjacent towers in a row are spaced 184' (100°) on a line bearing 60°GROUND SYSTEM: ^{true} 120 - 90' to 165' equally spaced copper radials plus
a counter poise consisting of 240 - 50' elevated radials
about each tower. Radials are shortened and bonded to
transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
DAY	<u>129.5</u> mV/m	<u> </u> mv/m	<u> </u> mv/m
NIGHT	<u>153.25</u> mv/m	<u>196.24</u> mv/m	<u>161.04</u> mv/m

NOTE: Please retain the Daytime directional antenna radiation pattern notified for Station KWUN in United States Change List Number 1430 dated June 24, 1971 and attach to this Revised Description Sheet and Nighttime patterns. This notification concerns only the addition of operation of the station with Daytime operation continued as previously notified.

CTR NO

Modified Standard Pattern

KWUN RADIO Exhibit E, April 1976, Page 8



DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: K Y O S Main Studio: Merced, California

Frequency: 1480 kcs.

Power: 5 kw

Notification List No. 270

Date: April 1, 1948 Class: III-A

GEOGRAPHICAL LOCATION
OF ANTENNA:

North Latitude: 37° 22' 30"

West Longitude: 120° 27' 37"

ANTENNA CHARACTERISTICS:

Authorized for Nighttime operation. (DA-N)
Number of elements: Three
Type of elements: Series-fed, uniform cross-section, guyed vertical steel towers.

TOWER:

North
eastCenterSouth
westHEIGHT ABOVE
INSULATORS:

220'

220'

220' (119.3°)

SPACING:

147.7' or 80° between adjacent towers

PHASING:

152.8°

0°

-152.8°

FIELD RATIO:

1.0

1.7

1.0

GROUND SYSTEM:

120 - 233' to 266' equally spaced radials plus
a 30' square ground screen about each tower base.
Radials shortened and bonded by transverse
bonding straps along intersections between
towers.

ORIENTATION:

Elements on a line bearing 56° true.

Predicted effective Night Field: 455 mv/m (at rated power).

1480 bc

KYOS, Merced, Cal. 1480 ko

MEASURED
NIGHT



KYOS, MERCED, CAL.

7-10-49

5kw, DAN

1480 kc

7/18/49G



LATITUDE 37° 22' 30"
LONGITUDE 120° 27' 37"

ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MVM FOR 1 KW	HEIGHT DEG
1	—	—	152.8	1.0	200	119.3
2	236	80	0	1.7	200	119.3
3	236	160	152.8	1.0	200	119.3

MEASURED NIGHTTIME
HORIZONTAL PLANE PATTERN
KYOS
MERCED, CALIFORNIA
1480KC. 5KW U, DA-N

KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

490519

KYOS, Merced, Cal. 1480 kc

KYOS

MEASURED
NIGHT NULLS


KYOS, MERCED, CAL.

7-10-49

5KW, DA-N

1480 kc

7/18/49G



○ MEASURED POINTS

----- THEORETICAL PATTERN

——— MEASURED PATTERN

LATITUDE
LONGITUDE

ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MV/M FOR 1 KW	HEIGHT DEG

EXPANDED SCALE
MEASURED NIGHTTIME
HORIZONTAL PLANE PATTERN
KYOS
MERCED, CALIFORNIA
1480 KC. 5KW U, DA-N

KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D C

490519

KYOS, Merced, Cal. 1480 kc

KYOS

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KYOS Main Studio: Merced, California
 Frequency : 1480 KHz Power : 5 kW Night 5 kW Day
 Notification: 1782 Date : October 26, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 37 ° 22 ' 30 "
 West Longitude: 120 ° 27 ' 37 "

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)
 Number of elements: 3
 Type of elements: Series excited, uniform cross-section, guyed, vertical steel towers.

TOWER	:	<u>SW(#1)</u>	<u>C(#2)</u>	<u>NE(#3)</u>		
HEIGHT ABOVE INSULATORS		<u>220'</u>	<u>220'</u>	<u>220'(119°)</u>		
NIGHT PHASING:		<u>0°</u>	<u>152.9°</u>	<u>-48.6°</u>		
NIGHT FIELD RATIO:		<u>1.0</u>	<u>1.93</u>	<u>1.29</u>		

SPACING AND
 ORIENTATION: Adjacent towers in a row are spaced 147.7' (80°) on a line bearing 56° true.

GROUND SYSTEM: 120 - 232' to 266' equally spaced copper radials plus a 30'x30' square ground screen about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD	
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>	
Day	451.7 mV/m			mV/m
Night	455 mV/m	310.6 mV/m		mV/m

Note:

KYOS

DIETZGEN CORPORATION
MADE IN U.S.A.

NO. 340R-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE






FIG. 1
PROPOSED MODIFIED HORIZONTAL
RADIATION PATTERN FOR KYOS
1480 kHz 5.0 KW-U-DA-N
MERCED, CALIFORNIA

A.E.Towne, Radio Consulting Engineer
Belmont, California

DIETZGEN CORPORATION
MADE IN U.S.A.

NO 340H-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE






DIETZEN CORPORATION
MADE IN U. S. A.

NO 340R-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE

KYOS

DIETZEN CORPORATION
MADE IN U.S.A.

NO. 340R-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



KYOS

DIETZEN CORPORATION
MADE IN U.S.A.

40-140M-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE





Fig. 5 (amended)

EXPANDED SCALES
PROPOSED HORIZONTAL RADIATION
AT THETA = 150°
KYOS 1480 KHz MERCED, CALIF.

KYOS



DIETZGEN CORPORATION
MADE IN U.S.A.

NO. 3400 P. DIETZGEN GRAPH PAPER
POLAR CO ORDINATE


Fig. 6 (amended)

EXPANDED SCALES
PROPOSED HORIZONTAL RADIATION
AT THETA = 20°
KYOS 1488 kHz MERCED, CALIF.

KYOS

DIETZEN CORPORATION
MADE IN U.S.A.


NO. 3400-P DIETZEN GRAPH PAPER
POLAR CO ORDINATE



KYOS

DIETZEN CORPORATION
MADE IN U.S.A.

NO. 340R P. DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



KYOS

DIETZGEN CORPORATION
MADE IN U.S.A.

NO. 340R-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE





Fig. 3
EXPANDED SCALES
PROPOSED HORIZONTAL RADIATION
AT THETA = 35°
KYOS 1480 KHZ MERCED, CALIF.


Fig. 10

EXPANDED SCALES
PROPOSED HORIZONTAL RADIATION
AT THETA = 40°
KTOS 1480 MHz MERCED, CALIF.
MEASURING TECHNIQUES

NO. 340R-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



NO. 340R-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



1270

DIETZEN CORPORATION
MADE IN U.S.A.
NO. 340R P. DIETZEN GRAPH PAPER
POLAR CO-ORDINATE




Fig. 13
PROPOSED HORIZONTAL RADIATION
AT THETA = 53°
KXOS 1480 KHz. MERCED, CALIF.

KYOS

DIETZGEN CORPORATION
MADE IN U. S. A.

NO. 340R-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE




FIG. 1A
PROPOSED HORIZONTAL RADIATION
AT THETA = 60°
KYOS 1480 KHZ MERCED, CALIF.

NO. 340R-P DIETZGEN
NOV 17 1977

WABB

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WABB

Main Studio: Mobile, Alabama

Frequency: 1480 kHz

Power: 5 kW

Notification List No. 1641

Date: July 16, 1975

Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS OF THE ANTENNA SYSTEMS:

Daytime	Nighttime
North Latitude: 30° 43' 11"	North Latitude: 30° 46' 26"
West Longitude: 88° 04' 16"	West Longitude: 88° 07' 08"

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 4

Type of elements: Series-excited, tower #3 uniform cross-section, guyed, towers #1, #2 and #4 Self-supporting, tapered, vertical steel towers.

TOWER:	NW(#4)	NC(#3)	SC(#2)	S(#1)
HEIGHT ABOVE INSULATORS:	360'	360' (195°)	200'	200' (108°)
PHASING:	0°	-142°	+64°	-85°
FIELD RATIO:	1.0	2.06	1.74	0.65

SPACING AND

ORIENTATION: From reference tower #4; tower #3 is spaced 167' (90.5°) on a line bearing 146° true, tower #2 is spaced 332' (180°) on a line bearing 140° true, and tower #1 is spaced 498' (270°) on a line bearing 140° true.

GROUND SYSTEM: 120-200' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of systems are bonded together.

Predicted effective Night Field: 477 mv/m at rated power.

DAYTIME ANTENNA CHARACTERISTICS

Authorized for Daytime operation (NDD).

Type of element: Series-excited, uniform cross-section, guyed, vertical steel tower.

Height above insulator: 240'

Ground System: 120-222' (ave) equally spaced copper radials.

Predicted effective Day Field: (omnidirectional) 462 mv/m at rated power.

Note: Please retain the Nighttime directional antenna radiation pattern notified for Station WABB in United States Change List Number 1225 dated July 19, 1967, and attach to this Revised Description Sheet. This notification concerns only a change in the Daytime operation of the station with Nighttime operation continued as previously notified.

CTR NO 30329A0


WABB

Measured Night
(6-28-68ct)

Station WABB
Mobile, Alabama

5kw, DA-N, U
1480 kc

7-17-68
GRANTED
LICENSE.



FCC File No. BL-11985
Accepted 6-14-68

Station WABB
Mobile, Alabama

1480 kc


WABB

Measured Non-DA
(6-28-68ct)

Station WABB
Mobile, Alabama

5kw, DA-N, U
1480 kc

7-17-68
GRANTED
LICENSE.



$E_{RMS} = 548 \text{ Mv/m}$

—○— Measured

LATITUDE $30^{\circ} 46' 26''$
LONGITUDE $88^{\circ} 07' 08''$

ANTENNA PARAMETERS

TOWER NO. 3
5 KW

G 3 = $195^{\circ} / 360^{\circ}$

FIGURE 22

MEASURED NON-DIRECTIONAL
PATTERN

Radio Station WABB
Mobile, Alabama

1480 KHz

5 KW, DA-N, U

L. J. V. du Treil & Associates, Inc.
CONSULTING RADIO ENGINEERS
201 Nelson Drive
NEW ORLEANS, LA. 70113

FCC File No. BL-11985
Accepted 6-14-68

Station WABB
Mobile, Alabama

1480 kc


WAME

PROPOSED DAY
(5-27-60g)

Station WWOK
Charlotte, North Carolina

5kw, DA-2, U
1480 KC

12-20-61
antenna
DA-2
1-20-62
pp. accepted
2 change
7 feet
35-17-05
40-52-34



COMMERCIAL RADIO EQUIPMENT CO.
RADIO ENGINEERING CONSULTANTS
WASHINGTON, D. C.

PATTERN:	Proposed Day Horizontal
FOR:	WWOK, Charlotte, N. C.
POWER:	5 KW
FREQ:	1480 KC
DATE:	March 28, 1960

FCC File No. BP-14127
Accepted 5-20-60

WWOK
Charlotte, North Carolina

1480 KC


WAME

Measured Day
(10-30-63ct)✓

Station WWOK
Charlotte, North Carolina


5kw, DA-2, U 1
1480 kc

5/13/64
painted to
large room & with three
rooms, & install
DA-2



HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION



APPLICANT	RADIO CHARLOTTE, INC. (WWOK)
LOCATION	CHARLOTTE, N. C.
FREQUENCY	1480 KC/S
POWER	5 KW-E (DA-2)
LATITUDE	35 DEG 17 MIN 05 SEC
LONGITUDE	81 DEG 02 MIN 34 SEC
WHEN USED	DA-2
RMS FIELD	414 MV/M
DATE	AUGUST 1963

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-10300
Accepted 10-7-63

Station WWOK
Charlotte, North Carolina

1480 kc

WAME


PROPOSED NIGHT
(5-27-60g)

Station WWOK
Charlotte, North Carolina

5kw, DA-2,U
1480 KC

20-61
initial copy
DA-2

20-62
T. receipt for
rec. for
35-17-05
80-52-348



10/218° 2.32/-73.2°
309° 90° 90° 90°
2.32/73.2° 1.0/-218°
RMS = 420 MV/M G's = 90°



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

WASHINGTON, D. C.

PATTERN: Proposed Night Horizontal
FOR: WWOK, Charlotte, N. C.
POWER: 5 KW FREQ: 1480 KC
DATE: March 28, 1960

FCC File No. BP-14127
Accepted 5-20-60

WWOK
Charlotte, North Carolina

1480 KC


WAME

Measured Night
(10-30-63ct)

Station WWOK
Charlotte, North Carolina


5kw, DA-2, U^a
1480 kc

5/12/64
granted CP
to change hour &
nt-trans location,
increase power,
& install DA-2



HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION



APPLICANT	RADIO CHARLOTTE, INC. (WWOK)
LOCATION	CHARLOTTE, N. C.
FREQUENCY	1480 KC/S
POWER	5 KW-U (DA-2)
LATITUDE	35 DEG 17 MIN 05 SEC
LONGITUDE	80 DEG 52 MIN 34 SEC
WHEN USED	NIGHTTIME
R.M.S. FIELD	427 MV/M
DATE	1 AUGUST 1963

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-10300
Accepted 10-7-63

Station WWOK
Charlotte, North Carolina

1480 kc

WAME

PROPOSED NIGHT NULLS
Accepted 11-17-60


Station WWOK
Charlotte, North Carolina

1480 KC
EXHIBIT NO. E-4B

10

M.E.O.V. ---

(AMENDED)



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

WASHINGTON, D. C.

PATTERN: Proposed Night Minima
FOR: WWOK, Charlotte, N. C.
POWER: 5 KW FREQ: 1480 KC
DATE: October 28, 1960

FCC File No. BP-14127
Accepted 11-17-60 (Amended)

WWOK

Charlotte, North Carolina

1480 KC


WAME

Measured Night Nulls
(10-30-63ct)

Station WWOK
Charlotte, North Carolina

5kw, DA-2, U
1480 kc

5/12/64
granted cpe
hazy hours and
int trans locations
increase power
and install DA-2



HORIZONTAL RADIATION PATTERN

EXPANDED VIEW

APPLICANT: PAM - CHARLOTTE, INC. (WWOK)
LOCATION: CHARLOTTE, N. C.
FREQUENCY: 1480 KC/S
POWER: 5 KW U (DA-2)
LATITUDE: 35 DEG 17' MIN 31 SEC
LONGITUDE: 81 DEG 52' MIN 24 SEC
WHEN USED: NIGHTTIME
RMS FIELD: 420 M/CM
DATE: AUGUST 1963

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-10300
Accepted 10-7-63

Station WWOK
Charlotte, North Carolina

1480 kc


WAME

Measured Non-DA
(10-30-63ct)

Station WWOK
Charlotte, North Carolina

5kw, DA-2, U
1480 kc 2

5/12/64
printed &
to change hour of
nt trans location,
increase power, &
install DA-2



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT: RADIO CHARLOTTE, INC. (WWOK)
LOCATION: CHARLOTTE, N.C.
FREQUENCY: 1480 KCS
POWER: 5 KW
LATITUDE: 35 DEG 11 MIN 11 SEC
LONGITUDE: 80 DEG 52 MIN 24 SEC
WHEN USED: NON-DIRECTIONAL SURVEY
RMS FIELD: 100 MV/M
DATE: AUGUST 1963

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-10300
Accepted 10-7-63

Station WWOK
Charlotte, North Carolina

1480 kc

CC

WCIN

DIRECTIONAL ANTENNA DESCRIPTION SHEET

MAY 22 1975

Station: WCIN

Main Studio: Cincinnati, Ohio

WASHINGTON, D.C.

Frequency: 1480 kHz

Power: 0.5 kW Night 5 kW Day

Notification List No. 1608

Date: November 27, 1974 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:North Latitude: 39° 09' 19"
West Longitude: 84° 30' 03"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 5

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	W(#5)	SW(#4)	SC(#3)	NC(#2)	NE(#1)
HEIGHT ABOVE INSULATORS:	150' (81.2°)	419.4'	419.4'	419.4'	419.4' (227.2°)
NIGHT PHASING:	-	-126.53°	+40.23°	-159.2°	0°
NIGHT FIELD RATIO:	-	0.25	0.876	1.24	1
DAY PHASING:	+30°	0°	-116°	-	-
DAY FIELD RATIO:	0.645	1	0.161	-	-

SPACING AND

ORIENTATION: Adjacent elements #4 thru #1 are spaced 166.1' (90°) on a line bearing
51.5° true.Tower #5 is spaced 240' (130°) on a line bearing 339° true from
tower #4.GROUND SYSTEM: 120-166' equally spaced copper radials plus a 24' square ground
screen about each tower. Radials are shortened and bonded to
transverse straps along intersections between towers.


Predicted effective Night Field: 136 mv/m at rated power.

Predicted effective Day Field: 408 mv/m at rated power.

Note: This notification concerns changes to add means of radiation to the directional
antenna patterns and corrections to heights of antennas.

AIR NO 31194A5


WCIN



N. LATITUDE 39° 09' 19"
W. LONGITUDE 84° 30' 03"

---M.E.O.V.
THETA = 0°


$E_{RSS} = 317.378$
 $E_{RMS} = 136.000$
 $RSS/RMS = 2.334$



RADIO STATION WCIN
CINCINNATI, OHIO
PROPOSED NIGHT PATTERN
1480 KHz. 0.5 KW DA-N

JOHN H. MULLANEY
CONSULTING
RADIO ENGINEER

FIGURE 6 A
AMENDED


 $E_{RSS} = 406.829$
 $E_{RMS} = 408.000$
 $RSS/RMS = 0.997$
 $G_3 = G_4 = 227.2^{\circ} \quad G_5 = 81.2^{\circ}$
 $339^{\circ}T$
 $\textcircled{5} .645 / 30^{\circ}$
 $51.5^{\circ}T$
 130°
 $\textcircled{2} .161 / -116^{\circ}$
 90°
 $\textcircled{1} 1 / 0^{\circ}$

RADIO STATION WCIN
CINCINNATI, OHIO
PROPOSED DAY PATTERN
1480 KHz 5-0.5 KW DA-2

JOHN H. MULLANEY

CONSULTING
RADIO ENGINEER

FIGURE 3

AMENDED 10/31/74

John H. MULLANEY AND ASSOCIATES

June 69 report

69/2/2

TABLE XIII

INVERSE FIELDS BASED ON RADIAL MEASUREMENT DATA

RADIO STATION WCIN
CINCINNATI, OHIO

1480 KHz - 0.5 KW / 5 KW - D - DA-2

DIAL	BEARING (DEGREES)	MEASURED FIELD - MV/M	
		NON-DA	DA-D
A	14	200	275
B	51.5	220	480
C	89	275	580
D	122	300	520
E	169	250	340
F	200	275	390
G	236	265	530
H	262	260	470
I	288	210	260
J	314	255	---
K	325	260	125
L	348	240	160
			70


June 69 report

THEORETICAL

- 100/0°
- 140/-159.2°
- 170/40.23°
- 250/-126.53°

OPERATING


- #1 = 1.000/0°
- #2 = 1.000/-20.2°
- #3 = 0.659/-43.6°
- #4 = 0.149/-69.1°



9' 19"
03"

ANTENNA PARAMETERS

01, 2, 3 & 4 = 227.8°



⊙ RADIAL VALUES

FIGURE 16

**NIGHTTIME DIRECTIONAL
HORIZONTAL POLAR PATTERN**

**RADIO STATION WCIN
CINCINNATI, OHIO**


1480 KHZ 0.5

PROPOSED DAY
(7-26-61ct)


Station WDAS
Philadelphia, Pennsylvania

1kw, 5kw-LS, DA-2
1480 KC

*9/6/61
printed of
with change in DA pattern*



North Latitude 39° 59' 53"
West Longitude 75° 12' 43"



FCC File No. BP-14897
Accepted 7-6-61

FIGURE 1
HORIZONTAL RADIATION PATTERN
(PROPOSED DAYTIME OPERATION)

MAX M. LEON, INC.

WDAS 1 KW, 5 KW-LS, DA-2 1480 KC
PHILADELPHIA, PENNSYLVANIA

Prepared by

Lohnes and Culver


Washington 4, D.C.

WDAS
Philadelphia, Pennsylvania 1480 KC

WDAS

Measured Day
(3-30-62ct)Station WDAS
Philadelphia, Pennsylvania1kw, 5kw-LS, DA-2, U
1480 kc

3-22-63
printed & for
changes in day
pattern.

FCC File No. BL-8951
Accepted 3-13-62Station WDAS
Philadelphia, Pennsylvania


1480 kc

WDAS

Measured Non-DA
(3-30-62ct)

Station WDAS
Philadelphia, Pennsylvania

1kw, 5kw-LS, DA-2, U
1480 kc



FCC File No. BL-8951
Accepted 3-13-62

Station WDAS
Philadelphia, Pennsylvania

1480 kc

PROPOSED
NIGHT

WDAS, PHILADELPHIA, PA.
7/2/52G

1 KW, U, DA-2

WDAS

1480 KC





FIGURE 1-A
PROPOSED NIGHTTIME
HORIZONTAL PLANE RADIATION PATTERN

MAX M. LEON, INC.

WDAS PHILADELPHIA, PENNSYLVANIA

1480 kc 1. kw U DA-2

E. C. PAGE
CONSULTING RADIO ENGR'S.
WASHINGTON, D. C.

VRE-JC

14 MAY 1952

PROPOSED
NIGHT NULLS

WDAS, PHILADELPHIA, PA.
7/2/52G

1 KW, U, DA-2

WDAS
1480 KC





FIGURE 1-B
EXPANDED MINIMA OF NIGHTTIME
HORIZONTAL PLANE RADIATION PATTERN

MAX M. LEON, INC.

WDAS PHILADELPHIA, PENNSYLVANIA

1480 kc 1. kw U DA-2

E. C. PAGE
CONSULTING RADIO ENGR'S.
WASHINGTON, D. C.

VRE-JC

14 MAY, 1952


WDAS

Measured Night
10/6/55G

STATION WDAS
PHILADELPHIA, PA.

1 KW
DA-2, U


1480 KC



PROPOSED DAY
(6-14-61g)

Station WG5B
Geneva, Illinois

500w, 1kw-LS, DA-2,U
1480 KC



RMS = 182 MV/M
h = 160' ± 87'

North Latitude
41° 54' 25"
West Longitude
88° 17' 43"

MODIFIED DAYTIME HORIZONTAL RADIATION
PATTERN FOR RADIO STATION WG5B AT
GENEVA, ILLINOIS ON 1480 KCS WITH 1000
WATTS-LS, 500 WATTS, DA-2 BP-11,038

RALPH J. BITZER, CONSULTING RADIO ENGR


*jurisdiction
to make change to
day pattern
6-12-61
4-12-63
granted L
for station*

WGSB

Measured Day
(2-28-62ct)

Station WGSB
Geneva, Illinois

500w, 1kw-LS, DA-2, U
1480 kc



FCC File No. BL-8860
Accepted 1-23-62

Station WGSB
Geneva, Illinois

1480 kc

WGSB GENEVA, ILLINOIS MEASURED DAYTIME
DIRECTIONAL PATTERN ON 1480 KCS. WITH
1000 WATTS-LS, 500 WATTS, DA-2 (BR-11038)
RALPH J. BITZER, CONSULTING RADIO ENGR.

Geneva, Ill.

WGSB


PROPOSED NIGHT
(11-29-57g)

New; Fox Valley Bcstng. Co.
Geneva, Illinois

500w,1kw-LS, DA-2,U
1480 KC

P-20-00
cont'd CP
for a new
station

KOE
POLAR CO-ORDINATE
KEUFEL & FESSER CO.
359-31G
MADE IN U.S.A.



N 41° 54' 25" L
W 88° 17' 43" L

FCC File No. BP-11,038
Accepted 11-26-57 (Amended)

Fox Valley Bcstng. Co.
Geneva, Illinois


1480 KC

WG-SB

Measured Night
(2-28-62ct)

Station WGSB
Geneva, Illinois

500w, 1kw-LS, DA-2, U
1480 kc



FCC File No. BL-8860
Accepted 1-23-62

Station WGSB
Geneva, Illinois

1480 kc


WGSB

Measured Non-DA
(2-28-62ct)

Station WGSB
Geneva, Illinois

500w, 1kw-LS, DA-2, U
1480 kc

K&E POLAR CO-ORDINATE
PATTERNS
359-31G



WGSB GENEVA, ILLINOIS NON-DIRECTIONAL
PROOF PATTERN USING TOWER NUMBER 4
WITH 500 WATTS ON 1480KCS (8P-N038)
RALPH J. BITZER, CONSULTING RADIO ENG

FCC File No. BL-8860
Accepted 1-23-62


Station WGSB
Geneva, Illinois

1480 kc

7136

#4 = 356 ft = 108 m
#1, 2, 3 = 370 ft = 113 m

2172.0 3172.0 2172.0 209.8



WHSC

- 4 THEO. 2.08/-89.2°
MEAS. 1.46/209°
S: 90°
- 3 THEO. 3.72/51°
MEAS. 1.07/2°
S: 90°
- 2 THEO. 2.56/-120.5°
MEAS. 0.538/-47°
S: 90°
- 1 THEO. 1.07/0°
MEAS. 0.077/135°

300 MV/M

200

100

1600 MV/M

1200

800

400

RMS = 559 MV/M

• MEASURED RADIAL

NIGHTTIME
MEASURED RADIATION PATTERN
WHSC 5 KW-U-DA-N 1460 KC
CANTON, OHIO
OCTOBER, 1967
KEAN, SKLOM & STEPHENS CO.
CONSULTING RADIO ENGINEERS
NINETEEN EAST CLINCY STREET
RIVERSIDE ILLINOIS 60546

100

MEASURED RADIAL

WHBC

500 MVM


400

200

RMS=545 MVM

NON-DIRECTIONAL RADIATION PATTERN
TOWER 3 FED 5 KW.
WHBC 5 KW-U-DA-N 1480 KC
CANTON, OHIO OCTOBER, 1967

KEAN, SKLOM & STEPHENS CO.
CONSULTING RADIO ENGINEERS
NINETEEN EAST QUINCY STREET
RIVERSIDE, ILLINOIS 60546




WHBC

Rec'd 10-7-47

9/17/48 60

WHBC 1480 KC




WHOM

Proposed Day
(12-28-67ct)

Station WHOM
New York, New York


5kw, DA-2, U
1480 kc
FIGURE 7A

12-6-67
GRANTED
CP TO CHANGE
ANTENNA LOC.
IN DA, SYSTEM



SITE COORDINATES
40° 50' 42" N
74° 01' 12" W

PROPOSED DAYTIME HORIZONTAL PLANE RADIATION PATTERN



PROGRESS BROADCASTING CORPORATION
NEW YORK, NEW YORK

Jones Cohen & Associates
Consulting Electronics Engineers

RADIO STATION WHOM
1480 KHZ

DA-2
STATION No. 670909AD

FCC File No. BP-17937
Accepted 12-12-67

Station WHOM
New York, New York


1480 kc

Proposed Night
(12-28-67ct)


Station WHOM
New York, New York

WHOM
5kw, DA-2, U
1480 kc

Figure 10A
Sheet 1 of 14
(Amended)



PROPOSED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN



PROGRESS BROADCASTING CORPORATION
NEW YORK, NEW YORK
Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION WHOM
1480 KHZ
5 KW U DA 2
PATTERN No 570909AN

FCC File No. BP-17937
Accepted 12-12-67

Station WHOM
New York, New York


1480 kc

WHOM

12-6-67
GRANTED CP
CHANGES IN DA SYSTEM.

Figure 10A

Sheet 2 of 14



PROPOSED NIGHTTIME RADIATION PATTERN AT VERTICAL ANGLE OF 0 DEGREES

FCC File No. BP-17937

Accepted 12-12-67

Station WHOM

New York, New York

1480 kc

New York, N.Y.

WHOM
1480

FIG. 5


JUL 29 1948 G

340°

License --- 0 ---

7-28-48


20°



WHOM
1480


JUL 29 1946 G

License 7-22-48



MEASURED HORIZONTAL PLANE RADIATION PATTERN FOR DAYTIME OPERATION

329° TRUE ④ ○ 0 / 0° 90° 180° ③ ● 0.52 / 160° 90° 180° ② ● 1.0 / 17° 90° 180° ① ● 0.52 / -180° 90° 180°	ATLANTIC BROADCASTING COMPANY WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON DC	WHOM 1480 KC 5 KW U DA-2 480727 E SUPERSEDES 480714 M
--	--	--



PROPOSED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

327° TRUE
(4) 0.798/119.86°
S
(3) 0.2.376/-40.98°
S
(2) 0.2.524/158.82°
S
(1) 0.1/0°
S = 100° = 184.6'
G = 195° (149° + 46° T.L.)

PROGRESS BROADCASTING
CORPORATION

NEW YORK, NEW YORK

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION WHOM

1480 KHZ

5 KW U DA-2

JULY 1973

1480

20-

340*

License 7-16-43.


$$At = 150'$$


4
74

PROPOSED NIGHT NULLS

Station WHOM
New York, New York

5kw, DA-2, U
1480 KC


FIG. 3



WHOM
1480

NY 29 150 G

License 7-16-48



MEASURED HORIZONTAL PLANE RADIATION PATTERN FOR NIGHTTIME OPERATION

329° TRUE ④ ● 1.0 / 54° ③ ● 2.7 / 101.5° ② ● 2.7 / 101.3° ① ● 1.0 / 54°	ATLANTIC BROADCASTING COMPANY WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON DC	WHOM 1480 KC 5 KW U DA-2 480714 K
--	--	--

MEASURED
NIGHT
NULLS


WHOM, JERSEY CITY, N.J.
2/7/49G

License 7/16/48

5kw, DA2

1480 kc

W/HOI



MEASURED HORIZONTAL PLANE RADIATION PATTERN FOR NIGHTTIME OPERATION

SITE:

40° 21' 10" N
74° 02' 51" W

DETAIL IN NULLS

40°-50-40
74°-01-06

ATLANTIC BROADCASTING COMPANY

WELDON & CARR
CONSULTING RADIO ENGINEERS
WASHINGTON DC

WHOM

1480 KC 5 KW U DA-2


480714 L

WIOS

Proposed Day
(12-27-68ct)

Station WIOS
Tawas City-East Tawas, Michigan

1kw, 5kw-LS, DA-2, U
1480 kc



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS	FIGURE A-3	STATION DATA																																																												
$G_1=162.6^\circ$ $G_2=G_3=81.3^\circ$ No. 1 ● $1/0^\circ$ 90° No. 2 ● $0.70/+100^\circ$ 90° No. 3 ○ Not Used 185° T.	<table border="1"> <thead> <tr> <th>TOWER</th> <th>ELECTRICAL HEIGHT</th> <th>SPACING</th> <th>PHASING</th> <th>FIELD RATIO</th> </tr> <tr> <th>No.</th> <th>h°</th> <th>s°</th> <th>ϕ°</th> <th>r</th> </tr> </thead> <tbody> <tr><td>1</td><td></td><td></td><td></td><td></td></tr> <tr><td>2</td><td></td><td></td><td></td><td></td></tr> <tr><td>3</td><td></td><td></td><td></td><td></td></tr> <tr><td>4</td><td></td><td></td><td></td><td></td></tr> <tr><td>5</td><td></td><td></td><td></td><td></td></tr> <tr><td>6</td><td></td><td></td><td></td><td></td></tr> <tr><td>7</td><td></td><td></td><td></td><td></td></tr> <tr><td>8</td><td></td><td></td><td></td><td></td></tr> <tr><td>9</td><td></td><td></td><td></td><td></td></tr> <tr><td>10</td><td></td><td></td><td></td><td></td></tr> </tbody> </table>	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	No.	h°	s°	ϕ°	r	1					2					3					4					5					6					7					8					9					10					PROPOSED 5 KW DAYTIME PATTERN ***** WIOS $\theta^\circ = 0^\circ$	CALL WIOS FREQ 1480 kc/s POWER 5 kw TYPE DA-2 TIME DAYTIME LAT. $44^\circ 15' 48''$ LONG. $83^\circ 32' 42''$ E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO																																																											
No.	h°	s°	ϕ°	r																																																											
1																																																															
2																																																															
3																																																															
4																																																															
5																																																															
6																																																															
7																																																															
8																																																															
9																																																															
10																																																															
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐																																																															

FCC File No. BP-18311
Accepted 12-12-68

Station WIOS
Tawas City-East Tawas, Michigan


1480 kc

WIOS

Proposed Night
(12-27-68ct)

Station WIOS
Tawas City-East Tawas, Michigan

1kw, 5kw-LS, DA-2, U
1480 kc



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE B-7	STATION DATA
$G_1 = 162.6^\circ$ $G_2 = G_3 = 81.3^\circ$ No. 1 $\circ 1/0^\circ$ 90° No. 2 $\circ 1.177/+122^\circ$ 90° No. 3 $\circ 0.436/-116^\circ$ 185° T.	TOWER No.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING V'	FIELD RATIO F'	PROPOSED NIGHTTIME DIRECTIONAL ANTENNA RADIATION PATTERN ***** WIOS ***** 11/67 GND LEVEL	CALL WIOS FREQ 1480 KHZ POWER 1.0 KW TYPE DA-2 TIME NIGHT LAT. N 44-15-48 LONG. W 83-32-42 E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
	1						
	2						
	3						
	4						
	5						
	6						
	7						
	8						
	9						
	10						

FCC File No. BP-18311
Accepted 12-12-68


Station WIOS
Tawas City-East Tawas, Michigan

1480 kc

Superior Hvac Co.

PROPOSED DAY
(6/26/57g)New, ~~R.S. Underhill~~
Tawas City-East Tawas, Michigan1kw, DA-D,D
1480 KC

Granted CP
9/5/57 for
new station
printed new CP
for new station
3-15-62

FCC File No. BP-11,115
Accepted 6/14/57R.S. Underhill
Tawas City- East Tawas, Michigan

1480 KC

Measured Day
(1-24-62ct)


Station WIOS
Tawas City - East Tawas, Michigan

1kw, DA-D, D
1480 kc

*noted new CP
new station
5-15-62
2CPT-#171
3-20-62*

*noted for
station*

NO. 340-D DIETZEN GRAPH PAPER
SELAR CO. INATE



FCC File No.
Accepted

Station WIOS
Tawas City - East Tawas, Michigan


1480 kc

WIOS

Measured Non-DA
(1-24162ct)

Station WIOS
Tawas City - East Tawas, Michigan

1kw, 0A-D, D
1480 kc



EUGENE DIEZGEN CO.
PRINTED IN U.S.A.


EUGENE DIEZGEN GRAPH PAPER
POLAR CO-ORDINATE

FCC File No.
Accepted

Station WIOS
Tawas City - East Tawas, Michigan


1480 kc


WISL
1480



CALCULATED HORIZONTAL PLANE RADIATION PATTERN FOR NIGHTTIME OPERATION

352° TRUE 99°/210° 1°/89° 1°/89° 99°/210° 8°108°	RADIO ANTHRACITE INCORPORATED SHAMOKIN PENNSYLVANIA	WISL SHAMOKIN PENNSYLVANIA
	WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON DC	1480 KC 1 KW U DA-M 470813A






CALCULATED HORIZONTAL PLANE RADIATION PATTERN FOR NIGHTTIME OPERATION

DETAILS IN NULLS	RADIO ANTHRACITE INCORPORATED SHAMOKIN PENNSYLVANIA	WISL SHAMOKIN PENNSYLVANIA
	WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON DC	1480 KC 1 KW U DA-M 4706138

WISL
1480

Rec'd 1-22-48


9/17/486




WISL
1480

Rec'd 1-22-47

9/17/486



MEASURED HORIZONTAL PLANE RADIATION PATTERN



RADIO ANTHRACITE INCORPORATED
SHAMOKIN PENNSYLVANIA

WELDON & CARR
CONSULTING RADIO ENGINEERS
WASHINGTON DC

WISL
SHAMOKIN PENNSYLVANIA

1480 KC 1 KW U DA-N
480118 B

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WISM

Main Studio: Madison, Wisconsin

Frequency: 1480 kHz

Power: 5 kW

Notification List No. 1579

Date: May 8, 1974

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 43° 01' 30"

West Longitude: 89° 23' 48"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 5

Type of elements: Towers #1, #2, #3 and #4 are series-excited, uniform cross-section, guyed, vertical steel towers. Tower #5 is tapered, self-supporting. Tower #2 is electrically sectionalized with detuning skirts to an effective electrical height of 108.3° (*)

TOWER:	SW(#1)	SC(#2)	NC(#3)	NE(#4)	E(#5)
HEIGHT ABOVE INSULATORS:	200'	480' (*)	200'	200'	200' (108.3°)
NIGHT PHASING:	0°	-141.68°	+74.86°	-70°	---
NIGHT FIELD RATIO:	1.0	2.324	2.181	0.81	---
DAY PHASING:	---	---	---	0°	+120°
DAY FIELD RATIO:	---	---	---	0.415	0.315

SPACING AND

ORIENTATION: Nighttime adjacent elements #1, #2, #3 and #4 are spaced 185' (100°) on a line bearing 17° true. Daytime elements #4 and #5 are spaced 111' (60°) on a line bearing 140° true.

GROUND SYSTEM: 120-250' equally spaced copper radials plus a 32' square ground screen about towers #4 and #5. 120-185' equally spaced copper radials plus a 24' square ground screen about towers #1, #2 and #3. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of systems are bonded together.

Predicted effective Night Field: 450 mv/m at rated power by adjustment of input power.

Predicted effective Day Field: 418 mv/m at rated power.

(Cont'd.)

WISM
1480 kHz

2.

Note: Please retain the Daytime directional antenna radiation pattern notified for Station WISM in United States Change List Number 1438, dated August 18, 1971, and attach to this Revised Description Sheet and Nighttime patterns. This notification concerns only a change in MEOV's of radiation in the Nighttime operation of the station with Daytime operation continued as previously notified.

CTR NO 30471A3


WISH

Proposed Night
(11-28-67ct)

Station WISM
Madison, Wisconsin

5kw, DA-2, U
1480 kc

1-29-67
GRANTED
MODIF. OF CP
CHANGES IN
NIGHTTIME LA
PATTERN (MECV)



$E_{RMS} = 450 \text{ MV/M (BY ADJUSTMENT)}$

LOCATION OF MINIMA - $104^{\circ}T, 129^{\circ}T, 158^{\circ}T$
 $236^{\circ}T, 265^{\circ}T, 290^{\circ}T$

LATITUDE: $43^{\circ} 01' 30''$

LONGITUDE: $89^{\circ} 23' 48''$

CHARLES E. BRENNAN
CONSULTING RADIO ENGINEERS
MILWAUKEE, WISCONSIN

ANTENNA PARAMETERS

ALL $G's = 108^{\circ}$
SPACING BETWEEN
ADJOINING TOWERS
IS 100° .

3 • $2.181/+74.86^{\circ}$

2 • $2.324/-141.68^{\circ}$

1 • $1.0/0^{\circ}$

670920

FIGURE 2

PROPOSED NIGHTTIME
DIRECTIONAL ANTENNA PATTERN

RADIO STATION WISM
MADISON, WISCONSIN

1480 KC

5000 DA-2 U

FCC File No. BMP-12206
Accepted 11-8-67

Station WISM
Madison, Wisconsin


1480 kc

5kw, DA-2, U
1480 kc

Station WISM
Madison, Wisconsin

Proposed Night Nulls
(11-28-67ct)

11-29-67
PRINTED MODIF. OF CP
CHANGES IN NIGHTTIME DA PATTERN
(1120V)



FCC File No. BMP-12206
Accepted 11-8-67

Station WISM
Madison, Wisconsin

1480 kc

WISM





FIGURE 1

HORIZONTAL RADIATION PATTERN



APPLICANT: WISM
 LOCATION: WISCONSIN
 FREQUENCY: 100.0 MHz
 POWER: 100 W
 LATITUDE: 43 DEG 00 MIN 00 SEC
 LONGITUDE: 88 DEG 00 MIN 00 SEC
 DATE: JAN 1974

JAN, 1974
 GILLIGAN, MOFFET & COMPANY
 1000 N. MILWAUKEE AVE.
 MILWAUKEE, WIS. 53233

FIGURE 1-C

WIDA - MADISON, WISCONSIN

0° ELEVATION PATTERN

JANUARY 1974 SILLIMAN, MOFFET & KOWAL, SR

MAXIMUM EXPECTED INTERFERING POWER

MAXIMUM POWER

MISSION - Vision

© 2011 by Columbia University

ADDRESS +074 SIIIIMAN; WJFFET d VIOV, SK

03066 601-0300 95-03083 2001800

WISM








FIGURE 1-0
WISM - MADISON, WISCONSIN
3° ELEVATION PATTERN
JANUARY 1974 SULLIVAN, WRIGHT & KOWALSKI
— — — MAXIMUM EXPECTED OFF-AIRWAY LOSS




WISM









WISMA



WISM





WISM






FIGURE 1-2


WISM - MADISON, W. SCOTLAND
45° ELEVATION PATTERN
JANUARY 1973 ST. LINDA, HOFFET & HOWALSO
--- MAXIMUM EXPECTED OPERATING VALUES



WISMA



WISM




WISM

PROPOSED DAY
(7/19/57g)

Station WISC
Madison, Wisconsin

1kw,5kw-LS, DA-2,U
1480 KC



FCC File No. BP-11,396
Accepted 7/16/57

WISC
Madison, Wisconsin


1480 KC

WISMA

MEASURED DAY
(12-21-59g)

Station WISM
Madison, Wisconsin

1/5KW
500w, 1kw-LS, DA-2, U
1480 KC



FCC File No. BL-7723
Accepted 11-24-59

WISM
Madison, Wisconsin

1480 KC

WISM

MEASURED NON-DA
(12-21-59g)

Station WISM
Madison, Wisconsin

^{1/5 Kw}
~~500w, 1kw~~ LS, DA-2, U
1480 KC




Figure 12
Measured Horizontal Radiation Pattern
0.5 Kw Test
Heart O' Wisconsin Broadcasters, Inc.
Radio Station WISM
1480 Kc 5 Kw/D, 1 Kw/N (DA-2)
Madison, Wisconsin
October 1959

PAGE, CREUTE, STEEL & WALDSCHMITT
Consulting Engineers
1413 K STREET, NORTHEAST
WASHINGTON 5, D. C.

Measured Day
(4-29-69ct)


Station WJBM
Jerseyville, Illinois

WJBM
500w, DA-D, D
1480 kc
page 43

Granted 5/4/69

License covering

Range




Measured RMS-125 MV/M

• Measured Field
----- MEOV
----- Measured Pattern

HORIZONTAL RADIATION PATTERN

WJBM - 0°



A-150' (81°)
Station WJBM
Jerseyville, Illinois

FCC File No. BL-12313
Accepted 4-3-69

APPLICANT :	Tri-County Broadcasting Co.
LOCATION :	Jerseyville, Illinois
FREQUENCY :	1480 KC/S
POWER :	500 Watts
LATITUDE :	39 DEG. 06 MIN. 46 SEC.
LONGITUDE :	90 DEG. 18 MIN. 43 SEC.
WHEN USED :	Daytime
RMS FIELD :	124 MV/M (Theoretical)
DATE :	January 31, 1967

Proof 2/26/69
RALPH J. BITZER
CONSULTING RADIO ENGINEERS
ST. LOUIS, MISSOURI

1480 kc


Measured Non-DA
(4-29-69ct)

Station WJBM
Jerseyville, Illinois

WJBM

500w, DA-D, D
1480 kc

*Monted 5/6/64
license covering
ranges*



HORIZONTAL RADIATION PATTERN

APPLICANT	Tri-County B/Cing Co.
LOCATION	WJBM Jerseyville, Ill.
FREQUENCY	1480 KC/S
POWER	250 Watts, Non-D
LATITUDE	39 DEG. 06 MIN. 46 SEC.
LONGITUDE	90 DEG. 18 MIN. 43 SEC.
WHEN USED	Non-D Proof
R.M.S. FIELD	117 MV/M
DATE	

RALPH J. BITZER
CONSULTING RADIO ENGINEERS

FCC File No. BL-12313
Accepted 4-3-69

Station WJBM
Jerseyville, Illinois

1480 kc

WJBM


Proposed Day
(2-28-67ct)

Station WJBM
Jerseyville, Illinois

500w, DA-D, D
1480 kc


BP-17622
GRANTED - P
5-5-67
CHANGE - IN
ANTENNA SYSTEM

OVER



HORIZONTAL RADIATION PATTERN

WJBM - 0°



APPLICANT	Tri-County Broadcasting Co.
LOCATION	Jerseyville, Illinois
FREQUENCY	1480 KC/S
POWER	500 Watts
LATITUDE	39 DEG 06 MIN 46 SEC
LONGITUDE	90 DEG 18 MIN 43 SEC
WHEN USED	Daytime
AMB FIELD	124 MV/M
DATE	January 31, 1967

RALPH J. BITZER
CONSULTING RADIO ENGINEERS
ST. LOUIS, MISSOURI

FCC File No. BP-17622
Accepted 2-21-67

Station WJBM
Jerseyville, Illinois

1480 kc


WKND

MEASURED NON-DA
(7-26-61ct)

Station WSOR
Windsor, Connecticut

500w, DA-D,D
1480 KC

E-13



COMMERCIAL RADIO EQUIPMENT CO.

Radio Engineering Consultants

WASHINGTON D C

MEASURED NON-DIRECTIONAL RADIATION
WSOR, NO. 1 TOWER, 1480 KC, 250 W
WINDSOR, CONNECTICUT
APRIL 1961

FCC File No. BL-8458
Accepted 7-14-61

WSOR
Windsor, Connecticut 1480 KC

WKND


MEASURED DAY
(7-26-61ct)

Station WSOR
Windsor, Connecticut

500w, DA-D,D
1480 KC

E-14

Lat. 41° 51' 10" N
Long. 72° 40' 43" W



COMMERCIAL RADIO EQUIPMENT CO.
Radio Engineering Consultants

WASHINGTON D C


FCC File No. BL-8458
Accepted 7-14-61

MEASURED DAYTIME PATTERN
WSOR, WINDSOR, CONNECTICUT
1480 KC, 500 W-D, DA
APRIL 1961


WSOR
Windsor, Connecticut 1480 KC

Windsor, Conn.

WKND

PROPOSED DAY
(7/15/57g)New, The Tobacco Valley B/Cng Co.
Windsor, Connecticut500w, DA-D,D
1480 KC

ESTIMATED EFFECTIVE FIELD AT ONE MILE IN THE HORIZONTAL PLANE

THE TOBACCO VALLEY BROADCASTING COMPANY
WINDSOR, CONNECTICUT

1480 kc DA-D 500 watts

570515

Figure 1

EXHIBIT E-1

FREDERIC D. SCHOTTLAND
Consulting Radio Engineer
WEST ORANGE, N. J.FCC File No. BP-11,339 The Tobacco Valley B/Cng Co.
Accepted 7/10/57 BMP 4087 Windsor, Connecticut

1480 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Stations: WLEE and WBBL Main Studio: Richmond, Virginia
(Both stations share time and use the same transmitter and antenna facilities)
Frequency: 1480 kHz Power: 5 kW

Notification List No. 1584 Date: June 12, 1974 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM: North Latitude: 37° 35' 50"
West Longitude: 77° 30' 39"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
Number of elements: 4
Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	NW(#1)	NC(#2)	SC(#3)	SE(#4)	
HEIGHT ABOVE INSULATORS:	300'	300'	300'	300'	(162.5°)
NIGHT PHASING:	-88.5°	+137.8°	0°	-137.8°	
NIGHT FIELD RATIO:	1.05	2.47	2.47	1	
DAY PHASING:	-	+163°	-17°	-163°	
DAY FIELD RATIO:	-	1.00	2.00	1.00	

SPACING AND

ORIENTATION: Adjacent elements #2, #3 and #4 are spaced 166' (90°) on a
line bearing 314° true. Tower #1 is spaced 338' (183°) on a
line bearing 316° true from tower #3.

GROUND SYSTEM: 120-166' equally spaced copper radials plus a 20' square
ground screen about each tower. Radials are shortened and
bonded to transverse straps along intersections between towers.

Predicted effective Day and Night Fields: 492 mv/m at rated power.

Note: Please retain the Daytime directional antenna radiation pattern
notified for station WLEE labelled "APPENDIX VI (AMENDED)" in United
States Change List Number 351 and attach to this Revised Description
Sheet and Nighttime patterns. This notification concerns only a
change to add M.E.O.V.'s of radiation to the Nighttime directional
antenna radiation pattern and to correct the nighttime field ratios of
tower #1 and #4 with Daytime operation continued as previously notified.

WBBL CTR NO 31199A4
WLEE CTR NO 30535A3

$$A = 0.00319 \text{ cm}^2/\text{mm}^2 \text{ cm}^2$$


AUG 5 1948
8 70

37-35-50
77-30-39

WLEE

1480

S - WBBL



WIP-3237 WLEE Amendment Recd 7-30-48

WLEE
S
WEE

PROPOSED
DAYTIME

WLEE, RICHMOND, VA.

5kw, DA-2

1480 kc

340°


350°

350°
10°

20°


30°

12/30/49G



12-28-49

Height - 300'



SITE: $37^\circ 35' 50'' N$
 $77^\circ 30' 39'' W$

DECEMBER 1949


CHAMBERS AND GARRISON
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

APPENDIX VI (AMENDED)


DAYTIME
HORIZONTAL RADIATION PATTERN
PROPOSED DIRECTIONAL ANTENNA
WLEE RICHMOND, VA.
1480 kc 5 kw, DA-2

WLEE, Richmond, Va. 1480 kc

4-5/72/6
6/22/18



— MEASURED PATTERN
○ MEASURED RADIALS




LATITUDE		37°	35'	50"		
LONGITUDE		77°	30'	39"		
ANTENNA NUMBER	AZ MUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MVM FOR 1 KW	HEIGHT DEG
1	S E E	S E E	—	—		—
2			163°	1.0		163°
3	D I A G R A M	D I A G R A M	—17°	2.0		163°
4			—163°	1.0		163°


MEASURED DAYTIME
HORIZONTAL PLANE PATTERN
WLEE
RICHMOND, VIRGINIA
1480 KC. 5KW. U, DA-2
540611

KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D.C.

BR1224 9/27/54



BR 1224
9/22/54




LATITUDE		37°	35'	50"		
LONGITUDE		77°	30'	39"		
ANTENNA NUMBER	AZIMUTH DEG	SWING DEG	PHASING DEG	FIELD RATIO	MV/M FOR 1 KW	MEAS DEG
1	SEE	SEE	-88.5	1.05		163°
2	SEE	SEE	137.8	2.47		163°
3	DIAGRAM	DIAGRAM	0	2.47		163°
4	DIAGRAM	DIAGRAM	-137.8	1		163°

MEASURED NIGHTTIME
HORIZONTAL PLANE PATTERN
WLEE
RICHMOND, VIRGINIA
1480 KC. 5 KW. U, DA-2
540611
KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

BR 1224 9/22/54

W L E E




PROPOSED NIGHT

Station WRDW
Augusta, Georgia

5kw, DA-N,U

1480 KC

HORIZONTAL PLANE RADIATION PATTERN
W R D W
1480 KC 5 KW D.A. NIGHT
W J HOLEY ATLANTA



PROPOSED NIGHT NULLS

Station WRDW
Augusta, Georgia

5kw, DA-N,U

1480 KC

WRDW

NL 33° 31' 02"
WL 82° 00' 30"

1/122°

90°

1.886/0°

90°

1/-122°

ENLARGED NULLS - HORIZONTAL PATTERN

W R D W


1480 KC.

5 KW.

D.A. NIGHT

W J HOLEY ATLANTA

KEUFFEL & ESSER CO. N.Y. NO. 384-231
Radio Engineers




WRSW

PROPOSED DAY
(5-8-61g)

Station WRSW
Warsaw, Indiana

500w, 1kw-LS, DA-2,U
1480 KC

6-20-62
granted increase
day power from
500w to 1kw
and change in DA.



FCC File No. BP-14718
Accepted 4-13-61

WRSW
Warsaw, Indiana

1480 KC



WRSW

Measured Day
(4-30-63ct)

Station WRSW
Warsaw, Indiana

500w, 1kw-LS, DA-2, U
1480 kc

4-29-63
granted license
overing increase
in day power
and change in
day DA pattern



W R S W
MEASURED DAY PATTERN
1480 KC 1 KW
WARSAW, INDIANA
DEC. 1962

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS


WARSAW
2 WARSAW, IND. 1480 kc



NEW, WARSAW, INDIANA
(Reub Williams & Sons, Inc.)

500w, DA-2

1480 kc



AMENDMENT RECD 7-6-50 ACC 7-14-50 BP-6670

NEW, Warsaw, Indiana 1480 kc


WRSW

MEASURED
NIGHT

WRSW, WARSAW, IND.
12/9/52G

500W, U, DA-2

1480 KC



RECD FCC 10/24/52 ACC 11/24/52 BL--4827

WRSW, WARSAW, IND.


1480 KC

WRSW

MEASURED WRSW, WARSAW, IND.
NIGHT NULLS 12/9/52G

500W, U, DA-2

1480 KC



RECD FCC 10/24/52 ACC 11/24/52 BL-4827

WRSW, WARSAW, IND.

1480 KC

WRSV

Measured Non-DA
(4-30-63ct)


Station WRSW
Warsaw, Indiana

500w, 1kw-LS, DA-2, U
1480 kc

29-6-3
nted because
ring increased
day power
age in day
pattern

EUGENE DIETZEN CO.

NO. 340 P DIETZEN GRAPH PAPER
POLAR CO-ORDIN.



WRSW ND PROOF
1480KC 500W
DEC. 1962

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

FCC File No. BL-9839
Accepted 3-26-63

Station WRSW
Warsaw, Indiana

1480 kc

WSAR

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WSAR
 Main Studio: Fall River, Massachusetts
 Frequency: 1430 kHz
 Power: 5 kW
 Notification Ref. No.: 1742
 Date: July 20, 1977
 Class: 1
 GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 41° 43' 20"
 West Longitude: 71° 11' 21"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (3A-1)
 Number of elements: 2
 Type of elements: Series excited, uniform cross-section, non-
 vertical steel towers.


TOWERS:	SW(#2)	NL(#1)
HEIGHT ABOVE INSULATORS:	397'	397' (215°)
PHASING:	471.0°	0°
FIELD RATIO:	1	1
SPACING AND ORIENTATION:	Towers are spaced 221.5' (120°) on a line bearing 247° true	
GROUND SYSTEM:	120-265' equally spaced copper radials plus a 43' square ground screen about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers	

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
RMS	RSS	RMS
561 mV/m	= mV/m	= mV/m


Note: This notification concerns changes in the daytime and nighttime
 directional antenna systems and radiation patterns.

Fig. 6
DA-1




PROPOSED HORIZONTAL PLANE RADIATION PATTERN

G = 215°	QUALITY RADIO CORPORATION FALL RIVER, MASSACHUSETTS Jules Cohen & Associates Consulting Electronics Engineers	STATION WSAR 1480 KHZ 5 KW U DA-1 MARCH 1976
-----------------	---	--




PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 5 DEGREES

QUALITY RADIO CORPORATION	STATION WSAR	FALL RIVER, MASSACHUSETTS
1480 KHZ	5 KW	U DA-1




PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 10 DEGREES

QUALITY RADIO CORPORATION	STATION WSAR	FALL RIVER, MASSACHUSETTS
1480 KHZ	5 KW	U DA-1




PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 15 DEGREES

QUALITY RADIO CORPORATION STATION WSAR FALL RIVER, MASSACHUSETTS
 1480 KHZ 5 KW U DA-1




PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 20 DEGREES

QUALITY RADIO CORPORATION
 1480 KHZ 5 KW U DA-1
 STATION WSAR FALL RIVER, MASSACHUSETTS




PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 20 DEGREES

QUALITY RADIO CORPORATION	STATION WSAR	FALL RIVER, MASSACHUSETTS
1480 KHZ	5 KW	U DA-1



PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 25 DEGREES


QUALITY RADIO CORPORATION	STATION WSAR	FALL RIVER, MASSACHUSETTS
1480 KHZ	5 KW	U DA-1



PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 30 DEGREES


QUALITY RADIO CORPORATION STATION WSAR FALL RIVER, MASSACHUSETTS
1480 KHZ 5 KW U DA 1

WSAR




PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 35 DEGREES

QUALITY RADIO CORPORATION	STATION WSAR	FALL RIVER, MASSACHUSETTS
1480 KHZ	5 KW	U DA-1




PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 40 DEGREES

QUALITY RADIO CORPORATION	STATION WSAR	FALL RIVER, MASSACHUSETTS
1480 KHZ	5 KW	U DA-1



PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 45 DEGREES


QUALITY RADIO CORPORATION	1480 KHZ	5 KW	U	DA-1	STATION WSAR	FALL RIVER, MASSACHUSETTS
---------------------------	----------	------	---	------	--------------	---------------------------



PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 50 DEGREES


QUALITY RADIO CORPORATION	STATION WSAR	FALL RIVER, MASSACHUSETTS
1480 KHZ	5 KW	U DA-1

WSAR



PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 55 DEGREES

QUALITY RADIO CORPORATION	1480 KHZ	5 KW	11 DAL	STATION WSAR	FALL RIVER, MASSACHUSETTS
---------------------------	----------	------	--------	--------------	---------------------------



PROPOSED RADIATION PATTERN AT VERTICAL ANGLE OF 60 DEGREES

QUALITY RADIO CORPORATION	STATION WSAR	FALL RIVER, MASSACHUSETTS
1480 KHZ	5 KW	U DA-1

WSAR

PROPOSED DAY
(4-24-58g)


Station WSAR
Fall River, Massachusetts

5kw, DA-2,U

1480 KC

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4 D. C.

*Granted 7/31/58 mod.
of C.P. to make changes
in DA system*



WSAR


MEASURED DAY
(2-26-60g)

Station WSAR
Fall River, Massachusetts


5kw, DA-2,U
1480 KC

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

11-23-62
fronted covering changed in
Front site and DA



North Latitude 41° 43' 23"
West Longitude 71° 11' 19"



MEASURED
HORIZONTAL PLANE PATTERN
FOR DAYTIME OPERATION
WSAR, FALL RIVER, MASSACHUSETTS
1480 KC 5 KW DA-2
JANUARY 1960

FCC File No. BL-7835
Accepted 2-18-60

WSAR
Fall River, Massachusetts

1480 KC


WSAR

PROPOSED NIGHT
(4-24-58g)


Station WSAR 5kw, DA-2,U
Fall River, Massachusetts 1480 KC

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

Granted 7/31/58 mod.
of CP to make changes
in PA system



NL 41° 43' 23''
WL 71° 11' 19''



FCC File No. BMP-8105
Accepted 4-11-58

WSAR
Fall River, Massachusetts

1480 KC

HORIZONTAL PLANE PATTERN FOR
PROPOSED NIGHTTIME OPERATION
WSAR, FALL RIVER, MASSACHUSETTS
1480 KC - 5 KW - DA-2
MARCH 1958

WSAR

MEASURED NIGHT
(2-26-60g)


Station WSAR
Fall River, Massachusetts

5kw, DA-2,U


1480 KC

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

11-23-62
printed & covering changes
in 4X mtr site and DA.



North Latitude 41° 43' 23''
West Longitude 71° 11' 19''



MEASURED
HORIZONTAL PLANE PATTERN
FOR NIGHTTIME OPERATION
WSAR, FALL RIVER, MASSACHUSETTS
1480 KC 5 KW DA-2
JANUARY 1960

FCC File No. BL-7835
Accepted 2-18-60

WSAR
Fall River, Massachusetts

1480 KC


MEASURED NON-DA
(2-26-60g)

Station WSAR
Fall River, Massachusetts

5kw, DA-2,U
1480 KC

North Latitude 41° 43' 23"
West Longitude 71° 11' 19"

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON, D. C.



FCC File No. BL-7835
Accepted 2-18-60

WSAR
Fall River, Massachusetts

1480 KC


WSDS

Measured Day
(8-24-62ct)

Station WYSI
Ypsilanti, Michigan

500w, DA-D, D
1480 kc

3-9-64
10.4
station




WSOS

Measured Non-DA
(8-24-62ct)

Station WYSI
Ypsilanti, Michigan

500w, DA-D, D
1480 kc

1/9/64
y for new
station



FCC File No. BL-9500
Accepted 8-8-62

Station WYSI
Ypsilanti, Michigan

1480 kc

YPSILANTI, MICH.

WS DS

PROPOSED DAY
(8-8-59g)

New Ann Arbor B/C Co.
Ypsilanti, Michigan


500w. D.
1480 KC

over

May 18, 1959
FIGURE 14-A
EXHIBIT 14-A

AMENDMENT

S = 90 Degrees.
U = 108 Degrees.
K = 190
Field Ratio = 1:1
RMS = 127 Mv/m.
G = 116 feet.
Azimuth 50 degrees T.



NL 42° 15' 50"
WL 83° 37' 45"

TOWER 2

TOWER 1

FCC File No. BP-13221 (Amended)
Accepted 7-13-59 (formerly BP-12447)

Ann Arbor B/C Co.
Ypsilanti, Michigan


1480 KC

Engineer John H Marsh

WTH 1

NORTH

COHEN & DIPPELL
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D.C. 20004



NORTH LATITUDE: 39° 30' 02"
WEST LONGITUDE: 87° 23' 10"

● MEASURED RADIAL

NIGHT PARAMETERS
TOWER NO. 1 1.0/0°
TOWER NO. 2 1.04/-105°
TOWER NO. 3 0.924/-7°
TOWER NO. 4 1.17/+62°

MEASURED HORIZONTAL PLANE RADIATION PATTERN
FOR THE NIGHTTIME OPERATION OF
WTH1, TERRE HAUTE, INDIANA
1480 kHz 1/5 KW DA-2 U
NOVEMBER 1970


WTHI

Measured Non-DA
(1-22-71ct)

Station WTHI
Terre Haute, Indiana

1kw, 5kw-LS, DA-2, U
1480 kc

COHEN & DIPPILL
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D.C. 20004



MEASURED NON-DIRECTIONAL UNATTENUATED
FIELD INTENSITY AT ONE MILE FOR
WTHI, TERRE HAUTE, INDIANA
1480 kHz 1/5 KW DA-2 U
NOVEMBER 1970


BMP-12801 Dated 10-6-69
 Modification of UP to make change in
 directional antenna system

WT+11

1kw, 5kw-LS, DA-2, U
 1480 kc

Station WTHI
 Terre Haute, Indiana

Proposed Night Nulls
 (10-28-69ct)



FCC File No. BMP-12801
 Accepted 10-14-69

Station WTHI
 Terre Haute, Indiana

1480 kc

WTHI

Proposed Night
(10-28-69ct)


Station WTHI
Terre Haute, Indiana

1kw, 5kw-LS, DA-2, U
1480 kc


Handwritten:
Modification of CP to make
inoperative in International
Antenna System

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4 D. C.

V = 0°



NORTH LATITUDE 39°30'06"
WEST LONGITUDE 87°23'19"



NIGHTTIME PARAMETERS				
PWS - 148.00 MW				
H - 115' 35" 4"				
TOWER	FIELD RATIO	SPACING	ORIENTATION	PHASE
No. 1	1.126	91.5°	N 8.84° E	114.5°
No. 2	1.0		REFERENCE TOWER	0°
No. 3	0.754	140°	N 25.1° E	24°
No. 4	1.0	171.32°	N 358.16° E	154.5°
No. 5	NOT USED AT NIGHT - DETUNED			
No. 6	NOT USED AT NIGHT - DETUNED			

COMPUTED HORIZONTAL
PLANE RADIATION PATTERN
FOR THE PROPOSED NIGHTTIME OPERATION OF
WTHI, TERRE HAUTE, INDIANA
1480 KHz 1 1/2 KW DA-2 U
AUGUST 1969

FCC File No. BMP-12801
Accepted 10-14-69

Station WTHI
Terre Haute, Indiana

1480 kc

Proposed Day
(10-28-69ct)

Station WTHI
Terre Haute, Indiana



1kw, 5kw-LS, DA-2, U
1480 kc

WTHI

NP-12801 GRANTED (11-6-69)
MODIFICATION OF CH 7-D
MAKE CHARGES IN
DIRECTIONAL ANTENNA
SYSTEM

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.

V = 0°



COMPUTED HORIZONTAL
PLANE RADIATION PATTERN
FOR THE PROPOSED DAYTIME OPERATION OF
WTHI, TERRE HAUTE, INDIANA
1480 KHz 1/5 KW DA-2 U
APRIL 1969

DAYTIME PARAMETERS		
RMS - 425.8 MV/M		
H - 165' - 89.4'		
FIELD RATIO	PHASE	
NO. 1	1.0	0°
NO. 2	NOT USED DURING DAY	
NO. 3	NOT USED DURING DAY	
NO. 4	NOT USED DURING DAY	
NO. 5	2.002	69.8°
NO. 6	2.132	138°

FCC File No. BMP-12801
Accepted 10-14-69

Station WTHI
Terre Haute, Indiana

1480 kc



WTHI

Measured Night
(1-22-71ct)

Station WTHI
Terre Haute, Indiana
NORTH

1kw, 5kw-LS, DA-2, U
1480 kc

COHEN & DIPPELL
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D.C. 20004



NORTH LATITUDE: 39° 30' 02"
WEST LONGITUDE: 87° 23' 10"

● MEASURED RADIAL

NIGHT PARAMETERS
TOWER NO. 1 10/0°
TOWER NO. 2 108/-105°
TOWER NO. 3 0.924/-7°
TOWER NO. 4 1.17/-62°

MEASURED HORIZONTAL PLANE RADIATION PATTERN
FOR THE NIGHTTIME OPERATION OF
WTHI, TERRE HAUTE, INDIANA
1480 kHz 1/5 KW DA-2 U
NOVEMBER 1970

FCC File No. BL-12840
Accepted 1-20-71

Station WTHI
Terre Haute, Indiana

1480 kc



WTHI

Measured Day
(1-22-71ct)

Station WTHI
Terre Haute, Indiana

1kw, 5kw-LS, DA-2, U
1480 kc

COHEN & DIPPELL
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D.C. 20004



DRY PARAMETERS

TOWER NO. 1 072/-163°

TOWER NO. 5 1.0/0°

TOWER NO. 6 0.883/+26°


MEASURED HORIZONTAL PLANE RADIATION PATTERN
FOR THE DAYTIME OPERATION OF
WTHI, TERRE HAUTE, INDIANA
1480 kHz 1/5 KW DA-2 U
NOVEMBER 1970

Proposed Day
(4-28-65cl)

Station WXIV
Windermere, Florida

5kw, DA-D, D
1480 kc

WVCF



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
$G_3 = 90^\circ$ ③ 1 0 /-25 170° 314' $G_2 = 200^\circ$ ② 2 0 /20 170° 314' $G_1 = 90^\circ$ ① 1 0 /25	TOWER No.	ELLIPTICAL HEIGHT G'	192° TOWER ORIENTATION S°	SPACING S'	PHASING V°	HORIZONTAL FIELD RMS F	FIELD RATIO F	ELEV. ANGLE B°	ELEVATION RMS FIELD E _g	CALL	WXIV
	1	90	182	170	25	242	1.0	0	515	FREQUENCY	1480 kc
	2	200	0	0	20	484	2.0	10		POWER	5 kw
	3	90	2	170	25	242	1.0	20		TIME OF OPERATION	DA-D
	4							30		TYPE OF OPERATION	Class III
	5							40		DAYTIME TOWERS	3
	6							50		NIGHTTIME TOWERS	0
	7							60		No. RADIO SETS PER TOWER	120
	8							70		LENGTH OF SPACES	90° 166'
	9							80		GROUND SURFACE DIMENSIONS	24' x 24'
	10							90		LAT.	28° 29' 51"
										LONG.	81° 28' 52"
										SUPERSEDES	
										PAT. NO.	640924
										FIG. 3 HORIZONTAL PATTERN American Home Stations, Inc. Windermere, Florida	

FCC File No. BP-16643
Accepted 4-7-65

Station WXIV
Windermere, Florida

1480 kc


Proposed Day
(12-29-66ct)

A. D. RING & ASSOCIATES - 10/60 - M

New; Yack Broadcasting Co., Inc.
Yackinville, North Carolina

1kw, DA-9, D
1480 kc

OVER



FCC File No. BP-17452
Accepted 12-8-66

New; Yackin Broadcasting Co., Inc.
Yackinville, North Carolina

1480 kc

WYDK

BL-12069 Granted (2-24-69)
 license covering new
 station

WYDK

WYDK 1480 KHz


1kw, DA-D, D
 1480 kc

Station WYDK
 Yadkinville, North Carolina

Measured Day
 (8-28-68ct)

A. D. RING &

N



FCC File No. BL-12069
 Accepted 8-21-68

Station WYDK
 Yadkinville, North Carolina

1480 kc


DL-12069 Granted (2-24-69)
license covering new station.

Measured Non-DA
(8-28-68ct)

Station WYDK
Yadkinville, North Carolina

1kw, DA-D, D
1480 kc

WYDK



FCC File No. BL-12069
Accepted 8-21-68



Station WYDK
Yadkinville, North Carolina

1480 kc

PROPOSED DAY
(6-14-61g)

New; Frederick County Bcstrs.
Winchester, Virginia

500w, DA-D,D
1480 KC



WILLIAM L. FOSS, INC.
Electronic Consultants
WASHINGTON, D. C.
227 14th Street N.W. RE 3883

WILLIAM L. FOSS, INC.
Electronic Consultants
WASHINGTON, D. C.
227 14th Street N.W. RE 3883

PATTERN NO
SUPERSEDES
APP

FCC File No. BP-12531
Accepted 5-19-61 (Amended)

Frederick County Broadcasters
Winchester, Virginia 1480 KC

CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

PART I

830705

11 a) New assignment ☒ b) Modification of characteristic of an assignment recorded in the plan ☐ c) Cancellation of an assignment ☐
 12 Modification under Section 4.2.14 Yes ☐ No ☐
 13 Date of bringing into service or cessation of operation

--	--	--

Year Month Day

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	(21) 1.5	(31) 2.5
r.m.s. value of radiation for station power (mV/m at 1 km)	(25) 321.8	(35) 160.9
Antenna type	(26) A	(36) A
Simple vertical antenna electrical height (degrees)	(27) 114.5	(37) 114.5

44 Remarks	COORDINATION UNDER ARTICLE 4:								
	COUNTRY	USA							
	IN PROGRESS	X							
	ACCEPTANCE OBTAINED								

CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

PART I

CANADA

Sheet No. 419

Date 830606

Assigned frequency (kHz)		(02)	1, 4, 9, 0,
Transmitting station	Name of the station	(03)	G, R, A, V, E, N, H, U, R, S, T, O, N,
	Call sign	(04)	_____
	Additional Identification	(05)	_____
	Station class	(06)	C,
	Operational Status	(07)	?
Country		(08)	CAN
Geographical coordinates of the transmitting station		(09)	7 9 W, 2, 4 ¹ 3, 3 ⁴ 4 N, 5 ¹ 2 3,

11 a) New assignment ☒ b) Modification of characteristic of an assignment recorded in the plan ☐ c) Cancellation of an assignment ☐

12 Modification under Section 4.2.14 Yes ☐ No ☒

13 Date of bringing into service or cessation of operation

--	--	--

Year Month Day

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	(21) 1.1	(31) 2.5
r.m.s. value of radiation for station power (mV/m at 1 km)	(25) 3.218	(35) 1.609
Antenna type	(26) A	(36) A
Simple vertical antenna electrical height (degrees)	(27) 11.45	(37) 11.45

44 Remarks	COORDINATION UNDER ARTICLE 4:							
	COUNTRY	USA						
	IN PROGRESS	X						
	ACCEPTANCE OBTAINED							

19-52

CBAM
1490

AIR SERVICES
TELECOMMUNICATIONS DIVISION
(5-10-116)



DEPARTMENT OF TRANSPORT

DESCRIPTIVE SHEET - OMNIDIRECTIONAL ANTENNA

Station Call: CBAM
Main Studio: Edmundston, New Brunswick
Frequency: 1490 Kc/s.
Power: 0.10 Kw.
Class: IV
Time: U

Notification Reference: NARBA Annex 3

Geographical Location:

North Latitude: $47^{\circ} 22'$ -
West Longitude: $68^{\circ} 20'$ -
(Exact location to be determined)

Antenna Characteristics:

Height: 105 ft. 60 degrees
Expected Efficiency: 90 mv/m at 1 mi. for 0.25 Kw.
or: 180 mv/m at 1 mi. for 1 Kw.

Ground System:

120 radials each 200 feet long

Type of Element:

Vertical tower radiator. Base insulated for series feed.

December 29, 1952

DEC 18-52 100 LATE 37

CFRC
1490

AIR SERVICES
TELECOMMUNICATIONS DIVISION

(5-10-107)



CANADA

DEPARTMENT OF TRANSPORT

DESCRIPTIVE SHEET - OMNIDIRECTIONAL ANTENNA

Station Call: CFRC
Main Studio: Kingston, Ontario
Frequency: 1490 Kc/s.
Power: 0.10 Kw. *100 W. 25*
Class: IV
Time: U

Notification Reference: NARBA Annex 3

Geographical Location:

North Latitude: 44° 13' 37"
West Longitude: 76° 29' 43"

Antenna Characteristics:

(see below)

Height: ----- ft. ----- degrees

Expected Efficiency: 56 mv/m at 1 mi. for 0.1 Kw.

or: 177 mv/m at 1 mi. for 1 Kw.

Ground System:

Counterpoise of parallel wires 130' long.

Type of Element:

T-Antenna: single wire, flat-top, 130 feet long, 110'
above ground.

December 18, 1952

CFWB

Description Sheet
(10-28-67ct)Station CFWB
Campbell River, B. C.250w, 1kw-LS, U, Class IV
1490 kcDESCRIPTIVE SHEET - OMNIDIRECTIONAL ANTENNA

STATION CALL: CFWB

MAIN STUDIO: CAMPBELL RIVER, B. C.

POWER: 1 KW D/0.25 KW Night

FREQUENCY: 1490 KC/5 CLASS: IV

NOTIFICATION LIST NO.: 232

DATE: September 28, 1967

GEOGRAPHICAL LOCATION:

NORTH LATITUDE: 50° 01' 01"

WEST LONGITUDE: 125° 15' 42"

MODE OF OPERATION:

ND (Non-directional 125° 15' 42")

ANTENNA HEIGHT ABOVE INSULATORS:

110' (60°)

GROUND SYSTEM:

120 radials are equally spaced, the north and south radials are greater than .33 wavelengths long (220'), all east and west radials are longer than 0.4 wavelengths (220') to provide an equivalent 0.4 wavelength ground radial system.

TYPE OF ELEMENT:

Square tower, uniform cross-section base insulated for series feed.

PREDICTED EFFECTIVE FIELD:

DAY 180 mv/m for 1 Kw

#176
Description Sheet
(3-30-63ct)

New Station
Campbell River, B.C.

CFWE
250w, U, Class IV
1490 kc

DESCRIPTION OF STATION

STATION: New

MAIN STUDIO: Campbell River, B.C.

POWER: 250 Watts

FREQUENCY: 1490 Kc/s

CLASS: IV

TYPE: U Operation

NOTIFICATION REFERENCE: 176

DATE: February 26, 1963

LOCATION:

North Latitude 50° 01' 01"

West Longitude 125° 15' 42"

DETAILS:

Mode of Operation:

ND (Non-directional) one element uniform cross section, guyed steel tower, base insulated for series feed.

HIGHT ABOVE INSULATORS:

110' (60°)

GROUND SYSTEM:

120 equally spaced radials, the north and south radials are greater than .33 wavelength long (220'), all east & west radials are longer than .4 wavelength (264') to provide an equivalent 0.4 wavelength ground radial system.

PREDICTED EFFECTIVE FIELD:

90 MW/M at 1 mile for 250 watts

or

180 MW/M at 1 mile for 1 Kw.




#199

CHYM

Description Sheet
(7-27-65ct)Station CHYM
Kitchener, Ontario5kw, 10kw-LS, DA-2, U, Class IV
1490 kc

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2



STATION CALL CHYM
 MAIN STUDIO Kitchener, Ontario
 FREQUENCY 1490 kc/s
 POWER Day 10 kw - 5 kw Night
 CLASS IV
 TIME Unlimited

NOTIFICATION REFERENCE 199..... DATE: May 10, 1965

GEOGRAPHICAL LOCATION Lat 43°23'06", Lon 80°30'00"

ARRAY CHARACTERISTICS Four elements, guyed, uniform cross section, base insulated, series feed. Height 165 feet or 90 degrees. No top loading.

ELEMENT	ONE	TWO	THREE	FOUR
BEARING	REF	00°	00°	00°
SPACING	REF	80° 146.8'	160° 293.6'	240° 440.4'
Day ratio	1000	1501	1147	246
Day phase	00°	-118.2°	117.6°	-30°
Night ratio	1000	1911	1632	567
Night phase	00°	-157.8°	44.3°	-113°

Ground System 120 radials per tower, #10 AWG bare, soft copper wire, spaced uniformly, depth 8 inches approximately. Radials bonded on a line between towers and bonded to soft copper strap at tower base. Maximum radial length 264 feet.

Day RMS 600 mv/m at 1 mile for 10 kw
 190 mv/m at 1 mile for 1 kw


Night RMS 393 mv/m at 1 mile for 5 kw
 176 mv/m at 1 mile for 1 kw

Mar 1965

5

#199

CHYM

Proposed Day
(7-27-65ct)Station CHYM
Kitchener, Ontario5kw, 10kw-LS, DA-2, U, Class IV
1490 kcPOLAR COORDINATE 359.31
DISTANCE

#199


CHYM

Proposed Night
(7-27-65ct)

Station CHYM
Kitchener, Ontario

5kw, 10kw-LS, DA-2, U, Class IV
1490 kc

K-E
PULP COORDINATE 350-31
REFUEL SYSTEM



DESCRIPTION SHEET
(8-22-61ct)

Station CKER
Kitchener, Ontario, Canada

5kw, 10kw-LS, DA-2, U,
1490 KC

REVISED

DIRECTIONAL ANTENNA DESCRIPTION SHEET



Station: CKER

Main Studio: Kitchener, Ont.

Frequency: 1490 kc.

Power: 10 kw Day/ 5 kw Night.

Classification List No. 300

Date: August 31, 1960

Location: North Lat. $43^{\circ} 23' 06''$
West Long. $80^{\circ} 30' 00''$

Antenna: Mode of Operation DA-2

4 guyed elements, uniform cross-section
base insulated, series fed.

Tower	#1 (South)	#2	#3	#4 (North)
Height above Insulators:	165'	165'	165'	165'
Overall height:	169'	169'	169'	169'
Spacing:	146 $\frac{2}{3}$ '	80°	80°	
Phasing day:	+139°	-6.0°	-139°	not used
Phasing night:	0°	-157.1°	+42.9°	-119.0°
Field ratio day:	1.0	1.89	1.0	
Field Ratio night	1.0	2.0	1.80	0.64

Ground System

120 radials per tower #10 AWG, bare soft-drawn copper wire,
uniformly spaced, depth 8" approximately, 264' long ($.4 \lambda$),
except for shortened radials between towers (bonded at inter-
sections).

Estimated Effective Field

393 mv/m (170 μ W at one mile)

601 mv/m (190 μ W at one mile)

Orientation of Towers

Towers are on a line bearing 0° of True North.

NOTE: This supersedes the data previously supplied for this assignment.

19.9.61


#150

PROPOSED DAY
(8-22-61ct)

Station CKCR
Kitchener, Ontario, Canada

5kw, 10kw-LS, DA-2, U
1490 KC

North Latitude $43^{\circ} 23' 06''$
West Longitude $80^{\circ} 30' 00''$



POLAR CO-ORDINATE 359.31

#150


PROPOSED NIGHT
(8-22-61ct)

Station CKCR
Kitchener, Ontario, Canada

5kw, 10kw-LS, DA-2, U
1490 KC

North Latitude $43^{\circ} 23' 06''$
West Longitude $80^{\circ} 30' 00''$

Vertical Angle 0°



#166

1501

Description Sheet
(2-28-62ct)

New Station
Wilmot Station, Nova Scotia

250w, 1kw, U, Class IV
1490 kc

DESCRIPTION SHEET - OMNIDIRECTIONAL ANTENNA

STATION CALL: LEW
MAIN STUDIO: Wilmot Station, N.S.
FREQUENCY: 1490 Kc/s
POWER: 1 Kw day/250 w night
CLASS: IV
TIME: N

Notification List No.: 166

Date: January 5, 1962

GEOGRAPHICAL LOCATION OF THE ANTENNA:

North Latitude: 44° 58' 36"

West Longitude: 65° 00' 32"

ANTENNA CHARACTERISTICS:

Height: 110' (60°)

Type of Element: Square uniform cross section, guyed,
insulated from ground, series fed, no
top loading.

Ground System: 120 radials of No. 10 P & S bare copper
wire, equally spaced around the tower,
extending 265' (approx. 0.4 of a wave-
length) and buried at a depth of approx.
8 inches.

Expected Efficiency: 181 mv/m at 1 mile per Kw. radiated
90.5 mv/m at 1 mile for 250 w. radiated



#19 10-283
AIR SERVICES
TELECOMMUNICATIONS DIVISION

5-10-283




DEPARTMENT OF TRANSPORT

CKBM
1490
REFER TO FILE NUMBER

DESCRIPTIVE SHEET - OMNIDIRECTIONAL ANTENNA

Station Call: ~~NEW~~ CKBM
Main Studio: Montmagny, Quebec
Frequency: 1490 KC.
Power: 250 W.
Class: IV
Time:



Notification Reference: #79 Dated: October 28, 1953

Geographical Location:

North Latitude: 47° 00' 09"

West Longitude: 70° 31' 01"

Antenna Characteristics:

Height: 110 Ft. 60 degrees

Expected Efficiency: mv/m at 1 mi. for 1 KW
or: 180 mv/m at 1 mi. for 1 KW

Ground System:

120 radials, spaced 3°, each 165' long.

Type of Elements:

One, uniform cross-section vertical radiator,
guyed, series fed, no top loading.

ALLOCATIONS SECTION
Dec 1 1953
ENGINEERING BUREAU
STANDARD BROADCAST DIVISION

Description Sheet
(9-26-68ct)

Station CKBM
Montmagny, Quebec

250w, 1kw-LS, U, Class IV
1490 kc

CKBM

TABLE 1

C O R R E C T E D
ANTENNA DESCRIPTION SHEET

STATION CALL: CKBM
MAIN STUDIO: MONTMAGNY, QUEBEC
FREQUENCY: 1490 kHz
POWER: .25N/1D kW
CLASS: IV
MODE: ND-U
TIME: UNLIMITED

NOTIFICATION LIST NO.: .167..... DATE: January 19, 1962

GEOGRAPHICAL LOCATION: Latitude: 46° 59' 55" North
Longitude: 70° 31' 01" West

ANTENNA CHARACTERISTICS -

PHYSICAL HEIGHT: 230' (125.5°)

TYPE OF ELEMENT: Steel tower of uniform square cross section; guyed, base insulated and series fed. Loaded by an umbrella consisting of the top 30' of the upper guy wires, a horizontal skirt and intermediate radial wires to provide an electrical height of approximately 163°.

GROUND SYSTEM: 120 equally spaced radials of #10 AWG bare copper wire, extending 165' (0.25λ) and buried 6"-8".

PREDICTED EFFICIENCY: 112.5 mV/m at 1 mile for .25 kW night
225 mV/m at 1 mile for 1 kW day

Note:

This concerns a reduction in tower height only.

CKEN

Description Sheet
(9-26-68ct)

Station CKEN 500w, 1kw-LS, DA-1, U, Class IV
Kentville, Nova Scotia 1490 kc

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

Station : CKEN Main Studio : Kentville, N.S.
Frequency : 1490 KHz Power : 1-D/0.5-N Class: IV
Notification List No.: 244 Date: AUGUST 23, 1968

GEOGRAPHICAL LOCATION : 45° 06' 40" N. Lat.
OF THE ANTENNA SYSTEM 64° 29' 35" W. Long.

ANTENNA CHARACTERISTICS :

Mode of Operation : DA-1, full time

No. of Elements : 2 (Two)

Type of Elements : Guyed, uniform cross-section,
base insulated, series fed,
no top loading.

Tower No. : 1 (SE) 2 (NW)

Height above insulator : 121.5' (66.3°) 121.5'

Spacing : 121.5' (66.3°)

Field Ratio : 1 1.45

Phasing : 0° + 147°

Orientation : 337° East of True North.

Ground System : 120 equiangularly spaced ra-
dials per tower, No. 10 AWG
soft-drawn copper wire, buried
8" approx., covering an area
equivalent to a 0.4 wavelength
radial system.

PREDICTED EFFECTIVE FIELD :

175 mV/m at one mile for 1 Kw radiated
124 mV/m at one mile for 0.5 Kw radiated.


PETER CAHN & ASSOCIATES

CKEN

Proposed Day & Night
(9-26-68ct)

Station CKEN
Kentville, Nova Scotia

500w, 1kw-LS, DA-1, U, Class IV
1490 kc




WNUS

PROPOSED DAY
(4-22-59g)

Station WTXL
West Springfield, Massachusetts

250w, 1kw-LS, DA-D,D
1490 KC



FCC File No. BP-12632
Accepted 3-20-59 (Amended)

WTXL
West Springfield, Massachusetts 1490 KC


quarrel 1 to increase any power
to 1 kw and install DA-D
5-11-60

WNUS

MEASURED DAY
(7-26-61ct)


Station WTXL 1kw, DA-D,D
West Springfield, Massachusetts 1490 KC

1-20-61
printed for
A-D



North Latitude $42^\circ 06' 00''$
West Longitude $72^\circ 37' 30''$

Engineer: LAWRENCE A. REILLY



MEASURED DAYTIME DA RADIATION
WTXL - WEST SPRINGFIELD, MASS.
1490 KC - 1 KW - DA-D

WNUS


MEASURED NON-DA
(7-26-61ct)

Station WTXL
West Springfield, Massachusetts 1490 KC

1kw, DA-D,D

North Latitude 42° 06' 00"
West Longitude 72° 37' 30"

Engineer: LAWRENCE A. REILLY



MEASURED NON-DIRECTIONAL RADIATION
WEST SPRINGFIELD, MASS.
1490 KC - 1 KW - DA-D

RCC File No. BL-8342
Accepted 6-16-61

WTXL
West Springfield, Massachusetts 1490 KC


WOHI

PROPOSED DAY
(2-2-59g)

Station WOHI
East Liverpool, Ohio

250w, 500w-LS, DA-D,U
1490 KC

*limited power
new station
1490*



A. D. RING & ASSOCIATES - 1/34 - M

FCC File No. BP-12678
Accepted 1-13-59

WOHI
East Liverpool, Ohio


1490 KC

WOHI

Measured Non-DA
(9-27-62ct)

Station WOHI
East Liverpool, Ohio

250w, 500w-LS, DA-D, U
1490 kc



FCC File No. BL-9531
Accepted 8-29-62

Station WOHI
East Liverpool, Ohio

1490 kc


WOLF

Proposed Day
(4-30-63ct)

Station WOLF
Syracuse, New York

250w, 1kw-LS, DA-D, U
1490 kc

8-9-63
Created mod.
FCC to make
change in
A system.




E_{RMS} 180 MV/M

----- MEOV

LATITUDE: 43° 03' 30"
LONGITUDE: 76° 10' 01"

ANTENNA PARAMETERS



JOHN H. MULLANEY
AND
ASSOCIATES
A DIVISION OF MULTIRONICS, INC.

FIGURE 3

AMENDED DAYTIME DIRECTIONAL
HORIZONTAL POLAR PATTERN


RADIO STATION
WOLF
SYRACUSE, NEW YORK

1490 KC 0.25/1 KW-LS, DA-D, U

Measured Day
(11-29-65ct)

Station WOLF
Syracuse, New York

WOLF
250w, 1kw-LS, DA-D, U
1490 kc



$E_{RMS} = 173 \text{ MV/M}$

LATITUDE: 43° 03' 30"
LONGITUDE: 76° 10' 01"

ANTENNA PARAMETERS

N 347.5° E
#2 1,76.5°
S
#1 1,20°

S = 45°-82.6'
G₁ = 180°
G₂ = 90°

FIGURE 18
MEASURED DAYTIME
HORIZONTAL POLAR PATTERN

RADIO STATION WOLF
SYRACUSE, NEW YORK

1490 KC

0.25/1 KW-LS, DA-D, U

WY BROADCASTING CO., INC.
ENGINEERING DEPARTMENT
ITHACA, N.Y.

FCC File No. BL-11020
Accepted 8-31-65


Station WOLF
Syracuse, New York

1490 kc

Measured Non-DA
(11-29-65ct)

Station WOLF
Syracuse, New York

WOLF
250w, 1kw-LS, DA-D, U
1490 kc



$E_{RMS} = 119 \text{ MV/M}$

LATITUDE: 43° 03' 30"

LONGITUDE: 76° 10' 01"

ANTENNA PARAMETERS

VY BROADCASTING CO., INC.
ENGINEERING DEPARTMENT
ITHACA, N.Y.

FIGURE 16
MEASURED NON-DA
HORIZONTAL POLAR PATTERN

RADIO STATION WOLF
SYRACUSE, NEW YORK

1490 KC

0.25/1 KW-LS, DA-D, U

FCC File No. BL-11020
Accepted 8-31-65

Station WOLF
Syracuse, New York


1490 kc

1490 KC

WVEC

MEASURED NON-DIRECTIONAL
(8/16/55G)STATION WVEC
HAMPTON, VIRGINIA250W
NON-DA, U

1490 KC 1490



109
DESCRIPTION SHEET
(1-28-65ct)

New Station
St. Catharines, Ontario

1kw, DA-D, D, Class II
1500 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET -

STATION : New MAIN STUDIO : St. Catharines, Ontario.
FREQUENCY : 1500 KC/S POWER : 1 KW, Class: II
NOTIFICATION LIST NO. 189 DATE : July 20, 1964


GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM

: North Latitude $43^{\circ} 12' 49''$
: West Longitude $79^{\circ} 11' 05''$

ANTENNA CHARACTERISTICS

MODE OF OPERATION : DA-D (Directional, daytime only)
NUMBER OF ELEMENTS : Two (2)
TYPE OF ELEMENTS : Uniform cross-section guyed steel towers, base insulated for series feed, no top loading
TOWER : 1 (W) 2 (E)
HEIGHT ABOVE INSULATORS : 110' (60.3°) 110' (60.3°)
OVERALL HEIGHT : 115' 115'
SPACING : 328' (180°) between towers
PHASING : 0° 0°
FIELD RADIO : 1.0 1.2
ORIENTATION : Tower on line bearing 100° East of True North
GROUND SYSTEM : 120 equally spaced radials of B and S No. 10 soft drawn bare copper wire per tower extending to distances between .36 and .5 wavelengths except where bonded on the common chord and buried approximately 8 inches.
PREDICTED EFFECTIVE FIELD : 175 MV/M at 1 mile for 1 KW.

1kw, DA-D, D, Class II
1500 kc



PROJECT #11401

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CKAY MAIN STUDIO: DUNCAN, B.C.
FREQUENCY: 1500 kHz POWER: 5 kW Day, 1 kW Night
NOTIFICATION LIST: 295 DATE: August 8, 1972
GEOGRAPHICAL LOCATION: Latitude 48° 44' 21" North
Longitude 123° 41' 58" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-2
Number of Elements: 2 (Two)
Type of Elements: Guyed steel towers, uniform cross-section, base insulated for series feed

<u>TOWER</u>	#1 (East)	#2 (West)
Height above base insulator:	130' (71.3°)	130' (71.3°)
Overall Height:	134'	134'
Day Ratio:	1.0	0.73
Day Phasing:	0°	-84°
Night Ratio:	1.0	0.85
Night Phasing:	0°	-63°


GROUND SYSTEM: 120 equally spaced radials per tower of No. 10 AWG bare soft copper wire, buried approximately 8 inches. No. 4 AWG copper wire joins the radials along the common chord. The effective length of the ground system is 0.4 wavelength.

SPACING AND ORIENTATION: Tower No. 2 is spaced 218' (120°) along a line bearing 275° True from Tower #1.

PREDICTED EFFECTIVE FIELDS:

Daytime 404 mV/m at 1 mile for 5 kW
181 mV/m at 1 mile for 1 kW
Nighttime 183 mV/m at 1 mile for 1 kW

REVISED MAY 31, 1972



#184

CKAY

Description Sheet
(6-29-64ct)New Station
Duncan, B.C.1kw, DA-1, U, Class II
1500 kc

2.4 DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: NEW

Main Studio: Duncan, B.C.

Frequency: 1500 kc/s

Power: 1 KW Class: II

Notification List No: 184

Date: February 10, 1964

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM:

North Latitude: 48° 44' 19"

West Longitude: 123° 41' 54"

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-1

Number of Elements: 2

Type of Elements: Guyed, uniform cross section,
base insulated, series fed, No
top loading.

TOWER:

No. 1 East

No. 2 West

HEIGHT ABOVE INSULATORS: 130'

130' (71.3°)

OVERALL HEIGHT: 134'

134'

SPACING:

218' (120°)

PHASING:

0°

-63°

FIELD RATIO:

1.0

0.85

ORIENTATION:

Towers on a line bearing 95° east of North

GROUND SYSTEM:


120 radials per tower of No. 10 AWG soft drawn copper
wire. Radials running between towers bonded to No. 4
AWG stranded copper wire positioned at right angles to
tower line. Effective length of ground system 0.4.

Predicted Effective Field RMS 183 mv/m (183mv/m for 1Kw)

Revised February 1962

✓ Bk

1kw, DA-1, U, Class II
1500 kc



DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CKAY MAIN STUDIO: DUNCAN, B.C.
 FREQUENCY: 1500 kHz POWER: 10 kW Day, 1 kW Night
 NOTIFICATION LIST: 383 DATE: March 28, 1979

GEOGRAPHICAL LOCATION: Latitude 48° 44' 21" North
 Longitude 123° 41' 58" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-2
 Number of Elements: 2 (Two)
 Type of Elements: Guyed steel towers, uniform cross-section, base insulated for series feed

<u>TOWER</u>	#1 (East)	#2 (West)
Height above base insulator:	130' (71.3°)	130' (71.3°)
Overall Height:	134'	134'
Day Ratio:	1.0	.31
Day Phasing:	0°	-81.7°
Night Ratio:	1.0	0.85
Night Phasing:	0°	-63°

GROUND SYSTEM: 120 equally spaced radials per tower of No. 10 AWG bare soft copper wire, buried approximately 8 inches. No. 4 AWG copper wire joins the radials along the common chord. The effective length of the ground system is 0.4 wavelength.

SPACING AND ORIENTATION: Tower No. 2 is spaced 218' (120°) along a line bearing 275° True from Tower #1.

PREDICTED EFFECTIVE FIELDS:

Daytime 560 mV/m at 1 mile for 10 kW
 177 mV/m at 1 mile for 1 kW

Nighttime 183 mV/m at 1 mile for 1 kW

This notification concerns only a change in the day-time power and radiation pattern. Please retain the night-time radiation patterns, which were notified in Change List 184 dated February 10, 1964.

CKAY




FIGURE 2
HORIZONTAL RADIATION PATTERN
DAYTIME - POLAR PLOT

CKAY DUNCAN, B.C.
1500 kHz 10 kW D/1 kW N DA-2 CLASS II
PROJECT #11406 REV. JANUARY 12, 1978

D.E.M. ALLEN & ASSOCIATES LTD
CONSULTING ENGINEERS

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: (NEW)

Main Studio: Dallas, Georgia

Frequency: 1500 kHz

Power: 1kw Day

Notification List No. 1783

Date: November 2, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:North Latitude: 33 56' 42"
West Longitude: 84° 49 41"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements:

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER: SE(#1) NW(#2)

HEIGHT ABOVE
INSULATORS: 170' (93.3°) 170' (93.3°)

DAY PHASING: 0° 45°

DAY FIELD RATIO: 1.00 0.75


SPACING AND
ORIENTATION: The towers are spaced 295.27' (162.1°) on a line
bearing 346.0° true.GROUND SYSTEM: 120-164' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap along
intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD	Q
	RMS	RSS	RMS	Factor
Day 1/	175.00 mv/m	187.96 mv/m	183.86 mv/m	$\frac{6 f(e)}{mv/m}$


1/ By adjustment of input power.

NL: 33° 56' 41.7"
WL: 84° 49' 40.6"



STANDARD HORIZONTAL RADIATION PATTERN

PROPOSED AM STATION
PAULDING PRODUCTIONS, INC.
1500 KHZ - 1 KW DA-D
DALLAS, GEORGIA
MARCH 1977




K FACTOR	150.368 mV/m
THEO. RMS	175 mV/m adj.
THEO. RSS	187.961 mV/m
STD. RMS	183.858 mV/m
Q FACTOR	6
ELECT. HEIGHT	96° - 170 FEET

ROBERT L. MILERS
CONSULTING RADIO ENGINEER
P.O. BOX 12 ROLLA, MISSOURI 65401 PHONE 314 266-2146

NL 33° 56' 41.7"
WL 84° 49' 40.6"

EXHIBIT E-5.1
Page 2



STANDARD HORIZONTAL RADIATION PATTERN

PROPOSED AM STATION
PAULDING PRODUCTIONS, INC.
1500 KHZ - 1 KW DA-D, 0.5 KW CH
DALLAS, GEORGIA
FEBRUARY 1978

CRITICAL HOURS PATTERN

0.75 / 45° 1.0 / 0°
346° ← + ——— 162° — 295.27 feet ——— + ———

K FACTOR	106.323 mV/m
THEO. RMS	123.74 mV/m
THEO. RSS	132.904 mV/m
STD. RMS	130.007 mV/m
Q FACTOR	6
ELECT. HEIGHT	96° - 170 FEET

ROBERT L. MIERS
CONSULTING RADIO ENGINEER
P.O. BOX 12 ROLLA, MISSOURI 65401 PHONE 314 366-3146

WHARTON, TEXAS

KANI


PROPOSED DAY & NIGHT
(8-8-59p)

New; V. M. Preston
Wharton, Texas

500w, DA-1, U

1500 KC

2-8-64
granted CP
for a new
station



S=160°=291.6'

G'S=98.7°=180'

J. G. ROUNTREE
CONSULTING RADIO ENGINEER
5622 DYER STREET
DALLAS 6, TEXAS

0.559/-63.5° 1/0° 0.559/63.5°
③ ← S → ② ← S → ① -21°T

NL 29° 19' 22"
WL 96° 03' 32"

RMS = 128 MV/M

FCC File No. BP-13223
Accepted 7-13-59

-----MEOV

V. M. Preston
Wharton, Texas

590310

V. M. PRESTON
WHARTON, TEXAS
1500 KC, 500W, DA-1, U

FIGURE 4A

1500 KC


WHARTON, TEXAS

KANI

PROPOSED DAY & NIGHT NULLS
(8-8-59g)

New; V. M. Preston
Wharton, Texas

500w, DA-1, U
1500 KC



S=160°=291.6'

G'S=98.7°=180'

0.559/-63.5° 1/0° 0.559/63.5°
③ ← S → ② ← S → ① — 21° T →

NL 29° 19' 22"
WL 96° 03' 32"

RMS = 128 MV/M

FCC File No. BP-13223
Accepted 7-13-59

-----MEOV

V. M. Preston
Wharton, Texas

J. G. ROUNTREE
CONSULTING RADIO ENGINEER
5622 DYER STREET
DALLAS 6, TEXAS


V. M. PRESTON
WHARTON, TEXAS
1500 KC, 500W, DA-1, U

590310

FIGURE 4 B

1500 KC

K A N I




HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION:

G'S = 98.7°
= 180°

S = 160°
= 291.6°



STATION: K A N I

LOCATION: WHARTON, TEXAS

FREQUENCY: 1500 KHz

POWER: 0.5 KW-U DA-1

LATITUDE: 29 d 19 m 22 s


LONGITUDE: 96 d 03 m 32 s

WHEN USED: DAY AND NIGHT

R.M.S. FIELD: 123.6 MV/M

DATE: JANUARY, 1978


KANI



HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION:

G'S = 98.7°
 = 180°
 S = 160°
 = 291.6°



STATION: K A N I

LOCATION: WHARTON, TEXAS

FREQUENCY: 1500 KHz

POWER: 0.5 KW-U DA-1

LATITUDE: 29 d 19 m 22 s

LONGITUDE: 96 d 03 m 32 s

WHEN USED: DAY AND NIGHT

R.M.S. FIELD: 123.6 MV/M


DATE: JANUARY, 1970

KOKN

Proposed Day
(11-29-65ct)


Station KOSG
Pawhuska, Oklahoma

5kw, UA-U, U
1500 kc



HORIZONTAL RADIATION PATTERN

ANTENNA LAYOUT



KOSG

Station
1500 kc
Frequency

PAWHUSKA, OKLAHOMA

5 kw
Power

Location

36° 40' 00", 96° 21' 48"

PROPOSED DAYTIME

G's = 120'

Fig. 1

FCC File No. BP-16736
Accepted 11-18-65

Station KOSG
Pawhuska, Oklahoma

1500 kc


KOKN

Measured Day
(5-28-68ct)

Station KOSG
Pawhuska, Oklahoma

5kw, DA-D, D
1500 kc

6-3-68
GRANTED
LICENSE
COV. CHANGE



Theoretical Values

#2 $\circ$ 0.7/-90°

S

#1 $\circ$ 1.0/0°

G = 120' = 66°

S = 300' = 165°

RADIO STATION KOSG
PAWHUSKA, OKLAHOMA

MEASURED DIRECTIONAL
HORIZONTAL PLANE RADIATION PATTERN
1500 KHZ 5000 WATTS

021568-3

FIGURE 3

MERL SAXON
CONSULTING RADIO ENGINEER
LUFKIN, TEXAS

FCC File No. BL-11960
Accepted 5-8-68

Station KOSG
Pawhuska, Oklahoma

1500 kc



KOKN

Measured Non-DA
(5-28-68ct)

Station KOSG
Pawhuska, Oklahoma

5kw, DA-D, D
1500 kc

6-3-68
GRANTED
LICENSE
COV. CHANGES



RADIO STATION KOSG PAWHUSKA, OKLAHOMA MEASURED NON-DIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN 1500 KHZ 500 WATTS	
021568-2	MERL SAXON CONSULTING RADIO ENGINEER LUFKIN, TEXAS
FIGURE 2	


KROQ KBBQ

Measured Day
(2-28-68ct)

Station KBBQ
Burbank, California

1kw, 10kw-LS, DA-2, U
1500 kc

2-9-68
GRANTED
LICENSE



THEORETICAL		OPERATING	
6 0.920/57.6°	2 0.246/34.9°	6 0.905/89.0°	2 0.250/133.0°
5 1.000/57.6°	5 0.246/115.1°	5 1/0°	3 0.250/81.0°
N. LAT. 34° 11' 47" S2-S3=450°=820 FT RMS=604 MV/M		N. LAT. 34° 11' 47" S2-S3=450°=820 FT RMS=604 MV/M	
W. LONG 118° 15' 30" S5-S6=35.5°=68.5 FT G=90°=164'		W. LONG 118° 15' 30" S5-S6=35.5°=68.5 FT G=90°=164'	
HAMMETT & EDISON CONSULTING RADIO ENGINEERS SAN FRANCISCO		RADIO STATION KBBQ 1500 KHZ 1 KW 10 KWLS DA-2 BURBANK, CALIFORNIA	

MEASURED HORIZONTAL RADIATION DAYTIME

UNATTENUATED FIELD INTENSITY
AT ONE MILE
1967 MEASUREMENTS

631015.1

FIGURE 13B

FCC File No. BL-10954
Accepted 1-30-68

Station KBBQ
Burbank, California

1500 kc


~~KBBQ~~ ~~KBBQ~~

Measured Night
(2-28-68ct)

Station KBBQ
Burbank, California

1kw, 10kw-LS, DA-2, U
1500 kc

2-9-68
GRANTED
LICENSE



THEORETICAL	OPERATING
1 1.0000 / 2.00°	1 0.384 / 107.5°
2 2.3982 / 117.17°	2 0.791 / 122.0°
3 2.3982 / 117.17°	3 1.000 / 0.0°
4 1.0000 / 2.00°	4 0.302 / 110.5°

N. LAT. 34° 11' 47" RMS=195 MV/M S=90°=164'
W LONG 118° 15' 30" G=90°=164'

HAMMETT & EDISON CONSULTING RADIO ENGINEERS SAN FRANCISCO	RADIO STATION KBBQ 1500 KHZ, 1 KW, 10 KWLS, DA-2 BURBANK, CALIFORNIA
---	--

MEASURED HORIZONTAL RADIATION NIGHTTIME

UNATTENUATED FIELD INTENSITY
AT ONE MILE
1967 MEASUREMENTS

6310151

FIGURE 13C

FCC File No. BL-10954
Accepted 1-30-68

Station KBBQ
Burbank, California

1500 kc

KBBQ

KBBQ

Measured Night Nulls
(2-28-68ct)


Station KBBQ
Burbank, California

1kw, 10kw-LS, DA-2, U
1500 kc

RADIO STATION KBBQ

MEASURED HORIZONTAL RADIATION, NIGHTTIME

2-9-68
GRANTED
LICENSE



631015.1
FCC File No. BL-10954
Accepted 1-30-68

Hammett & Edison
Consulting Radio Engineers
Station KBBQ
Burbank, California

FIGURE 13D
1500 kc

KROQ


KBBQ

Measured Non-DA
(2-28-68ct)

Station KBBQ
Burbank, California

1kw, 10kw-LS, DA-2, U
1500 kc

2-9-68
GRANTED
LICENSE




FCC File No. BL-10954
Accepted 1-30-68

Station KBBQ
Burbank, California

1500 kc

1kw, 10kw-LS, DA-2, U
1500 kc

2-7-66
WANTED CP
MAKE CHANGES
DAYTIME SYSTEM. DA



RMS = 615 MV/M

RADIO STATION KBLA
1500 KC. 1 KW. 10 KW-LS. DA-2
BURBANK, CALIFORNIA

UNATTENUATED FIELD INTENSITY
AT ONE MILE '

FIGURE 6

1500 kc

V-100


~~KBBQ~~ ~~KBLA~~

Proposed Night
(2-24-65 et)

Station KBLA
Burbank, California


1kw, 10kw-LS, DA-2, U
1500 kc

B.P. 11425
CP 2-11-65



N LAT 34° 11' 47"
W LONG 118° 15' 30"

S = G = 90° = 164'
RMS = 192 MV/M



PROPOSED HORIZONTAL RADIATION NIGHTTIME

UNATTENUATED FIELD INTENSITY
AT ONE MILE

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION KBLA
1500 KC. 1 KW. 10 KW-LS. DA-2
BURBANK, CALIFORNIA

641212.1

Figure 3

FCC File No. BMP-11425
Accepted 2-11-65 Amended

Station KBLA
Burbank, California

1500 kc


KROQ ~~KBBQ~~ ~~KBLA~~

Proposed Night Nulls
(2-24-65ct)

Station KBLA
Burbank, California

1kw, 10kw-LS, DA-2, U
1500 kc

RADIO STATION KBLA



Hammett & Edison
Consulting Radio Engineers

Figure 3A

641212.1

PROPOSED KSTP, ST. PAUL, MINN.
NIGHT 330° 340° 350° 0 10°

Revised 1/1/51
2050 kw, DA-2

KSTP
EXHIBIT VI

Parameters for 1500 kc

.5/-82.30 - 102.70 - 1/00 - 102.70 - .5/86.30
-87° (187°) -87°

Height - W - 291'
C & E - 335'

*20' tower
top winding*

NORTH

3000 2000 1000
MV/M

LINE OF TOWERS

106.50

WJSV - 111.50 - 930 MI

SITE: 45° 01' 31" N
93° 02' 02" W

CALCULATED UNATTENUATED RADIATION DIAGRAM AT ONE MILE

RMS FIELD 1590 MV/M

KSTP, ST. PAUL, MINNESOTA

1460 KC.
1500

50 KW

210°

200°

190°

180°


170°

160°

150°

KSTP, St. Paul, Minn. 1500 kc

330° 340° 350° 0 10° 20° 30°




LTC 11-2-65

50kw, DA-N, U
1500 kc

Station KSTP
St. Paul, Minnesota

Measured Night
(8-27-65ct)

A. D. R.




50kw, DA-N, U
1500 KC

Station KSTP
St. Paul, Minnesota

Measured Non-DA
(8-27-65ct)

A. D. RING &



FCC File No. BZ-5648
Station KSTP
St. Paul, Minnesota
Accepted 8-20-65
1500 kc


KTXO

Proposed Day
(6-28-67ct)


Station KTXO
Sherman, Texas

1kw, DA-D, D
1500 kc

OVER



HORIZONTAL RADIATION PATTERN



KTXO	SHERMAN, TEXAS	33° 41' 30", 96° 32' 22"
Station	Location	
1500 kc	1 KW DA-D	PROPOSED CALCULATED DAYTIME PATTERN
Frequency	Power	

$$G_a = 145 \text{ FT.} = 79.6^\circ$$

Station KTXO
Sherman, Texas

Fig. 1

1500 kc

FCC File No. BP-17679
Accepted 6-9-67


KXRX

Proposed Night
(6-28-65ct)

Station KXRX
San Jose, California

5kw, 10kw-LS, DA-2, U
1500 kc

11-5-65
GR INCR PWR
CHG DA




KXRX

Measured Night
(12-29-66ct)

Station KXRX
San Jose, California

5kw, 10kw-LS, DA-2, U
1500 kc

12-15-66
→ PAID
LICENSE
COVERING
INCREASE
IN POWER.



N. Lat. $37^\circ 21' 28''$
W. Long $121^\circ 52' 17''$

— Measured
--- Calculated




FIG. 2

MEASURED NIGHTTIME HORIZONTAL RADIATION

KXRX 1500 KC 5.0 KW DA-2

A.E. Towne Assoc. Inc., Radio Eng. Consultants, San Carlos, Calif.


KXRX

1 Day
(ct)

Station KXRX
San Jose, California

5kw, 10kw-LS, DA-2, U
1500 kc

6K INCR PWR
CHG PA




K X R X

PROPOSED DAY
(3-26-58g)

Station KXRX
San Jose, California

1kw, 10kw-LS, DA-2, U
1500 KC

12-7-60
granted CP for
DA-2
3-8-62 granted
P for increase in
day power and
larger in day DA
system.



FCC File No. BP-10,483
Accepted 3-21-58 (Amended)

KXRX
San Jose, California



KXRX - San Jose
Proposed 10 KW D.A.

1500 KC

Measured Day
(12-29-66ct)

Station KXRX
San Jose, California

5kw, 10kw-LS, DA-2, U
1500 kc



KXRX

Measured Non-DA
(12-29-66ct)


Station KXRX
San Jose, California

5kw, 10kw-LS, DA-2, U
1500 kc

12-15-66
GRANTED LICENSE
COVERING
INCREASE
IN POWER

EUGENE DIETZEN CO.
MADE IN U.S.A.

NO. 340-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-11443
Accepted 12-5-66

Station KXRX
San Jose, California

1500 kc


WAKE

Measured Day
(8-28-68ct)

Station WAKE
Valparaiso, Indiana

1kw, DA-D, D
1500 kc

*BL-12053
Granted 1-31-69
license covering
changes*



RMS
MEOV

185.2 MV/M

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 2A	STATION DATA
G's = 106.5° S = 160° #1 0.79/0° #2 1/1° 110° T	TOWER No.	ELECTRICAL HEIGHT h'	SPACING s'	PHASING φ'	FIELD RATIO F	MEASURED DAYTIME DIRECTIONAL PATTERN	CALL WAKE FREQ 1500 kHz POWER 1 Kw TYPE DA TIME DAYTIME LAT. 41-26-36 LONG. 87-02-54
	1					*****	
	2						
	3						
	4						
	5						
	6						
	7						
	8						
	9						
	10						
	DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐					JUNE 1968 PROOF	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.

FCC File No. BL-12053
Accepted 8-16-68

Station WAKE
Valparaiso, Indiana

1500 kc


WAKE

Measured Non-DA
(8-28-68ct)

Station WAKE
Valparaiso, Indiana

1kw, DA-D, D
1500 kc

*BL-12053
Granted 1-31-67
license covering
changes*



RMS MEQV 97.2 MV/M

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 2	STATION DATA
G's = 106.5° S = 160° No. 1 No. 2 (NC) 110° T	TOWER No.	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	MEASURED NON-DA RADIATION PATTERN USING WEST TOWER ***** JUNE 1968 PROOF	CALL WAKE FREQ 1500 kHz POWER 0.25 kw TYPE NDA TEST TIME DAYTIME LAT. 41-26-36 LONG. 87-02-54
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐						θ° 0°	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.

FCC File No. BL-12053
Accepted 8-16-68

Station WAKE
Valparaiso, Indiana

1500 kc


WAKE

MEASURED
Proposed Day
(8-28-67ct)

Station WAKE
Valparaiso, Indiana

1kw, DA-D, D
1500 kc

8-11-67
GRANTED CP
to make changes
in antenna system



RMS 179 MV/M
MEOV

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 2	STATION DATA
S = 160° G's = 106.5° No. 1 0.837/0° S No. 2 1/3°	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	MEASURED DAYTIME DIRECTIONAL 1964	CALL WAKE FREQ 1500 kc/s POWER 1 KW TYPE DA-D TIME DAY LAT. 41-26-36 LONG. 87-02-54
	No.	ft.	ft.	ft.	ft.	TOWER HEIGHT CHANGES 6/67	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
	1						
	2						
	3						
	4						
	5						
	6						
	7						
	8						
	9						
	10						
	DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐					0°	


FCC File No. BP-17813
Accepted 8-11-67

Station WAKE
Valparaiso, Indiana

1500 kc


WBR

10kw, DA-D,D
1500 KC



New; Radio One Five Hundred, Inc. 5kw, DA-D, D
Indianapolis, Indiana 1500 kc

1/23/63
granted CP
for new station



$S = 100^\circ = 182'$
 $G = 90^\circ = 164'$
 $RMS = 395 \text{ MV/M}$

 $N \text{ LAT } 39^\circ 52' 14''$
 $W. \text{ LONG. } 86^\circ 05' 17''$

HORIZONTAL RADIATION PATTERN
DAYTIME

UNATTENUATED FIELD INTENSITY
AT ONE MILE

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

NEW RADIO STATION
1500 KC, 5 KW, DA-D
INDIANAPOLIS, INDIANA

611222

FIGURE 5B

FCC File No. BP-13922 New; Radio One Five Hundred, Inc.
Accepted 10-15-62 Amended Indianapolis, Indiana

1500 kc


W.B.R.11

Measured Day
(5-28-64ct)

Station WNDY
Indianapolis, Indiana

5kw, DA-D, D
1500 kc

#200
5-14-64
Granted L
for new station



THEORETICAL 		OPERATING 	
N. LAT. 39° 52' 14"		RMS: 422 MV/M	S: 100° = 182°
W. LONG. 86° 05' 17"			G: 90° = 164°
HAMMETT & EDISON CONSULTING RADIO ENGINEERS SAN FRANCISCO		RADIO STATION WNDY 1500 KC. 5 KW. DA-D INDIANAPOLIS, INDIANA	

MEASURED DIRECTIONAL HORIZONTAL RADIATION PATTERN

UNATTENUATED FIELD INTENSITY AT ONE MILE

631202

FIGURE 10B

FCC File No. BL-10535
Accepted 4-28-64

Station WNDY
Indianapolis, Indiana


1500 kc

W.BRI'

Measured Non-DA
(5-28-64ct)

Station WNDY
Indianapolis, Indiana

5kw, DA-D, D
1500 kc



N LAT 39° 52' 14"
W. LONG 86° 05' 17"

G:90°-164'

RMS-188 MV/M

1 KW INTO TOWER 2 WITH TOWERS 1 & 3 FLOATING

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION WNDY
1500 KC. 5 KW. DA-D
INDIANAPOLIS, INDIANA

**MEASURED
NON-DIRECTIONAL
HORIZONTAL RADIATION PATTERN**

UNATTENUATED FIELD INTENSITY AT ONE MILE

631202

FIGURE 10A

FCC File No. BL-10535
Accepted 4-28-64

Station WNDY
Indianapolis, Indiana

1500 kc

PROPOSED DAY
(8-29-60g)

Station WJBK
Detroit, Michigan



5kw, 50kw-L.

WDEE

1500 KC

N. LAT. 42° 13' 51"
W. LONG. 83° 11' 55"

DAYTIME N



<u>10</u> 0.375 -226	<u>11</u> 0.514 -207.4	<u>12</u> 0.176 -194
<u>2</u> 1.185 -109	<u>3</u> 1.625 -90.4	<u>4</u> 0.555 -77
<u>6</u> 1.000 + 0	<u>7</u> 1.371 + 18.5	<u>8</u> 0.468 + 32

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN
600630.2

FIGURE 6A

FCC File No. BP-14275
Accepted 8-10-60 (was BP-13959)

WJBK
Detroit, Michigan

1500 KC

WDEE



Proposed Night
(1-29-68ct)

Station WJBK
Detroit, Michigan

5kw, 50kw-L3, OA-2, 0
1500 kc

N. LAT. 42° 13' 51"
W. LONG. 83° 11' 55"

NIGHTTIME N



$\frac{9}{1.00 \mid +0}$	$\frac{10}{2.76 \mid +0}$	$\frac{11}{2.76 \mid +0}$	$\frac{12}{1.00 \mid +0}$
$\frac{1}{1.47 \mid +98}$	$\frac{2}{4.06 \mid +98}$	$\frac{3}{4.06 \mid +98}$	$\frac{4}{1.47 \mid +98}$
$\frac{5}{50 \mid +204}$	$\frac{6}{1.38 \mid +204}$	$\frac{7}{1.38 \mid +204}$	$\frac{8}{.50 \mid +204}$

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN
671211

FIGURE 1A

FCC File No. BMP-12244
Accepted 1-2-68

Station WJBK
Detroit, Michigan

1500 kc



OVER

Proposed Night
(9-28-67ct)

Station WJBK
Detroit, Michigan

5kw, **WDEE**
1500 kc

N. LAT. 42° 13' 51"
W. LONG. 83° 11' 55"



$\frac{9}{1.00 \mid +0}$	$\frac{10}{2.76 \mid +0}$	$\frac{11}{2.76 \mid +0}$	$\frac{12}{1.00 \mid +0}$
$\frac{1}{1.47 \mid +98}$	$\frac{2}{4.06 \mid +98}$	$\frac{3}{4.06 \mid +98}$	$\frac{4}{1.47 \mid +98}$
$\frac{5}{.50 \mid +204}$	$\frac{6}{1.38 \mid +204}$	$\frac{7}{1.38 \mid +204}$	$\frac{8}{.50 \mid +204}$

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS



RADIO STATION WJBK
DETROIT, MICHIGAN
670824
FIGURE 1A

WDEE

Proposed Night
(11-27-64ct)

Station WJBK
Detroit, Michigan

5kw, 50kw-LS, DA-2, U
1500 kc



$\frac{9}{1.00 \text{ } [+0]}$	$\frac{10}{2.76 \text{ } [+0]}$	$\frac{11}{2.76 \text{ } [+0]}$	$\frac{12}{1.00 \text{ } [+0]}$
$\frac{1}{1.47 \text{ } [+98]}$	$\frac{2}{4.06 \text{ } [+98]}$	$\frac{3}{4.06 \text{ } [+98]}$	$\frac{4}{1.47 \text{ } [+98]}$
$\frac{5}{50 \text{ } [+204]}$	$\frac{6}{1.38 \text{ } [+204]}$	$\frac{7}{1.38 \text{ } [+204]}$	$\frac{8}{50 \text{ } [+204]}$

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN
640904

FIGURE 1

FCC File No. BMP-11354
Accepted 11-9-64

Station WJBK
Detroit, Michigan

1500 kc

WDEE



PROPOSED NIGHT
(8-29-60g)

Station WJBK
Detroit, Michigan

5kw, 50kw-L3, DA-2, U
1500 KC

N. LAT. 42° 13' 51"
W. LONG. 83° 11' 55"

NIGHTTIME N



$\frac{9}{50 \mid -204}$	$\frac{10}{1.38 \mid -204}$	$\frac{11}{1.38 \mid -204}$	$\frac{12}{.50 \mid -204}$
$\frac{1}{1.47 \mid -98}$	$\frac{2}{406 \mid -98}$	$\frac{3}{406 \mid -98}$	$\frac{4}{1.47 \mid -98}$
$\frac{5}{1.00 \mid -0}$	$\frac{6}{276 \mid -0}$	$\frac{7}{276 \mid -0}$	$\frac{8}{1.00 \mid -0}$

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

FCC File No. BP-14275
Accepted 8-10-60 (was BP-13959)

RADIO STATION WJBK
DETROIT, MICHIGAN
600701.2
WJBK
Detroit, Michigan
FIGURE 6A
1500 KC

Proposed Night Nulls
(1-29-68ct)


Station WJBK
Detroit, Michigan

5kw, 5

WDEE

1500 kc

AZIMUTH



PROPOSED 1500 kHz 5 kW NIGHTTIME
MEOV --- 0° ELEVATION

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN

671211

FIGURE 1B

FCC File No. BMP-12244
Accepted 1-2-68

Station WJBK
Detroit, Michigan



1500 kc

WDEE

Measured Day
(3-30-63ct)

Station WJBK
Detroit, Michigan

1kw, 10kw-LS, DA-2, U
1500 kc



THEORETICAL ANTENNA PARAMETERS

TOWER	RELATIVE FIELD	PHASE
1	1.00	0°
2	2.76	0°
3	2.76	0°
4	1.00	0°
5	1.00	90°
6	2.76	90°
7	2.76	90°
8	1.00	90°

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN

620517

FIGURE 17B

FCC File No. BZ-4853
Accepted 3-20-63

Station WJBK
Detroit, Michigan

1500 kc

WDEE



Measured Day Nulls
(3-30-63ct)

Station WJBK
Detroit, Michigan

1kw, 10kw-LS, DA-2, U
1500 kc

AUTHORIZED FACILITY
1500KC 10KW 10KW-LS DA-2

PATTERN NO. 620517-D
10 KW DAYTIME



THEORETICAL ANTENNA PARAMETERS

TOWER	RELATIVE FIELD	PHASE
1	1.00	0°
2	2.76	0°
3	2.76	0°
4	1.00	0°
5	1.00	90°
6	2.76	90°
7	2.76	90°
8	1.00	90°

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN

620517

FIGURE 17C

FCC File No. BZ-4853
Accepted 3-20-63

Station WJBK
Detroit, Michigan

1500 kc



WDEE

Measured Night
(3-30-63ct)

Station WJBK
Detroit, Michigan

1kw, 10KW-LS, DA-2, U
1500 kc

#203
11-16-64
painted map for
change in night
directional antenna
parameters



THEORETICAL ANTENNA PARAMETERS

TOWER	RELATIVE FIELD	PHASE
1	1.00	0°
2	2.76	0°
3	2.76	0°
4	1.00	0°
5	1.00	90°
6	2.76	90°
7	2.76	90°
8	1.00	90°

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN
620517
FIGURE 17D

FCC File No. BZ-4853
Accepted 3-20-63



Station WJBK
Detroit, Michigan

1500 kc

Measured Night Nulls
(3-30-63ct)

Station WJBK
Detroit, Michigan

WDEE
1KW, 10KW-LS, DA-2, U
1500 kc



THEORETICAL ANTENNA PARAMETERS

TOWER	RELATIVE FIELD	PHASE
1	1.00	0°
2	2.76	0°
3	2.76	0°
4	1.00	0°
5	1.00	90°
6	2.76	90°
7	2.76	90°
8	1.00	90°

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN

FCC File No. BZ-4853
Accepted 3-20-63

Station WJBK
Detroit, Michigan

620517

FIGURE 17E



1500 kc

WDEE

Measured Non-DA
(3-30-63ct)

Station WJBK
Detroit, Michigan

1kw, 10kw-LS, DA-2, U
1500 kc



TOWER

1
2
3
4
5
6
7
8

OPERATION

DETUNED
DETUNED
DETUNED
DETUNED
DETUNED
SERIES-FED
DETUNED
DETUNED

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN

620517

FIGURE 17A

FCC File No. BZ-4853
Accepted 3-20-63

Station WJBK
Detroit, Michigan

1500 kc

WOEE

PROPOSED
DAY



WJBK, DETROIT, MICH.
5/11/55G

DA-2
1 KW-10KW-LS

1500 KC

DAY

N LAT 42° 13' 51"
W LONG 83° 11' 55"



$S_1 = 173$ FEET = 95 DEGREES
 $S_2 = 392$ FEET = 215 DEGREES
 $G = 246$ FEET = 135 DEGREES

RADIO STATION WJBK

DETROIT, MICHIGAN

1500 KC 1 KW 10 KW-LS DA-2

NO.	1	2	3	4	5	6	7	8
I	1.0	2.76	2.76	1.0	1.0	2.76	2.76	1.0
ψ	0°	0°	0°	0°	90°	90°	90°	90°

A. EARL CULLUM, JR.

CONSULTING RADIO ENGINEERS

541202.1

FIGURE 7A

WDEE

PROPOSED
DAY NULLS



WJBK, DETROIT, MICH
5/11/55G

DA-2
1 KW-10KW-LS

1500 KC

N LAT. 42°13'51"
W LONG. 83°11'55"

DAY



S₁ = 173 FEET = 95 DEGREES
S₂ = 392 FEET = 215 DEGREES
G = 246 FEET = 135 DEGREES

RADIO STATION WJBK

DETROIT, MICHIGAN

1500 KC 1 KW 10 KW-LS DA-2

NO.	1	2	3	4	5	6	7	8
1	1.0	2.76	2.76	1.0	1.0	2.76	2.76	1.0
ψ	0°	0°	0°	0°	90°	90°	90°	90°

A. EARL CULLUM, JR.

CONSULTING RADIO ENGINEERS

541202

AMENDED

FIGURE 7B

WDEE

PROPOSED
NIGHT



WJBK, DETROIT, MICH.
5/11/55G

DA-2
1 KW-10KW-LS

1500 KC

N LAT 42° 13' 51"
W LONG 83° 11' 55"

NIGHT



$S_1 = 173$ FEET = 95 DEGREES
 $S_2 = 392$ FEET = 215 DEGREES
 $G = 246$ FEET = 135 DEGREES

RADIO STATION WJBK

DETROIT, MICHIGAN

1500 KC 1 KW 10 KW-LS DA-2

NO.	1	2	3	4	5	6	7	8
1	1.0	2.76	2.76	1.0	1.0	2.76	2.76	1.0
ψ	0°	0°	0°	0°	90°	90°	90°	90°

A. EARL CULLUM, JR.

CONSULTING RADIO ENGINEERS

541202.1

FIGURE 8A

Proposed Night Nulls
(9-28-67ct)


Station WJBK
Detroit, Michigan

5k

WDEE

1500 KC

AZIMUTH



PROPOSED 1500 kHz 5 kW NIGHTTIME
MEOV --- 0° ELEVATION

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
DETROIT, MICHIGAN
670824 FIGURE 1B

FCC File No. BMP-12166
Accepted 9-19-67

Station WJBK
Detroit, Michigan

1500 kc

WDEE

PROPOSED
NIGHT NULLS



WJBK, DETROIT, MICH.
5/11/55G

DA-2
1 KW-10KW-LS

1500 KC

N LAT. 42° 13' 51"
W LONG. 83° 11' 55"

NIGHT



RADIO STATION WJBK

DETROIT, MICHIGAN

1500 KC 1 KW 10 KW-LS DA-2

NO.	1	2	3	4	5	6	7	8
I	1.0	2.76	2.76	1.0	1.0	2.76	2.76	1.0
ψ	0°	0°	0°	0°	90°	90°	90°	90°


A. EARL CULLUM, JR.

CONSULTING RADIO ENGINEERS

541202 AMENDED FIGURE 8B

1500 KC

2





WDEE

Measured Day
(9-26-68ct)

Station WJBK
Detroit, Michigan

5kw, 50kw-LS, DA-2, U
1500 kc



TOWER	THEORETICAL RATIO AND PHASE		OBSERVED RATIO AND PHASE	
1	-	-	-	-
2	1.185	-109°	0.724	342.8°
3	1.625	-90.4	1.000	2.0
4	0.555	-77	0.412	13.3
5	-	-	-	-
6	1.000	0	0.448	93.2
7	1.371	18.6	0.651	109.3
8	0.468	32	0.224	122.0
9	-	-	-	-
10	0.375	-226	0.275	219.4
11	0.514	-207.4	0.357	244.7
12	0.176	-194	0.124	252.9

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
1500 kHz 5 kW 50 kW-LS DA-2
680520 FIGURE 2B

FCC File No. BL-12094
Accepted 9-19-68

Station WJBK
Detroit, Michigan



1500 kc

WDEE

Measured Non-DA
(9-26-68ct)

Station WJBK
Detroit, Michigan

5kw, 50kw-LS, DA-2, U
1500 kc



$S = 392' = 215^{\circ}$
 $Y = 173' = 95^{\circ}$
 $G = 240' = 132^{\circ}$

TOWER NO.6 SERIES EXCITED
ALL OTHER TOWERS DETUNED

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION WJBK
1500 kHz 5 kW 50 kW-LS DA-2
680520 FIGURE 2A

FCC File No. BL-12094
Accepted 9-19-68

Station WJBK
Detroit, Michigan

1500 kc

WFIF

Proposed Day
(2-28-69ct)


Station WFIF
Milford, Connecticut

5kw, DA-D, D
1500 kc

BMP-12647
Granted
2-18-69
Mod. of Co.
to make
changes

LUDENE DIETZEN CO.
MADE IN U.S.A.

LUDENE DIETZEN CO. RADAR PAPER
POLAR COORDINATE



FCC File No. BMP-12647
Accepted 2-14-69

Station WFIF
Milford, Connecticut

1500 kc

WFIF

Measured Day
(12-29-65ct)


Station WFIF
Milford, Connecticut

5kw, DA-D, D
1500 kc

SEE
REVERSE
SIDE 6/9/70

FOURTH DIET/BN, J.
GAC, IN D. C. A

NO. 200-P DIET/BN, J.
GAC, IN D. C. A



FCC File No. BL-11166
Accepted 12-16-65

Station WFIF
Milford, Connecticut

1500 kc

Measured Non-DA
(12-29-65ct)

Station WFIF
Milford, Connecticut

SEE
REVERSE
SIDE

6/9/70

WFIF
5kw, DA-D, D
1500 kc

EUGENE DIETZEL, JR.
MADE IN U. S. A.

NO. 340-P DIETZEL GR. W. PAPER
POLAR CO-ORDINATE




Figure 6
Measured 0.5 Kw Non-Da Horizontal Pattern
WFIF Milford, Connecticut
1500 Kc 5 Kw DA-D
August 1965

FCC File No. BL-11166
Accepted 12-16-65

Station WFIF
Milford, Connecticut

WGFT

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WGFT

Main Studio: Youngstown, Ohio

Frequency: 1500 kHz

Power: 0.5 kW

Modification List No. 1656

Date: October 29, 1975

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 06' 25"

West Longitude: 80° 34' 59"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 4

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	W(#1)	WC(#2)	EC(#3)	SE(#4)
HEIGHT ABOVE INSULATORS:	168'	168'	168'	168' (90°)
PHASING:	0°	-191.72°	-9.89°	+164.5°
FIELD RATIO:	1.0	2.0977	1.6840	0.625

SPACING AND

ORIENTATION: From reference tower #1; tower #2 is spaced 164' (90°) on a line bearing 93° true, tower #3 is spaced 326.2' (179°) on a line bearing 98° true and tower #4 is spaced 492' (264.5°) on a line bearing 106° true.

GROUND SYSTEM: 120-102' to 165' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

Predicted effective Field: 128.75 mv/m at rated power.



Note: Please retain the Daytime directional antenna radiation pattern notified for a new station at Youngstown, Ohio in United States Change List Number 1531 dated May 31, 1973 and attach to this Revised Description Sheet. This notification concerns only a change in parameters to the complimentary directional antenna parameters which produce the identical radiation pattern.

WGFT

Proposed Day (CH)
(2-28-67ct)

New; Media, Inc.
Youngstown, Ohio

500w, 250w-CH, DA-2, D
1500 kc



FCC File No. BP-17435
Accepted 2-7-67

New; Media, Inc.
Youngstown, Ohio


1500 kc

WGFT

Proposed Day
(2-28-67ct)

New; Media, Inc.
Youngstown, Ohio

500w, 250w-CH, DA-2, D
1500 kc



RMS 128.75 MV/M 210°
MEOV -----
10X -----

North Latitude $41^\circ 06' 28.9''$
West Longitude $80^\circ 34' 58.9''$

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 3-A	STATION DATA
	TOWER No.	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	Youngstown, Ohio Proposed Daytime Directional Antenna Pattern	CALL New FREQ 1500 KHz POWER 0.5 Kw TYPE DA-2 TIME Day LAT. $41^\circ 06' 28.9''$ LONG. $80^\circ 34' 58.9''$ E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
	1	90	ref	0	1.0		
	2	90	178	191.7152	0.9765		
	3	90	178	88.906	1.6248		
	4	90	264.5	164.5	0.625		
	5						
	6						
	7						
	8						
	9						
	10						

FCC File No. BP-17435
Accepted 2-7-67

New; Media, Inc.
Youngstown, Ohio

1500 kc

WGFT

SUPPLEMENTAL DIRECTIONAL ANTENNA
DESCRIPTION SHEET

Station: WGFT

Main Studio: Youngstown, Ohio

Frequency: 1500 kHz

Power: 0.5 kW

Notification List No. 1704

Date: October 5, 1976 Class: 11

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 06' 26"


West Longitude: 80° 34' 57"

Authorized for Daytime operation (DA-D).

Predicted effective Field: 128.75 mv/m at rated power.

Note: Please retain the daytime directional antenna radiation pattern notified for a new station at Youngstown, Ohio in United States Change List Number 1531, dated May 31, 1973 and the directional antenna description sheet notified in Change List No. 1656 dated October 29, 1975 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates of the center of the antenna system.

1kw, DA-D, D
1500 kc



WKBX

Measured Day
(2-22-71ct)

Station WKBX
Winston-Salem, North Carolina

10kw, 1kw-CH, DA-2, D
1500 kc





FIGURE 1X1VA
MEASURED HORIZONTAL RADIATION PATTERN
RADIO STATION WKBX
1500KC 10KW-D, 1KW-CH, DA-2
WINSTON SALEM, NORTH CAROLINA

WILLIAM L. FOSS, INC.
Electronic Consultants
WASHINGTON D. C.
827 16th Street, N.W. RE 3841

PATTERN NO
SUPERSEDES
APP

FCC File No. BL-12865
Accepted 2-11-71

Station WKBX
Winston-Salem, North Carolina

1500 kc

Measured Day Nulls
(2-22-71ct)

Station WKBX
Winston-Salem, North Carolina

WKBX
10kw, 1kw-CH, DA-2, D
1500 kc





FIGURE 2XV
MEASURED HORIZONTAL RADIATION PATTERN
RADIO STATION WKBX
1500 KC 10KW-D, 1KW-CH, DA-2
WINSTON SALEM, NORTH CAROLINA

WILLIAM L. FOSS, INC.
Electronic Consultants
WASHINGTON, D. C.
927 16th Street, N.W. DE 1663

PATTERN NO
SUPERSEDES
APP

FCC File No. BL-12865
Accepted 2-11-71


Station WKBX
Winston-Salem, North Carolina

1500 kc

Measured Day (CH)
(2-22-71ct)

Station WKBX
Winston-Salem, North Carolina

WKBX
10kw, 1kw-CH, DA-2, D
1500 kc



1KW-DA-CH.
RMS = 178 mW/m²
N. LAT. 36° 06' 34"
W. LONG. 80° 12' 42"

FIGURE LXIII
MEASURED HORIZONTAL RADIATION PATTERN
RADIO STATION WKBX
1500 KC 10KW-D, 1KW-CH, DA-2
WINSTON SALEM, NORTH CAROLINA

#4 130°
#3 100°
N 282° E 0.610°
h = 130'

WILLIAM L. FOSS, INC.
Electronic Consultants
WASHINGTON, D. C.
827 15th Street, N.W. RT. 1A-1

PATTERN NO.
SUPERSEDES
APP

FCC File No. BL-12865
Accepted 2-11-71

Station WKBX
Winston-Salem, North Carolina

1500 kc

Measured Non-DA
(2-22-71ct)

Station WKBX
Winston-Salem, North Carolina

WKBX
10kw, 1kw-CH, DA-2, D
1500 kc




FIGURE 1X11
MEASURED HORIZONTAL RADIATION PATTERN
RADIO STATION WKBX
1500 KC 10KW-D, 1KW-CH, DA-2
WINSTON SALEM, NORTH CAROLINA

WILLIAM L. FOSS, INC.
Electronic Consultants
WASHINGTON D. C.
927 16th Street N.W. NE 3803

PATTERN NO
SUPERSEDES
APP

FCC File No. BL-12865
Accepted 2-11-71

Station WKBX
Winston-Salem, North Carolina

1500 kc


WKBX

Proposed Day Nulls
(12-27-68ct)


Station WKBX
Winston-Salem, North Carolina

10kw, 1kw-CH, DA-2, D
1500 kc

12-18-307
Granted
5-10-69
CP to change
from 1 kw,
DA-D, DLO
10 kw, 1 kw-CH
DA-2, D



M.E.O.V.
N. LAT. 36° 06' 34"
W. LONG. 80° 12' 42"



h = 130 FT.
1+2 EXISTING

EXHIBIT VIIA
HORIZONTAL RADIATION PATTERN
EXPANDED SCALE
RADIO STATION WKBX
1500KC 10KW-D, 1KW-CH DA-2
WINSTON SALEM, N. C.



WILLIAM L. FERGUSON, INC.
Electronic Consultants
WASHINGTON D. C.
DET 12th Street, N. W. RE. 5003

PATTERN NO
SUPERSEDES
APP.

FCC File No. BP-18307
Accepted 11-27-68

Station WKBX
Winston-Salem, North Carolina

1500 kc



WKBX

Proposed Day
(12-27-68ct)

Station WKBX
Winston-Salem, North Carolina

10kw, 1kw-CH, DA-2, D
1500 kc

BP-18307
Granted
4/16/69 PA
to change
from 1kw, DA D,
Dlc 10 kw,
1kw-CH,
DA-2, D



h = 130 FT.
1 + 2 EXISTING

EXHIBIT VII
HORIZONTAL RADIATION PATTERN
RADIO STATION WKBX
1500KC 10KW-D 1KW-CH DA-2
WINSTON SALEM, N. C.



WILLIAM L. FOSB, INC.
Electronic Consultants
WASHINGTON D. C.
627 16th Street, N.W. RE 3882

PATTERN NO
SUPERSEDES
APP

FCC File No. BP-18307
Accepted 11-27-68

Station WKBX
Winston-Salem, North Carolina


1500 k.

WKBX

PROPOSED DAY
(7-26-61ct)

New; Stuart W. Epperson 1kw, DA-D, D
Winston-Salem, North Carolina 1500 KC

BP 12-
SP-17278
PA 710 KC, ND



1.0 / 120°
100° 0.6 / 0°
h = 130 FT.

EXHIBIT IV
HORIZONTAL RADIATION PATTERN
STUART W. EPPERSON
1500KC 1KW-DA-D WINSTON SALEM, N.C.

WILLIAM L. FUSE, INC.
Electronic Consultants
WASHINGTON 6, D. C.
627 14th Street, N. W. RE. 3863

PATTERN NO
SUPERSEDES
APP

FCC File No. BP-14909
Accepted 7-17-61

Stuart W. Epperson
Winston-Salem, North Carolina 1500 KC


WKBX

Measured Day
(3-26-65ct)

Station WKBX
Winston-Salem, North Carolina

1kw, DA-D, D
1500 kc

L.C. 11-3-65
BP 1727A
PA 710 KS MD



RMS = 177 mV/m
N. LAT. 36°06'34"
W. LONG. 80°12'42"

EXHIBIT II MEASURED DAYTIME HORIZONTAL RADIATION PATTERN WKBX 1500 KC 1KW-DA-DAY WINSTON SALEM, N.C.

1/130
N 282° E 100° 6/12°
h = 130 FT.

WILLIAM L. FOGG, INC.
Electronic Consultants
WASHINGTON D. C.
807 14th Street, N. W. NE. 10005

PATTERN NO.
SUPERSEDES
APP

FCC File No. BL-10767
Accepted 2-24-65

Station WKBX
Winston-Salem, North Carolina

1500 kc

WKBX

Measured Non-DA
(3-26-65ct)

Station WKBX
Winston-Salem, North Carolina

1kw, DA-D, D
1500 kc

*REC-11-3-65
SP-17-2-65
PA 7-16-65*




EXHIBIT I
MEASURED HORIZONTAL PLANE PATTERN
NON-DIRECTIONAL W. TOWER
WKBX 1500 KC 1KW-DA-DAY WINSTON SALEM, NC

WILLIAM L. FORD, INC.
Electronic Consultants
WASHINGTON, D. C.
927 15th Street, N. W. S.E. 30002

PATTERN NO
SUPERSEDES
APP

Measured Day
(2-22-71ct)

Station WKER
Pompton Lakes, New Jersey

WKER

1kw, DA-D, D


1500 kc

FIG. 22

NORTH

EUGENE DIETZGEN CO.
MADE IN U.S.A.

NO. 341-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-12851
Accepted 1-27-71

Station WKER
Pompton Lakes, New Jersey

1500 kc

Measured Non-DA
(2-22-71ct)

Station WKER
Pompton Lakes, New Jersey


WKER

1kw, DA-D, D
1500 kc

FIG 21

EUGENE DIETZGEN CO.
MADE IN U.S.A.

EUGENE DIETZGEN CO. CHART PATENT
POLAR CO-ORDINATE



FCC File No. BL-12851
Accepted 1-27-71

Station WKER
Pompton Lakes, New Jersey

1500 kc

WKER

Proposed Day
(3-28-68ct)

Station WKER
Pompton Lakes, New Jersey

1kw, DA-D, D
1500 kc

NORTH

DAY HORIZONTAL PLANE RADIATION


PROPOSED 1 KW. DA-DAY

WKER-1500 KHZ. POMPTON LAKES, N.J.

PAUL GODLEY CO.
CONSULTING RADIO ENGINEERS
LITTLE FALLS, N.J. 4/67

BP-17989
Granted
4/9/69
to increase
power from
500 W, DA-D
D to 1 kw
DA-D, D+
make changes
in AA
System

U.S. DEPARTMENT OF COMMERCE
FEDERAL BUREAU OF INVESTIGATION
WASHINGTON, D.C.



FCC File No. BP-17989
Accepted 3-19-68

Station WKER
Pompton Lakes, New Jersey

1500 kc

WKEK

Proposed Day
(3-30-63ct)


New; Upper Passaic County Radio
Pompton Lakes, New Jersey

500w, DA-D, D
1500kc

6-12-63
granted CP for
new AM station

4/24/64
granted move
of CP to change
int-trans
location

NO. 341 R. DIEZIGEN - IN PAPER
POLAR CO ORDINATE




FCC File No. BP-14863
Reinstated 3-20-63

New; Upper Passaic County Radio
Pompton Lakes, New Jersey

1500 kc

500w, DA-D, D
1500 kc



FCC File No. BL-10916
Accepted 5-21-65

Station WKER
Pompton Lakes, New Jersey

1500 kc

WKER

Measured Non-DA
(5-27-65ct)


Station WKER
Pompton Lakes, New Jersey

500w, DA-D, D
1500 kc

NORTH

LIC 5-27-65

FIG 18



FCC File No. BL-10916
Accepted 5-21-65

Station WKER
Pompton Lakes, New Jersey

1500 kc

~~WKIZ~~
1500 kHz

WKIZ

SUPPLEMENTAL AND CORRECTED
DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WKIZ

Main Studio: Key West, Florida

Frequency: 1500 kHz

Power: 0.25kw Night 0.25kw Day

Notification List No. 1787

Date July 10, 1980 Class: II


GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 24° 34' 01"

West Longitude: 81° 44' 54"

Note: Please retain the description sheet notified for station WKIZ in United States Change List number 1200, dated January 25, 1967 and attach to this supplemental Description Sheet and Directional Antenna patterns. This notification is for the purpose of notifying changes to the directional antenna pattern MEOV's.

WKIZ 1500KHz




--- MEOV
MARCH 1978

THE TOWER NUMBERS AND FIELD RATIOS HAVE BEEN CORRECTED.
SILLIMAN, MOFFET & KOWALSKI, P.C.

AMENDED FIGURE A1

FIGURE 1



LATITUDE		24° 34' 01" NORTH				
LONGITUDE		81° 44' 54" WEST				
ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MV/M FOR 1 KW	HEIGHT DEG
2	—	—	17	0.50		82.3
1	180	182	0	1.0		82.3
3	180	364	-17	0.61		82.3

HORIZONTAL
PLANE PATTERN
WKIZ
KEY WEST, FLORIDA
1500 KC 250 W U, DA-1
661213

KEAR & KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

WK12

Proposed Day & Night
(1-30-67ct)

Station WKIZ
Key West, Florida

250w, DA-1, U
1500 kc

BP-17538
GRANTED
1-20-67
CP CHANGES
IN DA PATTERN





FIGURE 1



LATITUDE 24° 34' 01" NORTH
LONGITUDE 81° 44' 54" WEST

ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MEAS. MV/M FOR 1 KW	HEIGHT DEG
1	-	-	17	0.506		82.3
2	180	182	0	0		82.3
3	180	364	-17	0.625		82.3

HORIZONTAL
PLANE PATTERN
WKIZ
KEY WEST, FLORIDA
1500 KC 250 W U, DA-1
661213

KEAR & KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

FCC File No. BP-17538
Accepted 1-11-67

Station WKIZ
Key West, Florida

1500 kc


WKIZ

Measured Day & Night
(6-28-67ct)

Station WKIZ
Key West, Florida

250w, DA-1, U
1500 kc

1-20-67
RENTED
LICENSE




WKIZ

MEASURED NON-DA
(5-28-59g)

Station WKIZ
Key West, Florida

250w, DA-1,U
1500 KC



$E_{RMS} = 97.8 \text{ MV/M (MEASURED)}$

○ = MEASURED RADIAL

LATITUDE: 24° 34' 02"
LONGITUDE: 81° 44' 53.8"

ANTENNA PARAMETERS

G = 82.3°

FIGURE 19A

HORIZONTAL POLAR PATTERN
(NON-DIRECTIONAL)

RADIO STATION WKIZ
KEY WEST, FLA.

1500 KC 250W DA-1,U

JOHN H. MULLANEY
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FCC File No. BL-7458
Accepted 5-13-59

WKIZ
Key West, Florida


1500 KC

Granted L- for new station
10-12-59

30° 20° 10° NORTH 350° 340° 330° 320° 310° 300° 290° 280° 270° 260° 250° 240° 230° 220° 210° 200° 190° 180° 170° 160° 150°

COHEN AND DIPPELL, P.C.
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D. C. 20004

EXPANDED SCALE



NOTE: DATA TAKEN FROM JANUARY 1962 PROOF.

NIGHTTIME PATTERN
WTOP, WASHINGTON, D.C.
1500 KC 50 KW DA-2
AUGUST 1973

MADE IN U. S. A.

NU. 301-P DITZEN GRAPH PAPER
POLAR CO-ORDINATE

EUGENE DIETZGEN CO.
MADE IN U. S. A.

NO. 341-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE

NORTH

WTOP

COHEN AND DIPPELL, P.C.
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D. C. 20004

40°
320°

50°
310°

60°
300°

70°
290°

80°
280°

90°
270°

100°
260°

110°
250°

120°
240°

130°
230°

140°
220°

320°
40°

310°
50°

300°
60°

290°
70°

280°
80°

270°
90°

260°
100°

250°
110°

240°
120°

230°
130°

220°
140°

2000

MV/M

1000

NOTE: DATA TAKEN FROM JANUARY 1962 PROOF.



DAYTIME PATTERN
WTOP, WASHINGTON, D.C.
1500 KC 50 KW DA-2
AUGUST 1973

WTOP

PROPOSED
(2/7/57g)

NIGHT Station WTOP
Washington, D.C.

50KW, DA-2,U
1500 KC



WTOP WTOP-WASHINGTON, D.C.

Station	50 KW	Location
Frequency	1630 MV/M (230/Y)	R.M.S. Field
No. of Elements	0.515 λ OR 337 FT	
MEASURED ☐	CALCULATED ☐	Height of Antenna
Pattern	410/11.12	Eng. Dept. No.

NIGHTTIME PATTERN



FCC File No.
BL-1117



WTOP
Washington, D.C.

1500 KC

PROPOSED
(2/7/57g)

DAY Station WTOP
Washington, D.C.

50 KW, DA-2, U
1500 KC



WTOP-WASHINGTON, D.C.

Station 1500	Power 50 KW	Location 1650 MV/M (233/KW)
Frequency 3	Power 0.515 λ OR 337 FT	R.M.S Field
No. of Elements MEASURED ☐ CALCULATED ☐	Height of Antenna 110/111.13	Eng. Dept. No.
DAYTIME PATTERN		



FCC File No.
BL-1117

WTOP
Washington, D.C.



1500 KC

Rec'd 11-25-47

Bl-S-220

WTOP- 1500


30° 330° 20° 340° 10° 350° 380° 10° 340° 20° 330° 30°



COLUMBIA BROADCASTING SYSTEM, INC.			
GENERAL ENGINEERING DEPARTMENT			
MEASURED UNATTENUATED FIELD INTENSITY			
AT ONE MILE			
DAY PATTERN			
WTOP WASHINGTON, D.C.			
50 KW		1500 KC	
APR. <i>OP</i>	DATE	ENG. CASE NO.	DWG. NO.
	11-13-47	E714	- 26

180° 210° 160° 200° 170° 180° 190° 200° 210° 150°

WTOP




WVOC

Proposed Day
(1-28-66ct)

Station WVOC
Battle Creek, Michigan

1kw, DA-D, D
1500 kc

PPL. 2-16-66
CHG. DA. CF



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 1B	STATION DATA
$\phi = 90^\circ \quad \phi_1 = 60^\circ \quad \phi_2 = 180^\circ$ $N = 0.012 \text{ m} = 1$ 	TOWER No.	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	PROPOSED DAYTIME DIRECTIONAL PATTERN	CALL WVOC FREQ 1500 Kc/S POWER 1 KW TYPE DA-D TIME DAYTIME LAT. 42° 17' 30" LONG. 85° 10' 08"
	1					WVOC - 10/65	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
	2						
	3						
	4						
	5						
	6						
	7						
	8						
	9						
	10						
	DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐					θ°	

FCC File No. BP-16472
Accepted 1-5-66 Amended

Station WVOC
Battle Creek, Michigan


1500 kc

Measured Day
(1-30-67ct)

Station WVOC
Battle Creek, Michigan

1kw, DA-D, D
1500kc

4-30-68
GRANTED
LICENSE.



RMS = 179.4 Mv/M at 10°

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 4	STATION DATA																																																					
G=99° S₁=60° S₂=180° N-002°-E #2 0.972/-21° #1 1.0/0°	<table><tr><th>TOWER No.</th><th>ELECTRICAL HEIGHT h_e</th><th>SPACING s</th><th>PHASING φ</th><th>FIELD RATIO F</th></tr><tr><td>1</td><td></td><td></td><td></td><td></td></tr><tr><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>3</td><td></td><td></td><td></td><td></td></tr><tr><td>4</td><td></td><td></td><td></td><td></td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></table>	TOWER No.	ELECTRICAL HEIGHT h _e	SPACING s	PHASING φ	FIELD RATIO F	1					2					3					4					5					6					7					8					9					10					WVOC MEASURED DAY DIRECTIONAL PATTERN		MAY - 1966	CALL WVOC FREQ 1500 Kc/S POWER 1 Kw TYPE DA-D TIME DAYTIME LAT. 42° 17' 30" LONG. 85° 10' 08" E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER No.	ELECTRICAL HEIGHT h _e	SPACING s	PHASING φ	FIELD RATIO F																																																								
1																																																												
2																																																												
3																																																												
4																																																												
5																																																												
6																																																												
7																																																												
8																																																												
9																																																												
10																																																												
DAYTIME OPERATION					NIGHT TIME OPERATION		θ° = 0°																																																					

FCC File No. BL-11492
Accepted 12-29-66

Station WVOC
Battle Creek, Michigan

1500 kc

Measured Non-DA
(1-30-67ct)


Station WVOC
Battle Creek, Michigan

1kw, DA-D, D
1500 kc

WVOC

4-30-68

GRANTED
LICENSE



RMS = 130.5 MV/M
MEOV

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS					FIGURE 5	STATION DATA
$G=99^\circ$ $S_1=60^\circ$ $S_2=180^\circ$ N-002"-E 		TOWER No.	ELECTRICAL HEIGHT h'	SPACING s'	PHASING V'	FIELD RATIO F'	WVOC MEASURED NON- DIRECTIONAL PATTERN USING SOUTHWEST TOWER $\theta^\circ = 0^\circ$	CALL WVOC FREQ 1500 KHz. POWER 0.5 kw TYPE DA-D TIME DAYTIME LAT. 42°17'30" LONG. 85°10'08"
1								
2								
3								
4								
5								
6								
7								
8								
9								
10								
○ = not used ● = NDA test FCC File No. BL-11492 Accepted 12-29-66		DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☐					E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.	


Station WVOC
Battle Creek, Michigan

1500 kc

Proposed Day
(5-25-62ct)

New; Z-B Broadcasting Co.
Zion, Illinois

250w, DA-D, D
1500 kc



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS										STATION DATA	
		TOWER	ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	PHASING	HORIZONTAL FIELD	FIELD RATIO	ELEV. ANGLE	ELEVATION RMS FIELD	CALL	NEW	
		#	ft	°	ft	°	dBm		°	dBm			
		3	75'	N266°E	100'	+165°		0.59	0	97.4	FREQUENCY	1000	
		1	75'	--	--	0°	123.5	1.0	10		POWER	0.25	
		2	75'	N86°E	100'	-165°		0.59	80		TYPE OF OPERATION	DAY	
		4							30		TYPE OF OPERATION	DA-D	
		5							40		DAYTIME TOWERS	3	
		6							50		NIGHTTIME TOWERS	--	
		7							60		NO RADIALS PER TOWER	120	
		8							70		LENGTH OF RADIALS	90' 164'	
9							80		GROUND SCREEN DIMENSION	24x24			
10									LAT.	42° 27' 18"			
		DAYTIME OPERATION ☒		NIGHTTIME OPERATION ☐						LONG.	87° 54' 01"		
										SUPERSEDES			
										PATTERN NO.	620320		

Z-B BROADCASTING CO. ZION, ILLINOIS		FIGURE 1 DATE APRIL 2, 1962
CONSULTING ENGINEERS	GEORGE P. ADAIR ENGINEERING COMPANY	
	WASHINGTON, D. C.	

FCC File No. BP-15458
Accepted 5-4-62

New; Z-B Broadcasting Co.
Zion, Illinois

1500 kc



WZBN

Proposed Day
(8-28-67ct)-

Station WZBN
Zion, Illinois

250w, DA-D, D
1500 kc

9-7-67
GRANTED
MODIF FCC CP
CHANGE IN
ANTENNA
SYSTEM



WZBN
HORIZONTAL RADIATION PATTERN
1500 KHZ 0.25 KW DA-D
ZION, ILLINOIS
JULY, 1967

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS


WZBN

Measured Day
(10-28-67ct)

Station WZBN
Zion, Illinois

250w, DA-D, D
1500 kc

OVER



PATTERN PARAMETERS

W. C. E.
S — S — S — 86° T
0.59 / +165 10 / 0 0.59 / -165 CALC.
0.448 / 167 10 / 0 0.509 / -165 MEAS.
S = 100° = 182'
H = 77° = 140 FEET

WZBN
HORIZONTAL RADIATION PATTERN
1500 KHZ 0.25 KW DA-D
ZION, ILLINOIS

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

FCC File No. BL-11762
Accepted 10-13-67

Station WZBN
Zion, Illinois


1500 kc

WZEN

Measured Non-DA
(10-28-67ct)

Station WZBN
Zion, Illinois

250w, DA-D, D
1500 kc



FCC File No. BL-11762
Accepted 10-13-67


Station WZBN
Zion, Illinois

1500 kc

Proposed Day
(6-28-67ct)

New; Jud, Incorporated
Ellwood City, Pennsylvania


250w, DA-D, D
1500 kc



FCC File No. BP-17749
Accepted 6-14-67

New; Jud, Incorporated
Ellwood City, Pennsylvania

1500 kc




The
was
Amended

PROPOSED NIGHT
(3-28-60g)

New; Geneco B/Cstng, Inc.
Marion-Jonesboro, Indiana

500w, 5kw-LS, DA-2, U
1500 KC



FCC File No. BP-13975
Accepted 3-24-60

Geneco Broadcasting, Inc.
Marion - Jonesboro,
INDIANA

1500 KC

Description Sheet
(8-27-65ct)

Station XEMS
Matamoros, Tamaulipas

1kw, DA-1, U, Class III
1500 kc

XEMS

DIRECTIONAL ANTENNA DESCRIPTION SHEET
(Issued July 21, 1965)

Station: XEMS

Main Studio: Matamoros, Tamaulipas

Frequency: 1500 kc/s

Power: 1kw

Notification List No. (*)

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: $25^{\circ} 52' 43''$

West Longitude: $97^{\circ} 31' 09''$

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-1)

Number of elements: 2

Type of elements: Guyed, vertical steel towers.

TOWER: #1(SW) #2(NE)

HEIGHT ABOVE
INSULATORS: 164' 164' (90°)

PHASING: 0° $+8^{\circ}$

FIELD RATIO: 1 1

SPACING AND

ORIENTATION: elements are spaced 328.1' (180°) on a line bearing 25.5° true.

GROUND SYSTEM: 120 - 164' equally spaced copper radials about each tower.

Predicted effective Field: 175 mv/m at rated power.


(*) FCC Note: This "supplementary" information corresponds to a change in an existing station assignment concerning which official notification has not been received in the Commission as of July 21, 1965.

XEMS

Proposed Day & Night
(8-27-65ct)

Station XEMS
Matamoros, Tamaulipas

1kw, DA-1, U, Class III
1500 kc



DESCRIPCION DEL SISTEMA DIRECCIONAL DE RADIACION

ESTACION X E R HESTUDIOS EN México, D.F.FRECUCENCIA 1500 Kcs.POTENCIA 20,000 Watts.CLASE II

LISTA DE CAMBIOS _____

FECHA _____

LOCALIZACION GEOGRAFICA
DEL SISTEMA RADIADORLONGITUD $99^{\circ} 07' 59''$ Oeste
LATITUD $19^{\circ} 23' 41''$ NorteAUTORIZADO PARA OPERACION NOCTURNA DA-MNUMERO DE ELEMENTOS RADIADORES: DOSTIPO DE ELEMENTOS RADIADORES: TORRES VERTICALES DE ACERO SOPORTA--
DAS CON RETENIDAS Y ALIMENTADAS EN -
SERIE

TORRES	Sur	Norte
ALTURA SOBRE LOS AISLADORES	$90^{\circ} = 50$ metros	$90^{\circ} = 50$ metros
SEPARACION ENTRE TORRES	$45^{\circ} = 25$ metros	
DEFASAMIENTO	0°	135°
MAGNITUDES RELATIVAS DE CORRIENTES	1	1
AZIMUT DEL EJE DE LAS TORRES	$10^{\circ} 00' 00''$	
RAIZ CUADRATICA MEDIA TEORICA	782.600 mV/M	
EFICIENCIA DEL SISTEMA RADIADOR	175 mV/M/Kw	

ALLOCATIONS SECTION

JUN 17 1953

ENGINEERING BUREAU
STANDARD BROADCAST DIVISION

INFORMATION COPY

REC'D 3/17/53 ACC. 4/9/53


XERH

PROPOSED
NIGHT

XERH, MEXICO, D.F.
(4/15/53G)

20,000 W, DA-N


1500 kc



INFORMATION COPY

REC'D 3/17/53 ACC. 4/9/53

PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/M A UNA MILLA.



ALLOCATIONS SECTION

RADIODIFUSORA
XERH
APR 17 1953
ENGINEERING BUREAU
STANDARD BROADCAST DIVISION
Mexico, D. F.

1500 Kc.
20 000 Watts.

ARTURO AMADOR.
MANUEL CASTELLANOS.
Posantes Ing. COMUNICACIONES.

XERH, Mexico, D.F.

1500 kc