

1510-1540

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
CJRS	Sherbrooke, QU	1510	50/10 kW/DA-2	3/15/77
CKOT	Tillsonburg, ON	1510	1 kW/DA-D	5/25/56
XEOF	Cortazer, ON	1510	5 kW/DA-D	7/1/72
NEW	Troy, OH	1510	0.25 kW/DA-D	11/2/79
KAAR	Mountlake Terrace, WA	1510	0.25 kW/DA-D	11/29/68
KURB	Mountlake Terrace, WA	1510	0.25 kW/DA-D	11/29/68
KDKO	Littleton, CO	1510	5/1 kW/DA-2	4/30/75
KEAM	Port Arthur, TX	1510	5 kW/DA-D	3/29/78
KGA	Spokane, WA	1510	50 kW/DA-N	4/12/47
KIRV	Fresno, CA	1510	10 kW/DA-D	11/2/79
KMOR	Littleton, CO	1510	1 kW/DA-1	9/7/56
KSOM	Ontario, CA	1510	1/10 kW/DA-2	3/28/69
WAHT	Annville-Cleona, PA	1510	5 kW/DA-D	9/26/68
WAUK	Waukesha, WI	1510	10 kW/DA-D	7/28/66
WINU	Highland, IL	1510	1 kW/DA-D	6/28/68
WINU	Highland, IL	1510	0.25 kW/DA-D	9/27/60
WITS	Boston, MA	1510	5/50 kW/DA-2	9/12/80
WMEX	Boston, MA	1510	5/50 kW/DA-2	1/28/69
WJCO	Jackson, MI	1510	5 kW/DA-D	8/24/62
WJIC	Salem, NJ	1510	2.5 kW/DA-D	5/16/80
WLAC	Nashville, TN	1510	50 kW/DA	2/20/45
WLKR	Norwalk, OH	1510	0.5 kW/DA-D	10/28/66
WMBA	Ambridge-Aliquippa, PA	1510	10 kW/DA-D	1/28/66
WNLC	New London, CT	1510	5/10 kW/DA-2	12/24/75
WPUT	Brewster, NY	1510	1 kW/DA-D	4/21/71

1510-1540

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WRAN	Dover, NJ	1510	0.5/10 kW/DA-2	5/27/69
WRGI	Marco Island, FL	1510	1 kW/DA-D	9/17/75
NEW	Naples, FL	1510	0.25 kW/DA-D	4/29/70
NEW	Monticello, IN	1510	0.25 kW/DA-D	11/29/66
NEW	Wabash, IN	1510	0.25 kW/DA-D	1/30/67
NEW	Pulaski, VA	1510	0.25 kW/DA-D	7/28/69
NEW	Roanoke, VA	1510	50 kW/DA-D	11/29/69
XERB	Cozumel, QR	1510	5 kW/DA-D	9/1/77
NEW	Langley, BC	1520	10 kW	7/26/83
KACY	Port Hueneme, CA	1520	1/50 kW/DA-2	6/29/70
KACY	Port Hueneme, CA	1520	1/10 kW/DA-2	12/22/64
KACY	Port Hueneme, CA	1520	1/5 kW/DA-2	2/26/60
KMPL	Sikeston, MO	1520	0.5/5 kW/DA-3	2/28/66
KOMA	Oklahoma City, OK	1520	50 kW/DA-N	10/14/71
KXKW	Lafayette, LA	1520	0.5/10 kW/DA-D	8/29/60
KYXI	Oregon City, OR	1520	10 kW/DA-1	8/3/55
KYXI	Oregon City, OR	1520	50 kW/DA-2	8/23/63
WANR	Toledo, OH	1520	1 kW/DA-2	3/27/70
WAOA	Auburn-Opelika, AL	1520	5 kW/DA-D	7/28/66
WEXM	Jamesville, VA	1520	0.5 kW/DA-D	2/20/75
WGNB	Indian Rocks Beach, FL	1520	1 kW/DA-D	4/30/63
WINW	Canton, OH	1520	1 kW/DA-D	12/15/60
WKBW	Buffalo, NY	1520	50 kW/DA-1	1/30/67
WKJR	Muskegon Heights, MI	1520	0.5 kW	8/28/79
WKJR	Muskegon Heights, MI	1520	10 kW/DA-D	5/27/70
WKNT	Kent, OH	1520	1 kW/DA-D	7/27/65

1510-1540

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WPOE	Greenfield, MA	1520	10 kW/DA-D	11/16/79
WRAI	San Juan, PR	1520	10 kW/DA-1	10/26/70
WSLT	Ocean City-Sommers Point, NJ	1520	1 kW/DA-D	6/14/61
WSVL	Shelbyville, IN	1520	0.25/1 kW/DA-2	4/10/61
WTGR	Myrtle Beach, SC	1520	5 kW/DA-D	10/73
WTLN	Apopka, FL	1520	5 kW/DA-D	12/15/60
XEEG	Panzacola, Tlax.	1520	0.5 kW/DA-D	7/29/70
NEW	Greenfield, MA	1520	5 kW/DA-D	5/27/69
NEW	Yorktown, TX	1520	0.5 kW/DA-D	9/28/66
NEW	Moncton, NB	1530	10/5 kW	7/26/83
NEW	Morden, MB	1530	10/1 kW/DA-2	3/28/79
KECK	Lincoln, NE	1530	5 kW/DA-D	1/28/66
KFBK	Sacramento, CA	1530	50 kW/DA-1	12/30/48
KGBT	Harlingen, TX	1530	50/10 kW/DA-1	1/21/52
KNBE	Lincoln, NE	1530	5 kW/DA-D	12/30/63
KNIE	Cheyenne, WY	1530	1/10 kW/DA-N	2/28/69
WCKY	Cincinnati, OH	1530	50 kW/DA-N	11/2/79
WDJZ	Bridgeport, CT	1530	5 kW/DA-D	11/9/79
WDJZ	Bridgeport, CT	1530	10 kW/DA-D	4/13/77
WFIC	Collinsville, VA	1530	1/0.25 kW/DA-D	5/27/70
WKDC	Elmhurst, IL	1530	0.25 kW/DA-D	9/28/67
WQLW	Flora, IL	1530	1 kW/DA-D	4/29/69
WKDC	Elmhurst, IL	1530	0.25 kW/DA-D	10/17/74
WPNO	Auburn, ME	1530	10 kW/DA-D	12/4/74
WRBX	Chapel Hill, NC	1530	5 kW/DA-D	4/27/77
WRBX	Chapel Hill, NC	1530	10 kW/DA-D	2/8/78

1510-1540

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WTHM	Lapeer, MI	1530	5 kW/DA-D	9/13/60
WTTI	Dalton, GA	1530	10 kW/DA-D	6/5/74
WTTI	Dalton, GA	1530	10 kW/DA-2	9/28/65
WYAZ	Yazoo City, MS	1530	0.25 kW/DA-D	8/22/69
NEW	Jacksonville, FL	1530	50 kW/DA-D	5/27/69
NEW	Wheaton, IL	1530	0.5 kW/DA-D	4/29/70
NEW	Flora, IL	1530	0.25 kW/DA-D	4/29/68
NEW	Lincoln, NE	1530	5 kW/DA-D	11/30/61
NEW	Matawan, NJ	1530	0.5 kW/DA-D	8/26/66
NEW	Somerville, NJ	1530	1 kW/DA-D	4/28/67
XEUR	Texcoco, Edo de MX	1530	5 kW/DA-1	3/22/71
CHFI	Toronto, ON	1540	50 kW/DA-D	7/27/62
CHIN	Toronto, ON	1540	50 kW/DA-D	8/24/83
KASA	Phoenix, AZ	1540	10 kW/DA-D	9/20/61
KBUY	Fort Worth, TX	1540	1/50 kW/DA-2	9/28/66
KBUY	Fort Worth, TX	1540	1/5 kW/DA-1	9/16/49
KBVU	Bellevue, WA	1540	1 kW/DA-1	4/24/64
KEDA	San Antonio, TX	1540	1/5 kW/DA-2	11/2/79
KFKF	Bellevue, WA	1540	25 kW/DA-2	12/27/68
KFKF	Bellevue, WA	1540	1 kW/DA-1	2/28/66
KGBC	Dallas, TX	1540	0.25/1 kW/DA-N	4/22/60
KKAP	Aptos-Capitols, CA	1540	10 kW/DA-D	11/9/79
KMFO	Aptos, CA	1540	10 kW/DA-D	12/12/80
KMPG	Hollister, CA	1540	5 kW/DA-D	9/26/68
KXEL	Waterloo, IA	1540	50 kW/DA	1/31/45
KZAM	Bellevue, WA	1540	5 kW/DA-N	6/18/75
KZLA	Los Angeles, CA	1540	10/50 kW/DA-2	3/19/76

1510-1540

<u>Station</u>	<u>Main Studio</u>	<u>Freq</u>	<u>Power</u>	<u>Date</u>
WBCO	Bucyrus, OH	1540	0.5 kW/DA-D	6/27/69
WNIO	Niles, OH	1540	0.5 kW/DA-D	4/22/60
WNRE	Circleville, OH	1540	1 kW/DA-D	12/4/74
WPTR	Albany, NY	1540	50 kW/DA-1	12/20/48
WRCP	Philadelphia, PA	1540	50 kW/DA-D	7/8/59
WRGM	Richmond, VA	1540	10 kW/DA-D	10/25/61
NEW	Santa Cruz, CA	1540	5 kW/DA-D	3/28/68
NEW	Napoleon, OH	1540	0.5 kW/DA-D	8/29/60
WRPL	Charlotte, NC	1540	10 kW/DA-D	9/27/78

ANTENNE DIRECTIONNELLE

STATION : CJRS, Sherbrooke, Qué. STUDIO PRINCIPAL: Sherbrooke, Qué.

PUISSANCE: 50 kw jour
10 kw nuit

FREQUENCE : 1510 KHz

CLASSE : II

TEMPS : U

NOTIFICATION NO: 362

DATE 1e 15 mars 1977

COORDONNEES GEOGRAPHIQUES: 45°21'05" latitude nord
71°57'30" longitude ouest

CARACTERISTIQUES D'ANTENNE

MODE D'OPERATION : AD-2

NOMBRE D'ELEMENTS : 4

DESCRIPTION DES ELEMENTS : Quatre mât d'acier de coupe uniforme haubanés, isolés à la base pour une alimentation en série. Aucune charge de tête

<u>TOURS</u>		<u>No. 1</u>	<u>No. 2</u>	<u>No. 3</u>	<u>No. 4</u>
Hauteur au-dessus des isolateurs:		163' (90°)	163'	163'	163'
Hauteur hors-tout		170'	170'	170'	170
Rapport de champ - jour			1.0	0.55	
- nuit		1.000	2.846	2.846	1.000
Phasage - jour			0°	-130°	
- nuit		-177°	+61°	-61°	+177°
Espacement		Ref.	163' (90°)	326' (180°)	489' (270°)
Orientation		Ref.	42°	42°	42°

SYSTEME DE MISE A TERRE : Pour chaque mât, 120 rayons espacés également en fils de cuivre mou No. 10 B&S de 261' (0.4) reliés au point de jonction commun et joints à un ruban de cuivre mou à la base de la tour

CHAMP PREVU

: Jour: 1343 mV/m @ 1 mi. pour 50 kw
190 mV/m @ 1 mi. pour 1 kw
Nuit: 585 mV/m @ 1 mi. pour 10 kw
185 mV/m @ 1 mi. pour 1 kw

CJRS




FIGURE 1. DIAGRAMME HORIZONTAL - JOUR

CJRS, Sherbrooke, Qué.

1510 KHz, 11, AD-2

Augmentation de puissance diurne 50 Kw

18 août 1976 Pierre Labarre & Ass. Ltée
PROJET 3101 St-Lambert, Qué



Description Sheet
(4-28-67ct)

New Station
Sherbrooke, Quebec

10kw, DA-2, U, Class II
1510 kc
" "

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2

STATION CALL:

MAIN STUDIO

.....

Sherbrooke, Quebec.

FREQUENCY

1510 kc/s

POWER

10,000 watts

CLASS

II

TIME

Unlimited

NOTIFICATION REFERENCE

List 223 March 3, 1967

GEOGRAPHICAL LOCATION

Lat 45° 21' 05", Lon 71° 57' 30"

ARRAY CHARACTERISTICS

Four elements, guyed, uniform cross section, base insulated, series feed. Height 163 feet or 90 degrees. No top loading.

ELEMENT	ONE	TWO	THREE	FOUR
spacing	ref	163' 90°	326' 180°	489' 270°
bearing	ref	042°	042°	042°
Day R		1.00	0.55	
Ø		00°	-130°	
Night R	1.000	2.846	2.846	1.000
Ø	-177°	-61°	-61°	-177°

Ground System 120 radials per tower, #10 AWG bare, soft copper wire, spaced uniformly, depth 8 inches approximately. Radials bonded on a line between towers and bonded to soft copper strap at tower base. Maximum radial length 261 feet.

R M S Day 601 mv/m at 1 mile for 10 kw
190 mv/m at 1 mile for 1 kw

Night 585 mv/m at 1 mile for 10 kw
185 mv/m at 1 mile for 1 kw

6 a


CJRS

Proposed Night
(4-28-67ct)

New Station
Sherbrooke, Quebec

10kw, DA-2, U, Class II
1510 kc

NOZ
GEUPPAL & ERSER CO.



215

CJRS

Description Sheet
(8-26-66ct)Station CALL
Sherbrook, Quebec10kw, DA-2, U, Class II
1510 kc

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2

STATION CALL
MAIN STUDIO
FREQUENCY
POWER
CLASS
TIME.....
Sherbrooke, Quebec
1510 kc/s
10,000 watts
II
Unlimited

NOTIFICATION REFERENCE

.214.... Date: July 2, 1966.

GEOGRAPHICAL LOCATION

Lat 45°21'05", Lon 71°57'30"

ARRAY CHARACTERISTICS

Three elements, guyed, uniform cross section, base insulated, series feed. Height 163 feet on 90 degrees. No top loading.

ELEMENT	ONE	TWO	THREE
spacing	ref	163' 90°	326' 180°
bearing	ref	042½°	042½°
Day R	1.00	0.55	
#	00°	-130°	
Night R	1.000	1.928	1.000
#	00°	-114.5°	+131.0°

Ground System

120 radials per tower, #10 AWG bare soft copper wire, spaced uniformly, depth approximately 8 inches. Radials bonded on a line between towers and lapped to soft copper strap at tower base. Average length 261 feet.

R M S

Day

601 mv/m at 1 mile for 10 kw
190 mv/m at 1 mile for 1 kw

Night

585 mv/m at 1 mile for 10 kw
185 mv/m at 1 mile for 1 kw


June 1966

5

215

Station CALL
Sherbrook, Quebec

10kw, DA-2, U, Class II,
1510 kc




215

CJRS

Proposed Night
(8-26-66ct)

Station CALL
Sherbrook, Quebec

10kw, DA-2, U, Class II
1510 kc



#103

CKOT.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: CKOT

Main Studio: Tillsonburg, Ont.

Frequency: 1510 Kc.

Power: 1 Kw. Class: II

Notification List No. 103


Date: May 25, 1956.Geographical Location of the
Centre of the Antenna System

North Latitude: 42° 52' 42"

West Longitude: 80° 44' 30"

Antenna: Mode of Operation - LA-L (day only) elements: two, vertical,
triangular, guyed, radiators of uniform cross-section. No top
loading.

<u>Tower:</u>	<u>(1) West</u>	<u>(2) East</u>
<u>Height above insulators:</u>	160' (93°)	160'
<u>Spacing:</u>	163' (90°)	
<u>Phasing:</u>	0°	155°
<u>Field Ratio:</u>	0	0.55

Orientation: Towers on a bearing 093° true.Predicted Effective Efficiency: 178 mv/m at 1 mile for 1 Kw.

Ground System: 120 radials #10 copper per tower, buried 10" below grade, bonded
to #6 copper at perimeter. Radials are not of equal length but
area of the ground system is equivalent to circular type ground
system with diameters 0.4 wavelength. Radials are bonded to a
24' x 24' ground screen of expanded copper at base of tower.

#103


CKOT

PROPOSED
DAY (7-27-56g)

STATION CKOT
TILLSONBURG, ONT.

1 KW CLASS II
DA-D, D

1510 KC



DIRECTIONAL ANTENNA DESCRIPTION SHEET
(Issued January 23, 1973)

DESCRIPCION DEL SISTEMA DIRECCIONAL DE RADIACION

OPERACIONDIURNA

ESTACION XEOF

UBICACION: COATZAC, GTO.

FRECUENCIA: 100 KHz.

POTENCIA: 5000W-D

NOTIFICACION N° _____

CLASE: AD-D D III

LOCALIZACION GEOGRAFICA DEL
SISTEMA RADIADOR

LONGITUD O: 100° 59' 55"

LATITUD N: 20° 30' 48"

CARACTERISTICAS DEL SISTEMA

AUTORIZADO PARA OPERACION

AD - D

NUMERO DE ELEMENTOS

DOS

TIPO DE ELEMENTOS

TORRES VERTICALES

TORRES

DOS CON RETENIDAS

ALTURA SOBRE LOS AISLADORES

OESTE 90° (49.67M)

ESTE 90° (49.67M)

SEPARACION ENTRE TORRES

00° (33.11M)

MAGNITUDES RELATIVAS DE CONTENIDO

1

1

DEFASEAMIENTO

0°

170

AZIMUT DEL EJE DE LAS TORRES

55° 00'

RAIZ CUADRATICA MEDIA TECNICA

0.714 mV/L

DEFASEAMIENTO DE CADA UNO DE LOS
ELEMENTOS A RESPECTO DEL EJE DE
DE POTENCIA RADIADA

198 mV/L

----- 0 ----- 0 ----- 0 -----

12

PATRON DE RADIACION HORIZONTAL TABULADO OPERACION DIURNA

XEOF

5000 W-AD-D


1510 KHZ

CORTAZAR, GTO.

$$E_f = 123.32 \cos(70^\circ \cos \phi + 36^\circ)$$

AZIMUTS		ϕ°	A cos	B $30^\circ A$	C B + 85	D cos C	E mV/m
55	55	0	1.0000	30.00	115.00	-0.4226	-541.655
45	65	10	0.9848	29.54	114.54	-0.415	-539.435
35	75	20	0.9397	28.19	118.19	-0.3939	-511.387
25	85	30	0.8660	25.98	110.98	-0.3584	-465.303
15	95	40	0.7660	22.98	107.98	-0.3090	-401.165
5	105	50	0.6428	19.28	104.58	-0.2470	-320.675
355	115	60	0.5000	15.00	100.00	-0.1736	-225.267
345	125	70	0.3420	10.26	95.26	-0.0914	-115.802
335	135	80	0.1736	5.21	90.21	-0.0034	-4.415
325	145	90	0.0000	0.00	85.00	0.0872	113.210
315	155	100	-0.1736	-5.21	79.79	0.1773	239.185
305	165	110	-0.3420	-10.26	74.74	0.2632	341.707
295	175	120	-0.5000	-15.00	70.00	0.3420	444.01
285	185	130	-0.5420	-19.28	65.72	0.4112	533.047
275	195	140	-0.5597	-22.38	62.02	0.4602	569.152
265	205	150	-0.5660	-25.53	59.02	0.5157	635.126
255	215	160	-0.5597	-28.19	56.81	0.5474	710.670
245	225	170	-0.5448	-29.54	55.46	0.5670	739.014
235	235	180	-0.0000	-30.00	55.00	0.5736	744.97

XE OF



[Handwritten signature]

Sección de Ingeniería
 140 radial en el con-
 do de la estación de co-
 municación y extensión
 de la línea de cable to-
 rre y en la estación de
 90° de cable de la co-
 municación de la es-
 tación.


XE OF

1510 KHZ.

CORTAZAR, GTO.

Sección
 REPRESENTACIONES
 TECNICAS
 Código 66 037
 060/0
 REPRESENTACIONES
 TECNICAS
 1510
 DICIEMBRE 1971


XEOF



EMA DE INGENIERIA

SEALAS

ERE ERCA



INDICACION

USADO

ESTRUCTURA DE 1972

ESTRUCTURA

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: (NEW)

Main Studio: Troy, Ohio

Frequency: 1510 kHz

Power: 0.25kw Day

Notification List No. 1783

Date: November 2, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:North Latitude: 40° 01' 08"
West Longitude: 84° 14' 29"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 6

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	NE(#1)	EC(#2)	SE(#3)	NW(#4)	WC(#5)	SW(#6)
HEIGHT ABOVE INSULATORS:	162.9'	162.9'	162.9'	162.9'	162.9'	162.9' (90.0°)
DAY PHASING:	0°	143°	-74.5°	76.5°	-140.5°	2°
DAY FIELD RATIO:	1.000	1.870	1.000	1.052	1.970	1.050

SPACING AND
ORIENTATION:

The towers are located in two parallel rows with 3 towers per row. Adjacent towers in a row are spaced 162.8' (90.0°) on a line bearing 200° true. End towers forming a side of the parallelogram are spaced 544.6' (301°) on a line bearing 241° true.


GROUND SYSTEM:

120 - 162.9' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day 83.000 mv/m	104.403 mv/m	92.613 mv/m

NEW
1510 kHz



$RMS_{thco} = 88.000 \text{ mV/m}$

$RMS_{std} = 92.613 \text{ mV/m}$

$RSS_{thco} = 104.403 \text{ mV/m}$

10X EXPANSION

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 6	STATION DATA
All G's = 90° #1 90° 301° #2 90° 301° #3 90° 301° #4 90° 301° #5 90° 301° #6 200°	TOWER	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	PROPOSED DAYTIME STANDARD PATTERN TROY, OHIO $\theta^\circ = 0$	CALL NEW
	$\lambda/4$	λ	$^\circ$	$\frac{F}{F_0}$	FREQ 1510 KHz		
	1			0	1.000		POWER 0.25 KW
	2			143	1.870		TYPE DA-D
	3			-74.5	1.000		TIME DAYTIME ONLY
	4			76.5	1.052		LAT. N 40-01-08
				-140.5	1.970		LONG. W 84-14-29
	5			2	1.050		E. HAROLD MUNN, JR. & ASSOCIATES, INC. COLDWATER, MICH.


KAAR

Measured Day
(11-29-68ct)

Station KURB
Mountlake Terrace, Washington

250w, DA-D, D
1510 kc

North Latitude 47° 48' 16"
West Longitude 122° 18' 01"



FCC File No. BL-12146
Accepted 10-30-68

Station KURB
Mountlake Terrace, Washington

1510 kc


KURB

Measured Non-DA
(11-29-68)

Station KURB
Mountlake Terrace, Washington

250w, DA-D, D
1510 kc

CURTIS DIETZEN CO.
MADE IN U. S. A.
NO TWO-P DIETZEN SPARK GAP
POLAR COORDINATE



REDS = 95 MV/M FOR .25 F.F.

FCC File No. BL-12146
Accepted 10-30-68

Station KURB
Mountlake Terrace, Washington

1510 kc

KAAR

Proposed Day
(10-26-65ct)


New; Mount-Ed-Lynn, Inc.
Mountlake Terrace, Washington

250w, DA-D, D
1510 kc

OVER

ENGINEER DIST. 1000
MADE IN U. S. A.

100% MILITARY GRADE PAPER
POLAR CO-ORDINATE



FCC File No. BP-16882
Accepted 10-21-65

New; Mount-Ed-Lynn, Inc.
Mountlake Terrace, Washington

1510 kc

KOKO

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KDKO

Main Studio: Littleton, Colorado

Frequency: 1510 kHz

Power: 5 kW Night 1 kW Day

Notification List No. 1630

Date: April 30, 1975

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 39° 33' 15"

West Longitude: 105° 02' 01"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 4

Type of elements: Series-excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	NW(#1)	WC(#2)	EC(#3)	SE(#4)
HEIGHT ABOVE INSULATORS:	200'	200'	200'	200' (110.5°)
NIGHT PHASING:	0°	+7.16°	+14.24°	+21.4°
NIGHT FIELD RATIO:	1	2.83	2.83	1
DAY PHASING:	-5.8°	+11.2°	+5.8°	---
DAY FIELD RATIO:	0.23	0.52	0.23	---

SPACING AND

ORIENTATION: Adjacent elements are spaced 370.6' (205°) on a line bearing
106° true.GROUND SYSTEM: 120-108' to 248' equally spaced copper radials plus a 48'
square ground screen about each tower. Radials are
shortened and bonded to transverse straps along intersections
between towers.


Predicted effective Night Field: 406.9 mv/m at rated power.

Predicted effective Day Field: 182.6 mv/m at rated power.

Note: Please retain the Daytime and Nighttime vertical directional antenna radiation patterns from 25° through 60° inclusive notified for Station KDKO in United States Change List Number 1296, dated November 26, 1968, and attach to this Revised Description Sheet and Nighttime horizontal and vertical angle patterns from 0° through 20° inclusive. This notification concerns only changes in meov's of radiation in the nighttime pattern with no changes in the daytime operation of the station.

CTR NO 30607A3


KDKO



AMENDED

FIGURE 3- A

HORIZONTAL RADIATION PATTERN



$$G_1 - G_2 - G_3 - G_4 = 110.5^\circ$$

APPLICANT :	KDKO
LOCATION :	LITTLETON, COLORADO
FREQUENCY :	1510 KC/S
POWER :	5000 WATTS
LATITUDE :	39 DEG 33 MIN 15 SEC
LONGITUDE :	105 DEG 02 MIN 01 SEC
WHEN USED:	NIGHTTIME
R.M.E. FIELD:	406.9 MV/M
DATE :	DECEMBER 1974

SILLMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
211 FOURTEENTH STREET, N.W.
WASHINGTON D.C. 20004


KDKO

Proposed Day
(9-26-68ct)


Station KDKO
Littleton, Colorado

5kw, 1kw-LS, DA-N, U
1510 kc

BP 18235
11-25-68
Granted
CP to change
operation
from 1 kw,
DA-1, U, to
5 kw, 1 kw-LS,
DA-2, U.



HORIZONTAL RADIATION PATTERN



APPLICANT	KDKO
LOCATION	LITTLETON, COLORADO
FREQUENCY	1510 KC/S
POWER	1,000 WATT
LATITUDE	39 DEG 33 MIN 15 SEC
LONGITUDE	105 DEG 02 MIN 00 SEC
WHEN USED	DAYTIME
RMS FIELD	182.6 MV/M
DATE	JUNE 1968

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-18235
Accepted 9-9-68

Station KDKO
Littleton, Colorado

1510 kc


KDKO

Proposed Night
(9-26-68ct)


Station KDKO
Littleton, Colorado

5kw, 1kw-LS, DA-N, U
1510 kc

BP-18235
Granted
11-25-68
To change
operation
from 1 kw
C4 +, U to
5kw, 1kw-LS,
DA-2, U



HORIZONTAL RADIATION PATTERN



G1 = G2 = G3 = G4 = 11.5°

APPL. CANT	KDKO
LOCATION	LITTLETON, COLORADO
FREQUENCY	1510 KC/S
POWER	5,000 WATTS
LATITUDE	39 DEG 33 MIN 15 SEC
LONGITUDE	105 DEG 02 MIN 01 SEC
WHEN USED	NIGHTTIME
RMS FIELD	406.9 MV/M
DATE	JUNE 1968

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-18235
Accepted 9-9-68

Station KDKO
Littleton, Colorado

1510 kc

KEAM

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KYKR

Main Studio: Port Arthur, Texas

Frequency: 1510 kHz

Power 5kw Day

Notification List No. 1773

Date: March 29, 1978 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 30° 03' 35"
West Longitude: 93° 58' 49"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: Series excited, Self supporting,
tapered, vertical steel towers.

TOWER: SW (#1) NE (#2)

HEIGHT ABOVE INSULATORS: 170.1 170.1 (94°)

PHASING: 0° +18°

FIELD RATIO: 1 0.65

SPACING AND
ORIENTATION:

With SW(#1) tower as reference the NE (#2) tower is spaced
344.3' (190°) on a line bearing 70° true.

GROUND SYSTEM: 120 - 163' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap along
intersections between towers. Centers of system are bonded
together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	401.8 mv/m	481.1 mv/m	422.2 mv/m

(This notification concerns a change in transmitter location, antenna system
and an increase in power.)

30° 03' 35"
93° 58' 49"

700 mv/m

600

400

200

RMS E(th) - 401.8 mv/m
RMS E(std) - 422.2 mv/m
RSS - 481.1 mv/m

70° T

②

0.65 / 18°

S

①

1 / 0°

STANDARD HORIZONTAL PLANE PATTERN

KELAM

RADIO STATION KYKR
PROPOSED OPERATION
PORT ARTHUR, TEXAS

1510 KHZ

5 KW

DA-D

051176

FIGURE C

G - 170.1' - 93.89°
S - 344.3' - 190°

Merl Saxen

CONSULTING RADIO ENGINEER

30° 03' 35"
93° 58' 40"

700 mv/m

600


400

200

RMS E(th) - 401.8 mv/m
RMS E(std) - 422.2 mv/m
RSS - 481.1 mv/m

BL-790205AB

70° T



NO
STANDARD HORIZONTAL PLANE PATTERN

RADIO STATION ~~KYKR~~ **KEAM**
PROPOSED OPERATION
PORT ARTHUR, TEXAS

1510 KHZ 5 KW DA-D

30-03-35N 93-58-49

051176

Merl Saxon
CONSULTING RADIO ENGINEER
LUFKIN, TEXAS

FIGURE C

G - 170.1° - 93.89°
S - 344.3° - 190°

NGA


PROPOSED NIGET

Station KGA
Spokane, Washington

50kw, DA-N,U
1510 KC

EUDINE DIETZGEN CO.

NO 340-P DIETZGEN GRAPH PAPER
POLAR CO-ORDIN.




H = 300'
= 1660

KGA
1510

AUG 4 1948 G

7-28-48




7-28-48

KGA
1510

AUG 1 1948 G

License 7-28-48



K G A
SPOKANE WASHINGTON
1510 KC 50 KW

POLAR DIAGRAM OF MEASURED RATIO
VALUES FOR
NON-DIRECTIONAL/DIRECTIONAL
OPERATION.

FIG. 5 (CORRECTED)


KGA

MEASURED
DAY (non-DA)

KGA, SPOKANE, WASH.

50kw, DAN

1510 kc



KGA, Spokane, Wash. 1510 kc

KIRV
1510kHz

SUPPLEMENTAL AND CORRECTED
DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KIRV

Main Studio: Fresno, California

Frequency: 1510 kHz

Power 10kw Day

Notification List No. 1785

Date: November 16, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 36° 42' 42"
West Longitude: 119° 49' 59"

Note: Please retain the description sheet and directional antenna radiation patterns notified for station KIRV in United States Change List Number 1783 dated November 2, 1979 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a change or correction in the geographical coordinates of the center of the antenna system.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KIRV

Main Studio: Fresno, California

Frequency: 1510

Power: 10kw Day

Notification List No. 1783

Date: November 2, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:North Latitude: 36° 42' 42"
West Longitude: 119° 49' 59"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	NW(#1)	SE(#2)
HEIGHT ABOVE INSULATORS:	185'	185' (105.2°)
DAY PHASING:	0°	-94.5°
DAY FIELD RATIO:	1.00	0.77

SPACING AND
ORIENTATION:The towers are spaced 162.6' (90°) on a line bearing
140° true.GROUND SYSTEM: 120 - 162' equally spaced copper radials plus 120-50'
interspaced radials about each tower.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	623.9 mv/m	635.4 mv/m	655.4 mv/m

KGA LIMIT

KGA
762 mi.

KIRV

Exhibit E1 Page 31

Appendix 1510 kHz Page

Client NEW LIFE ENTERP.

Date 1-22-79

FCC form 301 Sec V-A Pg. 1

KTIM
173
mi.TIM
MIT
X

X

1751
mi.
LIMIT
1386
mv/m

WLAC

RMS mv/m
 THEOR=623.9
 STD =655.4
 RSS =635.4
 E₁ =503.4

KSOM
 220 mi. LIMIT
 1250 mv/m

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
#1 Δ 110° $\downarrow$ 90° 162.6' $\downarrow$ 177/-94.5' $\downarrow$ 140° $G_1 = G_2$ $G_1 = 105.2^\circ 190'$		TOWER No.	ELECTRICAL HEIGHT G'	TRUE TOWER ORIENTATION Z°	SPACING S'	PHASING P°	HORIZONTAL FIELD E _{min}	FIELD RATIO F	ELEV ANGLE -g°	ELEVATION RMS FIELD E _g	CALL KIRV
		1	105.2	0	0	0	503.4	1.00	0	655.4	FREQUENCY 1510 kc
		2	105.2	140	90	-94.5	378.6	.77	10		POWER 10 kw
		3							20		TIME OF OPERATION DAY
		4							30		TYPE OF OPERATION DA-D
		5							40		DAYTIME TOWERS 2
		6							50		NIGHTTIME TOWERS -
		7							60		NO RADIALS PER TOWER 120
		8							70		LENGTH OF RADIALS 90 * 162 //
		9							80		GROUND SCREEN DIMENSION -
		10							E _g		LAT. 36° 42' 42"
		DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐								P _g 10 kw	LONG. 119° 57' 59"
											SUPERSEDES
											PATTERN No


LITTLETON, COLO

PROPOSED SKYLINE B/C INC.
NIGHT & DAY (DA-1) LITTLETON, COLORADO
(9-7-56g)

DA-1, U
1 KW

1510 KC

KMOR



FCC FILE NO. BP-10,751 Accepted 8-30-56

SKYLINE B/C INC.
LITTLETON, COLORADO

1510 KC

PROPOSED
NIGHT & DAY (DA-1) Littleton, Colorado
(9-7-56g)


Skyline B/C, Inc.

DA-1, U
1 KW

Littleton, Col

1510 KC

KMOR



----- MAXIMUM EXPECTED OPERATING VALUE

FIGURE 1-B

HORIZONTAL RADIATION PATTERN
(EXPANDED)

ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6
PHASE DEG	+5	+6	-6			
HEIGHT DEG	110	110	110			
FIELD RATIO	1.9	1.0	1.0			
NON-DA ANT						

FREQUENCY: 1510 KC
ASSIGNMENT: REQ. 1KW - U - DA-1
LONGITUDE: 105 DEG 03 MIN 35 SEC
LATITUDE: 39 DEG 33 MIN 12 SEC
WHEN USED: DAY AND NIGHT
R.M.S. FIELD: 182.2 MV/M
DATE: JULY 1956

ROBERT M. SKILLMAN
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

1510 KC

KSOM

Measured Day
(3-28-69ct)


Station KSOM
Ontario, California

1kw, 10kw-LS, DA-2, U
1510 kc

*Printed
1/12/69
KSOM
10kw-LS
DA-2, U
1510 kc*

EUGENE DIETZEN
FEB-69 IN U.S.A.

NO. 340 P. DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-12281
Accepted 3-25-69

Station KSOM
Ontario, California

1510 kc



KSOM

Measured Night
(3-28-69ct)

Station KSOM
Ontario, California

1kw, 10kw-LS, DA-2, U
1510 kc

*granted
1/12/69
license
increase
in daytime
power, to
1kw, 10kw-
LS, DA-2, U*



FCC File No. BL-12281
Accepted 3-25-69

Station KSOM
Ontario, California

1510 kc

KSOM

Measured Non-DA
(3-28-69ct)


Station KSOM
Ontario, California

1kw, 10kw-LS, DA-2, U
1510 kc

*measured 5/17/69
1000 ft
baseline
1000 ft
1KW, 10kw
LS, DA-2, U.*

EUGENE DIETZGEN CO.
DESIGNED IN U.S.A.

NO. 310 P. DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



TOWER 1 - NONDIRECTIONAL 1 KW.
KSOM 100/IN-DA-2-U 1510 KC
ONTARIO, CALIF. JANUARY, 1969

KEAN, SKLOM & STEPHENS CO.
CONSULTING RADIO ENGINEERS
NINETEEN EAST QUINCY STREET
RIVERSIDE, ILLINOIS 60546

FCC File No. BL-12281
Accepted 3-25-69


Station KSOM
Ontario, California

1510 kc

PROPOSED K O C S 1 KW, N-1 KW, D
NIGHT & DAY (DA-1) Ontario, California DA-1, U
(9-21-56g)

1510 KC

*Granted CP 3/6/57 to
install a DA-1 directional
antenna system*



NL 34° 05' 54.4"
WL 117° 36' 50.5"

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS										STATION DATA	
		TOWER No.	ELECTRICAL HEIGHT	TRUE TOWER COORDINATION	SPACING	PHASING	HORIZONTAL FIELD	FIELD RATIO	ELEV. ANGLE	ELEVATION POS. FIELD	CALL	K O C S	
1	110	0	0	0	165.2	1.0	0	194	FREQUENCY	1510			
2	110	9	90	112	0.525	0.525	10	194	POWER	1			
3	110	189	90	-112	0.525	0.525	20	194	TIME OF OPERATION	FULLTIME			
4							30	194	TYPE OF OPERATION	DA-1			
5							40	194	DAYTIME TOWERS	3			
6							50	194	NIGHTTIME TOWERS	3			
7							60	194	No. RADIALS PER TOWER	120			
8							70	194	LENGTH OF RADIALS	90 * 163 "			
9							80	194	GROUND SCREEN DIMENSION				
10							90	194	LAT.	34 * 02 * 42.5 "			
										LONG.			
										117 * 36 * 42.5 "			
										SLIPSIDES			
										PATTERN No.			
EXHIBIT NO. I-A (AMENDED) RADIO STATION K O C S ONTARIO, CALIFORNIA PROPOSED DA-1 — 1KW 1510 KC													
AUGUST — 1956													


KSOM ~~KASK~~

Proposed Day
(11-29-66ct)

Station KASK
Ontario, California

1kw, 10kw-LS, DA-2, U
1510 kc

2-15-67
GRANTED
CP 1 KW
2244 10 KW
TO



FCC File No. BP-17325
Accepted 11-14-66

Station KASK
Ontario, California

1510 kc


WAHT

Measured Day
(9-26-68ct)

Station WAHT
Annville-Cleona, Pennsylvania


5kw, DA-D, D
1510 kc

10-2-68
Granted
license



HORIZONTAL RADIATION PATTERN

FIGURE 1A



APPLICANT	ELITE COMMUNICATIONS
LOCATION	ANNVILLE-CLEONA, PENNSYLVANIA
FREQUENCY	1510 KC/S
POWER	5 KW
LATITUDE	41 DEG 15 MIN 00 SEC
LONGITUDE	76 DEG 00 MIN 00 SEC
WHEN USED	DAY
RMS FIELD	450 M/M
DATE	JULY 1968

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-12092
Accepted 9-13-68

Station WAHT
Annville-Cleona, Pennsylvania

1510 kc

WAHT

Proposed Day
(6-28-67ct)

Station WAHT
Annville-Cleona, Pennsylvania

5kw, DA-D, D
1510 kc

2-6-68
GRANTED
CP





FIGURE 1-A

HORIZONTAL RADIATION PATTERN



APPL. CANT. : WAHT
LOCATION : ANNVILLE-CLEONA, PA.
FREQUENCY : 1510 KC/S
POWER : 5,000 WATTS
LATITUDE : 40 DEG 17 MIN 44 SEC
LONGITUDE : 76 DEG 27 MIN 46 SEC
WHEN USED : DAYTIME
RMS FIELD : 440
DATE : JANUARY 1967

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BMP-12078
Accepted 6-14-67

Station WAHT
Annville-Cleona, Pennsylvania

1510 kc


WAHT

Measured Non-DA
(9-26-68ct)

Station WAHT
Annville-Cleona, Pennsylvania

5kw, DA-D, D
1510 kc

10-2-68
Granted
license





Wauk

Proposed Day
(7-28-66ct)

Station Wauk
Waukesha, Wisconsin

10kw, DA-D, D
1510 kc



Wauk RADIATION PATTERN
1510KC 10 KW DA-D
Waukesha, WISCONSIN
MAY, 1966

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

FCC File No. BP-17231
Accepted 6-30-66

Station Wauk
Waukesha, Wisconsin

1510 kc


PROPOSED DAY
(10-18-60g)

Station WAUX
Waukesha, Wisconsin

10kw, DA-D, U
1510 KC

WAUX

2-1-61
granted
increase power
and install
DA-D



FCC File No. BP-12885
Accepted 10-4-60 (Amended)

WAUX
Waukesha, Wisconsin



1510 KC

Wauk

Measured Day
(3-29-67ct)

Station Wauk
Waukesha, Wisconsin

10kw, DA-D, 0
1510 kc



Wauk
MEASURED RADIATION PATTERN
1510 KHZ 10 KW DA-D
WAUKESHA, WISCONSIN
AUGUST, 1966

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

FCC File No. BL-11584
Accepted 3-15-67

Station Wauk
Waukesha, Wisconsin

1510 kc


W A U K

Measured Day
(11-30-61ct)

Station WAUX
Waukesha, Wisconsin

10kw, DA-D, D
1510 kc

11-30-61
Antenna 100' high
in ground DA-D



FCC File No. BL-8805
Accepted 11-17-61

Station WAUX
Waukesha, Wisconsin


1510 kc

W A U K

Measured Non-DA
(3-29-67ct)

Station W A U K
Waukesha, Wisconsin

10kw, DA-D, D
1510 kc



FCC File No. BL-11584
Accepted 3-15-67

Station W A U K
Waukesha, Wisconsin


1510 kc

WAUK

Measured Non-DA
(11-30-61ct)

Station WAUX
Waukesha, Wisconsin

10kw, DA-D, D
1510 kc



FCC File No. BL-8805
Accepted 11-17-61

Station WAUX
Waukesha, Wisconsin

1510 kc


Proposed Day
(6-28-68ct)

Station WINU
Highland, Illinois


1kw, DA-D, D
1510 kc

WINU

SEE REVERSE SIDE.



HORIZONTAL RADIATION PATTERN



APPLICANT :	Radio Station WINU
LOCATION :	Highland, Illinois
FREQUENCY :	1510 KC/S
POWER :	1000 Watts
LATITUDE :	38 DEG. 45 MIN. 23 SEC.
LONGITUDE :	89 DEG. 39 MIN. 18 SEC.
WHEN USED :	Daytime
M.B. FIELD :	176 MV/M
DATE :	March 30th, 1968

RALPH J. BITZER
CONSULTING RADIO ENGINEERS
ST. LOUIS, MISSOURI

FCC File No. BP-18177
Accepted 6-20-68

Station WINU
Highland, Illinois

1510 kc

1510 KC

WINU

Measured Day
(3-30-64ct)


Station WINU
Highland, Illinois

250w, DA-D, D
1510kc

$Q_1 = Q_2 = 60^\circ = 108 \text{ feet}$

$38^\circ 45' 23.1''$
 $89^\circ 59' 18''$

Radio Station WINU, Highland, Illinois, Progressive Broadcasting Corporation
MEASURED DIRECTIONAL ANTENNA PATTERN 1510 kc. 250W-D, DA-D
This Exhibit Prepared November 18, 1963 by Paul Dean Ford, Engineer




FCC File No. BP-10414
Accepted 3-5-64

Station WINU
Highland, Illinois

1510kc

250w, DA-D, D
1510kc



FCC File No. BP-10414
Accepted 3-5-64

Station WINU
Highland, Illinois

1510kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WITS Main Studio: Boston, Massachusetts
Frequency: 1510 kHz Power: 50kw Night 50kw Day
Notification List No. 1789 Date: September 12, 1980 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 23' 10"
West Longitude: 71° 12' 01"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
Number of elements: 4
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	E(#1)	N(#2)	W(#3)	S(#4)
HEIGHT ABOVE INSULATORS:	360'	360'	360'	360' (199°)
NIGHT PHASING:	0°	+125.1°	-137.1°	+100.9°
NIGHT FIELD RATIO:	1.0	1.57	1.56	0.9
DAY PHASING:	—	0°	+92.1°	—
DAY FIELD RATIO:	—	1.0	1.16	—

SPACING AND
ORIENTATION:

The towers are located at the vertices of Rhombus the
sides of which are 90° in length on lines bearing
240° and 302° true.

GROUND SYSTEM: 120 - 162.8' equally spaced copper radials plus a 48' square
ground screen about each tower. Radials are shortened and
bonded to transverse straps along intersections between
towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS+</u>	<u>RSS</u>	<u>RMS</u>
Day	1786.5 mv/m	1801.99 mv/m	1876.4 mv/m
Night	1808 mv/m	1874.93 mv/m	1899 mv/m

WITS
1510 kHz






FIGURE 1A

STANDARD HORIZONTAL PLANE PATTERN



CALL	: WITS
APPLICANT	: MARINER COMMUNICATIONS INC.
LOCATION	: BOSTON, MASSACHUSETTS
FREQUENCY	: 1510 KHZ
POWER	: 50 KW
LATITUDE	: 42 DEG 23 MIN 10 SEC
LONGITUDE	: 71 DEG 12 MIN 1 SEC
WHEN USED	: DAY
R.M.S FIELD:	THEO: 1786.5 mV/m STD : 1876.4 mV/m
DATE	: FEBRUARY 1979
SILLIMAN, MOFFET & KOWALSKI, P.C. CONSULTING RADIO ENGINEERS 1000 BROAD LANE STREET GALVESTON, TX. 77550	

WITS
1510 kHz




AMENDED

FIGURE 3A

STANDARD HORIZONTAL PLANE PATTERN

G = 199° TOWERS
ERSS = 1874.93



CALL	: WITS
APPLICANT	: MARINER COMMUNICATIONS, INC.
LOCATION	: BOSTON, MASSACHUSETTS
FREQUENCY	: 1510 kHz
POWER	: 50 kW
LATITUDE	: 42 DEG 23 MIN 10 SEC
LONGITUDE	: 71 DEG 12 MIN 1 SEC
WHEN USED	: NIGHT
THEO. FIELD	: 1808.0 mV/m
STD	: 1899.0 mV/m
DATE	: OCTOBER 1979

SILLIMAN, MOFFET & KOWALSKI, P.C.
CONSULTING RADIO ENGINEERS
100 NORTH LANE STREET
ARLINGTON, VA. 22209

WITS

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WITS

Main Studio: Boston, Massachusetts

Frequency: 1510 kHz

Power 5kw Night 50kw Day

Notification List No. 1773

Date: March 29, 1978

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 16' 30"

West Longitude: 71° 01' 53"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 3

Type of elements: The N(#1) and S(#2) towers are series
excited, uniform cross-section, guyed:
The E(#3) tower is self supporting, series excited,
tapered; vertical steel towers.

TOWER:	S (#2)	N (#1)	E (#3)
HEIGHT ABOVE INSULATORS:	200	200	200 (110.5°)
NIGHT PHASING	135°	0°	---
NIGHT FIELD RATIO:	1.0	0.854	---
DAY PHASING:	0°	---	-45°
DAY FIELD RATIO:	1.0	---	1.27

SPACING AND
ORIENTATION:

The towers are located at the vertices of a triangle.
With the South (#2) tower as reference, the North Tower
is spaced 251' (138.7°) on a line bearing 358° true. The
East tower is spaced 244.3' (135°) on a line bearing 70°
true.

GROUND SYSTEM:

120 - 170' equally spaced copper radials plus a 24' square
ground screen about each tower. Radials are shortened and
bonded to a transverse strap along intersections between
towers.

PREDICTED EFFECTIVE FIELDS AT PATED POWER:


THEORETICAL

RMS

Day 1335 mv/m

Night 436 mv/m


Note: Please retain the Nighttime directional antenna radiation pattern notified for Station WMEX in the original 1941 Notification and attache to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in daytime MEOV of radiation and also a change in call letters from WMEX with Nighttime operation continued as previously notified.



PROPOSED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

G = 110.5°

Not used daytime
(N)
#1°



RICHMOND BROTHERS, INC.

BOSTON, MASSACHUSETTS

Jules Cohen & Associates
Consulting Electronics Engineers

STATION WMEX

1510 KHZ

5 KW, 50 KW-LS U DA-2

FEBRUARY 1977

DIRECTIONAL ANTENNA DESCRIPTION SHEET

WMEX
WITS

Station: WMEX Main Studio: Boston, Massachusetts
Frequency: 1510 kHz Power: 5 kW Night 50 kW Day
Notification List No. 1624 Date: March 18, 1975 Class: II
GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM: North Latitude: 42° 16' 30"
West Longitude: 71° 01' 53"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
Number of elements: 3
Type of elements: Series-excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	N(#1)	S(#2)	E(#3)
HEIGHT ABOVE INSULATORS:	200'	200'	200' (110.5°)
NIGHT PHASING:	0°	+135°	---
NIGHT FIELD RATIO:	0.854	1.0	---
DAY PHASING:	---	0°	-45°
DAY FIELD RATIO:	---	1	1.27

SPACING AND

ORIENTATION: Nighttime elements are spaced 251' (139°) on a line bearing 178° true. Daytime elements are spaced 244.3' (135°) on a line bearing 250° true.

GROUND SYSTEM: 120-170' equally spaced copper radials plus a 24' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.


Predicted effective Night Field: 436 mv/m at rated power.

Predicted effective Day Field: 1335 mv/m at rated power.

Note: Please retain the Nighttime directional antenna radiation pattern notified for Station WMEX in the original 1941 notification and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in the Daytime operation of the station with Nighttime operation continued as previously notified.

CTR NO 31204A3

WITS



PROPOSED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

G = 110.5°

Not used daytime
(N)

(C) S (E)
1.27 / 45°
250° T
S = 135° = 244.3°

RICHMOND BROTHERS, INC.

BOSTON, MASSACHUSETTS

Jules Cohen & Associates
Consulting Electronics Engineers

STATION WMEX

1510 KHZ

5 KW, 50 KW-LS U DA-2


DECEMBER 1974

Measured Day
(1-28-69ct)

BL 12231
GIL. (2-13-70) LIC. Covering increase in Power
DAYTIME
Station WMEX
Boston, Massachusetts


~~WMEX~~
5kw, 50kw-LS, DA-2, U
1510 kc

Figure 11



Site Coordinates
42° 16' 30" N
71° 01' 53" W

MEASURED DAYTIME HORIZONTAL PLANE RADIATION PATTERN



RICHMOND BROTHERS, INC.
BOSTON, MASSACHUSETTS

Jules Cohen & Associates
Consulting Electronics Engineers

STATION WMEX
1510 KHZ
5 KW 50 KW LS U DA 2
NOVEMBER 1968

FCC File No. BL-12231
Accepted 1-16-69

Station WMEX
Boston, Massachusetts


1510 kc

Measured Night
(1-28-69ct)


BL 12231
GTR (2-13-76) LIC increase in Daytime Power
Station WMEX
Boston, Massachusetts

WITS ~~WMEX~~
5kw, 50kw-LS, DA-2, U
1510 kc

Figure 12



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN



RICHMOND BROTHERS, INC.

BOSTON, MASSACHUSETTS

Jules Cohen & Associates
Consulting Electronics Engineers

STATION WMEX

1510 KHZ

5 KW, 50 KW-LS U DA-2

NOVEMBER 1968

FCC File No. BL-12231
Accepted 1-16-69

Station WMEX
Boston, Massachusetts


1510 kc

Measured Non-DA
(1-28-69ct)

BL 12231
CIR(2-13-70) Lc increase POWER
Station WMEX
Boston, Massachusetts


WMEX
5kw, 50kw-LS, DA-2, U
1510 kc

Figure 9



MEASURED NONDIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN

G = 110.5'



RICHMOND BROTHERS, INC.

BOSTON, MASSACHUSETTS

Jules Cohen & Associates
Consulting Electronics Engineers

STATION WMEX

1510 KHZ

5 KW. 50 KW-LS U DA-2

NOVEMBER 1968

FCC File No. BL-12231
Accepted 1-16-69

Station WMEX
Boston, Massachusetts

1510 kc


601TS

PROPOSED DAY
(1-29-60g)

Station WMEX
Boston, Massachusetts

5kw, 50kw-LS, DA-2, U
1510 KC

ERR. APP. 7-16-65
INC. FWR
CHG TO DA-2



42° 16' 30" N
71° 01' 53" W

PROPOSED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

G=110°
(W) s 1.0/0°
0.79/45°
250°T

(S) Not used
daytime

s = 135° = 244.3'

RICHMOND BROTHERS, INC.
BOSTON MASSACHUSETTS

Jules Cohen
Consulting Electronic Engineer

STATION WMEX

1510 KC

5 KW, 50 KW-LS U DA-2

DECEMBER, 1959

FCC File No. BP-13760

Accepted 1-14-60 (formerly BP-8771)

WMEX

Boston, Massachusetts


1510 KC

Proposed Day
(8-24-62ct)

Station WRST
Jackson, Michigan

5kw, DA-D, D
1510 kc

8-17-62
granted MCP
to change
location



$E_{RMS} = 396 \text{ MV/M}$

----- M.E.O.V.

LATITUDE: N 42° 11' 9.6" LONGITUDE: W 84° 22' 39"	ANTENNA PARAMETERS	FIGURE 1 (AMENDED) DAYTIME DIRECTIONAL HORIZONTAL POLAR PATTERN T.V. CORPORATION OF MICHIGAN, INC. JACKSON, MICHIGAN 1510 KC 5 KW, DA-D
JOHN H. MULLANEY CONSULTING RADIO ENGINEERS WASHINGTON, D. C.		

FCC File No. BMP-10381
Accepted

Station WRST
Jackson, Michigan

1510 kc

WJIC
1510 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WJIC Main Studio: Salem, New Jersey
Frequency: 1510 kHz Power: 2.5kw Day
Notification List No. 1786 Date: May 16, 1980 Class: II

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTIENNA SYSTEM:

North Latitude: 39° 34' 58"
West Longitude: 75° 27' 39"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D_
Number of elements: 4
Type of elements: Uniform cross-section, guyed, shunt
excited, vertical steel towers.

TOWER	N(#1)	NE(#2)	SE(#3)	S(#4)
HEIGHT ABOVE INSULATORS:	160' (88.39°)	145'	145'	145' (80.2°)
DAY PHASING:	0°	-80.29°	+175.46°	-82.99°
DAY FIELD RATIO:	1.0	0.642	0.542	0.775

SPACING AND ORIENTATION:

With the North (#1) tower as the reference, Tower #2(NE)
spaced 86.71° (156.89') on a line bearing 91.52° true;
Tower #3(SE) spaced 95.97° (173.65') on a line bearing
148.10° true; Tower #4(S) spaced 86.61° (156.71') on a
line bearing 188.46° true.


GROUND SYSTEM: 240 - 32' to 232' equally spaced copper radials about each tower.
Radials are shortened and bonded to transverse straps along
intersections between towers. Centers of system are bonded
together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL RMS	RSS	STANDARD RMS
Day	296.88 mV/m	324.234 mV/m	311.73 mV/m

WJIC
1510 kHz

57D



RSS - 324.234
RMS - 296.883
RSS/RMS RATIO-1.092
RMS STANDARD - 311.727

N.Lat. 39° 34' 58"
M.Long. 75° 27' 39"

G₁ = 88.39°
G₂, G₃ & G₄ = 80.20°

PETER V. GUSECKIS & ASSOC.
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.




FIGURE 4
PLOT of DAYTIME DIRECTIONAL
PATTERN
RADIO STATION WJIC
SALEM, NEW JERSEY
1510 KHz 2.5 KW-DA-D

TOWER	SPACING	BEARING
1 to 2	86.71°	91.52°
1 to 3	95.97°	148.10°
1 to 4	86.61°	188.46°


Measured Day
(4-30-63ct)

Station WJCO
Jackson, Michigan

5kw, DA-D, D
1510 kc

WJCO

5-14-63
revised
notes for
new A.M.
station




Measured Non-DA
(4-30-63ct)

Station WJCO
Jackson, Michigan

WJCO
5kw, DA-D, D
1510 kc


8-14-63
granted
license for
new AM
station.



WLAC

McNARY & CHAMBERS
RADIO ENGINEERS
WASHINGTON D.C.

1510
1510



CALCULATED HORIZONTAL PATTERN


WLAC. NASHVILLE. TENN.

150 KW - 1510 KC north 115°
OCTOBER 1940 west 91.3°

10-28-40

1510 KC
WLAC

MANLEY AND WREATHALL
RADIO ENGINEERS
WASHINGTON D C




WLKR

Proposed Day
(10-28-66ct)

New; Ohio Radio, Inc.
Norwalk, Ohio

500w, DA-D, D
1510 kc



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 3	STATION DATA
G's = 90° S 50° 1/130° #1 S #2 1.8/0° S 17-130° #3 115°	TOWER NO.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING V'	FIELD RATIO F'	PROPOSED DAYTIME DIRECTIONAL PATTERN	CALL NEW FREQ 1510 Khz POWER 0.5 Kw TYPE DA-D TIME Day LAT. N-41-16-45.3 LONG. W-82-39-22.8
	1						
	2						
	3						
	4						
	5						
	6						
	7						
	8						
	9						
	10						
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐						$\theta^\circ = 0$	E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.

FCC File No. BP-16659
Accepted 9-30-66 Amended

New; Ohio Radio, Inc.
Norwalk, Ohio

1510 kc


WLKR

Measured Day
(3-28-68ct)

Station WLKR
Norwalk, Ohio

500w, DA-D, D
1510 kc

*Antenna 475 ft high
beam - 100 ft high
a new standard
radio station*



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 6	STATION DATA																																																			
G's = 90° S = 90° 110° 1'	<table><thead><tr><th>TOWER No.</th><th>ELECTRICAL HEIGHT h</th><th>SPACING S</th><th>PHASING φ</th><th>FIELD RATIO F</th></tr></thead><tbody><tr><td>1</td><td>90°</td><td>90°</td><td>+119°</td><td>0.590</td></tr><tr><td>2</td><td>90°</td><td>90°</td><td>0°</td><td>1.000</td></tr><tr><td>3</td><td>90°</td><td>90°</td><td>-120°</td><td>0.486</td></tr><tr><td>4</td><td></td><td></td><td></td><td></td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></tbody></table> DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐	TOWER No.	ELECTRICAL HEIGHT h	SPACING S	PHASING φ	FIELD RATIO F	1	90°	90°	+119°	0.590	2	90°	90°	0°	1.000	3	90°	90°	-120°	0.486	4					5					6					7					8					9					10					WLKR MEASURED DAYTIME DIRECTIONAL PATTERN DECEMBER - 1967 θ° - 0°	CALL WLKR FREQ 1510 KHz. POWER 0.5 Kw TYPE DA-D TIME DAYTIME LAT. 41-16-45.3 LONG. 82-39-22.8 E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER No.	ELECTRICAL HEIGHT h	SPACING S	PHASING φ	FIELD RATIO F																																																						
1	90°	90°	+119°	0.590																																																						
2	90°	90°	0°	1.000																																																						
3	90°	90°	-120°	0.486																																																						
4																																																										
5																																																										
6																																																										
7																																																										
8																																																										
9																																																										
10																																																										

FCC File No. BL-11915
Accepted 3-26-68

Station WLKR
Norwalk, Ohio


1510 kc

WLKR

Measured Non-DA
(3-28-68ct)

Station WLKR
Norwalk, Ohio

500w, DA-D, D
1510 kc



RMS = 79.9 MV/M
MEOV

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 5	STATION DATA																																																					
G's = 90° S = 90° 110°	<table><tr><th>TOWER No.</th><th>ELECTRICAL HEIGHT h'</th><th>SPACING s'</th><th>PHASING φ'</th><th>FIELD RATIO F</th></tr><tr><td>1</td><td></td><td></td><td></td><td></td></tr><tr><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>3</td><td></td><td></td><td></td><td></td></tr><tr><td>4</td><td></td><td></td><td></td><td></td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></table>	TOWER No.	ELECTRICAL HEIGHT h'	SPACING s'	PHASING φ'	FIELD RATIO F	1					2					3					4					5					6					7					8					9					10					WLKR MEASURED NON-DIRECTIONAL PATTERN USING SOUTHEAST TOWER		DECEMBER - 1967	CALL WLKR FREQ 1510 KHz. POWER 0.187 Kw TYPE NDA TIME *** LAT. 41-16-45.3 LONG. 82-39-22.8
TOWER No.	ELECTRICAL HEIGHT h'	SPACING s'	PHASING φ'	FIELD RATIO F																																																								
1																																																												
2																																																												
3																																																												
4																																																												
5																																																												
6																																																												
7																																																												
8																																																												
9																																																												
10																																																												
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐					θ° = 0°		E.H.MUNN, JR. RADIO ENGINEER COLDWATER, MICH.																																																					

FCC File No. BL-11915
Accepted 3-26-68

Station WLKR
Norwalk, Ohio

1510 kc


WMBA

Proposed Day
(1-28-66ct)

Station WMBA
Ambridge-Aliquippa, Pennsylvania

10kw, DA-D, D
1510 kc

U.S. GOVERNMENT PRINTING OFFICE
1960 O-540-000
NO. 340R P. D12720 GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BP-13855
Record reopened 12-27-65

Station WMBA
Ambridge-Aliquippa, Pennsylvania

1510 kc

WNLC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WNLC	Main Studio: New London, Connecticut
Frequency: 1510 kHz	Power: 5 kW Night 10 kW Day
Notification List No. 1664	Date: December 24, 1975 Class: II
GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:	North latitude: 41° 22' 38"
	West Longitude: 72° 10' 02"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
Number of elements: 8
Type of elements: Series-excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	NW(#1)	(#2)	(#3)	(#4)	(#5)	SE(#6)	W(#7)	S(#8)
HEIGHT ABOVE INSULATORS:	All towers 220' (121.8°)							
NIGHT PHASING:	+151°	+18.29°	-113.83°	+113.83°	-18.29°	-151°	-	-
NIGHT FIELD RATIO:	1.0	3.279	5.294	5.062	2.857	0.7996	-	-
DAY PHASING:	-	-	0°	-	-	-	+33°	+150
DAY FIELD RATIO:	-	-	1	-	-	-	1.2	0.05

SPACING AND ORIENTATION: Nighttime, adjacent elements #1 through #6 are spaced 217' (120°) on a line bearing 305° true.

Daytime, tower #7 is spaced 275' (152°) on a line bearing 230° true from tower #3 and tower #8 is spaced 272.3' (150.51°) on a line bearing 193.77° true from tower #3.

GROUND SYSTEM: 120-163' equally spaced copper radials plus 120-50' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.



Predicted effective Night Field: 454 mv/m at rated power.

Predicted effective Day Field: 608 mv/m at rated power.

Note: Please retain the Nighttime directional antenna radiation pattern notified for station WNLC in United States Change List Number 837 dated November 22, 1960 and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in the daytime operation of the station with nighttime operation continued as previously notified.

WNLC

COHEN AND DIPPELL, P.C.
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D. C. 20004



HORIZONTAL PLANE RADIATION PATTERN
FOR THE DAYTIME OPERATION OF
WNLC, NEW LONDON, CONNECTICUT
1510 KHz - 5/10 KW - DA-2
JUNE 1975

TOWERS #1, 2, 4, 5, and 6 will be detuned
for daytime operation

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WNLC

Main Studio: New London, Connecticut

Frequency: 1510 kHz

Power: 5 kW Night 10 kW Day

Notification List No. 1593

Date: August 14, 1974 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 22' 38"
West Longitude: 72° 10' 02"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 8

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	NW(#1)	(#2)	(#3)	(#4)	(#5)	SE(#6)	W(#7)	S(#8)
HEIGHT ABOVE INSULATORS:	All towers 220' (121.8°)							
NIGHT PHASING:	+151°	+18.29°	-113.83°	+113.83°	-18.29°	-151°	-	-
NIGHT FIELD RATIO:	1.0	3.279	5.294	5.062	2.867	0.7996	-	-
DAY PHASING:	-	-30°	0°	+150°	+180°	-	+35°	+183°
DAY FIELD RATIO:	-	0.125	1	0.6	0.105	-	0.905	0.65

SPACING AND

ORIENTATION: Nighttime: Adjacent elements #1 through #6 are spaced 217' (120°) on
a line bearing 305° true.

Daytime: Adjacent elements #2 through #5 are spaced 217' (120°) on a
line bearing 305° true. Tower #7 is spaced 280' (155°) from
tower #3 on a line bearing 240° true. Tower #8 is spaced
280' (155°) from tower #4 on a line bearing 240° true.

GROUND SYSTEM: 120-163' equally spaced copper radials plus a 120-50' interspaced
radials about each tower. Radials are shortened and bonded to transverse
straps along intersections between towers.

Predicted effective Night Field: 454 mv/m at rated power.



Predicted effective Day Field: 640 mv/m at rated power.

Note: Please retain the Nighttime directional antenna radiation pattern notified
for station WNLC in United States Change List Number 887 dated November 22, 1960,
and attach to this Revised Description Sheet and Daytime pattern. This notifi-
cation concerns only a change in the Daytime operation of the station with
Nighttime operation continued as previously notified.

CTR NO 31203A3

WNLC

COHEN AND DIPPELL, P.C.
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D. C. 20004



$S_1 = 120^\circ$ Towers No. 1 & No. 6 are detuned for Day use
 $S_2 = 155^\circ$ Site Coordinates
 $S_3 = 150.51^\circ$ North Latitude $41^\circ 22' 38''$
 $H = 121.8^\circ$ West Longitude $72^\circ 10' 02''$

COMPUTED HORIZONTAL
PLANE RADIATION PATTERN
FOR THE PROPOSED DAYTIME OPERATION OF
WNLC, NEW LONDON, CONNECTICUT
1510 KHz - 5/10 KW - DA-2 U
MARCH 1974


WNLC

Measured Day
(12-30-63ct)-

Station WNLC
New London, Connecticut

5kw, 10kw-LS, DA-2, U
1510 kc

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4 D C




MEASURED HORIZONTAL
PLANE RADIATION PATTERN
FOR PROPOSED DAYTIME OPERATION
OF WNLC, NEW LONDON, CONNECTICUT
1510 KC - 5/10 KW - DA-2
JULY 1963

FCC File No. BL-9116
Accepted 12-12-63 Amended

Station WNLC
New London, Connecticut

1510 kc

V = 0°



H = 220' = 121.8°

NIGHTTIME PATTERN

1/±151° 3.279 /+18.29° 5.294 /-113.83° 5062/+113.83° 2.867 /-18.29° 0.7996 /-151°
N 305° E → ● 1 ● 2 ● 3 ● 4 ● 5 ● 6

S = 217' = 120°

COMPUTED
HORIZONTAL PLANE RADIATION PATTERN
FOR PROPOSED OPERATION OF
WHLC, NEW LONDON, CONN.
1510 KC, 5 KW, DA-2
JUNE 1960

NORTH LAT. 41° 22' 38"
WEST LONG 72° 10' 02"


WNLC

Measured Night
(4-27-62ct)

Station WNLC
New London, Connecticut

5kw, DA-2, U
1510 kc

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.



1/151	3.279/18.29	5.294/113.83	5.062/113.83	2.867/18.29	0.7996/151
N 305° E	● 1	● 2	● 3	● 4	● 5
0.1595/31.5	0.524/130	1.00/0	1.00/149	0.715/67.5	0.162/59.5
ACTUAL BASE CURRENT PARAMETERS					

NORTH LAT. 41° 22' 38"
WEST LONG. 72° 10' 02"

MEASURED
HORIZONTAL PLANE RADIATION PATTERN
WNLC, NEW LONDON, CONNECTICUT
1500 KC 5 KW DA-2
JANUARY 1962

FCC File No. BL-9116
Accepted 4-13-62

Station WNLC
New London, Connecticut

1510 kc


WNLC

Measured Non-DA
(4-27-62ct)

Station WNLC
New London, Connecticut

5kw, DA-2, U
1510 kc

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.



NON-DIRECTIONAL UNATTENUATED
FIELD INTENSITY AT ONE MILE FOR
WNLC - 5 KW - 1510 KC
NEW LONDON, CONNECTICUT
JANUARY 1962

FCC File No. BL-9116
Accepted 4-13-62

Station WNLC
New London, Connecticut

1510 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WPUT
Frequency: 1510 KHz
Notification List No. 1421
Main Studio: Brewster, New York
Power: 1kw
Date: April 21, 1971
Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:
North Latitude: 41° 24' 34"
West Longitude: 73° 37' 29"

ANTENNA CHARACTERISTICS


Authorized for Daytime operation. (DA-D)
Number of elements: 2
Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	N(#2)	S(#1)
HEIGHT ABOVE INSULATORS:	140'	140' (77.4°)
PHASING:	0°	+171°
FIELD RATIO:	1	0.51

SPACING AND
ORIENTATION: Elements are spaced 126.7' (70°) on a line bearing 170° true.

GROUND SYSTEM: 120 - 163' equally spaced copper radials plus a 24' square
ground screen about each tower. Radials are shortened and
bonded to a transverse strap along intersections between
towers.

Predicted effective Field: 187 mv/m at rated power.



PROPOSED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

#2 1/0
70° (126.7°)
#1 0.51/171°
170° True
G = 77.4° (140°)

BREWSTER BROADCASTING
CORPORATION
BREWSTER, NEW YORK

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION WPUT
1510 KHZ
1 KW D, DA
Pattern 701230

8-1-63
granted license
for one P.M.
station

WPUT

~~WBRW~~

Measured Day
(5-28-63ct)


Station WBRW
Brewster, New York

1kw, DA-D, D
1510 kc

$E_{rms} = 181 \text{ MV/M}$
(Measured)

— Measured Directional
Horizontal Pattern

○ Measured Radials



Spacing and Orientation

N350°E
"2" 0.85 $\angle 156.06^\circ$

70°

"1" 1.15 $\angle 10^\circ$

G = 140 feet = 77.36°

Latitude: $41^\circ 24' 34''$

Longitude: $73^\circ 37' 29''$

MEASURED DAYTIME
DIRECTIONAL
HORIZONTAL POLAR PATTERN

RADIO STATION WBRW

1510 Kc/s 1 KW-DA-D

BREWSTER, NEW YORK

FCC File No. BL-9989
Accepted 5-21-63

Station WBRW
Brewster, New York

1510 kc


Brewster, N.Y.

~~WBRW~~
WPUT

PROPOSED DAY
(5-27-60g)


New; Taconic Bcstrs.
Brewster, New York

1kw, DA-D, D
1510 KC



HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION



APPLICANT :	TACONIC BROADCASTERS
LOCATION :	BREWSTER, N. Y.
FREQUENCY :	1510 KC/S
POWER :	1 KW
LATITUDE :	41 DEG 22 MIN. 12 SEC.
LONGITUDE :	73 DEG 36 MIN. 26 SEC.
WHEN USED :	DAYTIME
R.M.S. FIELD :	180 MV/M
DATE :	APRIL 1960

SILLIMAN, MOFFET & ROHRER
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-14105
Accepted 5-16-60

Taconic Broadcasters Corporation
Brewster, New York

1510 KC

WPUT ~~WBRW~~

Measured Non-DA
(5-28-63ct)


Station WBRW
Brewster, New York

1kw, DA-D, D
1510 kc

$E_{rms} = 178 \text{ MV/M}$
(Measured)

— Measured NON-DA
Horizontal Pattern

⊙ Measured Radials



N150°E Fig 54

NON-DA HORIZONTAL PATTERN

RADIO STATION WBRW

1510 Kc/s 1 KW-D

BREWSTER, NEW YORK

Latitude: 41° 24' 34"

Longitude: 73° 37' 29"

FCC File No. BL-9989
Accepted 5-21-63

Station WBRW
Brewster, New York

1510 kc


WRAN

Measured Non-DA
(5-27-69ct)

Station WRAN
Dover, New Jersey


500w, 10kw-LS, DA-2, U
1510 kc
Figure 10

BL-12328
Granted 4/4/69
License
covering increase
in power



MEASURED NONDIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN

G-110°



Towers 1, 3 and 4 Not Used

S-203°-367.5'

LION BROADCASTING CO., INC.

DOVER, NEW JERSEY

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION WRAN

1510 KHZ

0.5 KW, 10 KW LS U DA 2

FEBRUARY 1969

FCC File No. BL-12328
Accepted 5-2-69

Station WRAN
Dover, New Jersey

1510 kc


WRAN

Measured Night
(5-27-69ct)

Station WRAN
Dover, New Jersey


500w, 10kw-LS, DA-2, U
1510 kc
figure 12

DL-12328
Granted 6/4/69
license covering
increase in
power



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

G=110°



S=203°-367.5°

LION BROADCASTING CO., INC.

DOVER, NEW JERSEY

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION WRAN

1510 KHZ

0.5 KW, 10 KW LS U DA 2

FEBRUARY 1969

FCC File No. BL-12328
Accepted 5-2-69

Station WRAN
Dover, New Jersey

1510 kc


WRAN

Measured Day
(5-27-69ct)


Station WRAN
Dover, New Jersey

500w, 10kw-LS, DA-2, U
1510 kc

*BL-1232, Granted
5/27/69 License
concerning increase
in power.*




MEASURED DAYTIME HORIZONTAL PLANE RADIATION PATTERN




500w, 10kw-LS, DA-2, U
1510 kc
Figure 1

MP-12654
Granted
3-21-69
rod. of
p. Caveling
Mangro



PROPOSED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN



LION BROADCASTING CO., INC.
DOVER, NEW JERSEY

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION WRAN

1510 KHz

65 KW. 10 FWT S. U DA 2

JANUARY 1969

FCC File No. BMP-12654
Accepted 3-19-69

Station WRAN
Dover, New Jersey

1510 kc

WRAN


Proposed Day
(10-28-67ct)

Station WRAN
Dover, New Jersey

500w, 10kw-LS, DA-2, U
1510 kc

Figure 1

9/11/68
CP FOR 05/10KW DA-2
BMP-12654
Hatched
(3-21-69)
Mod. 4 CP
Cover



PROPOSED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

	LION BROADCASTING CO., INC. DOVER, NEW JERSEY Jules Cohen & Associates Consulting Electronics Engineers	RADIO STATION WRAN 1510 KHZ 0.5 KW, 10 KW-LS U DA 2 APRIL 1967
--	--	--

FCC File No. BP-17757
Accepted 9-28-67

Station WRAN
Dover, New Jersey

1510 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WRGI Main Studio: Marco Island, Florida
 Frequency: 1510 kHz Power: 1 kW
 Notification List No. 1650 Date: September 17, 1975 Class: II

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 25° 59' 30"
 West Longitude: 81° 37' 30"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 4

Type of elements: Series-excited, uniform cross-section, guyed,
 vertical steel towers.

TOWER:	N(#3)	SW(#1)	NE(#4)	S(#2)
HEIGHT ABOVE INSULATORS:	160'	160'	160'	160' (88.5°)
PHASING:	+70°	0°	+194°	+124°
FIELD RATIO:	0.4	1.0	0.36	0.9


SPACING AND

ORIENTATION: The towers are located at the vertices of a parallelogram the long sides of which are 411' (227°) in length on a line bearing 7° true. The short sides are 144.7' (80°) in length on a line bearing 125° true.

GROUND SYSTEM: 120-163' equally spaced copper radials plus a 24' square ground screen about each tower. Radials are shortened and box to transverse straps along intersections between towers. Centers of systems are bonded together.

Predicted effective Field: 180 mv/m at rated power by adjustment of input power.

Note: This notification concerns only changes in means of radiation in the directional antenna pattern.




$E_{RMS} = 180 \text{ mV/m}$ (BY ADJUSTMENT)

----- MEOV

MAP 1075

LATITUDE: 25° 59' 30"
LONGITUDE: 81° 37' 30"

ANTENNA PARAMETERS



PETER V. GURECKIS & ASSOC.
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FIGURE 2
PROPOSED DIRECTIONAL
HORIZONTAL PATTERN

RADIO STATION WRGI
COLLIER BROADCASTING COMPANY
MARCO ISLAND, FLORIDA

1510 kHz

1.0 kW, DA-D

WRGI

CORRECTED DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WRGI

Main Studio: Marco Island, Florida

Frequency: 1510 kHz

Power: 1 kW

Notification List No. 1584

Date: June 12, 1974 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 25° 59' 30"

West Longitude: 81° 37' 30"

Authorized for Daytime operation (DA-D).


Predicted effective Field: 180 mv/m at rated power by adjustment of input power.

*Note: Please retain the description sheet and directional antenna radiation patterns notified for a new station at Marco Island, Florida in United States Change List Number 1528, dated May 9, 1973 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates of the center of the antenna system.

Proposed Day
(10-26-70ct)

New; Collier Broadcasting Co.
Marco Island, Florida

WRG1
1kw, DA-D, D
1510 kc



FCC File No. BP-18723
Accepted 10-13-70

New; Collier Broadcasting Co.
Marco Island, Florida

1510 kc

00

1

310° 320° 330° 340° 350° True North 10° 20° 30° 40° 50°






FIGURE 3-B
 MEASURED HORIZONTAL RADIATION PATTERN
 HRTI (AH) MARCO ISLAND, FLORIDA
 1510 KHZ
 1.0 KW DA-DAY
 DECEMBER, 1974
 JAMES M. JOHNSON & ASSOCIATES
 WEST PALM BEACH, FLORIDA


LATITUDE: 29° 59' 30"
 LONGITUDE: 81° 37' 30"

WRG 1

Proposed Day
(4-29-70oct)

New; Radio Voice of Naples
Naples, Florida

250w, DA-D, D
1510 kc



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS	FIGURE 3	STATION DATA																																																							
G's 100° S₁₂ 137.6' S₁₃ 272.4' S₁₅ 311.4' S₁₄ 439.9' S₁₆ 192.8' 282° 297° 76° 274° #4 #5 #1 #3 #2 #7	<table border="1"> <thead> <tr> <th>TOWER No.</th> <th>ELECTRICAL HEIGHT</th> <th>SPACING</th> <th>PHASING</th> <th>FIELD RATIO</th> </tr> </thead> <tbody> <tr><td>1</td><td>100</td><td>-</td><td>0</td><td>1.0</td></tr> <tr><td>2</td><td>100</td><td>76</td><td>130</td><td>1.96</td></tr> <tr><td>3</td><td>100</td><td>160.5</td><td>-100</td><td>1.0</td></tr> <tr><td>4</td><td>100</td><td>243</td><td>120</td><td>0.91</td></tr> <tr><td>5</td><td>100</td><td>172</td><td>-110</td><td>1.77</td></tr> <tr><td>6</td><td>100</td><td>106.5</td><td>19.5</td><td>0.91</td></tr> <tr><td>7</td><td></td><td></td><td></td><td></td></tr> <tr><td>8</td><td></td><td></td><td></td><td></td></tr> <tr><td>9</td><td></td><td></td><td></td><td></td></tr> <tr><td>10</td><td></td><td></td><td></td><td></td></tr> </tbody> </table>	TOWER No.	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO	1	100	-	0	1.0	2	100	76	130	1.96	3	100	160.5	-100	1.0	4	100	243	120	0.91	5	100	172	-110	1.77	6	100	106.5	19.5	0.91	7					8					9					10					PROPOSED DAY DIRECTIONAL RADIO VOICE OF NAPLES AMENDED 9/69 Naples, Florida	CALL NEW FREQ 1510 kHz POWER 0.25 Kw TYPE DA TIME DAY LAT. N26-07-11.5 LONG W81-46-16.5 E.H. MUNN, JR. RADIO ENGINEER COLDWATER, MICH.
TOWER No.	ELECTRICAL HEIGHT	SPACING	PHASING	FIELD RATIO																																																						
1	100	-	0	1.0																																																						
2	100	76	130	1.96																																																						
3	100	160.5	-100	1.0																																																						
4	100	243	120	0.91																																																						
5	100	172	-110	1.77																																																						
6	100	106.5	19.5	0.91																																																						
7																																																										
8																																																										
9																																																										
10																																																										
DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☐		6° 00'																																																								

FCC File No. BP-17991
Accepted 1-8-70 Amended

New; Radio Voice of Naples
Naples, Florida

1510 kc

BP-17991
AMENDED (11-24-60)

APPLICATION FOR Proposed Day
(9-26-68ct)

CP TO CHANGE

POWER FROM 1KW, DA-D, 0, TO

250 W,

DA-D, 0, 300°

CHANGE

ANTENNA -

TRANSMITTER

LOCATION


TO:

26-07-11.5

51-46-16.5

New; Radio Voice of Naples
Naples, Florida


1kw, DA-D, D
1510 kc




Proposed Day
(11-29-66ct)

New; Iroquois County Bcstg. Co.
Monticello, Indiana

250w, DA-D, D
1510 kc



HORIZONTAL RADIATION PATTERN



APPLICANT : Iroquois County Broadcasting Co.
LOCATION : Monticello, Indiana
FREQUENCY : 1510 KC/S
POWER : 0.25 KW
LATITUDE : 40 DEG. 45 MIN. 35 SEC.
LONGITUDE : 86 DEG. 46 MIN. 34 SEC.
WHEN USED : Daytime
R.M.S. FIELD : 88 MWM
DATE : 8/8/66

RALPH J. BITZER
CONSULTING RADIO ENGINEERS

FCC File No. BP-17397
Accepted 11-22-66


New; Iroquois County Bcstg. Co.
Monticello, Indiana

1510 kc

Proposed Day
(1-30-67ct)

New; Wabash Radio Company
Wabash, Indiana

250w, DA-D, D
1510 kc



RMS = 92.2 MV/M
MEOV ----

TOWER PLACEMENT SKETCH	PATTERN PARAMETERS					FIGURE 3	STATION DATA
357° T. ↑ No. 1 ○ 1/7° 130° No. 2 ○ 1/0° G's=107.3°	TOWER No.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING P'	FIELD RATIO F'	PROPOSED DAYTIME DIRECTIONAL PATTERN WABASH RADIO CO., WABASH - INDIANA θ° = 0°	CALL NEW
	1						FREQ 1510 KHz.
	2						POWER 0.25 Kw.
	3						TYPE DA-D
	4						TIME DAYTIME
	5						LAT. 40-47-19.8
	6						LONG. 85-49-35.3
	7						E.H.MUNN, JR.
	8						RADIO ENGINEER
	9						COLDWATER, MICH.
	10						
	11						
DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐							

FCC File No. BP-17506
Accepted 1-3-67


New; Wabash Radio Company
Wabash, Indiana

1510 kc

Proposed Day
(11-29-69ct)

New; Great American Bcstg. Corp.
Roanoke, Virginia

50kw, DA-D, D
1510 kc




RMS=1400.0 Mv/M
MEOV
20X

Amended

North Latitude 37° 11' 16"
West Longitude 79° 55' 45"

TOWER PLACEMENT SKETCH



PATTERN PARAMETERS

TOWER No.	ELECTRICAL HEIGHT G'	SPACING S'	PHASING P°	FIELD RATIO F
1	125°	Ref.	80°	
2	125°		160°	
3	125°		240°	
4	125°		320°	
5	125°			
6				
7				
8				
9				
10				

FIGURE 3

PROPOSED DAYTIME
DIRECTIONAL
ANTENNA SYSTEM

ROANOKE, VIRGINIA

February - 1969

θ° = 0°

STATION DATA

CALL NEW
FREQ 1510 KHz.
POWER 50 Kw
TYPE DA-D
TIME DAYTIME
LAT. 37-13-39
LONG. 79-57-40

E.H. MUNN, JR.
RADIO ENGINEER
COLDWATER, MICH.

FCC File No. BP-18499
Accepted 10-10-69

New; Great American Bcstg. Corp.
Roanoke, Virginia

1510 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: XERB

Main Studio: Cozumel, Q.R.

Frequency: 1510 kHz

Power: 5kw

Notification List No. 282

Date: September 1, 1977

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 20° 29' 02"
West Longitude: 86° 54' 19"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 3

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	S(#1)	C(#2)	N(#3)
--------	-------	-------	-------

HEIGHT ABOVE INSULATORS:	108.6'	108.6'	108.6' (60°)
-----------------------------	--------	--------	--------------

PHASING:	-108°	0°	+108°
----------	-------	----	-------

FIELD RATIO:	1	1.955	1
--------------	---	-------	---

SPACING AND
ORIENTATION:

Adjacent towers are spaced 162.9' (90°) on a line
bearing 12° true.

GROUND SYSTEM: 120 - 162.9' equally spaced copper radials about
each tower. Radials are shortened and bonded to
transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL

RMS

451.51 mv/m

1. LISTA DE CAMBIOS : -
2. FECHA : -
3. FRECUENCIA : 1510 KHz.
4. DISTINTIVO : X E R B
5. POBLACION : COZUMEL, Q.R.
6. UBICACION : LW 86° 54' 19" LN 20° 29' 02"
7. POTENCIA : 5 kW
8. CLASE : II

CARACTERISTICAS TECNICAS DEL RADIADOR.

9. TIEMPO DE OPERACION : DIURNO.
10. SISTEMA RADIADOR : AD-D
11. NUMERO DE ELEMENTOS : 3

TIPO DE ELEMENTOS RADIADORES.

12. TIPO DE ALIMENTACION : SERIE EN LA BASE.
13. SECCION TRANSVERSAL : TRIANGULAR DE 0.4 m/LADO.
14. TIPO DE ELEMENTO RADIADOR : VERTICAL
15. TIPO DE SOPORTES : RETENIDAS DE CABLE ACERO 1/4"
16. LONGITUD DEL COPETE CAPACITIVO : NO HAY.
17. SEPARACION ENTRE TORRES : 90° (49.66 m) ENTRE TORRES.
18. NUMERO DE ELEMENTOS : 3
19. ALTURA SOBRE EL AISLADOR : 60° (33.11 m CADA UNA)
20. DEFASAMIENTO : -108° 0° +108°
21. RELACION DE CORRIENTES : 1:1 1:1.95 1:1
22. DESCRIPCION DE LA ORIENTACION DEL SISTEMA RADIADOR : 12° DE AZIMUT (ver patrón horizontal)

SISTEMA DE TIERRA.

23. NUMERO DE RADIALES POR ELEMENTO. : 120
24. LONGITUD DE LOS RADIALES : 49.66 m.
25. TIPO DE RADIAL : ALAMBRE DE COBRE # 10

RADIACION DEL SISTEMA.

26. INTENSIDAD DE CAMPO TEORICO -- (OMNIDIRECCIONAL) DE LA POTENCIA RADIADA (RCM) : 451.51 mV/m
27. INTENSIDAD DE CAMPO EFECTIVO - TEORICO A 1609 m. POR KILOWATT - DE POTENCIA RADIADA. : 201 mV/m.

EL PERITO EN TELECOMUNICACIONES.

ING. JOSE LUIS GONZALEZ MARTES.
Registro # 026.

PATRON DE RADIACION HORIZONTAL TABULADO

(OPERACION DIURNA)

XERB

1510 KHZ.

CLASE II


5000 W.

AD-D

COZUMEL, Q.R.

$$E = 388.1168 [1 + 1.023 \cos(90^\circ \cos \varphi_2 + 108^\circ)]$$

AZIMUT		A	B	C	D	E mV/m.
φ_1	φ_2	$90 \cos \varphi_2$	$A + 108^\circ$	$\cos B$	$(1.023 C) + 1$	388.1168 D
12°	0°	90.0000	198.0000	- 0.9510	0.0270	10.5058
22°	10°	88.6327	196.6327	- 0.9581	0.0198	7.6856
32°	20°	84.5723	192.5723	- 0.9760	0.0015	0.5936
42°	30°	77.9423	185.9423	- 0.9946	-0.0175	- 6.7933
52°	40°	68.9440	176.9440	- 0.9985	-0.0215	- 8.3620
62°	50°	57.8509	165.8509	- 0.9696	0.0080	3.1184
72°	60°	45.0000	153.0000	- 0.8910	0.0885	34.3486
82°	70°	30.7818	138.7818	- 0.7522	0.2304	89.4579
92°	80°	15.6283	123.6283	- 0.5538	0.4334	168.2329
102°	90°	0.0000	108.0000	- 0.3090	0.6838	265.4236
112°	100°	-15.6283	92.3716	- 0.0413	0.9576	371.6863
122°	110°	- 30.7818	77.2182	0.2212	1.2263	475.9582
132°	120°	-45.0000	63.0000	0.4539	1.4644	568.3709
142°	130°	-57.8509	50.1490	0.6407	1.6555	642.5390
152°	140°	- 68.9439	39.0560	0.7765	1.7943	696.4329
162°	150°	- 77.9423	30.0576	0.8655	1.8854	731.7666
172°	160°	- 84.5723	23.4276	0.9175	1.9386	752.4291
182°	170°	- 88.6327	19.3672	0.9434	1.9651	762.6923
192°	180°	-90.0000	18.0000	0.9510	1.9729	765.7277



AZIMUT: 12°

SISTEMA DE TIERRA

120 RADIALES DE ALAMBRE DE
COBRE No. 10 EN CADA TORRE
DE 49.66 MTS. DE LONGITUD
CADA UNO, UNIDOS AL CRU-
ZARSE, POR ALAMBRE DEL
MISMO MATERIAL TIPO 00.
TODO EL SISTEMA ESTA
ENTERRADO 0.30 MTS.

XERB

COZUMEL, Q.R.

FRECUENCIA Y POTENCIA:

1510 KHZ.


5 KW. AD. - P

DISEÑO:

PERITO EN TELECOMUNICACIONES:
ING. J. LUIS GONZALEZ CORTES
REGISTRO No. 026.

DIBUJO:


A. P. L.



PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/m. A 1609M

ESQUEMA DE LAS TORRES Y SU ORIENTACION CON RESPECTO AL NORTE GEOGRAFICO

AZIMUT: 12°



XERB

COZUMEL, Q. R.

FRECUENCIA

1510 KHZ

POTENCIA:

5 KW. AD-9

DISEÑO:

PERITO EN TELECOMUNICACIONES
ING. J. LUIS GONZALEZ CORTES
REGISTRO No. 026

UTILIDAD

A. P. L.

XERB

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: XERB Main Studio: Cozumel. Q.R.
 Frequency: 1510 kHz Power: 5 kw
 Notification List No. 282 Date: September 1, 1977 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 20° 29' 02"
 West Longitude: 86° 54' 19"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)
 Number of elements: 3
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	#1(S)	#2(C)	#3(N)
HEIGHT ABOVE INSULATORS:	162.9'	162.9'	162.9' (90°)
DAY PHASING:	-100°	0°	100°
DAY FIELD RATIO:	1	2	1

SPACING AND
ORIENTATION:

The towers are located in a row. Adjacent towers are
 spaced 162.9' (90°) on a line bearing 12° true.

GROUND SYSTEM: 120 - 162.9' equally spaced copper radials about each tower.
 Radials are shortened and bonded to transverse straps along
 intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL
RMS
 Day 450.23 mv/m

FICHA DESCRIPTIVA DEL SISTEMA RADIADOR DIRECCIONAL DE LA ESTACION

XERB

- | | | |
|---------------------|---|-------------------------------|
| 1. LISTA DE CAMBIOS | : | |
| 2. FECHA | : | |
| 3. FRECUENCIA | : | 1510 KHz. |
| 4. DISTINTIVO | : | X E R B |
| 5. POBLACION | : | COZUMEL, Q.R. |
| 6. UBICACION | : | LW 86° 54' 19" LN 20° 29' 02" |
| 7. POTENCIA | : | 5 kW |
| 8. CLASE | : | II |

CARACTERISTICAS TECNICAS DEL RADIADOR.

- | | | |
|-------------------------|---|---------|
| 9. TIEMPO DE OPERACION | : | DIURNO. |
| 10. SISTEMA RADIADOR | : | AD-D |
| 11. NUMERO DE ELEMENTOS | : | 3 |

TIPO DE ELEMENTOS RADIADORES.

- | | | |
|--|---|---|
| 12. TIPO DE ALIMENTACION | : | SERIE EN LA BASE. |
| 13. SECCION TRANSVERSAL | : | TRIANGULAR DE 0.4 m/LADO. |
| 14. TIPO DE ELEMENTO RADIADOR | : | VERTICAL |
| 15. TIPO DE SOPORTES | : | RETENIDAS DE CABLE ACERO 1/4" |
| 16. LONGITUD DEL COPETE CAPACITIVO | : | NO HAY. |
| 17. SEPARACION ENTRE TORRES | : | 90° (49.66 m) ENTRE TORRES. |
| 18. NUMERO DE ELEMENTOS | : | 3 |
| 19. ALTURA SOBRE EL AISLADOR | : | 90° (49.66 m CADA UNA) |
| 20. DEFASAMIENTO | : | -100° 0° +100° |
| 21. RELACION DE CORRIENTES | : | 1 2 1 |
| 22. DESCRIPCION DE LA ORIENTACION DEL SISTEMA RADIADOR | : | 12° DE AZIMUT (ver patrón horizontal) |

SISTEMA DE TIERRA.

- | | | |
|--------------------------------------|---|-----------------------|
| 23. NUMERO DE RADIALES POR ELEMENTO. | : | 120 |
| 24. LONGITUD DE LOS RADIALES | : | 49.66 m. |
| 25. TIPO DE RADIAL | : | ALAMBRE DE COBRE # 10 |

RADIACION DEL SISTEMA.

- | | | |
|--|---|--------------------------------------|
| 26. INTENSIDAD DE CAMPO TEORICO -- (OMNIDIRECCIONAL) DE LA POTENCIA RADIADA (RCM) | : | 450.23mV/m |
| 27. INTENSIDAD DE CAMPO EFECTIVO - TEORICO A 1609 m. POR KILOWATT-DE POTENCIA RADIADA. | : | 201 mV/150. GRIL. DE TIERRA TEORICO. |

Ing. GRIL. DE TIERRA TEORICO
Departamento de Telecomunicaciones
Oficina de Asignaciones

EL PERITO EN TELECOMUNICACIONES.
Ing. JOSE LUIS GONZALEZ CORTES.
Registro # 026.

PATRON DE RADIACION HORIZONTAL TABULADO

(OPERACION DIURNA)

XERB

5000 W.

1510 KHZ.

AD - D


CLASE II

COZUMEL, Q.R.

$$E = 370.2242 [1 + \cos(90^\circ \cos \varphi_2 + 100^\circ)]$$

AZIMUT		A	B	C	D	EmV/m.
φ_1	φ_2	$90 \cos \varphi_2$	$A + 100$	$\cos B$	$1 + C$	$370.2242 D$
12°	0°	90.0000	190.0000	-0.9848	0.0152	5.6274
22°	10°	88.6320	188.6320	-0.9886	0.0114	4.2205
32°	20°	84.5640	184.5640	-0.9993	0.0007	1.1847
42°	30°	77.9400	177.9400	-0.9993	0.0007	0.2591
52°	40°	68.9400	168.9400	-0.9814	0.0186	6.8861
62°	50°	57.8430	157.8430	-0.9281	0.0719	27.3595
72°	60°	45.0000	145.0000	-0.8191	0.1809	66.9543
82°	70°	30.7318	130.7318	-0.6531	0.3469	128.4007
92°	80°	15.6233	115.6233	-0.4325	0.5675	210.0907
102°	90°	0.0000	100.0000	-0.1736	0.8264	305.9355
112°	100°	-15.6233	84.3716	0.0980	1.0980	405.5339
122°	110°	-30.7318	69.2182	0.3548	1.3548	501.5834
132°	120°	-45.0000	55.0000	0.5735	1.5735	592.5762
142°	130°	-57.8509	42.1490	0.7414	1.7414	644.7037
152°	140°	-68.9439	31.0560	0.8566	1.8566	687.3815
162°	150°	-77.9423	22.0576	0.9268	1.9268	713.3505
172°	160°	-84.5723	15.4276	0.9639	1.9639	727.1031
182°	170°	-88.6327	11.3672	0.9803	1.9803	733.1060
192°	180°	-90.0000	10.0000	0.9848	1.9848	734.8239

PROTECTOR



AFRICO


ESQUEMA DE LAS TORRES Y FUENTES -
CION CON RESPECTO DEL NORTE GEOGRAFICO

AZIMUT: 42° 12' 73' 1/100°

COZUMEL, Q. R.

DISEÑO
 PERITO EN TELECOMUNICACIONES
 ING. J. LUIS GONZALEZ
 CORTES REG. IN. 000
 DISEÑO

XERB



OFICINA CENTRAL DE TELECOMUNICACIONES
Departamento de Comunicaciones
Oficina de Asignación

REVISOR

AZIMUT: 02°

SISTEMA DE TIERRA

120 RADIALES DE ALAMBRE DE
COBRE No. 10 EN CADA TORRE
DE 49.66 MTS. DE LONGITUD
CADA UNO, UNIDOS AL CRU-
ZAMIENTO, POR ALAMBRE DEL
MISMO MATERIAL TIPO 00.
TODO EL SISTEMA ESTA
ENTERRADO 0.30 MTS.

XERB

COZUMEL, Q.R.

FRECUENCIA Y POTENCIA:

1510 KHZ.

5 KW. AD-D

DISEÑO:

PERITO EN TELECOMUNICACIONES
ING. J. LUIS GONZALEZ CORTES.

REGISTRO No. 020

DIBUJO:

A. P. L.

FORM FOR THE APPLICATION OF ARTICLE 4 OF THE AGREEMENT
CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

6 3 5 6

PART I GENERAL INFORMATION

01 Administration

CANADA

Sheet No. 421

Date 830726

Assigned frequency (kHz)		02	1 5 2 0
Transmitting station	Name of the station	03	L A N G L E Y B C
	Call sign	04	
	Additional identification	05	
	Station class	06	B
	Operational Status	07	P
Country		08	CAN
Geographical coordinates of the transmitting station		09	1 2 2 W 4 0 0 0 4 9 N 0 5 0 0

11 a) New assignment ☐ b) Modification of characteristic of an assignment recorded in the plan ☐ c) Cancellation of an assignment ☒

12 Modification under Section 4.2.14 Yes ☐ No ☐

13 Date of bringing into service or cessation of operation
Year Month Day

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	21 1 0 .	31 1 0 .
r.m.s. value of radiation for station power (mV/m at 1 km)	25	35
Antenna type	26 B	36 B
Simple vertical antenna electrical height (degrees)	27	37

44 Remarks

COORDINATION UNDER ARTICLE 4:

COUNTRY	USA								
IN PROGRESS									
ACCEPTANCE OBTAINED	No								

FORM FOR THE APPLICATION OF ARTICLE 4 OF THE AGREEMENT

6 3 5 6

CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

NEW
1520

PART I GENERAL INFORMATION

a Administration

CANADA

Sheet No.

417

Date

830321

Assigned frequency (kHz)		(02)	1 5 2 0
Transmitting station	Name of the station	(03)	L A N G L E Y B C
	Call sign	(04)	
	Additional identification	(05)	
	Station class	(06)	B
	Operational Status	(07)	P
Country		(08)	CAN
Geographical coordinates of the transmitting station		(09)	1 2 2 W 4 0 0 0 4 9 N 0 5 0 0

(11) a) New assignment

☐

b) Modification of characteristic of an assignment recorded in the plan

☒

c) Cancellation of an assignment

☐

(12) Modification under Section 4.2.14

Yes

☐

No

☒

(13) Date of bringing into service or cessation of operation

Year	Month	Day

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	(21) 1 0 .	(31) 1 0 .
r.m.s. value of radiation for station power (mV/m at 1 km)	(25)	(35)
Antenna type	(26) B	(36) B
Simple vertical antenna electrical height (degrees)	(27)	(37)

(44) Remarks

COORDINATION UNDER ARTICLE 4:

COUNTRY

USA

IN PROGRESS

X

ACCEPTANCE OBTAINED

REF **Serial No.**

PART II Section I

Description of a directional antenna consisting of vertical conductors

Sheet No. 417

Date _____

Country	CAH
USA	1
UK	1
FR	1
DE	1
IT	1
ES	1
PT	1
GR	1
TR	1
PL	1
CZ	1
SK	1
HU	1
RO	1
BG	1
RU	1
UA	1
BY	1
LT	1
LV	1
EE	1
SI	1
HR	1
BA	1
ME	1
RS	1
YU	1
MA	1
EG	1
SD	1
IL	1
IS	1
NO	1
SE	1
DK	1
FI	1
JP	1
IN	1
PK	1
BD	1
TH	1
PH	1
VN	1
LA	1
MY	1
SG	1
BR	1
AR	1
CL	1
PE	1
CO	1
VE	1
EC	1
GY	1
GF	1
MQ	1
RE	1
YT	1
TF	1
PM	1
WF	1
TK	1
FM	1
GU	1
MP	1
SA	1
AS	1
AK	1
HI	1
OR	1
WA	1
MT	1
ND	1
SD	1
NE	1
OK	1
KS	1
MO	1
IL	1
IN	1
OH	1
PA	1
NY	1
CT	1
RI	1
MA	1
VT	1
NH	1
ME	1
AK	1
HI	1
AS	1
GU	1
MP	1
SA	1
FM	1
TK	1
WF	1
PM	1
YT	1
RE	1
MQ	1
GF	1
GY	1
EC	1
VE	1
CO	1
PE	1
CL	1
AR	1
BR	1
SG	1
MY	1
LA	1
VN	1
PH	1
TH	1
BD	1
PK	1
IN	1
JP	1
FI	1
DK	1
SE	1
NO	1
IS	1
IL	1
SD	1
EG	1
MA	1
RS	1
BA	1
HR	1
SI	1
EE	1
LV	1
LT	1
BY	1
UA	1
RU	1
BG	1
RO	1
HU	1
SK	1
CZ	1
PL	1
TR	1
GR	1
PT	1
ES	1
IT	1
DE	1
FR	1
UK	1
USA	1

CH	U
----	---

Hours of operation

**Total number
of towers**

L	A	N	G	L	E					B	C
---	---	---	---	---	---	--	--	--	--	---	---

Name of transmitting station

(05)	(06)	(07)	(08)	(09)	(10)	(11)	(12)
Tower No.	Tower field ratio	Phase difference of the field ($\pm$ degree)	Electrical tower spacing (degrees)	Angular tower orientation (degrees)	Reference tower	Electrical height of tower (degrees)	Towers
1	1 •	1 0 •	1 0 •	1 0 •	0	19 10 •	0
2	2 • 7 2 7 6	- 1 1 9 • 7 3	1 0 0 •	3 5 4 •	0	9 0 •	0
3	2 • 7 2 7 6	1 2 0 • 7 7	2 0 0 •	3 5 4 •	0	9 0 •	0
4	1 •	2 2 • 5 5	3 1 1 0 • 2 7	3 5 0 • 3 6 0	0	9 0 •	0
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			
	•	•	•	•			
	•	•	•	•			
	1 •	1 •	1 •	1 •			

(14) r.m.s. value of radiation	(15) Type of pattern	(16) Special quadrature factor
9.87, 4.9	E	1.11

SUPPLEMENTARY INFORMATION


KACY

Measured Day
(6-29-70ct)

Station KACY
Port Hueneme, California

1kw, 50kw-LS, DA-2, U
1520 kc

N.Lat. $34^{\circ} 10' 02''$
W.Long. $119^{\circ} 08' 02''$



A.E. Towne Associates Inc., Consulting Engineers, San Carlos, California

FCC File No. BL-12623
Accepted 6-2-70

Station KACY
Port Hueneme, California

1520 kc

Measured Non-DA
(6-29-70ct)

Station KACY
Port Hueneme, California

KACY
1kw, 50kw-LS, DA-2, U
1520 kc

N.Lat $34^{\circ} 10' 02''$
W.Long. $119^{\circ} 03' 02''$




FIG. 2

MEASURED NON-DIRECTIONAL HORIZONTAL RADIATION
KACY 1520 KC PORT HUENEME, CALIF.

A.E.Towne Associates Inc., Consulting Engineers, San Carlos, California

FCC File No. BL-12623
Accepted 6-2-70

Station KACY
Port Hueneme, California

1520 kc

17304

SUPPLEMENTAL AND CORRECTED
DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KACY

Main Studio: Port Hueneme, California

Frequency: 1520 kc.

Power: 1kw Night 10kw Day

Notification List No. 948

Date: February 28, 1962 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 34° 10' 02"

West Longitude: 119° 08' 02"

Note: Please retain the description sheet and directional antenna radiation patterns notified for Station KACY in U.S. Change List No. 934, dated November 21, 1961 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a change in the geographical coordinates of the center of the antenna system.


KACY

Proposed Day
(10-28-67ct)

Station KACY
Port Hueneme, California

1kw, 50kw-LS, DA-2, U
1520 kc

10-30-68
wanted
P to
increase
height
otherwise
(1000) 310°
1400 ft.
50 kw.




KACY

Proposed Day
(3-30-64ct)

Station KACY
Port Hueneme, California

1kw, 10kw-LS, DA-2, U
1520kc



FCC File No. BP-16112
Accepted 3-10-64

Station KACY
Port Hueneme, California

1520


KACY

Measured Day
(12-22-64ct)

Station KACY
Port Hueneme, California

1kw, 10kw-LS, DA-2, U
1520 kc

BL-10680
GRANTED
12-31-64
CHG DAY DA




KACY

PROPOSED NIGHT
(2-26-60g)

Station KACY
Port Hueneme, California

1kw, 5kw-LS, DA-2,U
1520 KC

11-21-61
printed of
for DA-2



OT 15824, New sub No. 111111
to change DA patterns 4-18-60


KACY

Measured Night
(2-26-63ct)

Station KACY
Port Hueneme, California

1kw, 10kw-LS, DA-2, U
1520 kc

*4-11-63
wanted 2 covering
base in day
over and change
16A*



KMPL


Proposed Day (Non-CH)
(2-28-66ct)

Station KMPL
Sikeston, Missouri

500w, 5kw-LS, DA-3, U
1520 kc

Figure 1


ACP 2-9-66



SITE COORDINATES
36° 49' 25" N
89° 35' 45" W

PROPOSED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

G=1111'



SEMO BROADCASTING CORPORATION
SIKESTON, MISSOURI

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION KMPL
1520 KC/S

0.5 KW-N 5 KW-CH
5 KW-D U DA-3

OCTOBER 1965

FCC File No. BMP-11693
Accepted 2-8-66

Station KMPL
Sikeston, Missouri

1520 kc

KMPL


Measured Day
(5-27-66ct)

Station KMPL
Sikeston, Missouri

500w, 5kw-LS, DA-3, U
1520 kc

Figure 10

LIC 10-4-66



FCC File No. BL-11259
Accepted 4-26-66

Station KMPL
Sikeston, Missouri

1520 kc


KMPL

Proposed Day (CH)
(2-28-66ct)

Station KMPL
Sikeston, Missouri


500w, 5kw-LS, DA-3, U
1520 kc

Figure 3



PROPOSED CRITICAL HOURS HORIZONTAL PLANE RADIATION PATTERN

G=111°



SEMO BROADCASTING CORPORATION
SIKESTON, MISSOURI

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION KMPL
1520 KC/S

0.5 KW N 5 KW CH
5 KW D U DA-3

OCTOBER 1965

FCC File No. BMP-11693
Accepted 2-8-66

Station KMPL
Sikeston, Missouri

1520 kc

MCP-2-9-66


Measured Day (CH)
(5-27-66ct)

Station KMPL
Sikeston, Missouri

KMPL
500w, 5kw-LS, DA-3, U
1520 kc

Figure 12

LIC 10-4-66



FCC File No. BL-11259
Accepted 4-26-66

Station KMPL
Sikeston, Missouri

1520 kc

KMPL


Proposed Night
(2-28-66ct)

Station KMPL
Sikeston, Missouri

500w, 5kw-LS, DA-3, U
1520 kc

Figure 5
Sheet 1 of 14

MCP 2-9-66



SITE COORDINATES
36° 49' 25" N
89° 35' 45" W

PROPOSED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

111 121 131 141 151 161 86.5° 5 5 5 5 5 5 FIELD <table> <thead> <tr> <th></th> <th>Field Ratio</th> <th>Phase</th> </tr> </thead> <tbody> <tr> <td>111</td> <td>1.00</td> <td>+78.7°</td> </tr> <tr> <td>121</td> <td>2.84</td> <td>+48.3°</td> </tr> <tr> <td>131</td> <td>4.40</td> <td>+16.0°</td> </tr> <tr> <td>141</td> <td>4.40</td> <td>16.0°</td> </tr> <tr> <td>151</td> <td>2.84</td> <td>48.3°</td> </tr> <tr> <td>161</td> <td>1.00</td> <td>-78.7°</td> </tr> </tbody> </table> G=111° (200°) S=212° (381°)		Field Ratio	Phase	111	1.00	+78.7°	121	2.84	+48.3°	131	4.40	+16.0°	141	4.40	16.0°	151	2.84	48.3°	161	1.00	-78.7°	SEMO BROADCASTING CORPORATION SIKESTON, MISSOURI Jules Cohen & Associates Consulting Electronics Engineers	RADIO STATION KMPL 1520 KC/S 0.5 KW N 5 KW CH 5 KW D U DA 3 OCTOBER 1965
	Field Ratio	Phase																					
111	1.00	+78.7°																					
121	2.84	+48.3°																					
131	4.40	+16.0°																					
141	4.40	16.0°																					
151	2.84	48.3°																					
161	1.00	-78.7°																					

FCC File No. BMP-11693
Accepted 2-8-66

Station KMPL
Sikeston, Missouri

1520 kc


Proposed Night Nulls
(2-28-66ct)

Station KMPL
Sikeston, Missouri

KMPL
500w, 5kw-LS, DA-3, U
1520 kc

Figure 5

Sheet 2 of 14



PROPOSED NIGHTTIME RADIATION PATTERN AT VERTICAL ANGLE OF 0 DEGREES

1520 KC/S 0.5 KW-N 5 KW-CH 5 KW-D U DA-3

SEMO BROADCASTING CORPORATION

SIKESTON, MISSOURI

FCC File No. BMP-11693
Accepted 2-8-66

Station KMPL
Sikeston, Missouri

1520 kc


KMPL

Measured Night
(5-27-66ct)

Station KMPL
Sikeston, Missouri

500w, 5kw-LS, DA-3, U
1520 kc

Figure 14



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

(1)	(2)	(3)	(4)	(5)	(6)	86.5°
0	5	5	5	5	5	True
	Field Ratio					Phase
(1)	1.00					+78.7°
(2)	2.84					-48.3°
(3)	4.40					-16.0°
(4)	4.40					-16.0°
(5)	2.84					-48.3°
(6)	1.00					+78.7°

G=111' (200)
S=212' (381)

SEMO BROADCASTING CORPORATION
SIKESTON MISSOURI

Jules Cohen & Associates
Consulting Electronics Engineers

RADIO STATION KMPL
1520 KC/S
0.5 KW N 5 KW CH
5 KW D U DA 3
660228 N

FCC File No. BL-11259
Accepted 4-26-66

Station KMPL
Sikeston, Missouri

1520 kc


KMPL

Measured Non-DA
(5-27-66ct)

Station KMPL
Sikeston, Missouri

500w, 5kw-LS, DA-3, U
1520 kc
Figure 8

LIC 10-4-66



MEASURED NONDIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN (0.5 KW)

(4) • 170 G = 111 (200')	SEMO BROADCASTING CORPORATION SIKESTON, MISSOURI	RADIO STATION KMPL 1520 KC/S 0.5 KWN 5 KWCH 5 KWD U DA 3 Pattern 660228 ND
	Wes. C. L. & Associates Consulting Electronic Engineers	

FCC File No. BL-11259
Accepted 4-26-66

Station KMPL
Sikeston, Missouri

1520 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KOMA

Main Studio: Oklahoma City, Oklahoma

Frequency: 1520 kHz

Power: 50 kw

Notification List No. 1446

Date: October 14, 1971

Class: 1-B

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 35° 20' 00"

West Longitude: 97° 30' 16"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 3

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER: NW(#1) C(#2) SE(#3)

HEIGHT ABOVE
INSULATORS:

325' 325' 325' (181°)

PHASING:

-119.5° 0° +114.5°

FIELD RATIO:

0.510 1 0.510

SPACING AND

ORIENTATION:

Adjacent elements are spaced 162' (90°) on a line bearing
114.3° true.

GROUND SYSTEM:

120 - 259' equally spaced copper radials about each tower.
Radials are shortened and bonded to transverse straps along
intersections between towers.

Predicted effective Night Field: 1634 mv/m at rated power.



Predicted effective Day Field: (omnidirectional) 1682 mv/m at rated power.

Note: This notification concerns only a change in means of radiation in the
directional antenna radiation pattern.

CTR NO 31208A4

OKLAHOMA CITY, OKLAHOMA

KOMA



THEORETICAL PARAMETERS

TOWER	FIELD	PHASE
1	.510	-119.5°
2	1.000	0.0°
3	.510	+114.5°

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KOMA
1520 KC 50 KW DA-N



KOMA

Measured Night
(6-28-66ct)

Station KOMA
Oklahoma City, Oklahoma

50kw, DA-N, U
1520 kc

11315
108-2-66



ANTENNA PARAMETERS				
TOWER	THEORETICAL		OBSERVED	
	FIELD RATIO	PHASE	FIELD RATIO	PHASE
1	50	-119.5°	483	-115.5°
2	1000	0.0°	1000	0.0°
3	510	+114.5°	483	+108.5°

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KOMA
1520 KC 50 KW DA-N
651120
FIGURE 2B

FCC File No. BL-11315
Accepted 6-16-66

Station KOMA
Oklahoma City, Oklahoma

1520 kc



KOMA

Measured Non-DA
(6-28-66ct)

Station KOMA
Oklahoma City, Oklahoma

50kw, DA-N, U
1520 kc

BL 11315
-1C 8-2-66



ANTENNA PARAMETERS

TOWER	OPERATION
1	DETUNED
2	SERIES FED
3	DETUNED

PREPARED BY .
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KOMA
1520 KC 50 KW DA-N
651120.A FIGURE 2A

FCC File No. BL-11315
Accepted 6-16-66

Station KOMA
Oklahoma City, Oklahoma

1520 kc


KXKW

PROPOSED DAY
(8-29-60g)

New; General Communications, Inc.
Lafayette, Louisiana

500w, 10kw-CR, DA-D, U
1520 KC

*12/28/62
granted for
increase in day power
and DA-2
day DA for CH*



LATITUDE: 30° 16' 51"
LONGITUDE 92° 00' 53"

ANTENNA PARAMETERS




FIGURE 4

HORIZONTAL POLAR PATTERN
(CRITICAL HOURS)

GENERAL COMMUNICATIONS, INC.

1520 KC

0.5 KW-N, DA
10 KW-CH, DA
10 KW-N-DA, DAY, U

JOHN H. MULLANEY
CONSULTING RADIO ENGINEER
WASHINGTON, D.C.

FCC File No. BMP-9060
Accepted 8-8-60

General Communications, Incorporated
Lafayette, Louisiana

1520 KC


Lafayette, Louisiana

KXKW

PROPOSED DAY & NIGHT
(5-28-59g)

New; General Communications, Inc.
Lafayette, Louisiana

500w, DA-1,U
1520 KC



$E_{RMS} = 134.3 \text{ MV/M}$

---- MEOV

LATITUDE: 30° 16' 51"
LONGITUDE: 92° 00' 53"

ANTENNA PARAMETERS




FIGURE 4

PLOT OF
HORIZONTAL
POLAR PATTERN

GENERAL COMMUNICATIONS INC
LAFAYETTE, LA.

1520KC

0.5 KW-DA-1,U

JOHN H. MULLANEY
CONSULTING RADIO ENGINEER
WASHINGTON, D. C.

FCC File No. BP-12244
Accepted 5-4-59 (Amended)

General Communications, Incorporated
Lafayette, Louisiana

1520 KC

*Printed after new station
5-22-60*


LAFAYETTE, LA

KXKW

PROPOSED DAY & NIGHT NULLS
(6-16-59g)

New; General Communication, Inc.
Lafayette, Louisiana

500w, DA-D, D
1520 K




$E_{RMS} = 134.3 \text{ MV/M}$

---- ME0V

LATITUDE: 30° 16' 51"
LONGITUDE 92° 00' 53"

JOHN H. MULLANEY
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

ANTENNA PARAMETERS



TOWER PHASING
1. 6272 $\angle$ -126°
2. 1010°
3. 5425 $\angle$ 126°
4. 47 $\angle$ -126°
5. 75 $\angle$ 0°
6. 407 $\angle$ 126°

FIGURE 4A

PLOT OF
EXPANDED POLAR PATTERN
GENERAL COMMUNICATION INC.
LAFAYETTE, LA.

1520 KC

0.5 KW-DA-I, U

FCC File No. BP-12244
Accepted 5-18-59 (Amended)

General Communication, Incorporated
Lafayette, Louisiana

1520 KC

*James H. Mullaney
6-12-60*


Measured Day (CH)
(3-30-64ct)

Station KXKW
Lafayette, Louisiana

500w, 10kw-LS, DA-2, U
1520kc

KXKW

3-25-64
3:45/ae
in day power
7:14 2
(during CH)



LATITUDE: $30^{\circ} 16' 51''$
LONGITUDE: $92^{\circ} 00' 53''$

JOHN H. MULLANEY
AND
ASSOCIATES

A DIVISION OF MULTRONICS, INC.

ANTENNA PARAMETERS




FIGURE 16

MEASURED DAYTIME
CRITICAL - HOURS PATTERN

RADIO STATION KXKW
LAFAYETTE, LOUISIANA

1520 KC

0.5 KW, DA-N
10 KW, DA-CH
10 KW, NDA, DAY, U

FCC File No. BL-10444
Accepted 3-12-64

Station KXKW
Lafayette, Louisiana

1520kc


KXKW

MEASURED DAY & NIGHT
(2-17-61g)

Station KXKW
Lafayette, Louisiana

500w, DA-1,U
1520 KC

*plotted for
radiation
6-1-61*



$E_{RMS} = 132 \text{ MV/M (MEASURED)}$

LATITUDE: $30^{\circ} 16' 51''$
LONGITUDE: $92^{\circ} 00' 53''$

ANTENNA PARAMETERS




FIGURE 16
MEASURED HORIZONTAL
DIRECTIONAL PATTERN
RADIO STATION KXKW
LAFAYETTE, LOUISIANA
1520 KC 0.5 KW-U-DA-1

JOHN H. MULLANEY
CONSULTING RADIO ENGINEER
WASHINGTON, D. C.

FCC File No. BL-8211
Accepted 1-19-61

KXKW
Lafayette, Louisiana

1520 KC


K X K U

Measured Non-DA
(3-30-64ct)

Station KXKW
Lafayette, Louisiana

500w, 10kw-LS, DA-2, U
1520kc

7/27/64
fig for
release in
day 11H. 2
and 11H. 11
11H. 11



$E_{RMS} = 602 \text{ MV/M (MEASURED)}$

© RADIAL VALUES

LATITUDE: 30° 16' 51" LONGITUDE 92° 00' 53"	ANTENNA PARAMETERS	FIGURE 15 MEASURED DAYTIME NON-DIRECTIONAL PATTERN RADIO STATION KXKW LAFAYETTE, LOUISIANA 1520 KC 0.5 KW, DA - N 10 KW, DA - CH 10 KW, NDA, DAY, U
JOHN H. MULLANEY AND ASSOCIATES A DIVISION OF MULTRONICS, INC.	#3 TOWER G = 90° Station KXKW Lafayette, Louisiana	

FCC File No. BL-10444
Accepted 3-12-64


1520kc

KXKW

MEASURED NON-DA
(2-17-61g)

Station KXKW
Lafayette, Louisiana

500w, DA-1, U
1520 KC



LATITUDE 30°16'51"
LONGITUDE 92° 00'53"

ANTENNA PARAMETERS

* 2 TOWER

G=90°

JOHN H. MULLANEY
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FIGURE 15
MEASURED HORIZONTAL
NON-DIRECTIONAL PATTERN
RADIO STATION KXKW
LAFAYETTE, LOUISIANA
1520 KC 0.5 KW-U-DA-1

FCC File No. BL-8211
Accepted 1-19-61

KXKW
Lafayette, Louisiana

1520 KC

KYXI


PROPOSED DAY & NIGHT
(8/3/55G)

STATION KGON
OREGON CITY, OREGON

10KW
DA-1, U

1520 KC

SUPERSEDES # 550125 AA



HORIZONTAL PLANE RADIATION PATTERN

	CLACKAMAS BROADCASTERS INC. WELDON & CAPE Consulting Radio and Television Engineers Arlington, D.C. Dallas, Texas	KGON OREGON CITY OREGON 1520 KC 10 KW DA-1
--	--	--


KYXI

Measured Non-DA
(5-28-63ct)

Station KGON
Oregon City, Oregon

10kw, DA-1, U
1520 kc

8-16-63
checked
Lucia coming
hang in
antenna
transmitter
location.



N. LAT. 45°24' 44"
W. LONG. 122°34' 37"

G=90°=162' RMS = 1315 MV/M

50 KW INTO TOWER 2. TOWERS 1 & 3 FLOATING

HAMMETT & EDISON CONSULTING RADIO ENGINEERS SAN FRANCISCO	RADIO STATION KGON 1520 KC. 10 KW. DA-1 OREGON CITY, OREGON
---	---

**MEASURED
NON-DIRECTIONAL
HORIZONTAL RADIATION PATTERN**

UNATTENUATED FIELD INTENSITY
AT ONE MILE

621123

FIGURE 10A

FCC File No. 8L-10007
Accepted 5-17-63

Station KGON
Oregon City, Oregon

1520 kc


KYX1

Measured Day & Night
(5-28-63ct)

Station KGON
Oregon City, Oregon

10kw, DA-1, U
1520 kc

8-14-63
measured
in charge in
transmitter
location.




S=90°=162'

G=90°=162'

N. LAT. 45°24' 44"

W. LONG. 122°34' 37"



HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION KGON
1520 KC. 10 KW. DA-1
OREGON CITY OREGON

MEASURED DIRECTIONAL HORIZONTAL RADIATION PATTERN

UNATTENUATED FIELD INTENSITY
AT ONE MILE

621123

FIGURE 10B

FCC File No. BL-10007
Accepted 5-17-63

Station KGON
Oregon City, Oregon

1520 kc


KYXI

Proposed Day
(8-23-63ct)

Station KGON
Oregon City, Oregon

50kw, DA-2, U
1520 kc

8-23-63
Supted Mod
by CP to change
from DA-1 to
DA-2



S:90°=162'

G:90°=162'

RMS=1364 MV/M

N. LAT 45° 24' 44"

W. LONG 122° 34' 37"

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION KGON
1520 KC 50 KW. DA 2
OREGON CITY OREGON

DAYTIME HORIZONTAL RADIATION PATTERN

UNATTENUATED FIELD INTENSITY
AT ONE MILE

630709

FIGURE 2

FCC File No. BMP-10969
Accepted 7-29-63

Station KGON
Oregon City, Oregon

1520 kc


KYX1

Measured Day
(2-28-64ct)

Station KGON
Oregon City, Oregon

10kw, 50kw-LS, DA-2,
1520 kc

2-20-64
2g for 10kw N,
50kw D, DA-2.



S=90°=162'

G=90°=162'

RMS=1435 MV/M

N. LAT. 45° 24' 44"

W. LONG. 122° 34' 37"

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION KGON
1520 KC. 10. KW. 50 KW-LS. DA-2
OREGON CITY, OREGON

MEASURED DAYTIME HORIZONTAL RADIATION PATTERN

UNATTENUATED FIELD INTENSITY
AT ONE MILE

631016

FIGURE 8

FCC File No. BL-10362
Accepted 1-30-64

Station KGON
Oregon City, Oregon

1520 kc

DESCRIPTION OF WTTT NIGHTTIME DIRECTIONAL ANTENNA SYSTEM

- (a) Number of Towers: Six
- (b) Type of Elements: Uniform cross section, base insulated, guyed
- (c) Top Loading: None
- (d) Height of Elements: All six towers 165' above ground
(90° = 161.7)
(180° = 323.4')
- (e) Spacing and Orientation: No. 1 reference
(In-line array) No. 2 120° at 180° true
No. 3 240° at 180° true
No. 4 360° at 180° true
No. 5 480° at 180° true
No. 6 600° at 180° true
- (f) Field Ratios and Phasing: No. 1 1.0 $\angle -37.5^\circ$
No. 2 2.87 $\angle 121.8^\circ$
No. 3 4.54 $\angle -79.3^\circ$
No. 4 4.54 $\angle +79.3^\circ$
No. 5 2.87 $\angle -121.8^\circ$
No. 6 1.0 $\angle 37.5^\circ$
- (g) Ground System: 120 equally spaced radials around each tower, a maximum 150 feet of No. 10 bare copper wire buried approximately 6 inches deep in the ground. Intersecting radials are shortened and bonded to a transverse 2 inch copper strap midway between towers.
- (h) Location: N. Latitude 41° 34' 00"
W. Longitude 83° 34' 23"
- (i) Operation: 1520 kHz, 1 kw, DA-2

Measured Night
(3-27-70ct)

Station WTTO
Toledo, Ohio

1kw, DA-2, U
1520 kc





FIGURE 5.1
WTTO NIGHTTIME MEASURED
HORIZONTAL PATTERN DA

Engineer: John F. Brown

FCC File No. BRC-3412
Accepted 3-11-70

Station WTTO
Toledo, Ohio

1520 kc

Proposed Day
(3-29-67ct)Station WTTT
Toledo, Ohio1kw, DA-2, U
1520 kcGrandall C.P.
3-27-67to make changes in
daytime pattern

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
		TOWER No.	ELECTRICAL HEIGHT G'	TRUE TOWER ORIENTATION	SPACING S'	PHASING P'	HORIZONTAL FIELD MIN E	FIELD RATIO F	ELEV. ANGLE θ°	ELEVATION RMS FIELD dBm E _θ	CALL WTTT
		1	89	0	0	0	1.0	0	0	FREQUENCY 1520 kHz	
		2	89	260	190	0	1.98	10		POWER 1.0 kw	
		3	89	260	380	0	1.0	20		TIME OF OPERATION U	
		4	89	236.7	191	-93	1.0	30		TYPE OF OPERATION DA-2	
		5	89	234.7	210	-93	1.98	40		DAYTIME TOWERS 1, 2, 3, 4, 5	
		6	89	170	90	-93	1.0	50		NIGHTTIME TOWERS	
		7						60		No. RADIALS PER TOWER 120	
		8						70		LENGTH OF RADIALS 280 ft	
		9						80		GROUND SCREEN DIMENSION	
10								LAT. 41° 44' 15"			
		DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐								LONG. 83° 35' 19"	
										SUPERSEDES 669915	
										P. 670210	

WTTT Broadcasting Company
Toledo, Ohio
Carl E. Smith
Consulting Radio Engineers
Cleveland, Ohio

FIG. 1 A
DAYTIME ARRAY
MODIFIED HORIZONTAL PATTERN
EXPANDED SCALE


1520 kc

10-6-67
GRANTED LICENSE
NEW AM STATION

Measured Day
(3-29-67ct)

Station WTTQ
Toledo, Ohio

1kw, DA-2, U
1520 kc



TOWER PLACEMENT SKETCH	THEORETICAL PATTERN PARAMETERS						STATION DATA	
	POWER	ELECTRICAL HEIGHT	TO WAVELENGTH	SPACING	ANGLE	ANGLE	WTTQ	1520 kHz
	89	0	0	0	1.0	0	1.0	1.0
	89	260	190	0	1.98	0	1.0	1.0
	89	260	380	0	1.0	0	1.0	1.0
	89	246.7	391	0	1.0	0	1.0	1.0
	89	234.7	210	-25	1.98	0	1.0	1.0
	89	170	70	-93	1.0	0	1.0	1.0
							41	44
							83	15
							180	660928
								661226

FIG. 7.1 WTTQ DIRECTIONAL ANTENNA DAYTIME MEASURED HORIZONTAL PATTERN

CARL E. SMITH Consulting Radio Engineers
Cleveland, Ohio


WTTQ BROADCASTING COMPANY
Toledo, Ohio

WANR

PROPOSED ~~DAY~~ & NIGHT
(9-13-60g)

New; Rossford Bcstng., Inc.
Rossford - Toledo, Ohio

1kw, DA-1, U
1520 KC



5201
4-11-64
Printed
New Station

359.31G
POLAR CO-ORDINATE
K.E. PELUPPEL & FANOR CO.
MADE IN U.S.A.


FCC File No. BP-14279
Accepted 8-30-60

Rossford Broadcasting, Incorporated
Rossford - Toledo, Ohio

1520 KC

1kw, DA-2, U
1520 kc

10-6-67
GRANTED
LICENSE
FOR NEW AM STATION



TOWER PLACEMENT SKETCH		THEORETICAL PATTERN PARAMETERS							STATION DATA	
TOWER NO.	ELECT. FIELD HEIGHT FEET	TOWER ORIENTATION DEG.	SPACING FEET	1-H. HZ. FEET	WAVELENGTH FIELD FEET	FIELD RATIO	ELEV. ANGLE DEG.	ELEVATION ANGLE DEG.	CALL FREQUENCY kHz	WTTO FREQUENCY kHz
1	89	0	120	37.5	1.0	1.0	0	178.5	1.0	1520
2	89	180	120	121.8	2.87	4.0	20		1.0	1520
3	89	180	240	79.3	4.54	25			1.0	1520
4	89	180	300	79.3	4.54	30			1.0	1520
5	89	180	480	121.8	2.87	40			1.0	1520
6	89	180	600	37.5	1.0	50			1.0	1520

FIG. 6.1
AMENDED
WTTO DIRECTIONAL NIGHTTIME
MEASURED HORIZONTAL PATTERN


WANR

10-6-67
GRANTED LICENSE
FOR NEW AM
STATION

Measured Non-DA
(3-29-67ct)

Station WTTQ
Toledo, Ohio

1kw, DA-2, U
1520 kc



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
Tower No. 4 Used All Others Detuned		TOWER No.	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION °	SPACING ft	PHASING °	HORIZONTAL FIELD dBμV/m	FIELD RATIO %	ELEV. ANGLE °	ELEVATION RMS FIELD dBμV/m	CALL WTTQ	
		1								0	64	FREQUENCY 1520 kHz
		2								10		POWER 1.0
		3								20		TIME OF OPERATION U
		4	89							30		TYPE OF OPERATION DA-2
		5								40		DAYTIME TOWERS - - -
		6								50		NIGHTTIME TOWERS 1, 2, 3, 4, 5, 6
										60		NO RADIALS PER TOWER 120
										70		LENGTH OF RADIALS 269' 150'
										80		GROUND SCREEN DIMENSION
		DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☒								LAT 41° 34' 00" LONG 83° 34' 23" SUPERSEDES FIG. 6, 15 WTTQ NON-DIRECTIONAL NIGHTTIME MEASURED HORIZONTAL PATTERN		
		CARL E. SMITH Consulting Radio Engineers								WTTQ BROADCASTING CO. TOLEDO, OHIO		



WAOA

Proposed Day
(7-28-66ct)

New; Faulkner Radio, Inc.
Auburn-Opelika, Alabama

5kw, DA-D, D
1520 kc

6-7-67
GRANTED
FOR
+11 STATION



North Latitude 32° 39' 13"
West Longitude 85° 25' 25"

W.J. HOLEY
AUG. 1965

FCC File No. BP-16921
Accepted 6-27-66

New; Faulkner Radio, Inc.
Auburn-Opelika, Alabama

1520 kc

WAOA

Measured Day
(9-26-68ct)

Station WAOA
Auburn-Opelika, Alabama

5kw, DA-D, D
1520 kc


9-26-68
Granted
License

THEORETICAL PARAMETERS

#1 = $0.85/+135$
#2 = $1.0/0^\circ$

OPERATING PARAMETERS

#1 = $0.87/+125$
#2 = $1.0/0^\circ$



LATITUDE: $32^\circ 39' 21''$
LONGITUDE: $85^\circ 25' 25''$

JOHN H. MULLANEY
AND
ASSOCIATES

ANTENNA PARAMETERS

N - 345° - E

#1
S
#2

G = $90^\circ = 162'$
S = $90^\circ = 162'$

FIGURE 12
MEASURED DAY DIRECTIONAL

RADIO STATION WAOA
AUBURN-OPELIKA, ALABAMA

1520 KHz

5 KW, DA-D

FCC File No. BL-12090
Accepted 9-10-68

Station WAOA
Auburn-Opelika, Alabama

1520 kc


WAOA

Measured Non-DA
(9-26-68ct)

Station WAOA
Auburn-Opelika, Alabama

5kw, DA-D, D
1520 kc

9-26-68
Granted
license



WEXM

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WEXM

Main Studio: Jamesville, Virginia

Frequency: 1520 kHz

Power: 0.5 kW

Notification List No. 1620

Date: February 20, 1975

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:North Latitude: 37° 31' 46"
West Longitude: 75° 54' 43"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D) STANDARD PATTERN
Number of elements: 2Type of elements: Uniform cross-section, guyed, vertical
steel towers. Tower #1 is shunt excited,
tower #2 is series excited.


TOWER:	NW(#1)	SE(#2)
HEIGHT ABOVE INSULATORS:	300' (167°)	160' (90°)
PHASING:	0°	-98°
FIELD RATIO:	1.00	0.89
SPACING AND ORIENTATION:	Elements are spaced 161.8' (90°) on a line bearing 103° true.	

GROUND SYSTEM: 120-160' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap
along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
RMS	RSS	RMS
148 mv/m	153 mv/m	155 mv/m


Note: This notification concerns changes in the proposed directional antenna
system and radiation pattern.



PROPOSED HORIZONTAL PLANE STANDARD RADIATION PATTERN

G1 = 167° G2 = 90°	PARKER · REW ENTERPRISES JAMESVILLE, VIRGINIA Jules Cohen & Associates Consulting Electronics Engineers	RADIO STATION WEXM - 1520 KHZ 0.5 KW D DA PATTERN 741220A
--	---	---

WEXM



PROPOSED HORIZONTAL PLANE STANDARD RADIATION PATTERN

G1 - 167° G2 - 90°	PARKER REW ENTERPRISES JAMESVILLE, VIRGINIA Jules Cohen & Associates Consulting Electronics Engineers	RADIO STATION WEXM 1520 KHZ 0.5 KW D DA PATTERN 741220A
--------------------------------------	---	---

WGNB

POLAR COORDINATE
SCALE 1:1

10 LP


CLEVELAND INST. CO. RADIO ELECTRONICS
CLEVELAND, OHIO

Proposed Day
(4-30-63ct)

Station WGNP
Indian Rocks Beach, Florida

1kw, DA-D, D
1520 kc

5-9-63
Granted mod. of CP
to change DA pattern



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS							STATION DATA	
		TOWER	ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	PHASING	HORIZONTAL FIELD	FIELD RATIO	ELEV. ANGLE	ELEVATION RMS FIELD
		1	90°	0°	0	0	150.5	1.0	0	186
		2	90°	175°	160°	21°	120.5	0.8	10	
		3							20	
		4							30	
		5							40	
		6							50	
		7							60	
		8							70	
		9							80	
		10							90	
		11							100	
CARL E. SMITH CONSULTING RADIO ENGINEERS		FIG. 4.1 PROPOSED HORIZONTAL PATTERN							The World Christian Foundation Inc. Indian Rocks Beach, Fla. 1520 kc 1 kw DA-D	
									CALL New FREQUENCY 1520 POWER 1 TIME OF OPERATION DA-D TYPE OF OPERATION Class II DAYTIME TOWERS 2 NIGHTTIME TOWERS 2 NO RADIALS PER TOWER 120 LENGTH OF RADIALS 90° 162 ft GROUND SCREEN DIMENSIONS 24 x 24 L1 27° 49' 28" L2 82° 46' 47" SUPERCEDES PATTERN NO. 630324	

WG-NB

Measured Day
(9-29-64ct)

Station WGNP
Indian Rocks Beach, Florida

1kw, DA-D, D
1520 kc

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
		TOWER No	ELECTRICAL HEIGHT h	TRUE TOWER ORIENTATION θ	SPACING s	PHASING φ	HORIZONTAL FIELD E	FIELD RATIO F	ELEV ANGLE θ	ELEVATION ANGLE θ _h	CALL WGPN
		1	165	0	0	0		1.0	0	187.5	FREQUENCY 1520
		2	90	175	160	21		0.8	10		POWER 1
		3							20		TIME OF OPERATION DA-D
		4							30		TYPE OF OPERATION Class II
		5							40		NIGHTTIME TOWERS 2
		6							50		NIGHTTIME TOWERS --
		7							60		NO RADIALS PER TOWER 120
		8							70		LENGTH OF RADIALS 90 162 //
		9							80		GROUND SCREEN DIMENSION 24 x 24
		10							90		LONG. 27 50 26
											LONG. 82 46 10
											PERSECS 630408
											PATTERN No 2


Manly St. Jean
Radio Engineer
8705 Flamingo Ave.
Largo, Florida

Page 2- (g)

MEASURED DIRECTIONAL HORIZONTAL
PATTERN

The World Christian Radio Foundation Inc.
WGNP Indian Rocks Beach, Florida
1520 KC 1 kw DA-D
From original data of March 1963 and
from re-run data of June 1964, i.e. 355°.

BRC-2599 7-29-70
GR. (10-21-64) APPL



FCC File No. BRC-2529
Accented

Station WGNP
Indian Rocks Beach, Florida

1520 kc


WGNB

Measured Non-DA
(7-24-63ct)

Station WGNP
Indian Rocks Beach, Florida

1kw, DA-D, D
1520 kc

2-13-64
29 for new
station



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
		TOWER No	ELECTRICAL HEIGHT G	TRUE TOWER ORIENTATION θ°	SPACING S'	PHASING μ	HORIZONTAL FIELD E	FIELD RATIO F	ELEV. ANGLE θ°	ELEVATION RMS FIELD mv/m	CALL WGNP	FREQUENCY 1520
		1	265					0	185	POWER 1	TIME OF OPERATION DA-D	
		2						10		TYPE OF OPERATION Class II		
		3						20		DAYTIME TOWERS 2		
		4						30		NIGHTTIME TOWERS		
		5						40		NO. RADIALS PER TOWER 120		
		6						50		LENGTH OF RADIALS 90 - 162 //		
		7						60		GROUND SCREEN DIMENSION 24 x 24		
		8						70		LAT. 27 - 50 - 26		
		9						80		LONG. 82 - 46 - 10		
		10						90		SILVERSECS		
		☐ DAYTIME OPERATION ON ☐ NIGHTTIME OPERATION ON								PATTERN NO 630408		

FIG. 6.10 The World Christian Radio Foundation, Inc.
Measured Non-Directional Horizontal Indian Rocks Beach, Florida
Pattern 1520 kc 1 kw DA-D

CARL E. SMITH
CONSULTING RADIO ENGINEERS


WINW

Proposed Day Nulls (MEOW)
(7-28-66ct)

Station WINW
Canton, Ohio

1kw, DA-D, D
1520 kc

330° 340° 350° U 10° 20° 30°



FCC File No. BP-17225
Accepted 6-30-66

Station WINW
Canton, Ohio

1520 kc

7-8-66
DA
11528
2-6-67
CANTON
1000
DA
CHECKS

33476 POLAR COORDINATE

FREDERICK POST COMPANY

WINW


Measured Day
(5-27-66ct)

Station WINW
Canton, Ohio

1kw, DA-D, D
1520 kc

DA HORIZONTAL PATTERN
WINW CANTON, OHIO
1520 KC 1 KW - DA
FIGURE 2 APRIL, 1966

PETE JOHNSON
CONSULTING ENGINEERS
Kanawha Hotel Bldg., Charleston, W. Va.



North Latitude 40° 50' 41"
West Longitude 81° 21' 02"

FCC File No. BL-11288
Accepted 5-13-66

Station WINW
Canton, Ohio


1520 kc

WINW

Measured Day Nulls
(5-27-66ct)

Station WINW
Canton, Ohio

1kw, DA-D, D
1520 kc



FCC File No. BL-11288
Accepted 5-13-66

Station WINW
Canton, Ohio


1520 kc

WINW

Measured Non-DA
(5-27-66ct)

Station WINW
Canton, Ohio

1kw, DA-D, D
1520 kc



ND HORIZONTAL PATTERN
WINW CANTON, OHIO
1520 KC 1 KW ND-D
FIGURE 1 APRIL, 1966


PETE JOHNSON
CONSULTING ENGINEERS
Kanawha Hotel Bldg., Charleston, W. Va.

FCC File No. BL-11288
Accepted 5-13-66

Station WINW
Canton, Ohio

1520 kc

PAGE & DAVIS
Consulting Radio Engineers
WASHINGTON, D.C.




VVNDW

Measured Day & Night
(1-30-67ct)

Station WKBW
Buffalo, New York

50kw, DA-1, U
1520 kc



FCC File No. BRC-2229
Granted 11-14-63

Station WKBW
Buffalo, New York

1520 kc

330

30

PAGE & DAVIS

Consulting Radio Engineers

WASHINGTON, D. C.

NORTH

R.M.S.=1870 MV/M

300

60

210

MV/M

150

100

50

500

1000

1500

2000 MV/M

90

H=350'

1995F

F

120°

69.63°

120°

F

0°

ENLARGED VIEW

KOMA
1115 MILES

240

120

PONCE


PATTERN No.: 410924
 SUPERSEDES: 400525
 REINSTATES:

210

180

150

MEASURED EFFECTIVE FIELD AT 1 MILE
 WITH 50 KILOWATTS IN ARRAY FOR WKBW




HORIZONTAL RADIATION PATTERN		0° STANDARD PATTERN	
Standard Pattern RMS - 133.0 MV/M		APPLICANT : WKJR	
Theoretical RMS - 126.5 MV/M		LOCATION : Muskegon Heights, Mich	
RES - 188.6 MV/M		FREQUENCY : 1520 KC/S	
		POWER : 500 Watts	
		LATITUDE : 43 DEG 08 MIN 28 SEC	
		LONGITUDE : 86 DEG 14 MIN 50 SEC	
		WHEN USED : Nighttime	
		RMS FIELD : 133.0 MV/M	
		DATE : August 28th, 1979	
		RALPH J. SITZER CONSULTING RADIO ENGINEERS ST. LOUIS, MISSOURI	

Proposed Day
(5-27-70ct)

Station WKJR
Muskegon Heights, Michigan

WKJR
10kw, DA-D, D
1520 kc



HORIZONTAL RADIATION PATTERN

BP-17,961

True
0°
1°-162°
80°
1.528 10°
80°
0.723 162°

A-160°/165° (90°)

APPLICANT	WKJR
LOCATION	Muskegon Heights, Mich.
FREQUENCY	1520 KC/S
POWER	10 KW
LATITUDE	43 DEG 08 MIN 28 SEC
LONGITUDE	86 DEG 17 MIN 53 SEC
WHEN USED	Daytime
R.M.S. FIELD	585 MV/M
DATE	Sept. 16th, 1969

RALPH J. BITZER
CONSULTING RADIO ENGINEERS

FCC File No. BP-17961
Amended 10-14-69


Station WKJR
Muskegon Heights, Michigan

1520 kc

Proposed Day Nulls
(5-27-70ct)

Station WKJR
Muskegon Heights, Michigan

WKJR
10kw, DA-D, D
1520 kc
Page 12




HORIZONTAL RADIATION PATTERN

BP-17,961

APPLICANT	WKJR
LOCATION	Muskegon Heights, Mich.
FREQUENCY	1520 KC/S
POWER	10 KW
LATITUDE	43 DEG 08 MIN 28 SEC
LONGITUDE	86 DEG 11 MIN 53 SEC
WHEN USED	Daytime
RMS FIELD	585 MV/M
DATE	Sept. 16th, 1969

A-160°/165° (90°)



FCC File No. BP-17961
Amended 10-14-69

Station WKJR
Muskegon Heights, Michigan

1520 kc

RALPH J BITZER
CONSULTING RADIO ENGINEERS
ST. LOUIS, MISSOURI


WKJR

Proposed Day
(11-29-68ct)

Station WKJR
Muskegon Heights, Michigan


10kw, DA-D, D
1520 kc

BP-17961
GIL (4-16-70)
CP TO INCREASE POWER TO 10 KW
ADD INSTALL DIRECTIONAL ANTENNA



HORIZONTAL RADIATION PATTERN

BP-17,961



APPLICANT :	WKJR
LOCATION :	Muskegon Heights, Mich
FREQUENCY :	1520 KC/S
POWER :	10 KW
LATITUDE :	43 DEG 08 MIN 28 SEC
LONGITUDE :	86 DEG 14 MIN 53 SEC
WHEN USED :	Daytime
ARR. FIELD :	563
DATE :	Oct. 18th, 1967

RALPH J. BITZER
CONSULTING RADIO ENGINEERS

FCC File No. BP-17961
Accepted 11-1-68 Amended

Station WKJR
Muskegon Heights, Michigan

1520 kc


WKJR

Proposed Day Nulls
(11-29-68ct)

Station WKJR
Muskegon Heights, Michigan

10kw, DA-D, D
1520 kc

BP-17961
(7K-4-15-70)
CP TO INCREASE Pwr etc to 100kW
AND INCREASE DIRECTIONAL AREA



HORIZONTAL RADIATION PATTERN

Expanded Scale



APPLICANT :	WKJR
LOCATION :	Muskegon Heights, Mich
FREQUENCY :	1520 KC/S
POWER :	10 KW
LATITUDE :	43 DEG 08 MIN 28 SEC
LONGITUDE :	86 DEG 14 MIN 53 SEC
WHEN USED:	Daytime
M.M.S. FIELD:	563
DATE :	October 18th, 1967

RALPH J. BITZER
CONSULTING RADIO ENGINEERS

FCC File No. BP-17961
Accepted 11-1-68 Amended

Station WKJR
Muskegon Heights, Michigan

1520 kc

Measured Day
(7-27-65ct)Station WKNT
Kent, Ohio1kw, DA-D, 0
1520 kc

WKNT

Measured Non-DA
(7-27-65ct)

Station WKNT
Kent, Ohio

1kw, DA-D, D
1520 kc

10. 2-11-65

EUGENE DIETZEN CO.
MADE U.S.A.

NO. 347-D DIETZEN GRAPH PAPER
POLAR CO-ORDINATE




FIG. 6.12
MEASURED NON-DIRECTIONAL
PATTERN, 250 W. TOWER NO. 5

WKNT	KENT	OHIO
1520 kc	1 kw	DA-D
650106		

Carl E. Smith Consulting Radio Engineers

FCC File No. BL-10957
Accepted 7-22-65

Station WKNT
Kent, Ohio

1520 kc


WKNT

Proposed Day Nulls
(7-27-65ct)

Station WKNT
Kent, Ohio

1kw, DA-D, D
1520 kc

MCP 3-11-65



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
		TOWER No.	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION deg	SPACING ft	PHASING deg	HORIZONTAL FIELD dB/m	FIELD RATIO F	ELEV. ANGLE deg	ELEVATION RMS FIELD dB/m	CALL New
1	90	0	0	-100	62.6	0.5	0	185	FREQUENCY 1520		
2	90	118	180	0	95.8	0.765	12		POWER 1 kw		
3	90	118	360	100	62.6	0.5	20		TIME OF OPERATION DA-D		
4	90	128.9	412	208	62.6	0.5	30		TYPE OF OPERATION Class II		
5	183.6	137.1	238	108	95.8	0.765	40		DAYTIME TOWERS 6		
6	90	178	90	8	62.6	0.5	50		NIGHTTIME TOWERS -		
7							60		NO RADIALS PER TOWER 120		
8							70		LENGTH OF RADIALS 90' 162"		
9							80		GROUND SCREEN DIMENSION 24' x 24'		
10							90		LAT. 41° 09' 35"		
							100		LONG 81° 18' 19"		
									SUPERSEDES 601003		
		DAYTIME OPERATION ☒ NIGHTTIME OPERATION ☐								PATTERN No 650322	

CARL E. SMITH
CONSULTING RADIO ENGINEERS

FIG. 3. 2D
EXPANDED HORIZONTAL PATTERN
KENT-RAVENNA B/C CO.
KENT, OHIO



WKNT

Proposed Day Nul1s
(7-27-65ct)

Station WKNT
Kent, Ohio

1kw, DA-D, D
1520 kc

MCP 3-11-65



FCC File No. BMP-11447
Accepted 2-2-65

Station WKNT
Kent, Ohio


1520 kc

WKNT

Proposed Day
(7-27-65ct)

Station WKNT
Kent, Ohio

1kw, DA-D, D
1520 kc



TOWER PLACEMENT SKETCH

90° = 161.7'
156° = 280'
180° = 323.4'

PATTERN PARAMETERS

TOWER No.	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION °	SPACING ft	PHASING °	HORIZONTAL FIELD dBu	FIELD RATIO F	ELEV ANGLE °	ELEVATION HGT FIELD dBu
1	90	0	0	-100	62.6	0.5	0	185
2	90	118	180	0	95.8	0.765	10	
3	90	118	360	100	62.6	0.5	20	
4	90	128.9	412	208	62.6	0.5	30	
5	183.6	137.1	238	108	95.8	0.765	40	
6	90	178	90	8	62.6	0.5	50	
7							60	
8							70	
9							80	
10							90	

STATION DATA

CALL	New
FREQUENCY	1520 kc
POWER	1 kw
TIME OF OPERATION	DA-D
TYPE OF OPERATION	Class II
DAYTIME TOWERS	6
NIGHTTIME TOWERS	-
NO RADIALS PER TOWER	120
LENGTH OF RADIALS	90° 162 ft
GROUND SCREEN DIMENSION	24' x 24'
LAT.	41° 09' 35"
LONG	81° 18' 19"
SUPERSEDES	641211
PATTERN No	650322

DAYTIME OPERATION ☒

NIGHTTIME OPERATION ☐

P. =

CARL E. SMITH
CONSULTING RADIO ENGINEERS

Fig. 3.1B

PROPOSED HORIZONTAL PATTERN
KENT-RAVENNA B/C CO.
KENT, OHIO

CARL E. SMITH
CONSULTING RADIO ENGINEERS

Fig. 3.1B
PROPOSED HORIZONTAL PATTERN
KENT-RAVENNA B/C CO.
KENT, OHIO

NEW-
1520 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: (NEW)

Main Studio: Greenfield, Massachusetts

Frequency: 1520 kHz

Power 10kw Day

Notification List No. 1783

Date: November 2, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 36' 39"

West Longitude: 72° 38' 45"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER: E(#1) W(#2)

HEIGHT ABOVE
INSULATORS: 130' (72.3°) 130' (72.3°)

DAY PHASING: 0° 109°

DAY FIELD RATIO: 1.0 1.0

SPACING AND
ORIENTATION: The towers are spaced 143.8' (80°) on a line bearing
282.5° true.

GROUND SYSTEM: 120 - 162' equally spaced copper radials plus 60 - 50'
interspaced radials about each tower.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	596.7 mv/m	661.0 mv/m	626.8 mv/m

GREENFIELD, MASSACHUSETTS
1520 kHz

Figure
2-1




Figure 2-1. Proposed Horizontal Radiation Pattern

WPOE
1520kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WPOE

Main Studio: Greenfield, Massachusetts

Frequency: 1520 kHz

Power 10kw Day

Notification List No. 1785

Date: November 16, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 36' 12"

West Longitude: 72° 36' 21"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	W(#2)	E(#1)
HEIGHT ABOVE INSULATORS:	196'	196' (109°)

DAY PHASING:	100°	0°
--------------	------	----

DAY FIELD RATIO:	0.92	1.0
------------------	------	-----

SPACING AND
ORIENTATION: Adjacent towers in a row are spaced 161.8' (90°) on
a line bearing 277° true.

GROUND SYSTEM: 120 - 162' equally spaced copper radials plus 60 - 50'
interspaced radials about each tower. Radials are shortened
and bonded to a transverse strap along intersections between
towers. Centers of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL RMS	RSS	STANDARD RMS
Day	630.2 mv/m	657.6 mv/m	662.0 mv/m




Figure 2-1. Proposed Horizontal Radiation Pattern

Measured Day & Night
(10-26-70ct)

Station WRAI
San Juan, Puerto Rico


WRAI
10kw, DA-1, U
1520 kc

THEORETICAL PARAMETERS

#1 = $1/0^\circ$
#2 = $0.969/-107.6^\circ$

MEASURED PARAMETERS

#1 = $1/0^\circ$
#2 = $0.881/-109.5^\circ$



$E_{RMS} = 605 \text{ MV/M}$

————— = MEASURED
- - - - - = MEQV

LATITUDE: $18^\circ 21' 00''$
LONGITUDE: $66^\circ 09' 25''$

ANTENNA PARAMETERS

#1
80°
#2
N-113°-E
G = 83.4°

FIGURE 14

MEASURED DIRECTIONAL
PATTERN

RADIO STATION WRAI
SAN JUAN, PUERTO RICO

JOHN H. MULLANEY
AND
ASSOCIATES

1520 KHz

10 KW, DA-1, U

FCC File No. BL-12731
Accepted 9-30-70


Station WRAI
San Juan, Puerto Rico

1520 kc

Measured Non-DA
(10-26-70ct)

Station WRAI
San Juan, Puerto Rico

WRAI
10kw, DA-1, U
1520 kc



FCC File No. BL-12731
Accepted 9-30-70

Station WRAI
San Juan, Puerto Rico


1520 kc

Proposed Day & Night
(6-29-70ct)

Station WRAI
San Juan, Puerto Rico

SEE
REVERSE
SIDE
6/29/70

WRAI
10kw, DA-1, U
1520 kc




WRAI

Proposed Day & Night
(11-29-66ct)

Station WRAI
Rio Piedras, Puerto Rico

10kw, DA-1, U
1520 kc

12-20-67
GRANTED
APPLICATION
TO CHANGE
LOCATION



FCC File No. BP-17292
Accepted 10-28-66

Station WRAI
Rio Piedras, Puerto Rico


1520 kc

WRAI

Proposed Day & Night
(9-26-68ct)


Station WRAI
San Juan, Puerto Rico

10kw, DA-1, U
1520 kc



$E_{RMS} = 610 \text{ MV/M}$ _____

----- = MEOV

LATITUDE: 18° 21' 00" LONGITUDE: 66° 09' 25"	ANTENNA PARAMETERS 	FIGURE 2 DIRECTIONAL HORIZONTAL POLAR PATTERN RADIO STATION WRAI SAN JUAN, PUERTO RICO 1520 KC 10 KW, DA-1, U
JOHN H. MULLANEY AND ASSOCIATES		

FCC File No. BMP-12470
Accepted 8-8-68

Station WRAI
San Juan, Puerto Rico

1520 kc

Bi-States Broadcasters
Ocean City-Sommers Point, New Jersey 1520 KC


WSLT

Measured Day
(10-26-64ct)

Station WSLT
Ocean City-Somers Point, New Jersey

1kw, DA-D, D
1520 kc

#203
10-30-64
granted L for
new station



FCC File No. BL-10647
Accepted 10-19-64

Station WSLT
Ocean City-Somers Point, New Jersey


1520 kc

WSLT

Measured Non-DA
(10-26-64ct)

Station WSLT
Ocean City-Somers Point, New Jersey

1kw, DA-D, D
1520 kc



FCC File No. BL-10647
Accepted 10-19-64

Station WSLT
Ocean City-Somers Point, New Jersey

1520 kc


WSVL

PROPOSED DAY
(4-10-61g)

Station WSVL
Shelbyville, Indiana

250w, 1kw-LS, DA-2, U
1520 KC

2-6-62
anted CP for
W Day and DA-2



K-E POLAR CO-ORDINATE
KUPPEL & FOSBER CO.

FCC File No. BP-14668
Accepted 3-8-61

Station WSVL
Shelbyville, Indiana

1520 KC

Shelbyville, Ind.


WSVL

PROPOSED DAY & NIGHT
(3-23-59g)

New; Shelby County B/C Co.
Shelbyville, Indiana

250w, DA-1,U

1520 KC



FCC File No. BP-11202
Accepted 2-5-59 (Amended)

Shelby County Broadcasting Company
Shelbyville, Indiana

1520 KC

Granted for new station
6-22-60


WSVL

MEASURED DAY
(4-10-61g)

Station WSVL
Shelbyville, Indiana

250w, DA-1, U
1520 KC

*parted for
in station*



K-E POLAR CO-ORDINATE
KNUFEL & ENGLISH

Theoretical RMS 80 MVM
Measured RMS 105 MVM

WSVL SHELBYVILLE, INDIANA DIRECTIONAL
PROOF OF PERFORMANCE ON 1520 KGS
WITH 250 WATTS, DA-1 BR-II, 202
RALPH J. BITZE, CONSULTING ENGINEER

FCC File No. BL-8251
Accepted 3-28-61

WSVL
Shelbyville, Indiana


1520 KC

WSVL

MEASURED NON-DA
(4-10-61g)

Station WSVL
Shelbyville, Indiana

250w, DA-1, U
1520 KC



FCC File No. BL-8251
Accepted 3-28-61

WSVL
Shelbyville, Indiana

1520 KC

WSVL


Measured Non-DA
(7-24-63ct)

Station WSVL
Shelbyville, Indiana

250w, 1kw-LS, DA-2, U
1520 kc

7-27-63
inserted as
as included in
log power to
increase from DA-1
to DA-2.

• Measured Inverse Field



FCC File No. BL-10122
Accepted 7-2-63

Station WSVL
Shelbyville, Indiana

1520 kc


WSVL

Measured Day
(7-24-63ct)

Station WSVL
Shelbyville, Indiana

250w, 1kw-LS, DA-2, U
1520 kc

9-27-63
beamed beam
or increased
by power change
from DA-1 to
DA-2




KOM POLAR COORDINATE 350-310

WTGR

RMS (std.) = 484.9 MV/M
 RMS (th) = 461.6 MV/M
 RSS (th) = 448.2 MV/M

WILLIS E. DECKER
 CONSULTING ENGINEER
 WASHINGTON, D. C.



279.3°T ← 3 — 200.2° — 2 — 92.6° — 1 → 108.1°T

No.	Ht.	Phase	Ratio
1	89.0'	0.0°	1.00
2	166.8'	134.7°	1.07
3	89.0'	212.0°	1.14

Lat: 33° 42' 20", Long: 78° 53' 23"

FIGURE 6

CALCULATED DAYTIME
 STANDARD HORIZONTAL RADIATION PATTERN
 GRAND STRAND BROADCASTING CORPORATION

WTGR, MYRTLE BEACH, SOUTH CAROLINA

1520 KHz

5 KW

DA-D, D

OCTOBER 1973


WTLN

PROPOSED DAY
(12-15-60g)

New; Adair Charities, Inc.
Apopka, Florida

5kw, DA-D,D
1520 KC

7-25-62
Granted Cofc
new AM station



FCC File No. BP-14484
Accepted 12-7-60

Adair Charities, Inc.
Apopka, Florida

1520 KC


WTLN

Measured Day
(6-29-64)

Station WTLN
Apopka, Florida

5kw, DA-D, D
1520 kc

BL-10589
GRANTED
1-13-65



Description Sheet
(7-29-70ct)

Station XEEG
Panzacola, Tlax.

XEEG
500w, DA-D, D, Class II
1520 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: XEEG

Main Studio: Panzacola, Tlax.

Frequency: 1520 kHz

Power: 0.5 Kw

Notification List No. 263

Date: May 16, 1970

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 19 ° 08 ' 30 "
West Longitude: 98 ° 12 ' 00 "

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: guyed, vertical steel towers.

TOWER: NW(#2) SE(#1)

HEIGHT ABOVE

INSULATORS: 162' 162' (90°)

PHASING: +15° 0°

FIELD RATIO: 1 1

SPACING AND

ORIENTATION: Elements are spaced 297' (165°) on a line bearing 290° true.

GROUND SYSTEM: 120-162' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap
along intersections between towers.


Predicted effective Field: 134.349 mv/m at rated power.

XEEG

Proposed Day
(7-29-70ct)

Station XEEG
Panzacola, Tlax.


500w, DA-D, D, Class II
1520 kc



PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/m. A 1609M

ESQUEMA DE LAS TORRES Y SU ORIENTACION CON RESPECTO AL NORTE GEOGRAFICO

AZIMUT: 290°



XEEG

PANZACOLA, TLAX.

FRECUENCIA

1520 KHZ.
0.5 KW. AD-D.

DISEÑO:


JAIME ROBLEDO ROMERO.
RADIOTELEFONISTA DE 1. 1010

DIBUJO:

A. P. A.

5kw, DA-D, D
1520 kc

North Latitude	72°	36'	45"
West Longitude	42°	34'	31"




1520 kc

Proposed Day
(9-28-66ct)

New; DeWitt Radio
Yorktown, Texas

500w, DA-D, D
1520 kc



FCC File No. BP-17138
Accepted 9-21-66

New; DeWitt Radio
Yorktown, Texas

1520 kc

FORM FOR THE APPLICATION OF ARTICLE 4 OF THE AGREEMENT

6 3 5 9

CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

PART I GENERAL INFORMATION

Ⓐ Administration

CANADA

Sheet No. 421

Date	830726
------	--------







Assigned frequency (kHz)		02	1,5,3,0
Transmitting station	Name of the station	03	M,O,N,C,T,O,N, , , , , N,B
	Call sign	04	, , , , , , , , , ,
	Additional Identification	05	, , , , , , , , , ,
	Station class	06	B
	Operational Status	07	P
Country		08	CAN
Geographical coordinates of the transmitting station		09	6,4,W,4,7,0,0, unk 6,N,0,4,0,0

11 a) New assignment ☐ b) Modification of characteristic of an assignment recorded in the plan ☒ c) Cancellation of an assignment ☐

12 Modification under Section 4.2.14 Yes ☐ No ☒

13 Date of bringing into service or cessation of operation

Year	Month	Day

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	(21) 	(31) 
r.m.s. value of radiation for station power (mV/m at 1 km)	(25) 	(35) 
Antenna type	(26) 	(36) 
Simple vertical antenna electrical height (degrees)	(27) 	(37) 

44 Remarks	COORDINATION UNDER ARTICLE 4:								
	COUNTRY	USA							
	IN PROGRESS	X							
	ACCEPTANCE OBTAINED								

IFRL Serial No.

6	3	5	9
---	---	---	---

Description of a directional antenna consisting of vertical conductors

421 830726

Date _____

7

C A H

②

N	B
---	---

--	--

1

--	--

--	--

$$\frac{N}{O}$$
I

U

$$\frac{N}{O}$$

①

©

Total number
of towersHours of operationCountryName of transmitting station

3

[illegible]

(14)	(15)	(16)
r.m.s. value of radiation	Type of pattern	Special quadrature factor
6.75, 7.8	E	
	mV/m at 1 km	my/m at 1 km

17 SUPPLEMENTARY INFORMATION						
Azimuth	60	157	222	290	355	
Angle	0	21	35	0	14	
Radiation	1104.3	572.7	33.7	87.6	845.9	

NEW
1530

STATION: NEW	MAIN STUDIO: Morden, Manitoba
FREQUENCY: 1530 kHz	POWER: 10 kW Day CLASS: II 1 kW Night
NOTIFICATION LIST NO: 383	DATE: March 28, 1979
GEOGRAPHICAL LOCATION:	Latitude 49° 07' 16" North Longitude 98° 04' 01" West

Mode of Operation:	DA-2
Number of Elements:	4 (Four)
Type of Elements:	Guyed steel towers, uniform cross-section, base insulated for series feed

Tower	#1 (South)	#2 (South-Centre)	#3 (North-Centre)	#4 (North)
Height above base insulator	150' (84°)	150' (84°)	150' (84°)	150' (84°)
Overall height:	155'	155'	155'	155'
Day Field Ratio:	--	1.0	1.0	--
Day Phasing:	--	0°	-68°	--
Night Field Ratio:	0.365	1.0	1.0	0.365
Night Phasing:	+150°	Ref.	-152.4°	+58°
Spacing:	160.8' (90°)	Ref.	160.8' (90°)	321.6' (180°)
Orientation:	175°	Ref.	360°	360°

GROUND SYSTEM: 120 equally spaced radials per tower of No. 10 B & S gauge bare soft copper wire, buried approximately 8". Length of radials 257' (0.4 wavelength) with the exception of those joined along the common chords.

Nighttime: 214 mV/m at 1 mile for 1 kW

Daytime: 574 mV/m at 1 mile for 10 kW
182 mV/m at 1 mile for 1 kW

January 9, 1978

NEW




FIGURE 4

HORIZONTAL RADIATION PATTERN
NIGHTTIME - POLAR PLOT

NEW AM MORDEN, MANITOBA
1530 kHz 10 kW D/1 kW N DA-2 CLASS II
PROJECT #17102 JANUARY 9, 1978

D.E.M. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS

ER

160° 160° 170° 180° 190° 200° 210°
210° 200° 190° 180° 170° 160° 150°






FIGURE 5

HORIZONTAL RADIATION PATTERN
NIGHTTIME - EXPANDED PLOT

NEW AM 1530 KHz 10 KW D/T KW N DA-2 CLASS I
PROJECT #17102 JANUARY 9, 197

DEM. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS

NEW



VERTICAL RADIATION PATTERNS

FIGURE 6

NEW AM

1530 kHz

PROJECT #17102

10 kW D/1 kW N

DA-2



MORDEN, MANITOBA

CLASS II

JANUARY 9, 1978

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

EP



VERTICAL RADIATION PATTERNS

FIGURE 7

NEW AM
1530 kHz
PROJECT #17102

10 KW D/1 KW N



DA-2

MORDEN, MANITOBA

CLASS II

JANUARY 9, 1978

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS



VERTICAL RADIATION PATTERNS

FIGURE 8



NEW AM
1530 kHz 10 kW D/1 kW N
PROJECT #17102

MORDEN, MANITOBA
CLASS 11

DA-2

JANUARY 9, 1978

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS E.R.



VERTICAL RADIATION PATTERNS

FIGURE 9

NEW AM
1530 KHz

10 KW D/1 KW N



MORDEN, MANITOBA
DA-2 CLASS II

PROJECT #17102

JANUARY 9, 1978

D.E.N. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

3.0



VERTICAL RADIATION PATTERNS

FIGURE 10

NEW AM

1530 kHz

PROJECT #17102

10 kW D/I LW H


MORDEN, MANITOBA

DA-2 CLASS II

JANUARY 9, 1978

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

6.2



PROJECT #17102

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: NEW MAIN STUDIO: Morden, Manitoba
 FREQUENCY: 1530 kHz POWER: 10 kW Day CLASS: II
 1 kW Night

NOTIFICATION LIST NO: 383 DATE: March 28, 1979

GEOGRAPHICAL LOCATION: Latitude 49° 07' 16" North
 Longitude 98° 04' 01" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-2
 Number of Elements: 4 (Four)
 Type of Elements: Guyed steel towers, uniform cross-section, base insulated for series feed

Tower	#1 (South)	#2 (South-Centre)	#3 (North-Centre)	#4 (North)
Height above base insulator	150' (84°)	150' (84°)	150' (84°)	150' (84°)
Overall height:	155'	155'	155'	155'
Day Field Ratio:	--	1.0	1.0	--
Day Phasing:	--	0°	-86°	--
Night Field Ratio:	0.365	1.0	1.0	0.365
Night Phasing:	+150°	Ref.	-152.4°	+58°
Spacing:	160.8' (90°)	Ref.	160.8' (90°)	321.6' (180°)
Orientation:	175°	Ref.	360°	360°

GROUND SYSTEM: 120 equally spaced radials per tower of No. 10 B & S gauge bare soft copper wire, buried approximately 8". Length of radials 257' (0.4 wavelength) with the exception of those joined along the common chords.

PREDICTED EFFECTIVE FIELD:

Nighttime: 214 mV/m at 1 mile for 1 kW

Daytime: 580 mV/m at 1 mile for 10 kW
 183 mV/m at 1 mile for 1 kW

This Description Sheet is a replacement for that notified in Canadian Change List No. 383, the latter being incorrect with respect to the day-time phasing and RMS. Please retain the notified day-time and night-time radiation patterns.

January 9, 1978

Revised March 8, 1979




FIGURE 3
 HORIZONTAL RADIATION PATTERN
 DAYTIME - POLAR PLOT

NEW AM	MORDEN, MANITOBA
1530 kHz	10 kW D/1 kW N DA-2 CLASS II
PROJECT #17102	JANUARY 9, 1978
	REVISED MARCH 8, 1979


DE M. ALLEN & ASSOCIATES LTD
 CONSULTING ENGINEERS

Measured Day
(1-28-66ct)

Station KL0L
Lincoln, Nebraska

~~KL0L~~
~~KECK~~
5kw, DA-D, D
1530 kc

LIC 2-10-66



FCC File No. BL-11187
Accepted 1-19-66

Station KL0L
Lincoln, Nebraska

1530 kc


KECK ~~KLOL~~

Measured Non-DA
(1-28-66ct)

Station KLOL
Lincoln, Nebraska

5kw, DA-D, D
1530 kc


LIC 2-10-66



FCC File No. BL-11187
Accepted 1-19-66

Station KLOL
Lincoln, Nebraska

1530 kc



KFBK

MEASURED
DAY&NIGHT

KFBK, SACRAMENTO, CAL.

Supplemental to License 12-23-48

50kw, DA1

1530 kc


12/30/48G

SITE: 38° 50' 54" N.
121° 28' 58" W.

TRUE NORTH

9/0° - 170° - 1/18.5° - 78°T

Height - 652'




9/9/48

1530

KGB

NOV 1 1970

WINCOPPER 1212
HARRISON (FEC)



John Creutz
Consulting Radio Engineer
319 Bond Bldg. REpublic 2151
Washington, D. C.


MEASURED
NIGHT

KSOX, HARLINGEN, TEXAS
1/21/52G

10KW, 50KW-LS, U, DA-N

1530 KC KGE

2-21-61
printed for
new station



John Creutz
Consulting Radio Engineer
115 Bond Bldg. Republic 2151
Washington, D. C.


KGBT

MEASURED
NON-DA

KSOX, HARLINGEN, TEXAS
1/21/52G

10 KW, 50KW-LS, U, DA-N

1530 KC



John Creutz
Consulting Radio Engineer
319 Bond Bldg. Republic 2151
Washington, D. C.

APPL RECD 11/21/51 ACC 1/18/52 BL-4649

KSOX, HARLINGEN, TEXAS

1530 KC


KWBE

Proposed Day
(12-30-63ct)-

Station KNBE
Lincoln, Nebraska

5kw, DA-D, D
1530 kc

1-16-64
Grated
rod of CP
5 change
internal -
new location
to change DA



$E_{RMS} = 395 \text{ kV/M (BY ADJUSTMENT)}$

AMENDMENT TO RP-15043
SUPERB'S PATTERN NO. E10616

LATITUDE $40^{\circ} 42' 30''$ LONGITUDE $96^{\circ} 35' 47''$	ANTENNA PARAMETERS ALL $\theta's = 111.7^{\circ}$	FIGURE 7 HORIZONTAL RADIATION PATTERN RADIO STATION KNBE LANCASTER COUNTY BROADCASTING COMPANY LINCOLN, NEBRASKA 1530 KC 5000 DA-D
CHARLES E. BRENNAN CONSULTING RADIO ENGINEERS MILWAUKEE, WISCONSIN		

FCC File No. BMP-11102
Accepted 12-6-63

Station KNBE
Lincoln, Nebraska

1530 kc


(SEE REVERSE SIDE)

KNIE

Proposed Night
(2-28-69ct)

Station KCGO
Cheyenne, Wyoming

1kw, 10kw (5kw-CH) LS, DA-N-CH, U
1530 kc



FCC File No. BMP-12651
Accepted 2-12-69

Station KCGO
Cheyenne, Wyoming

1530 kc


SEE REVERSE SIDE

KNIE

Proposed Day CH
(2-28-69ct)

Station KCGO
Cheyenne, Wyoming

1kw, 10kw (5kw-CH) LS, DA-N-CH, U
1530 kc




FCC File No. BMP-12651
Accepted 2-12-69

Station KCGO
Cheyenne, Wyoming

1530 kc

KNIE

1kw, 10kw(5kw-CH)LS, DA-N-CH, U
1530 kc



330° 340° 350° 0 100 200 300
 K N I E
 CHY
 NORTHERN STATES BROADCASTING
 1530 kHz / CORPORATION
 1kW-D 5kW-CH, DA 1kW-N, DA DA-2
 CHEYENNE, WYOMING
 MARCH 1973


EXHIBIT E-3.04A

AMENDED

MEASURED DIRECTIONAL
 HORIZONTAL RADIATION PATTERN
 UNATTENUATED FIELD AT ONE MILE

CRITICAL HOURS

amended to show
 measured pattern's RMS




K.C.H.Y.
NORTHERN STATES BROADCASTING
1530 kHz / CORPORATION
10KW-D 5KW-CH, DA 1KW-N, DA DA-2
CHEYENNE, WYOMING
MARCH 1973

KNIE
EXHIBIT E-8.048

AMENDED

amended to show
measured pattern & RMS

MEASURED NIGHTTIME DIRECTIONAL
HORIZONTAL RADIATION PATTERN
UNATTENUATED FIELD AT ONE MILE



WCKY
1530 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WCKY

Main Studio: Cincinnati, Ohio

Frequency: 1530

Power: 50kw Night 50kw Day

Notification List No. 1783

Date: November 2, 1979 Class: I-B

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 39° 04' 07"
West Longitude: 84° 36' 20"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation (DA-N)

Number of elements: 3

Type of elements: Series excited, uniform cross-section,
guyed, shunt excited, self supporting,
tapered, vertical steel towers.

TOWER:	E(#1)	W(#2)	N(#3)
HEIGHT ABOVE INSULATORS	345' (193°)	345' (193°)	350' (196°)
NIGHT PHASING:	0°	40°	145°
NIGHT FIELD RATIO:	1.8	1.0	0.7

SPACING AND
ORIENTATION:

The west tower (#2) is spaced 123.1° from the East
tower (#1) on a line bearing 280° true. The North
tower (#3) is spaced 85.2° on a line bearing 322° true.

GROUND SYSTEM:

120-300' equally spaced copper radials plus a 48' X 46'
square ground screen under each tower. Radials are
shortened and bonded to transverse straps along inter-
sections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL

FVS

FSS

Day - 1781.9 mv/m

Night 1600 mv/m

Note: This notification concerns only a change in the Nighttime operation of the
station with Daytime operation continued as previously notified.

WCKY
1530 kHz

NORTH LATITUDE: 39° 04' 07"
WEST LONGITUDE: 84° 36' 20"




FIGURE 2 (CORRECTED)
NIGHTTIME HORIZONTAL PLANE
RADIATION PATTERN
WCKY 50 kW-U, DA-N 1530 kHz
CINCINNATI, OHIO

Prepared by
Lohnes and Culver Washington, D. C
July, 1978

PROPOSED DAY

Station WCKY
Cincinnati, Ohio

50kw, DA after IS at
Sacramento, California 1530 KC


WCK

EUGENE DIETZEN CO.
MADE IN U.S.A.


NO. 340-P DIETZEN GRAPH PAPER
POLAR CO-ORD. TYPE

MURPHY & CHAMBERS
RADIO ENGINEERS
WASHINGTON, D.C.

UNITED STATES



HORIZONTAL RADIATION PATTERN
PROPOSED FOR
WCKY —
50KW — 1530 KC



10-29-38

WCKY

150'

MENARY & CHAMBERS
RADIO ENGINEERS
WASHINGTON, D. C.

PATTERN NO 411016
SUPERSEDES 381029
REINSTATES :

R.M.S. FIELD
1534 MV/M





Figure 3



PROPOSED HORIZONTAL PLANE RADIATION PATTERN

G - 100 (180°) 0.563 (29.1°) 42 (NE) 90° 90° 90° 90° 0.458 (24.3°) 225°	RADIO STATION WDJZ BRIDGEPORT, CONNECTICUT Jules Cohen & Associates Consulting Electronics Engineers	PROPOSED OPERATION 1530 KHZ 5 KW D 9A Pattern 770504
--	--	--

Note: This notification concerns only a reduction in the Daytime power and RMS.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WDJZ

Main Studio: Bridgeport, Connecticut

Frequency: 1530 kHz

Power: 10 kW

Notification List No. 1729

Date: April 13, 1977

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 10' 09"

West Longitude: 73° 13' 14"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 3

Type of elements: Series-excited, Self-supporting, tapered, vertical steel towers.

TOWER: ' SW(#3)	C(#1)	NE(#2)
HEIGHT ABOVE		
INSULATORS: 180'	180'	180' (100.8°)
PHASING: +94.8°	0°	+259.1°
FIELD RATIO: 0.458	1.0°	0.563

SPACING AND


ORIENTATION: From the center reference tower #1; tower #2 is spaced 161' (90°) on a line bearing 50° true, and tower #3 is spaced 161' (90°) on a line bearing 225° true.

GROUND SYSTEM: 120-160' equally spaced copper radials plus a 24' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of systems are bonded together.


Predicted effective Field: 631 mv/m at rated power.

Note: This notification concerns changes in transmitter location and directional antenna system and radiation pattern.

MARCH 1977



PROPOSED HORIZONTAL PLANE RADIATION PATTERN



RADIO STATION WDJZ
 BRIDGEPORT, CONNECTICUT

Jules Cohen & Associates
 Consulting Electronics Engineers

PROPOSED OPERATION

1530 KHZ

10 KW D DA

Pattern 730306A

Measured Non-DA
(5-27-70ct)


SET
REVERSE
Station WFIC ^{WDC 6/24/70} 1kw, DA-D/250w-ND (CH), D
Collinsville, Virginia 1530 kc

GOHEN & DIPPELL

CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D.C. 20004

EUGENE DIETZEN CO.
MADE IN U. S. A.

NO. 341-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-12613
Accepted

Station WFIC
Collinsville, Virginia


1530 kc

Proposed Day
(9-28-67ct)


New; Du Page County Bcstg., Inc.
Elmhurst, Illinois

WKDC
250w, DA-D, D
1530 kc

BP-16292
Danted
125/69
App.
for new
FM station
in Elmhurst



HORIZONTAL RADIATION PATTERN



APPLICANT	Du Page County Broadcasting, Inc.
LOCATION	Elmhurst, Illinois
FREQUENCY	1530 KC/S
POWER	.25 KW
LATITUDE	41° DEG 51' MIN 50" SEC
LONGITUDE	87° DEG 56' MIN 49" SEC
WHEN USED	Daytime
RMS FIELD	95 MV/M
DATE	August 1967

WILLIS C. BEECHER
CONSULTING ENGINEER
WASHINGTON, D. C.




Figure 1

MEASURED DAYTIME DIRECTIONAL
HORIZONTAL PLANE
RADIATION PATTERN

Station WNDG
Elmhurst, Illinois

1530 kHz 250 Watts DA-1

A. D. RING & ASSOCIATES

32-10-868

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WPNO

Main Studio: Auburn, Maine

Frequency: 1530 kHz

Power: 10 kW

Notification List No. 1609

Date: December 4, 1974

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:North Latitude: 44° 04' 39"
West Longitude: 70° 16' 54"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D) STANDARD PATTERN

Number of elements: 2

Type of elements: Series-excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	W(#2)	E(#1)
HEIGHT ABOVE INSULATORS:	214.4'	214.4' (120°)
PHASING:	+53.14°	0°
FIELD RATIO:	0.67	1.00

SPACING AND

ORIENTATION: Elements are spaced 241.2' (135°) on a line bearing 70° true.

GROUND SYSTEM: 120-160' equally spaced copper radials plus 120-50' inter-spaced radials about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers. Centers of systems are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
618.2 mv/m	613.9 mv/m	649.4 mv/m

COHEN AND DIPPELL
P. M. D.

MAY 15 1975

WASH. D.C.


WPNO

N. Lat. 44° 04' 39"
W. Long. 70° 16' 54"

WPNO
STANDARD
HORIZONTAL PLANE RADIATION
1530 Kc 10 Kw DA-D
AUBURN, MAINE

R.S.S. = 613.9 mv/m
Theo. R.M.S. = 618.2 mv/m
Std. R.M.S. = 649.4 mv/m

320°
310°
300°
290°
280°
270°
260°
250°
240°
230°
220°



EUGENE DISTZGEN CO.
MAD. U. S. A.

NO. 340-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE

PATTERN No. 730518A

RALPH T. WINQUIST
Consulting Engineer
BRIDGEPORT CONNECTICUT

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: (new) Main Studio: Flora, Illinois
Frequency: 1530 kHz Power: 1kw
Notification List No. 1423 Date: May 5, 1971 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 38 ° 41' 37 "
West Longitude: 88 ° 28' 52 "

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 4

Type of elements: Series-excited, uniform cross-section, guyed.
vertical steel towers.

TOWER:	SW(#1)	NW(#2)	NE(#3)	SE(#4)
HEIGHT ABOVE INSULATORS:	160'	160'	160'	160' (90°)
PHASING:	0°	+149°	+249°	+100°
FIELD RATIO:	1.0	1.4	1.4	1.0

SPACING AND

ORIENTATION: The towers are located at the vertices of a parallelogram
the sides of which are 160' (90°) in length, on lines bearing
12° true and 82° true.


GROUND SYSTEM: 120 - 80' to 160' equally spaced copper radials plus 120 - 50
interspaced radials about each tower. Centers of systems are
bonded together.

Predicted effective Field: 190 mv/m at rated power.


Proposed Day
(4-29-69ct)

New; The Virginia Broadcasting Corp.
Flora, Illinois

1kw, DA-D, D
1530 kc



HORIZONTAL RADIATION PATTERN



FCC File No. 18498
Accepted 4-2-69

New; The Virginia Broadcasting Corp.
Flora, Illinois

1530 kc

FLORA, ILLINOIS

WQLW





FIGURE 1-A

N 12° E

HORIZONTAL RADIATION PATTERN



G = 90°

APPLICANT :	Virginia Broadcasting Corp.
LOCATION :	Flora, Illinois
FREQUENCY :	1530 KC/S
POWER :	1.0 Kw
LATITUDE :	38 DEG 41 MIN 37 SEC.
LONGITUDE :	88 DEG 28 MIN 52 SEC.
WHEN USED :	Daytime
R.M.S. FIELD :	190 mV/m
DATE :	February 1969

ROBERT L. PURCELL

WASHINGTON, D. C.

WRBX

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WRBX Main Studio: Chapel Hill, North Carolina
 Frequency: 1530 kHz Power: 5 kW
 Notification List No. 1731 Date: April 27, 1977 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 35° 58' 07"
 West Longitude: 79° 00' 10"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: Series excited, uniform cross-section, guyed, vertical steel towers, 109.2 degrees in electrical height, plus 14.0 degrees of top loading by upper sections of guy wires.

TOWER: N(#2) S(#1)
 HEIGHT ABOVE
 INSULATORS: 195' 195' (*)

PHASING: +50° 0°

FIELD RATIO: 0.850 1

SPACING AND

ORIENTATION: Towers are spaced 250' (140°) on a line bearing 310° true.

GROUND SYSTEM: 120-161' equally spaced copper radials about each tower.
 Radials are shortened and bonded to a transverse strap along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
434.8 mv/m	437.6 mv/m	456.8 mv/m

Note: This notification concerns changes in the directional antenna system and radiation pattern and in the transmitter location.

WRRV 1530 Hz. about 40 ft. N.C.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

1-1-2

Station: WRDX

Main Studio: Chapel Hill, North Carolina

Frequency: 1530 kHz

Power: 10kw

Notification Dist No. 1760

Date: February 8, 1973

Class: 11

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North latitude: 35° 58' 07"
West longitude: 79° 00' 10"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. DA-D

Number of elements: 2

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers, top loaded to
an effective electrical height of 123.2°. (*)

TOWER: NW SE

HEIGHT ABOVE
INSULATORS: 195' 195' (*)

PHASING: +50° 0°

FIELD RATIO: 1 1

SPACING AND
ORIENTATION: Towers are spaced 250' (140°) on a line bearing 310° true.

GROUND SYSTEMS: 120 - 161' equally spaced copper radials about each tower.
Radials are shortened and bonded to a transverse strap
along intersections between towers.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

THEORETICAL		STANDARD
RMS	RSS	RMS
1/ 602 mv/m	606 mv/m	632 mv/m
1/ By adjustment of input power.		

This notification concerns a power increase from 5kw.

RSS : 606mV/m
 R_h : 602mV/m
 RMS : 632mV/m
 Et

STANDARD
 HORIZONTAL
 PLANE PATTERN




PROPOSED DAY
(9-13-60g)

New; Lapeer Bcstng. Co.
Lapeer, Michigan

5kw, DA-D,D
1530 KC

1-22-62
granted CP
or new station
4-29-63
granted license



FCC File No. BP-14304
Accepted 9-2-60

Lapeer Broadcasting Company
Lapeer, Michigan

1530 KC

WTHM

Measured Day
(5-28-63ct)


Station WTHM
Lapeer, Michigan

5kw, DA-D, D
1530 kc

7-29-63
Plotted & checked
at WTHM station

LOG LINE UNIT: 101°

NO. 3408 P DIETZEN GRAPH PAPER
"POLAR CO-ORDINATE"



FCC File No. BL-9872
Accepted

Station WTHM
Lapeer, Michigan

1530 kc


WTHM

Measured Non-DA
(5-28-63ct)

Station WTHM
Lapeer, Michigan

5kw, DA-D, D
1530 kc

4-29-63
panted license
or new station



FCC File No. BL-9872
Accepted

Station WTHM
Lapeer, Michigan

1530 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WTTT Main Studio: Dalton, Georgia
 Frequency: 1530 kHz Power: 10 kW
 Notification List No. 1583 Date: June 5, 1974 Class: II

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: $34^{\circ} 47' 09''$
 West Longitude: $85^{\circ} 02' 40''$

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)
 Number of elements: 3
 Type of elements: Series-excited, uniform cross-section, guyed
 vertical steel towers.

TOWER:	NW(#3)	N(#2)	S(#1)	
HEIGHT ABOVE INSULATORS:	161'	161'	161'	(90°)
PHASING:	+201.94°	+119.04°	0°	
FIELD RATIO:	0.096	0.863	1	

SPACING AND


ORIENTATION: From reference tower #1: Tower #2 is spaced 107.14' (60°) on a line bearing 355° true, and tower #3 is spaced 189.29' (106°) on a line bearing 322° true.

GROUND SYSTEM: 120-88' to 160' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers. Centers of systems are bonded together.

Predicted effective Field: 618.1 mv/m at rated power.

Note: This notification concerns changes in the antenna system and radiation pattern.


WTTT 1



Latitude 34°47'09"
Longitude 85°02'40"

-----M.E.O.V.
Theta = 0°

$E_{RMS} = 618.105$
 $E_{RSS} = 784.194$
 $RSS/RMS = 1.269$



HORIZONTAL PLANE PATTERN
WTTT BROADCASTERS, INC.
RADIO STATION WTTT
DALTON, GEORGIA
1530 KHZ

JOHN H. MULLANEY
CONSULTING
RADIO ENGINEER


FIGURE 5
(C14)2

Proposed Day
(2-28-64ct.)

New; Cherokee Broadcasters
Dalton, Georgia

10kw, DA-2, D
1530 kc

WTTI



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
		TOWER NO.	ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	PHASING	HORIZONTAL FIELD RATIO	FIELD RATIO	ELEV. ANGLE	ELEVATION RMS FIELD	CALL NEW-DALTON, GA.
		1	90'	0°	60'	0°	0.0	0.68	0		FREQUENCY 1530
		2	90'	N355°E							POWER 10
		3									TIME OF OPERATION MID-DAY
		4									TYPE OF OPERATION DA-2
		5									DAYTIME TOWERS 1 & 2
		6									NIGHTTIME TOWERS ---
		7									NO. RADIALS PER TOWER 120
		8									LENGTH OF RADIALS 160 ft.
		9									GROUND SCREEN DIMENSION ---
		10								LAT. 34° 47' 09"	
										LONG. 85° 02' 40"	
										SUPERSEDES 81963	
										PATTERN No. 121863	
FIGURE 4-8 HORIZONTAL PLANE PATTERN DAYTIME NON-CRITICAL HOURS OPERATION CHEROKEE BROADCASTERS DALTON, GA. NEW STANDARD STATION 1530KC 10KW-D(DA-2)											


WTTI

Measured Day
(9-28-65ct)

Station WTTI
Dalton, Georgia

10kw, DA-2, D
1530 kc

IC 10-19-65



$E_{RMS} = 599 \text{ mv/m}$

O= MEASURED RADIALS

LATITUDE: $34^{\circ}47'09''$
LONGITUDE: $85^{\circ}02'40''$

ANTENNA PARAMETERS

#2 $\uparrow$ N355°E
0.703 / 150°
G=90°
S=60°
#1 $\circ$ 1.00 / 0°

AMBROSE W. KRAMER
CONSULTING RADIO ENGINEER
WASHINGTON, D. C.

FIGURE-31
HORIZONTAL POLAR PATTERN
DAY, D.A.10 kw. DA-2
WTTI, BP-15105, DALTON
1530 kc/s.
June 1, 1965

FCC File No. BL-11037
Accepted 9-20-65

Station WTTI
Dalton, Georgia


1530 kc

WTTI

Measured Day (CH)
(9-28-65ct)

Station WTTI
Dalton, Georgia

10kw, DA-2, D
1530 kc



O = MEASURED RADIALS

E_{RMS} = 583 mv/m

LATITUDE: 34°47'09"
LONGITUDE: 85°02'40"

AMBROSE W. KRAMER
CONSULTING RADIO ENGINEER
WASHINGTON, D. C.

ANTENNA PARAMETERS

#2 N355°e
0.973 / 125°
G=90°
S=60°
#1 1.00 / 0°

FIGURE-33
HORIZONTAL POLAR PATTERN
CRITICAL HOURS, D.A.
WTTI, BP-15105, DALTON
1530 kc/s, 10 kw. DA-2
June 1, 1965

FCC File No. BL-11037
Accepted 9-20-65

Station WTTI
Dalton, Georgia

1530 kc



WTTI

Measured Non-DA
(9-28-65ct)

Station WTTI
Dalton, Georgia

10kw, DA-2, D
1530 kc

Lat; 34° 47' 09"
Long; 85° 02' 40"
NORTH TOWER USED



$E_{rms} = 425 \text{ mv/m}$

O = Measured Radials

X = Cross Radials

AMBROSE W. KRAMER
CONSULTING RADIO ENGINEER

FIGURE 29

Graph of N. D. A. Horizontal Polar Pattern


Radio Station W T T I - BP-15, 105

1530 kc/s, 10 kw D. A. D/C. H.

Dalton, Georgia

WYAZ

Measured Pattern
 Calculated Pattern
 Measured RMS 101 WVA



HORIZONTAL RADIATION PATTERN
 DIRECTIONAL
 RADIO STATION WYAZ
 1530 KHZ 0.25 KW DA-D
 YAZOO CITY, MISSISSIPPI

E. W. BIE
 MARCH, 1974


BL-18,027

WYAZ

Proposed Day
(8-22-69ct)

New; Gateway Broadcasting Co., Inc.
Yazoo City, Mississippi

250w, DA-D, D
1530 kc



FCC File No. BP-18027
Accepted 8-1-69 Amended


New; Gateway Broadcasting Co. Inc.
Yazoo City, Mississippi

1530 kc

Proposed Day
(5-27-69ct)

New; Integrated Broadcasting Co., Inc.
Jacksonville, Florida

50kw, DA-D, D
1530 kc



$E_{RMS} = 1850$

Engineer: Robert A. Bennis

LATITUDE: $30^{\circ} 21' 47.6''$
LONGITUDE: $81^{\circ} 45' 8.6''$

ANTENNA PARAMETERS

NO. 1	1.0	60°	S = 90°
NO. 2	.9	95°	G = 210°

N-0°-E
O NO. 2
S
O NO. 1

FIGURE 5

PROPOSED HORIZONTAL
PATTERN

INTEGRATED BROADCASTING

JACKSONVILLE

FLORIDA

FCC File No. BP-18493
Accepted 5-20-69



New; Integrated Broadcasting Co., Inc.
Jacksonville, Florida

1530 kc

Proposed Day
(4-29-70 Oct)

New; Central Dupage County Bcstg Co.
Wheaton, Illinois

500w, DA-D, D
1530 kc



PROPOSED RADIATION PATTERN
CENTRAL DUPAGE COUNTY B/C

1530 KC 0.5 KW DA-D
WHEATON, ILLINOIS

JULY, 1967

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE ILLINOIS



FCC File No. BP-16465 New; Central Dupage County Bcstg Co.
Hearing Reopened 2-11-70 Wheaton, Illinois

1530 kc

Proposed Day
(4-29-68ct)

New; Doyle Ray Flurry
Flora, Illinois

250w, DA-D, D
1530 kc



DIRECTIONAL RADIATION PATTERN			
Doyle Flurry			
☐ MEASURED	☒ PROPOSED		
FREQ 1530 (KHZ)	POWER 0.25 (KW)	☒ DA-D	
N. LAT. 38° 40' 59"		☐ DA-N	
W. LONG. 88° 29' 01"		☐ N-D	
LOCATION: Flora, Illinois			
DATE: March, 1968			
ROBERT A. JONES CONSULTING ENGINEERS LA GRANGE, ILLINOIS			

FCC File No. BP-18076
Accepted 4-17-68


New; Doyle Ray Flurry
Flora, Illinois

1530 kc

Proposed Day
(11-30-61ct)

New; Lancaster County B/C Co. 5kw, DA-D, D
Lincoln, Nebraska 1530 kc

5-1-63
painted CP
for new station
8-1-63
A D




$E_{RMS} = 395 \text{ MV/M}$

LATITUDE: $42^{\circ} 45' 00''$
LONGITUDE: $96^{\circ} 33' 56''$

CHARLES E. BRENNAN
CONSULTING RADIO ENGINEERS
MILWAUKEE, WISCONSIN

ANTENNA PARAMETERS



HORIZONTAL RADIATION PATTERN
LANCASTER BROADCASTING COMPANY
LINCOLN, NEBRASKA

1530 KC

5000 DA-D

610816

FIGURE 7

FCC File No. BP-15083
Accepted 9-20-61

New; Lancaster County B/C Co.
Lincoln, Nebraska

1530 kc

Proposed Day
(8-26-66ct)

New; Jupiter Associates, Inc. PA - 500w, DA-D, D
Matawan, New Jersey 1530 kc





FIGURE 4
CALCULATED HORIZONTAL PLANE PATTERN
JUPITER ASSOCIATES, INC.
MATAWAN, NEW JERSEY
1530KC. 0.5KW D, DA-D
BP-14178 DOC. 14755
MAY 1966

WILLIS C. BECKER
CONSULTING ENGINEER
WASHINGTON, D C

FCC File No. BP-14178
Accepted 8-2-66 Amended


New; Jupiter Associates, Inc.
Matawan, New Jersey

1530 kc

Proposed Day
(4-28-67ct)

New; Somerset County Broadcasting Co.
Somerville, New Jersey

1kw, DA-D, D
1530 kc



FCC File No. BP-14234
Reinstated 12-21-66

New; Somerset County Broadcasting Co.
Somerville, New Jersey

1530 kc

Description Sheet
(3-22-71ct)

Station XEUR
Texcoco, Edo. de Mexico

XEUR
5kw, DA-1, U, Class II
1530 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET
(Issued: March 22, 1971)

Station: XEUR Main Studio: Texcoco, Edo. de Mexico
Frequency: 1530 kHz Power: 5kw
Notification List No. (*) Date: (*) Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM: North Latitude: 19° 25' 45"
West Longitude: 98° 56' 57"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-1)
Number of elements: 4
Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	SW(#1)	NW(#2)	SE(#3)	NE(#4)
HEIGHT ABOVE INSULATORS:	179'	179'	179'	179' (100°)
PHASING:	0°	+84°	+67°	+122°
FIELD RATIO:	1	1	1	1

SPACING AND

ORIENTATION: The towers are located at the vertices of a parallelogram the long
sides of which are 304' (170°) in length on a line bearing 15.865°
true. The short sides are 214' (120°) in length on a line bearing
55.865° true.

GROUND SYSTEM: 90 equally spaced copper radials about each tower. Radials are
shortened and bonded to transverse straps along intersections
between towers.

Predicted effective field: 413.021 mv/m at rated power.


(*) FCC Note: Notification of basic information for this change in a Notifi-
cation List has not been received as of this issue date. Supple-
mentary information was transmitted by letter of March 10, 1971,
in accordance with provisional procedures for exchange of notifi-
cations established in a Memorandum of Understanding between the
Delegations of the United States and Mexico signed in Washington
on November 27, 1968.

CTR NO 20630A3

Proposed Day & Night
(3-22-71ct)

Station XEUR
Texcoco, Edo. de Mexico


XEUR
5kw, DA-1, U, Class II
1530 kc



PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/M A 1609 Mts.

ESQUEMA DE LAS TORRES Y SU ORIENTACION CON RESPECTO AL NORTE AZIMUTONICO.

AZIMUT
15° 51' 55"



RADIODIFUSORA

XEUR

TEXCOCO, Edo. Méx.

5,000 Wattz.
1530 KHz.

DISEÑO:

Cia. DYCE, S. de R. L.
Ing. Felipe Ruiz Gutierrez.
Alberto Torres Soto

DIBUJO

E. S. S. M. A.

XEUR

DESCRIPTION SHEET
(2-24-65ct)

Station XEUR
Mexico, D.F.

5kw, DA-1, U, Class II
1530 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET (Issued January 11, 1965)

Station: XEUR

Main Studio: Mexico, D.F.

Frequency: 1530 kc/s

Power: 5kw

Notification List No. (*)

North Latitude: 19° 25' 45"

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

West Longitude: 98° 56' 57"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-1)

Number of elements: 4

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

Tower:	#1(SW)	#2(NW)	#3(SE)	#4(NE)
Height above insulators:	178.81'	178.81'	178.81'	178.81'(100°)
Phasing:	0°	+50°	+72°	+122°
Field Ratio:	1	1	1	1

Spacing and

Orientation: The towers are located at the vertices of a parallelogram the long sides of which are 303.66'(170°) in length on a line bearing 355.867° true. The short sides are 214.35'(120°) in length on a line bearing 35.867° true.

Ground System: 90' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along inter-sections between towers. Centers of systems are bonded together.

Predicted effective Field: 402.234 mv/m at rated power.

*FCC Note: This "supplementary information" as defined in Annex VI of the U.S.-Mexico bilateral agreement was neither accompanied nor preceded by "basic information" as defined in Annex VI at the time it was received on January 11, 1965. In addition, the call letters and location specified involve conflicts with previous notifications. Pending clarification, therefore, this information is being issued for information purposes only.


XEUR

Proposed Day & Night
(2-24-65ct)

Station XEUR
Mexico, D.F.


5kw, DA-1, U, Class II
1530 kc

Hoja No. 2



PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/M A 1609 Mts

ESQUEMA DE LAS TORRES Y SU ORIENTACION
CON RESPECTO AL NORTE ASTRONOMICO.



RADIODIFUSORA

XEUR

TEXCOCO, Edo. de Méx.

1530 KHz.
5,000 Watts.

DISENO:

Cia. DYCE S. de R. L.
Ing. Felipe Ruiz Gutierrez.
Alberto Torres Soto.

DIBUJO:

E. SESMA

#169

CHFI

Description Sheet
(7-27-62ct)Station CHFI
Toronto, Ontario, Canada50kw, DA-D, D, Class II
1540 kcCORRECTED
DIRECTIONAL ANTENNA
DESCRIPTION SHEET

STATION: CHFI

MAIN STUDIO: Toronto, Ontario

FREQUENCY: 1540 KCS

POWER: 50 KW CLASS: II

Notification List No: 169

DATE: March 23, 1962.Geographical Location
of the Antenna System:North Latitude: 43° 35' 27"
West Longitude: 79° 39' 14"

ANTENNA CHARACTERISTICS

Mode of Operation:

DA/D

Number of Elements:

2

Type of Elements:

guyed, uniform cross-section, series
fed, no top loading

TOWERS:

NE

SW

HEIGHT OVER INSULATORS:

200' (115°)

200' (115°)

OVERALL HEIGHT:

205'

205'

SPACING

106.5' (60°)

PHASING:

-130°

+0

RATIO:

0.820

1.00

GROUND SYSTEM:


120 radials per tower 0.4 wavelengths
long, spaced 3° around tower base.
Radials bonded to common chord.PREDICTED EFFECTIVE FIELD: 220 MV/M for 1 KW
1855 MV/M for 50 KW

ORIENTATION:

035° True

NOTE: Please retain the antenna radiation pattern notified for station CHFI in Canadian Change List No. 169, dated March 23, 1962 and attach to this corrected description sheet. This only concerns corrections in the phasing and field ratio from that previously shown.



June 6, 1962.



#169

Station CHFI
Toronto, Ontario

50kw,DA-D,D,Class II
1540 kc



FORM FOR THE APPLICATION OF ARTICLE 4 OF THE AGREEMENT

1 2 4 24

CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

PART I GENERAL INFORMATION

01 Administration

CANADA

Sheet No. 422

Date 830824

Assigned frequency (kHz)		02	1 5 4 0
Transmitting station	Name of the station	03	T O R O N T O O N
	Call sign	04	C H I N
	Additional identification	05	
	Station class	06	B
	Operational Status	07	P
Country		08	CAN
Geographical coordinates of the transmitting station		09	79 W 2 2 5 0 4 3 N 3 6 5 5

11 a) New assignment ☐ b) Modification of characteristic of an assignment recorded in the plan ☒ c) Cancellation of an assignment ☐

12 Modification under Section 4.2.14 Yes ☐ No ☒

13 Date of bringing into service or cessation of operation
Year Month Day

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	21 5 0	31
r.m.s. value of radiation for station power (mV/m at 1 km)	25 2 1 7 8 . 2 5	35
Antenna type	26 B	36
Simple vertical antenna electrical height (degrees)	27	37

44 Remarks	COORDINATION UNDER ARTICLE 4:							
	COUNTRY	USA						
	IN PROGRESS	X						
	ACCEPTANCE OBTAINED							

PART IV

Description of the top-loaded or sectionalized towers used for :

- A) Directional antenna systems for towers entered in Part 11 Section I as top-loaded or sectionalized (column 12), or
- B) Non-directional antenna towers entered in Part 1 as top-loaded or sectionalized (column 26 or 36)

(01)	T	O	R	O	N	T							O	N
------	---	---	---	---	---	---	--	--	--	--	--	--	---	---

Name of transmitting station

02

N
A
C

Country

422

Sheet No.

50

Hours of Operation

1	2	4	2	4
---	---	---	---	---


IFRB Serial No.

[illegible]

CHINA
1540

CHIN
1540

FIGURE 1



FORM FOR THE APPLICATION OF ARTICLE 4 OF THE AGREEMENT
 CHARACTERISTICS OF A REGION 2 BROADCASTING STATION IN THE BAND 535 - 1605 kHz

12.424

DAY
 CHIN
 1540

PART I GENERAL INFORMATION

Ⓐ Administration

CANADA

Sheet No.

4/2

Date

82 05 04

Assigned frequency (kHz)		⓪2	1540
Transmitting station	Name of the station	⓪3	TORONTO
	Call sign	⓪4	CHIN
	Additional identification	⓪5	
	Station class	⓪6	
	Operational Status	⓪7	
		⓪8	CAN
Geographical coordinates of the transmitting station		⓪9	79W 39N 43N 352.7

⓪1 a) New assignment ☐ b) Modification of characteristic of an assignment recorded in the plan ☒ c) Cancellation of an assignment ☐

⓪12 Modification under Section 4.2.14 Yes ☐ No ☒

⓪13 Date of bringing into service or cessation of operation
 Year Month Day

STATION PARAMETERS	DAYTIME OPERATION	NIGHT-TIME OPERATION
Station power (kW)	⓪21	⓪31
r.m.s. value of radiation for station power (mV/m at 1 km)	⓪25	⓪35
Antenna type	⓪26	⓪36
Simple vertical antenna electrical height (degrees)	⓪27	⓪37

⓪44 Remarks

COORDINATION UNDER ARTICLE 4

COUNTRY

USA

IN PROGRESS

ACCEPTANCE OBTAINED

X

Sheet No. _____Hours of
operation[illegible]

Existing day operation. Planned night operation in Rio de Janeiro Plan is at different site.



KASA

PROPOSED DAY
(9-20-61ct)

New; Eastside Broadcasting Co.
Phoenix, Arizona

10kw, DA-D, D
1540 kc

#200
8-13-64
printed copy
for new station



G = 90°
GS = 120 ± 90°

Lat 33° 22' 36"
Long 112° 05' 25"

EXHIBIT E-2

PROPOSED NEW STATION
1540 kc 10 kw DA-D
PHOENIX, ARIZONA

ARCHER S. TAYLOR
CONSULTING RADIO ENGINEER
PO BOX 1478
MISSOULA, MONTANA

JUNE 1961

FCC File No. BP-15022
Accepted 8-23-61

New; Eastside Broadcasting Co.
Phoenix, Arizona

1540 kc


KAS

Proposed Day Nulls
(12-29-66ct)

Station KASA
Phoenix, Arizona

10kw, DA-D, D
1540 kc

12-21-66
GRANTED
MODIFICATION
OF CP
TO SPECIFY
MEOV'S.




FCC File No. BMP-11937
Accepted 12-5-66

Station KASA
Phoenix, Arizona

1540 kc

KASA

Measured Day
(2-28-67ct)Station KASA
Phoenix, Arizona10kw, DA-D, D
1540 kcNorth Latitude $33^{\circ} 22' 36''$
West Longitude $112^{\circ} 05' 25''$ BL-11560
GRANTED
LICENSE
-OV. NEW
FM STATION
4-12-67

MALARKEY, TAYLOR & ASSOCIATES
FCC File No. BL-11560
Accepted 2-20-67

Station KASA
Phoenix, Arizona

KEUFFEL & ESSER CO., N. Y. NO. 343A
POLAR CO-ORDINATE

1540 kc


KASA

Measured Non-DA
(2-28-67ct)

Station KASA
Phoenix, Arizona

10kw, DA-D, D
1540 kc

BL-11560
GRANTED
LICENSE
4-12-67



MALARKEY, TAYLOR & ASSOCIATES

FCC File No. BL-11560
Accepted 2-20-67

Station KASA
Phoenix, Arizona

KEUFFEL & ESSER CO., N. Y. NO. 343A
POLAR CO-ORDINATE


1540 kc

KBUY ~~KCUL~~

Measured Night
(9-28-66ct)

Station KCUL
Fort Worth, Texas

1kw, 50kw-LS, DA-2, U
1540 kc



FCC File No. BZ-6059
Accepted 8-31-66

Station KCUL
Fort Worth, Texas


FIGURE 2B
1540 kc

KBUY ~~KCUL~~

Measured Non-DA
(9-28-66ct)

Station KCUL
Fort Worth, Texas

1kw, 50kw-LS, DA-2, U
1540 kc



FCC File No. BZ-6059
Accepted 8-31-66

Station KCUL
Fort Worth, Texas

FIGURE 2A
1540 kc


KBUY

~~KCUL~~

Measured Night Nulls
(9-28-66ct)

Station KCUL
Fort Worth, Texas

1kw, 50kw-LS, DA-2, U
1540 kc



FCC File No. BZ-6059
Accepted 8-31-66

Station KCUL
Fort Worth, Texas

FIGURE 2C

1540 kc


over

KBUY ~~KCUL~~

MEASURED DAY
(5-8-61g)

Station KCUL
Fort Worth, Texas

1kw, 50kw-LS, DA-2, U
1540 KC



FCC File No. BL-8318
Accepted 5-1-61

KCUL
Fort Worth, Texas


1540 KC

KBUY ~~KCUL~~

MEASURED NON-DA
(5-8-61g)

Station KCUL
Fort Worth, Texas

1kw, 50kw-LS, DA-2, U
1540 KC



North Latitude 32° 39' 05"
West Longitude 97° 11' 38"

Figure 3
MEASURED ONE KILOWATT
NON-DIRECTIONAL HORIZONTAL
RADIATION PATTERN
KCUL 1540 KC Ft. Worth, Texas
50,000 Watts Day 1,000 Watts Night
DA 2

FCC File No. BL-8318
Accepted 5-1-61

KCUL
Fort Worth, Texas 1540 KC


KBUY KCUL

PROPOSED DAY
(6-17-60g)

Station KCUL
Fort Worth, Texas

1kw, 50kw - LS, DA-2, U
1540 KC

*no
points met
from
DA*



N 6.7° E

1.0/-32°
1.96/8.3°
1.0/+22°

FIGURE IV
DATE: NOVEMBER 17, 1960
BY: W. L. FORD, INC.
FOR: KCUL, 50 KW-DAY, DA-2, FORT WORTH, TEXAS

WILLIAM L. FORD, INC.
Electronic Consultants
WASHINGTON, D. C.
927 1st Street, N.W. NE 20002

PATTERN NO
SUPERSEDES
APP.

FCC File No. BMP-9011
Accepted 6-13-60

KCUL
Fort Worth, Texas

1540 KC




FIGURE 6B (AMENDED)

NIGHT HORIZONTAL
RADIATION PATTERN

EAST-WEST BROADCASTING COMPANY
FORT WORTH, TEXAS

1KW (5KW-L) UDA MAR. 1947 1540 KC/S




FIGURE 7B (AMENDED)

NIGHT EXPANDED HORIZONTAL
RADIATION PATTERN

EAST-WEST BROADCASTING COMPANY
FORT WORTH, TEXAS

1KW(5KWLS) UDA MAR 1947 1540 KC/S

KCU
1540

KBU

FT. WORTH, TEXAS

NORTH BAHAMAS 1180 MI
NASSAU 1180 MI
SOUTH BAHAMAS 1180 MI
BAYTON ROUGE 1180 MI
NEW ORLEANS 1180 MI

GALVESTON 200 MI

KCU 1180 MI
KBU 1180 MI

KBUY KCUL


MEASURED
NIGHT

KCUL, FORT WORTH, TEXAS

9-16-49

1kw, 5kw-LS, DA1

1540 kc



KCUL, Fort Worth, Tex. 1540 kc

OVER

KBUY ~~KCUL~~

MEASURED
NIGHT NULLS


KCUL, FORT WORTH, TEXAS

9-16-49

1kw, 5kw-LS, DA1

1540 kc

9/22/49G



OVER

KBVU


Measured Day & Night
(4-24-64ct)

Station KBVU
Bellevue, Washington

1kw, DA-1, U
1540 kc

MEASURED HORIZONTAL
RADIATION PATTERN

KBVU 1540 KC 1KW
DA-1
BELLEVUE,
WASHINGTON



FCC File No. BL-10466
Accepted 3-26-64

Station KBVU
Bellevue, Washington

1540 kc


KBVU

PROPOSED NIGHT & DAY Northwest B/C, Inc. 1 KW, DA-1
(DA-1) (1-29-57g) Bellevue, Washington

1540 K C

Fig. 7a
Horizontal Radiation Pattern
Proposed Radio Station
Northwest Broadcasters, Inc.
Bellevue, Washington
1540kc 1 kw DA-1
December, 1956

PAGE. CREUTZ, STEEL & WALDSCHMITT, INC.
COMMUNICATIONS BUILDING
710 FOURTEENTH STREET, NORTHWEST
WASHINGTON 5, D C



FCC File No. BP-10,521 Accepted 1-10-57

Northwest B/C Co.
Bellevue, Washington 1540KC

6-21-61
revised CP
5-13-63 MCP
revised for
WL: 47-35-57
WL: 122-11-17


8-12-63
mod. of CP
submitted

KBVU

Measured Non-DA-
(4-24-64ct)

Station KBVU
Bellevue, Washington

1kw, DA-1, U
1540 kc



FCC File No. BL-10466
Accepted 3-26-64

Station KBVU
Bellevue, Washington

1540 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KEDA Main Studio: San Antonio, Texas
 Frequency: 1540 Power: 1kw Night 5kw Day
 Notification List No. 1783 Date: November 2, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: , North Latitude: 29° 21' 30"
 West Longitude: 98° 21' 05"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
 Number of elements: 6
 Type of elements: Series excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	SE(#1)	EC(#2)	NE(#3)	SW(#4)	WC(#5)	NW(#6)
HEIGHT ABOVE INSULATORS:	160'	160'	160'	160'	160'	160' (90.2°)
NIGHT PHASING:	102.5°	0.0°	-101.4°	-19.5°	-122°	136.6°
NIGHT FIELD RATIO:	0.65	1.0	0.45	0.57	0.87	0.39
DAY PHASING:	---	100°	---	140°	0.0°	---
DAY FIELD RATIO:	---	0.9	---	0.4	1.0	---

SPACING AND
ORIENTATION:

The towers are located in two parallel rows with 3 towers per row. Adjacent towers in a row are spaced 558.85' (315°) on a line bearing 3° true. End towers forming a side of the parallelogram are spaced 159.67' (90°) on a line bearing 304° true.

GROUND SYSTEM: 120-160' equally spaced copper radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	426.6 mv/m	458.2 mv/m	448.2 mv/m
Night	188.6 mv/m	254.3 mv/m	198.1 mv/m

KEDA
1540 kHz
DA-2

North Lat. 29° 21' 30"
West Long. 98° 21' 05"





FIGURE 1

PROPOSED DAYTIME HORIZONTAL PLANE
STANDARD RADIATION PATTERN

STATION KEDA
D & E BROADCASTING CO., INC.
SAN ANTONIO, TEXAS

Pres. 1540 kHz	1 kW	DAY
Prop. 1540 kHz	5 kW-D; 1 kW-N	DA-2

A. D. RING & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

1540 kHz

DA-2

North Lat. 29° 21' 30"
West Long. 98° 21' 05"





FIGURE 2

PROPOSED NIGHTTIME HORIZONTAL PLANE
STANDARD RADIATION PATTERN


STATION KEDA
O & E BROADCASTING CO., INC.
SAN ANTONIO, TEXAS

Pres. 1540 kHz 1 kW DAY
Prop. 1540 kHz 5 kW-D; 1 kW-N DA-2

A. D. RING & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

KE-1A
1540 kHz
DA-N

FIGURE 3-A



KFKF


Proposed Day
(12-27-68ct)

Station KFKF
Bellevue, Washington

25kw, DA-2, U
1540 kc

THE ENCL. DIAGRAM CO.
MADE IN U. S. A.

NO. 1000 DUE TO IN. 2000 1000 1000
POLAR COORDINATE



FCC File No. BP-18308
Accepted 12-11-68

Station KFKF
Bellevue, Washington

1540 kc

KFKF


Proposed Night
(12-27-68ct)

Station KFKF
Bellevue, Washington

25kw, DA-2, U
1540 kc

CURVES BETWEEN
1000 AND 1400

CURVES BETWEEN
1000 AND 1400



J. B. HATFIELD
CONSULTING RADIO ENGINEER
806 36TH AVENUE
SEATTLE, WASHINGTON 98122

1540 K.C. U., DA-2 25 K.W.-3
BELLEVUE, WASHINGTON
JUNE 1968

FCC File No. BP-18308
Accepted 12-11-68

Station KFKF
Bellevue, Washington

1540 kc


KFKF

Proposed Day & Night
(2-28-66ct)


Station KFKF
Bellevue, Washington

1kw, DA-1, U
1540 kc

8-8-67 CP
GRANTED
FOR A STANDARD
BROADCAST STATION



HORIZONTAL RADIATION PATTERN



G = 90°

APPL CANT	BELLEVUE BROADCASTERS
LOCATION	BELLEVUE, WASHINGTON
FREQUENCY	1540 KC/S
POWER	1 KW, DA-1
LATITUDE	47 DEG 35 MIN 40 SEC
LONGITUDE	122 DEG 10 MIN 56 SEC
WHEN USED	UNLIMITED
RMS FIELD	190 MV/M
DATE	DECEMBER 1965

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-17059
Accepted 2-7-66

Station KFKF
Bellevue, Washington

1540 kc


KFKF

Proposed Day & Night Nulls
(2-28-66ct)

Station KFKF
Bellevue, Washington

1kw, DA-1, U
1540 kc

8-8-67 C.P.
PRINTED
FOR A STATION
BROADCAST
STATION



EXPANDED VIEW

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-17059
Accepted 2-7-66

Station KFKF
Bellevue, Washington

1540 kc

KFKF

Measured Day & Night
(2-28-69ct)

Station KFKF
Bellevue, Washington

1kw, DA-1, U
~~1450~~ kc
1540

BRC-3325
Granted
(4-9-69)
~~modification of~~
~~license~~

RMS = 197 mV

PARTIAL RE PROOF OF FIELD STRENGTH

MEASURED HORIZONTAL ACCELERATION
FOR STATION KFKF, BELLEVUE, WASHINGTON
~~1450~~ KC, 1.0 RM, DA-1, U, 1540
JANUARY 1969

FCC File No. BRC-3325
Accepted 2-24-69

Station KFKF
Bellevue, Washington

~~1450~~ kc
1540

KFKF

Measured Non-DA
(1-29-68ct)


Station KFKF
Bellevue, Washington

1kw, DA-1, U
1540 kc

OVER

EUDENE DIETZGEN CO.
MADE IN U. S. A.

NO. 340-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE




FCC File No. BL-11785
Accepted 1-16-68

Station KFKF
Bellevue, Washington

1540 kc


1540
NIGHT

--- M.E.O.V.



RMS = 96.3 MV/M

PATTERN 470117



TOWER FIELD PHASE

1	1.0	0°
2	0.4	-75°

S = 160° OR 284'

G = 117°

A. EARL CULLUM, JR.

CONSULTING RADIO ENGINEERS
DALLAS TEXAS

RADIO STATION KGBC

1540 KC 250 WATTS DA

FIGURE 5A

Spent 40 days change antenna & tower
Location new covered; NL 29-10-57
WL 94-48-16

Proposed night

KGBC



MEASURED NIGHT
(4-22-60g)

Station KGBC
Galveston, Texas

250w, 1kw-LS, DA-N,U
1540 KC

LAT. 29° 18' 51"
LONG. 94° 48' 16"

NIGHT



TOWER	FIELD	PHASE
1	1.0	0
2	0.4	-75

PATTERN BASED ON MEASUREMENTS

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KGBC
GALVESTON, TEXAS
591229

FIGURE 2 B

FCC File No. BL-7865
Accepted 3-30-60

KGBC
Galveston, Texas

1540 KC

11-14-60 granted for change
in antenna & mile studies location

KGBC


MEASURED NON-DA
(4-22-60g)

Station KGBC
Galveston, Texas


250w, 1kw-LS, DA-N,U
1540 KC

LAT. 29° 18' 51"
LONG. 94° 48' 16"

DAY



7-14-60 printed & for change in
Antenna, Unit & studied location



TOWER	OPERATION
1	DETUNED
2	SERIES FED

PATTERN BASED ON MEASUREMENTS

PREPARED BY
THE FIRM OF A. EARL CULLUM, JR.
CONSULTING ENGINEERS

RADIO STATION KGBC
GALVESTON, TEXAS
591229
FIGURE 2 A

FCC File No. BL-7865
Accepted 3-30-60

KGBC
Galveston, Texas

1540 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: K K A P Main Studio: Aptos-Capitola, California
 Frequency: 1540 kHz Power 10 kW Day
 Notification List No. 1784 Date: November 9, 1979 Class: II

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 36° 58' 50"
 West Longitude: 121° 34' 43"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)
 Number of elements: 2
 Type of elements: Series excited, guyed, tapered,
 vertical steel towers.

TOWER:	S (#1)	N (#2)
HEIGHT ABOVE INSULATORS:	162' (91.3°)	162'
DAY PHASING:	0°	60°
DAY FIELD RATIO:	1.000	1.863
SPACING AND ORIENTATION:	The towers are spaced 223.9' (126.2°) on a line bearing 25° true.	

GROUND
 SYSTEM: 120-150' equally spaced copper radials about each tower.
 Radials are shortened and bonded to a transverse strap
 along intersections between towers.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL	STANDARD
	<u>RMS</u>	<u>RMS</u>
Day <u>1/</u> 594/78 mV/m	581.73 mV/m	624.84 mV/m

1/ By adjustment of input power.

GRANT E. WHITFIELD
Consulting Radio Engineer
APTOS, CALIFORNIA

KZAP
1540 KHz



KMFO
1540KHz
DA-D

GRANT R. WEAVER

Cumulative Radio Engineer

ARTOS, CALIFORNIA

N
-25°
126.25°
1.353 1.350°
94.3°
G = 4.45
1.0 LC°




FIG. 1A

DAYTIME STANDARD

RADIATION PATTERN

KMFO

1540 KHz 10 dB DA-D

Artos-Capitol, Calif.
(0° ABOVE HORIZONTAL)

1.353 1.350 mW/M² (Theoretical)
1.353 1.350 mW/M² (Standard)
1.353 1.350 mW/M²

150° 160° 170° 180° 190° 200° 210°
210° 200° 190° 180° 170° 160° 150°

KMPG

Proposed Day
(9-26-68ct)

Station KMPG
Hollister, California

5kw, DA-D, D
1540 kc




FIG.1


PROPOSED HORIZONTAL RADIATION
KMPG HOLLISTER, CALIFORNIA
1540 KC 5.0 KW DA-D

A.E.Towne Associates Inc., Consulting Engineers, San Carlos, California

KXEL

MP-1524

KXEL
1546



KXEL


MP-1524

KXEL
1540

PAUL F GOOLEY
MONTCLAIR, N.J.
FEB. 1942

FIG. 2

HORIZONTAL PLANE PATTERN
IN REGION OF MINIMUM
PROPOSED STATION
WATERLOO, IOWA
1540 KC. - D.A. - 50 KW.
2 ELEMENT ARRAY - SPACED 125°
PHASED 76°
CURRENTS 1:1




KEUFFEL & ESSER CO. N. Y. NO. 3438
POLAR CO-ORDINATE
SCALE NO. 34

1340 KC
KXEL

ENGINE DIVISION
JUL 13 1942


W. H. DIETZEN SPARK PAPER
CLEAR FOR DATE



WEASURED HORIZONTAL PATTERN
KXEL WATERLOO IOWA
50,000 Watts D.A. 1540 KC
spaced 125°
phased 76°

A. James Ebel
November 1942

1540 KC
KXEL



EXPANDED
MEASURED HORIZONTAL PATTERN
KXEL WATERLOO IOWA
50,000 Watts D.A. 1540 KC
spaced 125°
phased 76°

A. James Ebel
November 1942

EUGENE DIETZEN CO.

EUGENE DIETZEN GRAPH PAPER
POLAR CO-ORDINATE

KZAM

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KZAM Main Studio: Bellevue, Washington
 Frequency: 1540 kHz Power: 5 kW
 Notification List No. 1637 Date: June 18, 1975 Class: II

GEOGRAPHICAL LOCATION OF THE
 CENTER OF THE ANTENNA SYSTEM: North Latitude: 47° 35' 28"
 West Longitude: 122° 10' 56"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N) MODIFIED STANDARD
 Number of elements: 3 PATTERN
 Type of elements: Series-excited, uniform cross-section,
 guyed, vertical steel towers.

TOWER:	W(#1)	C(#2)	E(#3)
HEIGHT ABOVE INSULATORS:	160'	160'	160' (90°)
PHASING:	-90°	0°	+90°
FIELD RATIO:	0.5	1	0.5

SPACING AND
 ORIENTATION: Adjacent elements are spaced 160' (90°) on a line bearing
 276° true.

GROUND SYSTEM: 120-160' equally spaced copper radials plus a 24' square
 ground screen about each tower. Radials are shortened
 and bonded to transverse straps along intersections between
 towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	RMS	RSS	RMS
Daytime	426 mv/m	---	---
Nighttime	439.2 mv/m	418.5 mv/m	460.09 mv/m


MODIFIED PATTERN AUGMENTATION:

Azimuth of Maximum Augmentation	Augmented Radiation	Span of Augmentation	
	E ₂	From	To
116°	22.0 mv/m	26°	206°

Note: This notification concerns a change to augment the standard pattern.

CTR NO 30390A4

KZAM



9° indicates augmentation span limits (260 to 206°). Maximum augmentation occurs at 116°.

HATFIELD & DAWSON
 CONSULTING ENGINEERS
 APRIL 1975

Field values computed prior to augmentation are depicted by a broken line.

EXPANDED SCALE

THEORETICAL PATTERN RMS = 418.5 MV/M
 THEORETICAL PATTERN RMS = 439.2 MV/M

STANDARD RMS PRIOR TO AUGMENTATION = 460.09 MV/M

FIGURE ONE

NIGHTTIME HORIZONTAL PLANE
 MODIFIED STANDARD PATTERN

KZES 1540 kHz 5kW DA-N
 BELLEVUE, WASHINGTON

MODIFIED STANDARD HORIZONTAL
 PLANE PATTERN RMS = 461.7 MV/M

DL-13,997

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KBES

Main Studio: Bellevue, Washington

Frequency: 1540 kHz

Power: 5 kW

Notification List No. 1567

Date: February 13, 1974

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 47° 35' 28"

West Longitude: 122° 10' 56"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 3

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	W(#1)	C(#2)	E(#3)
HEIGHT ABOVE INSULATORS:	160'	160'	160' (90°)
PHASING:	-90°	0°	+90°
FIELD RATIO:	0.5	1	0.5

SPACING AND

ORIENTATION: Adjacent elements are spaced 160' (90°) on a line bearing
276° true.GROUND SYSTEM: 120-160' equally spaced copper radials plus a 24' square
ground screen about each tower. Radials are shortened and
bonded to transverse straps along intersections between towers.

THEORETICAL


STANDARD

	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Daytime	426 mv/m	---	---
Nighttime	439.2 mv/m	418.5 mv/m	469.09 mv/m

CTR NO 30390A3



JUNE 1973



LAT. 47° 35' 28.5"
LONG. 122° 10' 56"


FIG. 2-A
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(HORIZONTAL PLANE)

KBES 1540KHz 5KW DA-N

BELLEVUE EASTSIDE RADIO, LTD
BELLEVUE, WASHINGTON



JUNE 1973



N 276° E ← .5/-90° 1/0° 90° 50° .5/90°
G=90°


FIG. 2-B
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(5° ABOVE HORIZONTAL)

KBES 1540KHz 5KW DA-N

BELLEVUE EASTSIDE RADIO, LTD.
BELLEVUE, WASHINGTON



JUNE 1973



N 276° E ← 5/90° — 90° — 1/0° — 30° — 5/90°
G = 90°


FIG. 2-C
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(10° ABOVE HORIZONTAL)

KBES 1540KHz 5KW DA-N

BELLEVUE EASTSIDE RADIO, LTD.
BELLEVUE, WASHINGTON



JUNE 1975




N 276° E ← .5/-90° 90° 1/0° 90° .5/90°
G=90°

FIG. 2-K
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(50° ABOVE HORIZONTAL)
KBES 1540KHz ~ 5KW DA-N
BELLEVUE EASTSIDE RADIO, LTD
BELLEVUE, WASHINGTON

LZAM



JUNE 1973



N 276° E ← 5/90° 1/0° 90° 90° 5/90°
G=90°

FIG. 2-L
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(55° ABOVE HORIZONTAL)

KBES 1540KHz 5KW DA-N

BELLEVUE EASTSIDE RADIO, LTD
BELLEVUE, WASHINGTON

Standard Pattern

KZAM



JUNE 1973





FIG. 2-M
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(60° ABOVE HORIZONTAL)

KBES 1540KHz 5KW DA-N

BELLEVUE EASTSIDE RADIO, LTD.
 BELLEVUE, WASHINGTON



JUNE 1973



N 270° E
 5/90°
 1/0°
 5/90°
 G=50°

FIG. 2-D

PROPOSED NIGHTTIME STANDARD
 RADIATION PATTERN
 (15° ABOVE HORIZONTAL)

KBES 1340KHz 5KW DA-N

BELLEVUE EASTSIDE RADIO, LTD
 BELLEVUE, WASHINGTON



JUNE 1973




FIG. 2-E

PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(20° ABOVE HORIZONTAL)

KBES

1540KHz


5KW

DA-N

BELLEVUE EASTSIDE RADIO, LTD.
BELLEVUE WASHINGTON



JUNE 1973



N 276° E
 $\frac{5}{1} - 90^\circ$
 90° — $\frac{1}{10}^\circ$ — 90° — $\frac{5}{90}^\circ$
 G = 90°

LAT. 47° 35' 40"
 LONG. 122° 10' 56"


FIG. 2-F
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(25° ABOVE HORIZONTAL)

KDES 1540KH: 5KW DA-N

BELLEVUE EASTSIDE RADIO, LTD.
 BELLEVUE, WASHINGTON



JUNE 1973



N 275° E — 5/90° — 30° — 1/0° — 30° — 5/90°
G = 90°


FIG. 2-G
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(30° ABOVE HORIZONTAL)

KBES 1540KHz 5KW DA-N

BELLEVUE EASTSIDE RADIO, LTD.
BELLEVUE, WASHINGTON



JUNE 1973



N 276° E ← 5/90° — 1/0° — 5/90°
G-90°

FIG. 2-H
PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(35° ABOVE HORIZONTAL)
 KBES 1540KHz 5KW DA-N
 BELLEVUE EASTSIDE RADIO, LTD
 BELLEVUE, WASHINGTON



JUNE 1973




FIG. 2-I

PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(40° ABOVE HORIZONTAL)

KBES

1540 KHz

5 KW

DA-N

BELLEVUE EASTSIDE RADIO, LTD.
BELLEVUE, WASHINGTON



JUNE 1973




FIG. 2-J

PROPOSED NIGHTTIME STANDARD
RADIATION PATTERN
(45° ABOVE HORIZONTAL)

KBES

1540KHz

5KW

DA-N

BELLEVUE EASTSIDE RADIO, LTD.
BELLEVUE, WASHINGTON

KZLA

KPOL

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KPOL

Main Studio: Los Angeles, California

Frequency: 1540 kHz

Power: 10 kW Night 50 kW Day

Notification List No. 1676

Date: March 19, 1976

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 34° 04' 43"

West Longitude: 118° 11' 05"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 3

Type of elements: Series-excited, uniform cross-section, guyed
vertical steel towers.

TOWER:	W(#3)	C(#2)	E(#1)
HEIGHT ABOVE INSULATORS:	250'	250'	250' (141°)
NIGHT PHASING:	-105°	0°	+105°
NIGHT FIELD RATIO:	0.49	1.0	0.49
DAY PHASING:	-122°	0°	+135°
DAY FIELD RATIO:	0.325	1.0	0.325

SPACING AND

ORIENTATION: Adjacent elements are spaced 159.5' (90°) on a line bearing
255° true.GROUND SYSTEM: 120-200' equally spaced copper radials about each tower.
Radials are shortened and bonded to transverse straps along
intersections between towers.


Predicted effective Night Field: 552 mv/m at rated power.

Predicted effective Day Field: 1425.5 mv/m at rated power.

Note: Please retain the Daytime directional antenna radiation pattern notification for station KPOL in United States Change List Number 895 dated February 8, 1961, and attach to this Revised Description Sheet and Nighttime patterns. This notification concerns only a change in the Nighttime operation of the station with Daytime operation continued as previously notified.


CTR NO 31212A4

KPOL



ANTENNA NO.	1	2	3
FIELD	0.49	1.0	0.49
PHASE	105°	0°	-105°
SPACING	0°	90°	180°
ORIENTATION	0°	255°	255°
HEIGHT	141°	141°	141°

N. LAT.	34° 4' 43"
W. LONG.	118° 11' 5"
RMS STD	mv/m
RMS TH	650 mv/m



KZLA KPOL


PROPOSED DAY
(7-29-60g)

Station KPOL
Los Angeles, California

10kw, 50kw-LS, DA-2, U
1540 kc

V=0°

2-8-61
printed copy
sent to DA-2



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA			
90° = 159.5' AT 1540 KC.		TOWER NO.	ELECTRICAL HEIGHT ft	TRUE TOWER OBSERVATION ft	SPACING ft	PHASING °	HORIZONTAL FIELD dBu	FIELD RATIO F	ELEV. ANGLE °	ELEVATION dBu	CALL	KPOL	
		1	141	0	0	0	1425.5	1.0	0	1316	FREQUENCY	1540	
		2	141	75	90	+135		0.325	10		POWER	50	
		3	141	255	90	-122		0.325	20		TIME OF OPERATION	UNLIMITED	
		4								30		TYPE OF OPERATION	DA-2
		5								40		DAYTIME TOWERS	3
		6								50		NIGHTTIME TOWERS	3
		7								60		NO RADIALS PER TOWER	120
		8								70		LENGTH OF RADIALS	112 - 200 ft
		9								80		GROUND SCREEN DIMENSION	
10								90		LAT	34° 04' 43"		
										LONG	118° 11' 06"		
										SUPERSEDES NOVEMBER, 1958			
										PATTERN NO.			

EXHIBIT NO. 1
(AMENDED)

RADIO STATION KPOL — LOS ANGELES
PROPOSED 50 KW — DA — DAY — 1540 KC

JUNE
1960

FCC File No. BP-12770
Accepted 7-21-60 (Amended)

KPOL
Los Angeles, California

1540 kc



KPOL

Measured Day
(4-27-62ct)

Station KPOL
Los Angeles, California

10kw, 50kw-LS, DA-2, U
1540 kc

5.17.62
Granted L covering
increase in day power
and change to DA-2



FCC File No. BL-9083
Accepted 4-6-62

Station KPOL
Los Angeles, California

1540 kc

KPOL


KPOL

PROPOSED NIGHT
(3/22/55G)

STATION KPOL
LOS ANGELES, CALIFORNIA

10 KW
DA-N, U

1540 KC



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS						STATION DATA		
		1	2	3	4	5	6	7	8	9
W. ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	PHASE	HORIZONTAL FIELD	FIELD RATIO	ELEVATION ANGLE	TRANS FIELD	CALL	KPOL	
141	0	0	0	552	1.0	0	650	FREQUENCY	1540	
141	75	90	+105		0.49	10		POWER	10	
141	250	90	-105		0.49	20		TIME OF OPERATION	NIGHT	
						30		TYPE OF OPERATION	DA	
						40		DAYTIME TOWERS	1	
						50		NIGHTTIME TOWERS	3	
						60		NO. PACKS PER TOWER	120	
						70		LENGTH OF RADIALS	112	
						80		GROUND RISE CONTINUOUS	200	
						90		AT	34	
						100		LONG	118	
						110		SHORT	11	
						120		SUPRESEDES	06	
						130		ATTENUES		

EXHIBIT NO. I-A

RADIO STATION KPOL LOS ANGELES

PROPOSED 10 KW-DA-NIGHT — 1540 KC

OCTOBER 1954

KPOL

MEASURED NIGHT
(4/24/57g)

Station KPOL
Los Angeles, California

10kw, DA-N, U
1540 KC

*Granted license
6/10/57 for
DA-N*




FIGURE NO 13

PATTERN BASED ON FIELD INTENSITY MEASUREMENTS
STATION KPOL 1540 KC - 10 KW - NIGHTTIME DA-N
LOS ANGELES, CALIFORNIA
SEPTEMBER - 1956

T & T RADIO MEASUREMENTS CO.

3821 ATLANTIC AVENUE
LONG BEACH 2, CALIFORNIA



Radio Engineering Consultants

FCC File No. BL-6588
Accepted 4/15/57

KPOL
Los Angeles, California



1540 KC

KZLA KPOL

Measured Non-DA
(4-27-62ct)

Station KPOL
Los Angeles, California

10kw, 50kw-LS, DA-2, U
1540 kc



FCC File No. BL-9083
Accepted 4-6-62

Station KPOL
Los Angeles, California

1540 kc


WBCO

Measured Day
(6-27-69ct)


Station WBCO
Bucyrus, Ohio

500w, DA-D, D
1540 kc

36-12383
wanted
1/2/69
license
selling
changes



HORIZONTAL RADIATION PATTERN



APPLICANT	WBCO
LOCATION	Bucyrus, Ohio
FREQUENCY	1540 KHZ
POWER	500 W
VELOCITY	40 DEG 40 MIN 40 SEC
LONGITUDE	90 DEG 0 MIN 00 SEC
WHEN USED	10/1/69
NAME FIELD	10/1/69
DATE	MAY 1969

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-12383
Accepted 6-16-69

Station WBCO
Bucyrus, Ohio

1540 kc


WBCO

Measured Non-DA
(6-27-69ct)

Station WBCO
Bucyrus, Ohio

500w, DA-D, D
1540 kc

BL-12383
Granted
8/12/69
license
pending
change



○ MEASURED RADIAL VALUES

FIGURE 1-B

HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT	WBCO
LOCATION	BUCYRUS, OHIO
FREQUENCY	1540 KHZ
POWER	0.5 KW (500 W)
LATITUDE	40 24 45 MIN 47 SEC
LONGITUDE	82 07 50 MIN 05 SEC
WHEN USED	NON-DIRECTIONAL SURVEY
RMS FIELD	100 mV/m
DATE	MAY, 1969

SULLIVAN, MURPHY & KNEISLEY
CONSULTING RADIO ENGINEERS
WASHINGTON, DC

FCC File No. BL-12383
Accepted 6-16-69

Station WBCO
Bucyrus, Ohio

1540 kc

1540 kc


WBCO

Proposed Day Nulls
(2-28-69ct)

Station WBCO
Bucyrus, Ohio

500w, DA-D, D
1540 kc

BP-18440
Granted
2-11-69
IP to
make changes
in daytime
directional
antenna
system



EXPANDED VIEW

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-18440
Accepted 2-7-69

Station WBCO
Bucyrus, Ohio

1540 kc

Niles, Ohio


WNIO

PROPOSED DAY
(4-22-60R)


New: The Niles B/C Co.
Niles, Ohio

500w, DA-D.D
1540 KC

4-11-63
granted application for
new AM station



CARL E. SMITH
CONSULTING RADIO ENGINEERS

TOWER PLACEMENT SKETCH		PATTERN PARAMETERS										STATION DATA	
		POWER	ELECTRICAL	TRUE	SPACING	PHASING	HORIZONTAL	FIELD	ELEV	SITUATION	CALL	NEW FREQUENCY 1540 POWER 0.5 TIME OF OPERATION DA-D TYPE OF OPERATION CLASS II DAYTIME TOWERS 3 NIGHTTIME TOWERS NO RADIALS PER TOWER 120 LENGTH OF RADIALS 90 x 160 GRO. WAVE DIMENSIONS 24x24 LAT 41 07 56 LONG 80 45 40 SUPERSEDES PATTERN NO 600130	
		W	C	D	S	P	E	R	A	S			
		1	90	0	0	5	105.9	1.9	0	127			
		2	90	75	158	62	55.7	1.0	10				
		3	90	255	158	62	55.7	1.0	20				
		4							30				
		5							40				
		6							50				
		7							60				
		8							70				
		9							80				
		10							90				
DAYTIME OPERATION ☒		NIGHTTIME OPERATION ☐											

THE NILES B/C CO.
NILES, OHIO

FIG. 3
HORIZONTAL PATTERN


WN10

Measured Day
(2-28-64ct)


Station WN10
Niles, Ohio

500w, DA-D, D
1540 kc

8/6/64
checked
and OK
for station



HORIZONTAL RADIATION PATTERN



APPLICANT	WN10
LOCATION	NILES, OHIO
FREQUENCY	1540 KC/S
POWER	0.5 KW DA-D
LATITUDE	41 DEG 07 MIN 56 SEC
LONGITUDE	80 DEG 45 MIN 40 SEC
WHEN USED	DIRECTIONAL DAYTIME
R M S FIELD	136.2 MV/M
DATE	OCTOBER 1963

RAYMOND E. ROHRER & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FCC File No. BL-10380
Accepted 2-12-64

Station WN10
Niles, Ohio

1540 kc


WNIC

Measured Day Nulls
(2-28-64ct)

Station WNIO
Niles, Ohio

500w, DA-D, D
1540 kc

4/6/64
Granted
license for
new AM
station



EXPANDED VIEW

RAYMOND E. ROHRER & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FCC File No. BL-10380
Accepted 2-12-64

Station WNIO
Niles, Ohio


1540 kc

WNIO

Measured Non-DA
(2-28-64ct)

Station WNIO
Niles, Ohio

500w, DA-D, D
1540 kc



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL FIELD SURVEY

APPLICANT	WNIO
LOCATION	NILES, OHIO
FREQUENCY	1540 KC/S
POWER	0.5 KW DA-D
LATITUDE	41 DEG 07 MIN 56 SEC
LONGITUDE	80 DEG 45 MIN 40 SEC
WHEN USED	NON-DIRECTIONAL PROOF
R.M.S. FIELD	135 MV/M
DATE	OCTOBER 1963

RAYMOND E. ROHRER & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FCC File No. BL-10380
Accepted 2-12-64

Station WNIO
Niles, Ohio

1540 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WNRE

Main Studio: Circleville, Ohio

Frequency: 1540 kHz

Power: 1 kW

Notification List No. 1609

Date: December 4, 1974

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 39° 38' 21"

West Longitude: 82° 57' 30"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 4

Type of elements: Series-excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	NW(#4)	NC(#3)	SC(#2)	SE(#1)
HEIGHT ABOVE INSULATORS:	180'	180'	180'	180' (101°)
PHASING:	+138°	0°	-140°	+79°
FIELD RATIO:	0.55	1.0	0.78	0.25

SPACING AND

ORIENTATION: Adjacent elements are spaced 177.5' (100°) on a line
bearing 318° true.GROUND SYSTEM: 120-160' equally spaced copper radials plus 120-50'
interspaced radials about each tower. Radials are
shortened and bonded to transverse straps along inter-
sections between towers. Centers of systems are bonded
together.

Predicted effective Field: 207 mv/m at rated power.

Note: This notification concerns only a change to add meows of
radiation to the directional antenna pattern.

COHEN AND DOWELL
RECEIVED

MAY 15 1975

WASHINGTON, D.C.

WNRE




FIGURE 1
HORIZONTAL PLANE RADIATION PATTERN
CIRCLEVILLE BROADCASTING COMPANY
WNRE 1540 KHz 1KW DA-DAY
CIRCLEVILLE, OHIO

Prepared by
Lohnes and Culver Washington, D. C.
October, 1974

WNRE

Proposed Day
(11-28-67ct)

New; Circleville Bcstg. Co.
Circleville, Ohio

1kw, DA-D, D
1540 kc




FIGURE 5 AMENDED
HORIZONTAL PLANE RADIATION PATTERN
CIRCLEVILLE BROADCASTING COMPANY
1540 KC 1 KW, DA-DAY
CIRCLEVILLE, OHIO

Prepared by
Lohnes and Culver Washington, D. C.
September, 1967

North Latitude 39° 38' 21"
West Longitude 82° 57' 30"

FCC File No. BP-17868

New; Circleville Bcstg. Co.

Accepted 10-25-67 Amended Circleville, Ohio

1540 kc

Proposed Day
(9-28-67ct)

New; Circleville Bcstg. Co.
Circleville, Ohio

WNKE
1kw, DA-D, D
1540 kc




FIGURE 5
HORIZONTAL PLANE RADIATION PATTERN
CIRCLEVILLE BROADCASTING COMPANY
1540 KC 1 KW, DA-DAY
CIRCLEVILLE, OHIO

Prepared by
Lohnes and Culver Washington, D. C.

August, 1967

NORTH LATITUDE 39° 38' 08"
WEST LONGITUDE 82° 58' 34"

FCC File No. BP-17868

New; Circleville Bcstg. Co.


WNRE

Proposed Day
(6-28-67ct)

New; George E. Worstell
Circleville, Ohio

1kw, DA-D, D
1540 kc

PAGE 7



EUGENE DIETZEN CO.
MADE IN U. S. A.

D-P - GEN - H P
POLAR ORIGINATE

N

FCC File No. BP-17648
Accepted 6-2-67

Gardner & Jones - Consulting Radio Engineers
New; George E. Worstell
Circleville, Ohio

1540 kc

WNRE




FIGURE 8
 MEASURED HORIZONTAL RADIATION PATTERN
 DA-D OPERATION
 WNRE 1KW-D, DA 1540 KHz
 CIRCLEVILLE BROADCASTING COMPANY
 CIRCLEVILLE, OHIO

Prepared by
 Lohnes and Culver Washington, D. C.
 October, 1974

WPTR

SED
F&DAY

WPTR, ALBANY, NY

50kw, DA1

WPTR - 1540 KC

12/20/48G

330°


340°

350°

10°

20°

30°



AMENDMENT RECD 12-15-48 BP-6920

BP-6920

170°

160°

150°

MEASURED
NIGHT & DAY

WPTR, ALBANY, N. Y.

50kw, DA-1

WPTR-1540KC

WPTR



6-29-49

10°

20°

30°

320°

310°

300°

290°

280°

270°

260°

250°

240°

230°

220°

40°

50°

60°

70°

80°

90°

100°

110°

120°

130°

140°



R & C - 6/49

MV/M

3000

RADIAL VALUE

MEASURED

COMPUTED

2000

1000

COMPUTED
RMS = 1790 MV/M

KXEL
949 MI.

MEASURED
RMS = 1740 MV/M

ZNS
1265 MI.

FIGURE 2

MEASURED DIRECTIONAL
HORIZONTAL PLANE RADIATION PATTERN

WPTR

PATROON BROADCASTING COMPANY, INC.
Albany, New York

1540 kc - 50 kw - U - DA - 1

A. D. RING & CO.

CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

SITE: 42° 44' 01" N
73° 51' 49" W

210°

200°

190°

180°

170°

160°

150°

WPTR, Albany, N. Y. 1540 kc

WPTR

50kw, DA-1


1540 kc

MEASURED
NIGHT&DAY NULLS.


WPTR, ALBANY, N. Y.

6-29-49

7/14/49G



SITE: 42° 44' 01" N
73° 51' 49" W



WPTR, Albany, N. Y. 1540 kc


WRCP

MEASURED NON-DA
(7-8-59g)

Station WJMJ
Philadelphia, Pennsylvania

50kw, DA-D, D
1540 KC

Granted to install DA-D 11-18-59



LATITUDE 40° 02' 46" LONGITUDE 75° 14' 15"	ANTENNA PARAMETERS	FIGURE 18 MEASURED NON-DA HORIZONTAL POLAR PATTERN RADIO STATION WJMJ PHILADELPHIA, PENN.
JOHN H. MULLANEY CONSULTING RADIO ENGINEERS WASHINGTON, D. C.	G = 81.7° + T.L.	
		1540 KC 50 KW, DA-D

FCC File No. BL-7529
Accepted 7-2-59

WJMJ
Philadelphia, Pennsylvania


1540 KC

MEASURED DAY
(7-8-59g)

Station WJMJ
Philadelphia, Pennsylvania


50kw, DA-D, D
1540 KC

Granted L to install DA-D 11-18-59



LATITUDE: 40° 02' 46"
LONGITUDE: 75° 14' 15"

ANTENNA PARAMETERS



G = 81.7° + T.L.

FIGURE 20

MEASURED DAYTIME
DIRECTIONAL
HORIZONTAL POLAR PATTERN
RADIO STATION WJMJ
PHILADELPHIA, PENN.

JOHN H. MULLANEY
CONSULTING RADIO ENGINEER
WASHINGTON, D. C.


1540 KC

50KW, DA-D

PROPOSED DAY
(7-8-59g)

Station WJMJ
Philadelphia, Pennsylvania

50kw, DA-D, D
1540 KC



LATITUDE 40° 02' 46"
LONGITUDE 75° 14' 15"

ANTENNA PARAMETERS




FIGURE 4

DAYTIME HORIZONTAL
POLAR PATTERN

RADIO STATION WJMJ
PHILADELPHIA, PA

1540 KC 50 KW-DA-D

JOHN H. MULLANEY
CONSULTING RADIO ENGINEER
WASHINGTON, D.C.

FCC File No. BMP-8575
Accepted 6-15-59

WJMJ
Philadelphia, Pennsylvania

1540 KC

*granted M.C.P. make
changes in DA-System*

Measured Day
(1-28-70ct)

Station WRCP
Philadelphia,


Pennsylvania

50kw, DA-D, D
1540 kc

North Latitude 40° 02' 46"
West Longitude 75° 14' 15"

BL 12466
Circ (2-6 70) Like CIP per changes

WRCP




FCC File No. BL-12466
Accepted 1-21-70

Station WRCP
Philadelphia, Pennsylvania

1540 kc

BP-18639 Granted
 9-24-69 CP for
 changes.



WRCP


WRGM

PROPOSED DAY
(10-25-61ct)

New; 1540 Radio, Inc.
Richmond, Virginia

10kw, DA-D, D
1540 kc

3-7-63
granted of
for new station



WRGN

PROPOSED DAY NULLS
(10-25-61ct)

New; 1540 Radio, Inc.
Richmond, Virginia

10kw, DA-D, D
1540 kc




FIGURE 1-B (AMENDED)

EXPANDED VIEW

SILLIMAN, MOFFET & ROHRER
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-14813 Amended
Accepted 9-18-61

New; 1540 Radio, Inc.
Richmond, Virginia

1540 kc


WR & M

Measured Day
(6-29-64ct)


Station WRGM
Richmond, Virginia

10kw, DA-D, D
1540 kc

LIC. 8-19-64



HORIZONTAL RADIATION PATTERN



G = 300 Feet = 169° (PLUS TOP LOADING)

APPLICANT	DAWN
LOCATION	RICHMOND, VIRGINIA
FREQUENCY	1540 KC/S
POWER	10 KW, DA-D
LATITUDE	37 DEG 37 MIN 10 SEC
LONGITUDE	77 DEG 25 MIN 24 SEC
WHEN USED	DAYTIME
RMS FIELD	819 mV/m
DATE	APRIL 1964

RAYMOND E. ROHRER & ASSOCIATES

CONSULTING RADIO ENGINEERS

WASHINGTON, D. C.

FCC File No. BL-10600
Accepted 6-1-64

Station WRGM
Richmond, Virginia

1540 kc


WRGM

Measured Day Nulls
(6-29-64ct)

Station WRGM
Richmond, Virginia

10kw, DA-D, D
1540 kc

LIC. 8-19-64



EXPANDED VIEW

RAYMOND E. ROHRER & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FCC File No. BL-10600
Accepted 6-1-64

Station WRGM
Richmond, Virginia

1540 kc

WRGM

Measured Non-DA
(6-29-64ct)

Station WRGM
Richmond, Virginia

10kw, DA-D, D
1540 kc

LIC. 8-19-64




FIGURE 1

HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL PATTERN

APPLICANT	WRGM
LOCATION	RICHMOND, VIRGINIA
FREQUENCY	1540 KC/S
POWER	10 KW, DA-D
LATITUDE	37 DEG 37 MIN 10 SEC
LONGITUDE	77 DEG 25 MIN 24 SEC
WHEN USED	NON-DIRECTIONAL SURVEY
RMS FIELD	501 MV/M
DATE	APRIL 1964

RAYMOND E. ROHRER & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D C

FCC File No. BL-10600
Accepted 6-1-64

Station WRGM
Richmond, Virginia

1540 kc


Proposed Day
(3-28-68ct)

New; St. Cross Broadcasting, Inc.
Santa Cruz, California

5kw, DA-D, D
1540 kc

EUGENE DIMYDZEN CO.
MADE IN U.S.A.

EUGENE DIMYDZEN CO.
MADE IN U.S.A.



FCC File No. BP-18014
Accepted 3-19-68

New; St. Cross Broadcasting, Inc.
Santa Cruz, California

1540 kc

PROPOSED DAY
(8-29-60g)

New; The Downriver Bcstng. Assn.
Napoleon, Ohio

500w, DA-D, D
1540 KC

EUGENE DIETZEN CO
NEW YORK, N.Y.

NO 340-P DIETZEN GRAPH PAPER
POLAR CO-ORDS




FIGURE 3
PROPOSED RADIATION PATTERN

NAPOLEON, OHIO

1540 KC - 0.5 KW - DA-D

E. H. MANN, JR.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WRPL Main Studio: Charlotte, North Carolina
 Frequency : 1540 KHz Power : -- Night 10 kW Day
 Notification: 1779 Date : September 27, 1978 Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 35° 12' 12"
 West Longitude: 80° 48' 44"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation (DA-D)

Number of elements: 3

Type of elements: Uniform cross-section, guyed, Shunt
excited, vertical steel towers.

TOWER :	<u>S(#3)</u>	<u>C(#2)</u>	<u>N(#1)</u>	_____	_____	_____
HEIGHT ABOVE INSULATORS :	<u>150'</u>	<u>150'</u>	<u>150'(85°)</u>	_____	_____	_____
PHASING :	<u>+71.0°</u>	<u>-136.14°</u>	<u>0°</u>	_____	_____	_____
FIELD RATIO:	<u>1.008</u>	<u>1.919</u>	<u>1.000</u>	_____	_____	_____


SPACING AND

ORIENTATION: Adjacent towers in a row are spaced 106.4' (60°) on a line bearing 175° true.

GROUND SYSTEM: 120-85' to 240' equally spaced copper radials plus a 24' square ground screen about each tower. Radials are shortened and bonded to transverse along intersections between towers. Centers of system are bonded together.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	RMS	RSS	RMS
Day	<u>615.570</u> mV/m	<u>1347.446</u> mV/m	<u>646.348</u> mV/m



Standard Pattern


LATITUDE: 35°12'12"N
LONGITUDE: 80°08'12"W



LBA

LAWRENCE DEHR ASSOCIATES, INC.
GREENVILLE, N.C. 27631

ANTENNA PARAMETERS



$$S_1 = S_2 = 60^\circ$$

$$G_1 = G_2 = G_3 = 85^\circ$$

RSS_{ch}/RMS_{ch} = 0.159
RSS_{ch} = 17.71446
RSS_{red} = 1014.813
RMS_{ch} = 615.577
RMS_{red} = 615.577

FIGURE 17

PROPOSED STANDARD DAYTIME
HORIZONTAL PATTERN

RADIO STATION WRPL
CHARLOTTE, NORTH CAROLINA

1540 KHZ 10 KM, DA-2