

960-970

Station	Main Studio	Freq	Power	Date
NEW	Milton, ON	960	0.5 kW/DA-1	3/28/68
NEW	Mont-Joli, QU	960	1 kW/DA-N	10/18/78
CFAC	Calgary, AB	960	50 kW/DA-N	7/29/70
CFAC	Calgary, AB	960	10 kW/DA-N	10/24/58
CFTJ	Cambridge, ON	960	1 kW/DA-1	5/8/79
CHNS	Halifax, NS	960	10 kW/DA-N	7/2/58
CKWS	Kingston, ON	960	5/10 kW/DA-2	6/27/69
KABL	Mount Pocono, PA	960	1 kW/DA-D	8/22/80
KABL	Mount Pocono, PA	960	5 kW/DA-1	6/16/59
KALE	Richland, WA	960	1/5 kW/DA-N	10/5/77
KARZ	Phoenix, AZ	960	5 kW/DA-N	8/26/66
KOVO	Provo, UT	960	1 kW/DA-N	4/2/48
KGIR	Cape Girardeau, MO	960	0.5/5 kW/DA-N	10/28/68
KGIR	Cape Girardeau, MO	960	0.5/1 kW/DA-N	4/14/49
KGKL	San Angelo, TX	960	1/5 kW/DA-N	1/31/46
KGWA	Enid, OK	960	1 kW/DA-1	2/26/48
KLAD	Klamath Falls, OR	960	5 kW/DA-N	3/29/78
KMA	Shenandoah, IA	960	5 kW/DA-N	9/4/59
KNEB	Scottsbluff, NE	960	0.5/1 kW/DA-2	9/12/50
KNEZ	Lompoc, CA	960	0.5 kW/DA-N	8/12/60
WABG	Greenwood, MS	960	0.5/1 kW/DA-N	5/17/50
WBOC	Salisbury, MD	960	1/5 kW/DA-2	11/28/55
WBRC	Birmingham, AL	960	5 kW/DA-N	3/22/71
WDLM	East Moline, IL	960	1 kW/DA-D	4/29/69
WEAV	Plattsburgh, NY	960	5 kW/DA-2	9/28/79
WELI	New Haven, CT	960	1 kW/DA-N	9/47
WELI	New Haven, CT	960	5 kW/DA-N	3/3/58

960-970

Station	Main Studio	Freq	Power	Date
WFGL	Fitchburg, MA	960	1/2.5 kW/DA-2	8/22/80
WFIR	Roanoke, VA	960	5 kW/DA-N	2/51
WFTC	Kinston, NC	960	1/5 kW/DA-N	7/50
WGRO	Lake City, FL	960	1/0.5 kW/DA-N	9/28/79
WHYL	Carlisle, PA	960	5 kW/DA-D	10/1/75
WJAZ	Albany, GA	960	5 kW/DA-D	3/27/70
WRFC	Athens, GA	960	0.5 kW	11/3/50
WRFC	Athens, GA	960	0.5/1 kW	11/8/50
WSBT	South Bend, IN	960	5 kW/DA-2	9/28/79
WTCH	Shawano, WI	960	1 kW/DA-N	9/25/74
XEDF	Laredo, Tamps	960	0.1/0.5 kW/DA-1	6/6/56
CBZ	Fredericton, NB	970	10 kW/DA-N	5/17/74
CKCH	Hull, QU	970	5 kW/DA-1	12/3/54
CJYR	Edson, AB	970	10 kW/DA-1	8/28/67
CKCH	Hull, QU	970	10/5 kW/DA-2	11/30/81
KAKC	Tulsa, OK	970	1/2.5 kW/DA-2	9/12/80
KAKC	Tulsa, OK	970	0.5/1 kW/DA-2	12/12/58
KBEE	Modesto, CA	970	1 kW/DA-2	7/23/48
KBIS	Bakersfield, CA	970	1 kW/DA-2	5/20/75
KCHV	Coachella, CA	970	1/5 kW/DA-2	3/30/64
KIXL	Austin, TX	970	1 kW/DA-D	1/9/57
KNUU	Paradise, NV	970	0.5/5 kW/DA-2	8/22/80
KOIN	Portland, OR	970	5 kW/DA-N	9/8/48
KOOK	Billings, MT	970	5 kW/DA-N	3/22/55
KQAQ	Austin, MN	970	1 kW/DA-D	4/5/57
KQAQ	Austin, MN	970	0.5/5 kW/DA-2	3/8/61
KREM	Spokane, WA	970	1/5 kW/DA-N	9/28/79

960-970


Station	Main Studio	Freq	Power	Date
KREM	Spokane, WA	970	1/5 kW/DA-N	4/11/55
KSYL	Alexandria, LA	970	1 kW/DA-N	3/22/48
WAMD	Aberdeen, MD	970	0.5 kW/DA-2	6/11/56
WANV	Waynesboro, VA	970	1/5 kW/DA-2	1/29/64
WATH	Athens, OH	970	5 kW/DA-D	5/27/69
WAVE	Louisville, KY	970	5 kW/DA-2	5/8/61
WCSH	Portland, ME	970	5 kW/DA-N	5/2/47
WDAY	Fargo, ND	970	5 kW/DA-N	1/23/51
WEBR	Buffalo, NY	970	5 kW/DA-1	9/26/68
WFLA	Tampa, FL	970	5 kW/DA-2	11/12/75
WIIN	Atlanta, GA	970	5 kW/DA-D	6/26/57
WJMX	Florence, SC	970	1/5 kW/DA-N	11/30/49
WKHM	Jackson, MI	970	1 kW/DA-2	1/11/50
WMAY	Springfield, IL	970	0.5/1 kW/DA-2	8/24/62
WNTA	Newark, NJ	970	5/1 kW/DA-N	10/29/56
WOZN	Jacksonville, FL	970	1 kW/DA-D	12/15/60
WREO	Ashtabula, OH	970	1/5 kW/DA-2	3/22/71
WRKN	Brandon, MS	970	1 kW/DA-D	4/28/66
WTBF	Troy, AL	970	0.5/5 kW/DA-2	3/22/55
WWDJ	Hackensack, NJ	970	5 kW/DA-2	7/28/66
WWSW	Pittsburg, PA	970	5 kW/DA-2	5/11/48
NEW	Edson, AB	970	10 kW/DA-1	3/28/68
XEDF	Mexico, DF	970	5/10 kW/DA-N	11/29/62

ANTENNA DESCRIPTION SHEET

STATION CALL: NEW
MAIN STUDIO: Milton, Ontario
FREQUENCY: 960 Kc/s
POWER: 500 Watts Day and Night
CLASS: 111
MODE: DA-1
TIME: Unlimited
NOTIFICATION LIST NO.: 8..... DATE March 11, 1968
GEOGRAPHICAL LOCATION: Latitude: $43^{\circ} 27' 46''$
Longitude: $79^{\circ} 48' 56''$
ARRAY CHARACTERISTICS: 6 guyed steel towers of uniform cross section, base insulated, series fed, no top loading.
TOWER: 1 2 3 4 5 6
 N NE NW SE E
HEIGHT: 171' (60°) all towers.
CURRENT: 0.51 1.0 0.51 0.51 1.0 0.51
PHASE: $+155^{\circ}$ 0° -155° $+155^{\circ}$ 0° -155°
SPACING: Long sides=1-6; 2-5; 1-4= 255° @ 220° Az.
 Short sides=1-2-3; 4-5-6= 50° @ 260° Az.
GROUND SYSTEM: 120 equally spaced copper radials per tower, buried 6-8" deep of average effective length of 410' (0.4 wavelength)
ORIENTATION: Towers 1-2-3 and 4-5-6 constitute the short sides of this parallelogram array and are at an azimuth of 260° . The long sides, towers 3-6, 2-5; 1-4 are at an azimuth of 220°
PREDICTED EFFICIENCY: 175 mv/m for 1 KW
 133.6 mv/m for 0.5 KW.

Rev: Jan 19th/68

Sketch of Tower Layout and
Site: FEW Milton, Ont. 960 kc/s.



Parameter

1=0.51/-155°

2=1.0/0°

3=0.51/-155°

4=0.51/+155°

5=1.0/0°


6=0.51/-155°

Long sides=235' $\theta = 30^\circ$
Short side=50' $\theta = 60^\circ$

Proposed Day & Night
(3-28-68ct)

New Station
Milton, Ontario


500w, DA-1, U, Class III
960 kc



Proposed Day & Night Nulls
(3-28-68ct)

New Station
Milton, Ontario

500w, DA-1, U, Class III
960 kc



Horizontal Pattern Minima
NEW Milton, Ont. 960 kc/s, 0.5 KW, DA-1
Drawn: G.W.Lee. App: Dec 14th/67
Rev: Jan 17th/68

N° 11504

DESCRIPTION

STATION : Nouvelle STUDIO PRINCIPAL: Mont-Joli, Qué.
POISSANCE : 1 kW FREQUENCE : 660 kHz Classe III
LISTE D'AVIS NO: 377 DATE : le 18 octobre 1978
EMPLACEMENT GEOGRAPHIQUE: Latitude nord : 48° 35' 24"
Longitude ouest: 68° 08' 20"

CARACTERISTIQUES D'ANTENNE

MODE D'OPERATION : AD-N
NOMBRE D'ELEMENTS: 2 de nuit, 1 de jour
GENRE D'ELEMENTS :

<u>PYLONE</u>	<u>No. 1 (SE)</u>	<u>No. 2 (NO)</u>
<u>HAUTEUR AU-DESSUS DE L'ISOLATEUR</u>	70°	70° (200', 60.96 m)
<u>ESPACEMENT</u>	Réf.	80° (227.8', 69.43 m)
<u>ORIENTATION</u>	Réf.	333.5°
<u>PHASAGE</u>	Réf.	-109°
<u>RAPPORT D'INTENSITE DE CHAMP</u>	1.00	0.90
<u>EFFICACITE PREVUE</u>	Jour 185 mV/m à 1 mille pour 1 kW Nuit 195 mV/m à 1 mille pour 1 kW	
<u>MISE A LA TERRE</u>	120 fils no. 10 espacés équiangulairement enfouis environ 20 cm sous la surface d'une longueur équivalente à 0.4λ avec courroie d'interconnexion à la bissectrice.	

PROJET 4601

Pierre Labarre & Associés Ltée
St-Lambert, Qué., Canada

15 mars 1978






FIGURE 2. PATRON DIRECTIONNEL-VERTICAL

AZ. 204.6, 206.9, 210.5, 235.6

Nouvelle station de radiodiffusion VA
Mont-Toli, Qué.

Classe III; 1 kW jour et nuit; AC-N; 960 kHz

REQJET 4601 Pierre Labarre & Associés Ltée
15 mars 1973 St-Lambert, Québec, Canada






FIGURE 4. RAYON DIRECTIONNEL-VERTICAL

As. 221.6, 333.5

Nouvelle station de radiodiffusion MA

Mont-Joli, Québec

Classe III; 1 kW jour et nuit; AD-R; 969 kHz

PROJET 4601

Pierre Libarte & Associés Ltée

15 mars 1972

St-Lambert, Québec, Canada


I - DESCRIPTION DU SYSTEME A ANTENNE DIRECTIONNELLE


1. LETTRES D'APPEL: (nouveau poste)
2. EMLACEMENT: Mont-Joli, Qué.
3. FREQUENCE: 960 KHz.
4. PUISSANCE: 1 KW jour et nuit.
5. CLASSE: III.
6. NOTIFICATION NO: 359 DATE: October 4, 1976
7. COORDONNEES: Latitude nord: 48° 35' 15"
Longitude ouest: 68° 03' 01"
8. SYSTEME D'ANTENNE: a) Fonctionnement: directionnel AD-N.
b) Type: deux (2) éléments à section triangulaire, haubanés et alimentés en série.
c) Mise à la terre: 120 fils #10 espacés également, d'une longueur équivalente à 0.4λ avec courroies d'interconnexion, le tout enfoui à env. 8" sous la surface.
9. MATS D'ANTENNE:
- | | #1 (SE) | #2 (NO) |
|-----------------------------------|---------|------------|
| Orientation (Az): | Ref. | 333.5° |
| Hauteur au-dessus de l'isolateur: | 70° | 70° (200') |
| Espacement: | Ref. | 60° |
| Phasage: | 0° | -115° |
| Rapport d'intensité de champ: | 1.00 | 0.96 |
10. EFFICACITE PREVUE: a) Jour: 185.0 mV/m à 1 mille pour 1 KW.
b) Nuit: 180.0 mV/m à 1 mille pour 1 KW.

YVES R. HAMEL
INGENIEUR-CONSEIL
3772 AVENUE KENT,
MONTREAL, QUE. H3S 1H3

46 4412


K·S POLAR CO-ORDINATE
CURTIS & ESSER CO. MADE IN U.S.A.





46 4412

K-E POLAR CO-ORDINATE
KEUTEL & ESSER CO. WASHINGTON



220°
140°230°
130°240°
120°250°
110°260°
100°270°
90°280°
80°290°
70°300°
60°310°
50°320°
40°

FIGURE 44

PATRON DIRECTIOBEL - PLAN VERTICAL

Az 222.31°, 221.95°, 221.63° et 224.26°

NOUVEAU POSTE COMMERCIAL RADIOPHONIQUE MA

MONT-JOLI, QUE.

CLASSE III 1 KM JOUR ET NUIT AD-H 960 KHz

MRS. R. RAMEL

INGENIEUR-CONSEIL

gph

220°/m

Az 221.95°

Az 222.31°

Az 221.63°

Az 224.26°

WFIR

WFIR

WFIR

WFIR

mV/m

100

50

100

50

100

mV/m

0°

350°

20°

30°

110

120

130

140

150

160

170

180

190

200

210

220

230

240

250

260

270

280

290

300

310


320

330

340

350

PATRON DIRECTIONNEL - PLAN VERTICAL
 AZ 224.97°, 226.51°, 226.32° et 235.59°
 NOUVEAU POSTE COMMERCIAL RADIOPHONIQUE MA
 MONT-JOLI, QUE.
 CLASSE 117.1 KW JOUR ET NUIT AD-N 960 KHz
 MIES R. HAMEL
 INGENIEUR-CONSEIL




Proposed Night
(7-29-70ct)

Station CFAC
Calgary, Alberta

CFAC
50kw, DA-N, U, Class III
960 kc

Wavelength 359.31G
Miles



199

CFAC

Description Sheet
(6-28-65ct)Station CFAC
Calgary, Alberta50kw, DA-N, U, Class III
960 kcDirectional Antenna Description Sheet

Station : CFAC Main Studio : Calgary, Alberta

Frequency : 960 kc Power : 50 kw Class : III

Notification List No. : 199 Date : May 10, 1965

Geographical Location

of Antenna System : N. Lat. 50° 53' 51", W. Long. 114° 09' 57"

Antenna Characteristics : Mode of Operation : DA-N
 Number of Elements : 3
 Type of Element : guyed, uniform
 cross-section,
 no top loading

	<u>North Tower</u>	<u>Centre Tower</u>	<u>South Tower</u>
Height above insulator	257' (90°)	435' (153°)	257'
Overall Height	262'	440'	262'
Spacing	328' (115°) between adjacent towers		
Phasing	85° lag	0°	85° lead
Field Ratio	1.0	2.32	1.0
Orientation	Centre line through towers bears N9°W.		
Ground System	Around each tower base, 120 radials, 415' long, spaced 3°.		
Predicted Effective Field :	1490 mv/m at 1 mile (211 per kw)		


199

CFAC

Proposed Night
(6-28-65ct)

Station CFAC
Calgary, Alberta

50kw, DA-N, U, Class III
960 kc



#123
DESCRIPTION SHEET
(10-24-58g)

Station CFAC
Calgary, Alberta, Canada

CFAC
10kw, DA-N, U, Class III
960 KC

Station: CFAC

Main Studio: Calgary, Alberta

Frequency: 960 Kcs

Power: 10 Kw Class: III

Notification List No. 123

Date: July 2, 1958

GEOGRAPHICAL LOCATION
OF THE ANTENNA SYSTEM:

North Latitude: 50° 56' 52"

West Longitude: 114° 03' 47"

ANTENNA CHARACTERISTICS

Mode of Operation: DA-N

Number of elements: Two

Type of elements: Guyed uniform cross-section.

Series-fed, no top loading

TOWER:	North	South
HEIGHT ABOVE INSULATORS:	176'	435'
SPACING:	365' (135°)	
PHASING:	75° LAG	0°
PI LD RATIO:	0.70	1.0
ORIENTATION:	Centre line through towers bears N 16° W	
GROUND SYSTEM:	120 radials 500' Long Spaced 3°	120 radials 500' Longspaced 3° plus 120 radials 60' long interspaced
Predicted effective field	650 mv/m. (206 for 1 kw)	


#123

CFAC

PROPOSED NIGHT
(10-24-58g)

Station CFAC
Calgary, Alberta, Canada

10kw, DA-N, U, Class III
960 KC



ANTENNA DESCRIPTION SHEET

CFTJ

DIRECTIONAL DA-1

Station Call: C P T J
 Location: Cambridge, Ontario.
 Frequency: 960 khz
 Power: 1000 watts
 Class: III
 Time: Unlimited

Notification Reference: List 384 May 8, 1979

Geographical Coordinates: Lat $43^{\circ}20'55''$, Lon $80^{\circ}14'45''$

Array Characteristics: Five elements, guyed, uniform cross section, base insulated, series feed. Height 220 feet, top loaded to effect height of 85 degrees.

ELEMENT	ONE	TWO	THREE	FOUR	FIVE
Spacing	Ref	197.40° 562.2'	180.00° 512.7'	192.57° 548.5'	75.00° 213.6'
Bearing	Ref	45.68°	68.00°	90.91°	160.00°
Ratio	1.00	---	0.75	0.66	0.88
Phase	00°	---	10°	125°	115°


Ground System 120 radials per tower, #10 AWG bare, soft copper wire, spaced uniformly, depth 8 inches approximately. Radials bonded along lines between towers and bonded to soft copper straps at tower bases. Maximum radial length 410 feet.

Predicted RMS 185 mv/m at 1 mile for 1000 watts



Jne 1978

5

POLAR CO-ORDINATE





HORIZONTAL ANTENNA PATTERN
CFTJ CAMBRIDGE, ONTARIO
1004 W. DA-1 960 kHz III
George Mathers, P. Eng.
June 1978 #6



VERTICAL RADIATION PATTERNS

CFTJ CAMBRIDGE, ONTARIO
 1000 W DA-1 960 kHz III
 George Mather, P. Eng.



Jne 1978



VERTICAL RADIATION PATTERNS

CFTJ CAMBRIDGE, ONTARIO
1000 w DA-1 960 khz III
George Mather, P. Eng.

Jne 1978



VERTICAL RADIATION PATTERNS

CPTJ, CAMBRIDGE, ONTARIO
1000 W DA-1 960 Khz III
George Mather, P. Eng.

Jne 1978

ANTENNA DESCRIPTION SHEET

CFTJ

STATION CALL: CFTJ
 MAIN STUDIO: CAMBRIDGE, ONTARIO
 FREQUENCY: 960 kHz
 POWER: 1 kW
 CLASS: III
 MODE: DA-2
 TIME: UNLIMITED

NOTIFICATION LIST NO.: .351. DATE: Feb. 11/76

GEOGRAPHICAL LOCATION: Latitude: 43° 20' 55" North
 Longitude: 80° 14' 45" West


ARRAY CHARACTERISTICS: Five guyed steel towers of uniform cross section; base insulated series fed; top loaded using the upper guy wires for an effective height of approximately 85°.

TOWER NUMBER:	1 NW	2 NE	3 CE	4 SE	5 SW
HEIGHT ABOVE INSULATOR:	220'	220'	220'	220'	220' (77.3°)
DAY FIELD RATIO:	1.00	-	0.75	0.66	0.88
DAY PHASE ANGLE:	0°	-	10°	125°	115°
NIGHT FIELD RATIO:	1.00	1.00	1.00	-	1.00
NIGHT PHASE ANGLE:	0°	352°	117°	-	125°
SPACING:	ref.	198.47° 561.7'	180.0° 512.2'	192.57° 548.0'	75.0° 213.4'
ORIENTATION:	ref.	045.73°	068°	090.91°	160°

GROUND SYSTEM: 120 equally spaced copper radial wires per tower, buried 6"-12", of average length 410' (0.4λ), excluding those along the common chords.

PREDICTED EFFICIENCY: 185 mV/m at one mile for 1 kW day and night.

FIGURE 1






CFTJ - CAMBRIDGE, ONTARIO
1 kW DA-2 960 kHz
DAY HORIZONTAL PATTERN
J.G.E. FEB. 1975

FIGURE 2

CFT

POLAR CO-ORDINATE







VERTICAL RADIATION PATTERNS

CFTJ - CAMBRIDGE, ONTARIO

1 kW DA-2 960 kHz

J.G.E.

MARCH 1973





VERTICAL RADIATION PATTERNS

CFTJ - CAMBRIDGE, ONTARIO

1 kW DA-2 960 kHz

J.G.E. MARCH 1973



VERTICAL RADIATION PATTERNS

CFTJ - CAMBRIDGE, ONTARIO

1 kW DA-2 960 kHz

J.G.E. MARCH 1973

#123

CHNS

DESCRIPTION SHEET
(10-24-58g)Station CHNS
Halifax, Nova Scotia10kw, DA-N, U, Class III
960 KC

Station: CHNS

Main Studio: Halifax, Nova Scotia

Frequency: 960 Kcs

Power: 10 Kw Class: III

Notification List No. 123

Date: July 2, 1958ANTENNA LOCATION
ANTENNA SYSTEM:

North Latitude: 44° 40' 49"

West Longitude: 63° 39' 35"

ANTENNA CHARACTERISTICS

Mode of Operation: DA-N

Number of elements: Two

Type of elements: Base Insulated, Series-fed.

TOWER:	p1 South West	p2 North East
HEIGHT ABOVE ANTENNATORS:	224' (78°)	224' (78°)
OVERALL HEIGHT:	229'	229'
ANGLE:	415' (145°)	
BEARING:	0	314°
FIELD RATIO:	1.0	1.2
ORIENTATION:	On line bearing 060° true	
GROUND SYSTEM:	120 radials 410' Long (0.4 wavelengths) spaced 3° about each tower. 120 radials 35' Long interspaced	
Predicted effective field	Night	563 mv/m (178 mv/m for 1 kw)
	Day	585 mv/m (185 mv/m for 1 kw)


CHNS

#123

PROPOSED NIGHT
(10-24-58g)

Station CHNS
Halifax, Nova Scotia

10kw, DA-N,U, Class III
960 KC



KE POLAR COORDINATE 359.31
LEUPOLD RESERVOIR

Description Sheet
(6-27-69ct)

Station CKWS
Kingston, Ontario

5kw, 10kw-LS, DA-2, U, Class III
960 kc

CORRECTED DATA
ANTENNA DESCRIPTION SHEET
DIRECTIONAL DA-2

STATION CALL C K W S
MAIN STUDIO Kingston, Ontario
FREQUENCY 960 kc/s
POWER Day 10 kw, 5 kw Night
CLASS III
TIME Unlimited
NOTIFICATION REFERENCE ...206... Date: December 14, 1965
GEOGRAPHICAL LOCATION Lat $44^{\circ} 10' 51''$, Lon $76^{\circ} 27' 49''$
ARRAY CHARACTERISTICS Four elements, guyed, uniform cross section, base insulated, series feed. Height 175 ft or 61.5 degrees. No top loading.

ELEMENT	ONE	TWO	THREE	FOUR	FIVE	SIX
Bearing	Ref	307°	$335^{\circ} 51'$	356°	347°	348.983°
Spacing	Ref	122° $347.5'$	267.35° $761.4'$	171° $487.0'$	100.064° $285'$	293.92° $837.141'$
Day ratio	1.000	0.8200	0.6724	0.8200	not used	not used
Night ratio	1.000	not used	not used	not used	0.95238	0.52381
Day phase	00°	-97°	-154°	-57°	not used	not used
Night phase	00°	not used	not used	not used	238°	116°
Ground System	120 radials per tower, #10 AWG bare, soft copper wire, spaced uniformly, depth 8 inches approximately. Radials bonded on a line between towers and bonded to soft copper strap at tower base. Maximum radial length 410 feet.					
Day R M S	556 mv/m at one mile for ten kilowatts 176 mv/m at one mile for one kilowatt					
Night R M S	391 mv/m at one mile for five kilowatts 175 mv/m at one mile for one kilowatt					

NOTE: Correction relative to night-time pattern parameters necessitated by change of reference tower.


May 1969.

CKWS

Proposed Day
(6-27-69ct)

Station CKWS
Kingston, Ontario

5kw, 10kw-LS, DA-2, U, Class III
960 kc




CKWS

Proposed Night
(6-27-69ct)

Station CKWS
Kingston, Ontario

5kw, 10kw-LS, DA-2, U, Class III
960 kc

CKWS - 960 kc.



206

CKWS

Description Sheet
(2-28-66ct)

Station CKWS
Kingston, Ontario

5kw, 10kw-LS, DA-2, U, Class III
960 kc

ANTENNA DESCRIPTION SHEET

DIRECTIONAL DA-2

STATION CALL C K W S
MAIN STUDIO Kingston, Ontario
FREQUENCY 960 kc/a
POWER Day 10 kw, 5 kw Night
CLASS III
TIME Unlimited
NOTIFICATION REFERENCE 206 Date: December 14, 1965
GEOGRAPHICAL LOCATION Lat 44°10'51", Lon 76°27'49"
ARRAY CHARACTERISTICS Four elements, guyed, uniform cross section, base insulated, series feed. Height 175 ft or 61.5 degrees. No top loading.

ELEMENT	ONE	TWO	THREE	FOUR
Bearing	ref	307°	335°51'	356°
Spacing	ref	122° 347.5'	267.35° 261.4'	171° 487.0'
Day ratio	1.0000	0.8200	0.6724	0.8200
Day phase	00°	-97°	-154°	-57°

Ground System 120 radials per tower, #10 AWG bare, soft copper wire, spaced uniformly, depth 8 inches approximately. Radials bonded on a line between towers and bonded to soft copper strap at tower base. Maximum radial length 410 feet.

Day R M S 556 mv/- at one mile for ten kilowatts
176 mv/- at one mile for one kilowatt

NOTE: Please retain daytime pattern notified for CKWS Kingston in Canadian Change List No. 206 dated December 14, 1965 and attach to this description sheet and nighttime pattern.

December 23, 1965

Aug 1965


5

CKWS

Proposed Day
(1-28-66ct.)

Station CKWS
Kingston, Ontario

5kw, 10kw-LS, DA-2, U, Class III
960 kc



HORIZONTAL DAYTIME PATTERN
C & N, S KINGSTON, ONTARIO
2075 km DA-2 560 No III
George Wather, P. Eng.
Aug 1965 # 6


#206

CKWS

Proposed Night
(2-28-66ct)

Station CKWS
Kingston, Ontario

5kw, 10kw-LS, DA-2, U, Class III
960 kc
700 KC.



WITH
206

CKWS
960

Description of Proposed Antenna

Station CKWS

Main Studio Kingston, Ont.

Power 5000 watts

Frequency 960 kc

(a) Location: ~~Lat. 48° 10' 51" Long. 76° 27' 49" (lat. corrected)~~ *New Location: Lat. 44° 10' 51" North Long. 76° 27' 49" West.*

(b) Number of radiators: 3

(c) Type of radiators: Identical guyed radiators of uniform cross-section, insulated at the base for series feed. No top loading is used.

(d) Height of radiator above base insulator: 175 ft.

(e) Height of radiator above ground level: 130 ft. (60°)

(f) Overall height of towers above mean sea level: 451 ft.

(g) Orientation: See Fig. 1

(h) Spacing: Middle tower to north tower - 553 ft. (1940)

Middle tower to south tower - 285 ft. (1000)

(i) Current ratio and phasing: North tower - 1.1 @ 122°

Middle tower - 2.0 @ 0°

South tower - 2.1 @ 122°

Ground system: Each radiator to have a ground system comprising 120 radials with lengths as shown in Fig. 1. The radials will be bonded together at the radiators and where possible, will be buried to a depth of at least 6 inches.

NEW
960 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: NEW

Main Studio: Mount Pocono, Pennsylvania

Frequency: 960 kHz

Power: 1kw Day

Notification List No. 1788

Date: August 22, 1980 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 41° 04' 41"
West Longitude: 75° 23' 33"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 4

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWERS:	C(#1)	NNE(#2)	NE(#3)	ENE(#4)
HEIGHT ABOVE INSULATORS	256' (90°)	256'	256'	256'
DAY PHASING:	0°	-59.65°	+221.88°	+162.24°
DAY FIELD RATIO:	1	1	1	1

SPACING AND
ORIENTATION:

The towers are located at the vertices of a parallelogram
the long sides of which are 569' (200°) in length on a
line bearing 92.5° true. The short sides are 199' (70°)
in length on a line bearing 51° true.


GROUND SYSTEM:

120 - 256' to equally spaced copper radials plus 120 - 50'
interspaced radials about each tower. Radials are shortened
and bonded to a transverse strap along intersections between
towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	175 mv/m	258.7 mv/m	183.875 mv/m

NEW
-960 kHz



STANDARD HORIZONTAL RADIATION PATTERN

FIGURE 1-A (AMENDED)



960 KC

#169-C/T - Jan 24-62
 moved to change site.
 NL: 57-45-04
 WL: 122-22-52

KABL


Measured Day & Night
(11-29-65ct)

Station KABL
Oakland, California

5kw, DA-1, U
960 kc

F-16-67 GRANTED LICENSE
INCREASE IN POWER AND
CHANGE OF ANTENNA TRANSM. LOC.

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.



North Latitude $37^{\circ} 40' 40''$
West Longitude $122^{\circ} 18' 53''$

MEASURED HORIZONTAL PLANE PATTERN
KABL, OAKLAND, CALIFORNIA
960 KC - 5 KW - DA-1
SEPTEMBER 1965

MEASURED PARAMETERS

$1052/18^{\circ}$

$1/0^{\circ}$

$0.471/-12^{\circ}$

H=88° = 250 FEET

S=95° = 270 FEET

LINE OF TOWERS N 100° E

FCC File No. BL-11113
Accepted 10-29-65

Station KABL
Oakland, California

960 kc

KABL


Measured Non-DA
(11-29-65ct)

Station KABL
Oakland, California

5kw, DA-1, U
960 kc

1-16-67 GRANTED LICENSE
INCREASE IN POWER AND
CHANGE OF ANTENNA
TRANSMITTER LOCATION,

GEORGE C. DAVIS
CONSULTING ENGINEERS
RADIO-TELEVISION
WASHINGTON 4, D. C.



MEASURED NON-DIRECTIVE PATTERN
KABL, OAKLAND, CALIFORNIA
960 KC - 5 KW
SEPTEMBER 1965

FCC File No. BL-11113
Accepted 10-29-65

Station KABL
Oakland, California

960 kc

KALE

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KALE Main Studio: Richland, Washington
Frequency : 960 kHz Power : 1kw Night 5kw Day
Notification List No.: 1752 Date : October 5, 1977 Class: 1

GEORGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 46° 14' 34"
West Longitude: 119° 10' 48"

Authorized for Night operation (DA-N)

PREDICTED EFFECTIVE DAY FIELD: (omnidirectional center tower) 454 mv/m at
rated power.


Note: Please retain the description sheet and directional antenna radiation
patterns notified for Station KALE in United States Change List
Number 397, dated March 21, 1951 and attach to this supplemental
Description Sheet. This notification is for the purpose of indicating
an increase in daytime power from 1 kw with no change in the nighttime
operation.

PROPOSED
NIGHT

KALE, RICHLAND, WASH.

1kw, DA-N

960 kc



AMENDED 2/7/51 BF-7728

KALE, Richland, Wash. 960 kc


KALE

MEASURED
NIGHT

KALE, RICHLAND, WASH.
4/3/52G

1 KW, U, DA-N

960 KC



APPL RECD 3/6/52 ACC 4/2/52 BL-4693

KALE, RICHLAND, WASH.


960 KC

KALE

MEASURED
NON-DAKALE, RICHLAND, WASH.
4/3/52G

1 KW, U, DA-N

960 KC



APPL RECD 3/6/52 ACC 4/2/52 BL-4693

KALE, RICHLAND, WASH.

960 KC


KARZ ~~KOOL~~

Measured Night
(8-26-66ct)

Station KOOL
Phoenix, Arizona

5kw, DA-N, U
960 kc

LIC 9-26-66



FCC File No. BL-11373
Accepted 8-10-66

Station KOOL
Phoenix, Arizona

960 kc


KARZ ~~KOOL~~

Measured Non-DA
(8-26-66ct)

Station KOOL
Phoenix, Arizona

5kw, DA-N, U
960 kc

109-26-66



N LAT. 33° 39' 12"
W LONG 111° 55' 39"

RMS: 425 MV/M
G: 90°-256'

5 KW INTO TOWER 3 WITH TOWERS 1 2 AND 4 FLOATING

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION KOOL
960 KC. 5 KW. DA N
PHOENIX, ARIZONA

MEASURED NON-DIRECTIONAL HORIZONTAL RADIATION

UNATTENUATED FIELD INTENSITY AT ONE MILE

660601

FIGURE 10A

FCC File No. BL-11373
Accepted *-10-66

Station KOOL
Phoenix, Arizona

960 kc

KARZ

K00L


Proposed Night
(9-28-65ct)

Station K00L
Phoenix, Arizona

5kw, DA-N, U
960 kc


3P 16 694
CP 10-18-65
CHG NIGHT LOC.
(TWO SITES)

BP 17 260
CHG DAY LOC
CP 8-12-66



N. LAT. 33° 39' 02"
W. LONG. 111° 55' 43"

S = 110°: 314'
G = 90°: 256'
RMS = 450 MV/M



PROPOSED HORIZONTAL RADIATION NIGHTTIME

UNATTENUATED FIELD INTENSITY
AT ONE MILE

HAMMETT & EDISON
CONSULTING RADIO ENGINEERS
SAN FRANCISCO

RADIO STATION K00L
960 KC. 5 KW. DA-N
PHOENIX, ARIZONA

650326


FIGURE 5B

FCC File No. BP-16694
Accepted 8-31-65

Station K00L
Phoenix, Arizona

960 kc

PROVOTUUA
 CK-LIC PATTERN 646
 RWG



NIGHT-TIME
 HORIZONTAL RADIATION PATTERN
 PROPOSED FOR
 RADIO STATION KOVO
 960 kc 1000 w
 Jay W. Wright


FIGURE 7


KAY K PROVO, UTAH


~~KOVO~~
960

APR 2 1948 G

N
O






ANTENNA PLACEMENT SKETCH		PATTERN SHAPE PARAMETERS						PATTERN SIZE		
		ANTENNA	TRUE ORIENTATION	SPACING	PHASING	FIELD RATIO	HORIZON-TAL FIELD INTEN-SITY	ELECTRICAL HEIGHT	ELEVATION ANGLE	RMS FIELD INTEN-SITY mv/m
		No	θ°	S°	ψ°	r	$E_{mv/m}$	h°	θ°	E_0
		1	0	0	0	1.0	92.6	90	0	128.6
		2	52	300	-125	0.606	56.1	90	10	
		3	232	300	+125	0.606	56.1	90	20	
		4							30	
		5							40	
		6							50	
		7							60	
		8							70	
		9							80	
		10								
		11							$E_s =$	mv/m
									$P_r =$	kw
Applicant: OSCAR C. HIRSCH										
Location: CAPE GIRARDEAU, MISSOURI										
FCC file: 84-P-4289							Pattern No. 470207			
Call Letters: KFVS							Supersedes 460702			
Frequency: 960 KC							Prepared by CARL E. SMITH			
Rated Power: 500 W							Date FEB 7, 1947			

PROPOSED HORIZONTAL PLANE PATTERN

FIG. 1

6-4289



ANTENNA PLACEMENT SKETCH

Diagram illustrating the antenna placement sketch. The sketch shows three antennas (1, 2, 3) relative to North (N). Antenna 1 is at 0 degrees. Antenna 2 is at 52 degrees with a spacing of 300 units. Antenna 3 is at 232 degrees with a spacing of 300 units. The distance from the center to each antenna is 56.1 units. The angle between antennas 2 and 3 is 92.6 degrees.

PATTERN SHAPE PARAMETERS

PATTERN SIZE

ANTENNA	TRUE ORIENTATION	SPACING	PHASING	FIELD RATIO	HORIZONTAL FIELD INTENSITY	ELECTRICAL HEIGHT	ELEVATION ANGLE	RMS FIELD INTENSITY
No	θ°	S°	ψ°	r	E_{mvm}	A°	θ°	E_0
1	0	0	0	1.0	92.6	90	0	128.6
2	52	300	-125	0.606	56.1	90	10	
3	232	300	+125	0.606	56.1	90	20	
4							30	
5							40	
6							50	
7							60	
8							70	
9							80	
10								
11								

Applicant	OSCAR C. HIRSCH
Location	CAPE GIRARDEAU, MISSOURI
FCC file	84-P-4289
Call Letters	KFVS
Frequency	960 KC
Rated Power	500 W
Pattern No.	470207
Supersedes	460702
Prepared by	CARLE E. SMITH
Date	FEB. 7, 1947

EXPANDED HORIZONTAL PLANE PATTERN

FIG. 2

P-42-89


KGIR

KFVS

Measured Night
(10-28-68ct)

Station KFVS
Cape Girardeau, Missouri

500w, 5kw-LS, DA-K, U
960 kc



FCC File No. BZ-6970
Accepted 10-25-68

Station KFVS
Cape Girardeau, Missouri

960 kc


KG1K

KFVS

Measured Night Nulls
(10-28-68ct)

Station KFVS
Cape Girardeau, Missouri

500w, 5kw-LS, DA-N, J
960 kc



FCC File No. B7-6970
Accepted 10-25-68

Station KFVS
Cape Girardeau, Missouri


960 kc

KG1K ~~KFVS~~

Measured Non-DA
(10-28-68ct)

Station KFVS
Cape Girardeau, Missouri

500w, 5kw-LS, DA-N, U
960 kc.



FCC File No. 82-6970
Accepted 10-25-68


Station KFVS
Cape Girardeau, Missouri

960 kc

KG I K ~~KFVS~~
960

9/8/48


30 granted CP to
increase ray (ND)
power to 5 kw - 6-5-61
3.62 - granted L to increase ND power.



KFVS Directional Antenna
Measured horizontal pattern
f = 960 kc
P = 500 watts
rms = 125 mv/m at 1 mile.

CAPE GIRARDEAU Mo

9/7/48G

KGIR ~~KFVS~~
960

o Directional Antenna Measurements
 x Non-Directional Measurements
 converted by directional non-
 directional ratio measurements.

KFVS Directional Antenna
 Expanded horizontal plane pattern.
 f- 960 kc.
 P- 500 watts.
 rms- 125 mv/m at 1 mile.

CARE GIRARDEAU, Mo.

KGIR KFVS


MEASURED
DAY(non-DA)

KFVS, CAPE GIRARDEAU, MO.

License 7-12-48

500w, 1kw-LS, DAN 960 kc


4/14/49G



SITE: 37° 19' 10" N
89° 28' 40" W

K F V S Non-Directional Antenna
Measured horizontal pattern.
f= 960 kc.
P= 1 kw (daytime)
rms= 191 mv/m at one mile
P= 500 watts
rms= 135 mv/m at one mile

KFVS, Cape Girardeau, Mo. 960 kc



PAT #	H32N11		
NO. TOWERS	2		
S°	219°	S'	623.5'
#	33.5	r	.78
1 KW RMS	188		
KW RMS			
TOWER LINE	211.5	°TRUE	
VL Deg.	86.4°		
VL Feet	246		
OA Feet	251		
PAT.	1.0414		
UNIT rms:	K:	180.5	



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON, D. C. HOLLYWOOD


PATTERN **PROPOSED NIGHTTIME**
 FOR **KGKL, SAN ANGELO, TEXAS**
 POWER **1 KW** FREQ **960 KC**
 DATE **1/31/46** BY **ELD**

MEASURED NIGHT

Station KGXL
San Angelo, Texas1kw, 5kw-LS, DA-N, U
960 KC

NGN

EXHIBIT NO. 3-d



PATTERN H32N11 PROOF

Power: 1 KW-N 5KW-D DA-N

Frequency: 960 KC

No. Towers: 2

Spacing : 219°

Phasing : 33.5° $r = .78$

Tow. Line : 211.5°

" Height : 246'



COMMERCIAL RADIO EQUIPMENT CO.

Consulting Radio Engineers

KANSAS CITY

WASHINGTON D C

HOLLYWOOD

FOR: SAN ANGELO, TEXAS


DATE: June 4 '47

BY: KMH


KGWA

ENID, OKLA.
960 KC 1KW D N

3/11/48



PUBLIC BROADCASTING SERVICE INC. ENID, OKLAHOMA		Figure 1 Series 480213C
PROPOSED DIRECTIONAL ANTENNA PATTERN		960 KC 1000 WATTS DAY-NIGHT
		FRANK H. McINTOSH <i>Consulting Radio Engineer</i> Washington, D.C.



SPACING
1-2 = 200°
3-4 = 200°
1-4 = 90°
2-3 = 90°
H = 90°

Rec'd. 2-26-48

Amendment To BP-5821

KGWA

MEASURED
NIGHT&DAY

KGWA, ENID, OKLA.

330°
10°

3. 1kw, DA-1

960 kc

5/10/50G

Engineer: Doyle E. Collup

SITE: 36° 26' 13" N
97° 55' 16" W

BL-3992


recd 3-14-50

Granted 5-2-50

120
21.50
260
300
23.5 mv
10.5 mv
9.5 mv
16.0 mv
KMA

CODER BOOK COMPANY, INC. NORWOOD, MASSACHUSETTS

NO. 3224. POLAR CO-ORDINATE.



150°
210°

160°
200°

170°
190°

EXHIBIT 8

190°
170°

200°
160°

KGWA, Enid, Okla. 960 kc

KGWA
960 kc 1 kw DA-1
H 900
1-2, 3-4 = 200° 569'
1-4, 2-3 = 90° 256'

KLAD

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KLAD

Main Studio: Klamath Falls, Oregon

Frequency: 960 kHz

Power: 5kw

Notification List No. 1773

Date March 29, 1978

Class: III

GEOGRAPHICAL LOCATION OF THE CENTERS
OF THE DAYTIME AND NIGHTTIME ANTENNA SYSTEMS:

DAYTIME

42° 11' 38" North Latitude
121° 22' 27" West Longitude

NIGHTTIME

42° 09' 43" North Latitude
121° 39' 02" West Longitude

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 4

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWERS:	W (#4)	(#3)	(#2)	E (#1)
HEIGHT ABOVE INSULATORS:	260'	260'	260'	260' (91.2°)
PHASING:	-45	-255°	+255°	+45°
FIELD RATIO:	1.0	2.8	2.8	1.0
SPACING AND ORIENTATION:	Adjacent towers in a row are spaced 228' (80°) on a line bearing 301° true.			
GROUND SYSTEM:	120-256' equally spaced copper radials plus 120-50' interspaced radials about each tower. Radials are shortened and bonded to transverse straps along intersections between towers.			

DAYTIME ANTENNA CHARACTERISTICS

Authorized to Daytime operation (ND)

Height above insulators: 320' (112.4°)

Ground System: 120-175' equally spaced copper radials
about the towers.


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	416 mv/m	—	—
Night	464.60 mv/m	1056.63 mv/m	488.62 mv/m

Note: This notification concerns only a change to add new nighttime operation with Daytime operation continued as previously notified.

STANDARD HORIZONTAL PLANE PATTERN, NIGHTTIME

KLAD



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
Q=260'		TOWER #	ELECTRICAL HEIGHT	TOWER OPERATING	SPACING	PHASING	HORIZONTAL FIELD	FREQ. RATIO	ELEV. ANGLE	STATION DATA	
		1	91.2	50	5	25	1.5	1.5	1.5	CALL	
		2	91.2	50	5	25	1.5	1.5	1.5	FREQUENCY	
		3	91.2	50	5	25	1.5	1.5	1.5	POWER	
		4	91.2	50	5	25	1.5	1.5	1.5	TIME OF OPERATION	
		5								DATE OF OPERATION	
		6								DATE OF OPERATION	
		7								DATE OF OPERATION	
		8								DATE OF OPERATION	
		9								DATE OF OPERATION	
		10								DATE OF OPERATION	
		DATE OF OPERATION								DATE OF OPERATION	
GEOL. LYNCH, CONSULTING ENGINEER MODESTO, CALIFORNIA		960 RADIO, INC. (KLAD) ALAMATH FALLS, OREGON								FIGURE 4	
										Amended December 1973	
• PROPOSED AMENDED OPERATION, 5 KW U DAY-N (PRESENT OPERATION 5 KW NO-D) •										SEPTEMBER 1973 •	


SEPTEMBER 1973

PROPOSED NIGHT
(9-4-59g)

Station KMA
Shenandoah, Iowa


5kw, DA-N,U
960 KC

*granted CP to replace two towers
(10-2-59)
granted L for changes in Topload 5-18-60*



HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION



$$S_F 199' = 69.89^\circ$$

$$G_1 = G_3 = 84.29^\circ \text{ TOP LOADED}$$

$$G_2 = 168.59^\circ$$

APPLICANT	KMA
LOCATION	SHENANDOAH, IOWA
FREQUENCY	960 KC/S
POWER	5 KW
NL	40° 46' 48"
WL	95° 21' 23"
WHEN USED	NITES
R.M.S. FIELD	454, 14
DATE	JULY 1959

SILLIMAN, MOFFET & ROHRER
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BP-13317
Accepted 8-17-59

KMA
Shenandoah, Iowa

960 KC


KMA

PROPOSED NIGHT NULLS
(9-4-59g)

Station KMA
Shenandoah, Iowa

5kw, DA-N,U
960 KC

*Granted CP to replace two towers
(10-6-59)
Granted L for changes in Sept. 1-18-61*



HORIZONTAL RADIATION PATTERN

EXPANDED VIEW

APPLICANT	KMA
LOCATION	SHEANDOAH, IOWA
FREQUENCY	960 KC/S
POWER	5 KW
NL	40° 46' 48"
WL	95° 21' 23"
WHEN USED	NITES
RMS FIELD	454.14 MV/M
DATE	JULY 1959
SILLIMAN, MOFFET & ROHRER CONSULTING RADIO ENGINEERS WASHINGTON, D.C.	

FCC File No. BP-13317
Accepted 8-17-59

KMA
Shenandoah, Iowa

960 KC


FIGURE 1.A

WASHINGTON, DC

MEASURED NON-DA
(3-8-61g)

Station KMA
Shenandoah, Iowa

5kw, DA-N,U
960 KC



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT	KMA
LOCATION	SHENANDOAH, IOWA
FREQUENCY	960 KC/S
POWER	5 KW
LATITUDE	40 DEG 46 MIN 48 SEC
LONGITUDE	95 DEG 21 MIN 23 SEC
WHEN USED	DAYTIME
R & S FIELD	579.6 MV/M
DATE	DECEMBER 1960
SILLIMAN, MOFFET & ROHRER	
CONSULTING RADIO ENGINEERS	
WASHINGTON, D.C.	

FCC File No. BL-8229
Accepted 2-23-61

KMA
Shenandoah, Iowa

960 KC


KNEB

PROPOSED
DAYTIME

KNEB, SCOTTSBLUFF, NEBR.

500w, 1kw-LS, DA-2

960 kc



AMENDMENT RECD. 9-1-50 ACC. 9-8-50 BP-7035

KNEB, Scottsbluff, Nebr. 960 kc


KNEB

MEASURED
DAY

KNEB, SCOTTSBLUFF, NEB.

500w, 1kw-LS, DA-2

960 kc



KNEB, Scottsbluff, Neb. 960 kc

960 kc

KNEB, Scottsbluff, Nebr. 960 kc


KNEB

MEASURED
NIGHT

KNEB, SCOTTSBLUFF, NEB.

500w, 1kw-LS, DA-2

960 kc



KNEB, Scottsbluff, Neb. 960 kc


KNEB

MEASURED
NIGHT NULLS

KNEB, SCOTTSBLUFF, NEB.

500w, 1kw-IS, DA-2

960 kc




KNEB, Scottsbluff, Neb. 960 kc

500w, ~~1kw~~-LS, DA-N, U
960 KC

8158-2-17-61
 Amend to delete request
 for increase in pay
 -5-61
 united up to
 still DA-N

PROPOSED NIG
 (8-2-60g)
 NO post

KACL
 330°
 320°
 310°
 300°
 290°


[illegible]

KNEZ

PROPOSED NIGHT NULLS
(8-29-60g)

Station KNEZ
Lompoc, California

500w, 1kw-LS, DA-N, U
960 KC



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS							STATION DATA	
TOWER NO.	ELECTRICAL HEIGHT G	TRUE TOWER ORIENTATION D	SPACING S	PHASING V	HORIZONTAL FIELD M	FIELD RATIO F	ELEVATION ANGLE D	ELEVATION H	GAIL KNEZ	
1							0		FREQUENCY 960	KC
2							10		POWER 0.5	W
3							20		TIME OF OPERATION U	
4							30		TYPE OF OPERATION DA-N	
5							40		LAYTIME TOWERS F	
6							50		NIGHTTIME TOWERS S	
7							60		N. FACTOR 100	
8							70		CONDUCTANCE	
9							80		GROUND RESISTANCE	
10							90			
11							100			
12							110			
13							120			
14							130			
15							140			
16							150			
17							160			
18							170			
19							180			
20							190			
21							200			
22							210			
23							220			
24							230			
25							240			
26							250			
27							260			
28							270			
29							280			
30							290			
31							300			
32							310			
33							320			
34							330			
35							340			
36							350			
37							360			

L-11 (V-11)
 FROM 11-11-60
 KNEZ
 LOMPOC, CALIF.



Approved 7-11-60
 Thomas H. Ferguson
 Consulting Engineer

500w, DA-N, U
960 kc

Station KNEZ
Lompoc, California

140 333 1442

1-25-63
granted L
or change in hours & DA-N



960 kc

KNEZ

Measured Non-DA
(9-27-62ct)

Station KNEZ
Lompoc, California

500w, DA-N, U
960 kc




FIGURE NO. 11

NON-DIRECTIONAL RADIATION PATTERN BASED ON FIELD INTENSITY MEASUREMENTS

960 KC 0.5 KW DA-N

STATION KNEZ — LOMPOC, CALIFORNIA



— JUNE / 1962


FCC File No. BL-9511
Accepted 8-22-62

Station KNEZ
Lompoc, California

960 kc

960 kc

WABG



MEASURED
NIGHT


WABG, GREENWOOD, MISSISSIPPI

500W, 1KW-LS, U, DA-N

960 KC

WABG

7/5/51G



John Creutz
Consulting Radio Engineer
319 Bond Bldg. Republic 2151
Washington, D. C.

APPL RECD 6/26/51

WABG, GREENWOOD, MISSISSIPPI, 960 KC


WBOC

PROPOSED DAY
(11-28-55G)

STATION WBOC
SALISBURY, MARYLAND

1KW, 5KW-LS
DA-2, U

960 KC



Granted license 11/25/56

MEASURED DAY
010-21-56g)

Station W B O C
Salisbury, Maryland


1 KW, 5 KW, DA-2, U

W B O C
960 K C

A. D. RING & CO - 1/52 - 1000



(1) 0 — 90° — 0 — 143° T
(256.2 FT.)
COMPUTED: 1/0°
MEASURED: 1/0°
1/-48°
1.23/-45°



38° 23' 03" Latitude
75° 34' 48" Longitude

FCC File No.
BL-6351

Accepted 10-12-56

Station W B O C
Salisbury, Maryland


960 K C

MEASURED NON-DA Station W B O C
(10-21-56g) Salisbury, Maryland

1 KW, 5KW, DA-2, U 960 K C

WBOC

granted license 1/2 5/56



A. D. RING & ASSOCIATES - 1/14 - M

FCC File No.
BL-6351


Accepted 10-12-56

Station W B O C
Salisbury, Maryland

960 K C

MM-2550

WBOC-960 KC



1 — 90° — 2 — 143° TRUE —
 $\frac{1}{\sqrt{2}}$ 0.82/-151°
 G=142° G=90°




WBOC

MEASURED NIGHT
(2/7/57g)

Station WBOC
Salisbury, Maryland

1KW, DA-N, U
960 KC →

330° 340° 350° 10° 20° 30°




Measured Night
(3-22-71ct)

Station WBRC
Birmingham, Alabama

WBRC
5kw, DA-N, U
960 kc

EUGENE DIETZGEN CO.
MADE IN U. S. A.

NO. 341-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-12880
Accepted 2-26-71

Station WBRC
Birmingham, Alabama

960 kc

Measured Non-DA
(3-22-71ct)


Station WBRC
Birmingham, Alabama

WBRC
5kw, DA-N, U
960 kc

COHEN & DIPPILL
CONSULTING ENGINEERS
RADIO - TELEVISION
WASHINGTON, D.C. 20004

EUGENE DIETZGEN CO.
MADE IN U. S. A.

NO. 341-P DIETZGEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-12880
Accepted 2-26-71

Station WBRC
Birmingham, Alabama

960 kc

Proposed Night
(8-26-70ct)

Station WBRC
Birmingham, Alabama

5kw, DA-N, U
960 kc


SEE REVERSE SIDE

WBRC

GOMEN & DIPPILL

CONSULTING ENGINEERS
RADIO TELEVISION
WASHINGTON, D.C. 20004

V = 0



$.91 \pm 107.8^\circ$ 1.010
 $N 10^\circ E, TRUE$ 110.7° 110.7°
HEIGHT NO. 1 = 281.14' HEIGHT NO. 2 = 277.45'

NORTH LATITUDE: 33° 42' 00"
WEST LONGITUDE: 86° 45' 00"

COMPUTED HORIZONTAL
PLANE RADIATION PATTERN
FOR THE PROPOSED NIGHT-TIME OPERATION OF
WBRC, BIRMINGHAM, ALABAMA
960 KHZ - 5 KW - DA-N U
JULY 1970

FCC File No. BP-18810
Accepted 7-31-70

Station WBRC
Birmingham, Alabama

960 kc


SEE REVERSE SIDE

WBRC

5kw, DA-N, U
960 kc

Station WBRC
Birmingham, Alabama

Proposed Night Nu11s
(8-26-70ct)




960 KC

Station WBRU
Birmingham, Alabama

FCC File No. BP-18810
Accepted 7-31-70


PAGE & DAVIS
Consulting Radio Engineers
WASHINGTON, D. C.



WBRC, BIRMINGHAM, ALABAMA
DIRECTIVE ANTENNA FOR NIGHTTIME USE
HORIZONTAL PLANE PATTERN
UNATTENUATED FIELD AT ONE MILE
960 KILOCYCLES 5 KILOWATTS


PAT. NO. 410228
SUPER. 390800

PAGE & DAVIS
Consulting Radio Engineers
WASHINGTON, D.C.



MEASURED GROUND WAVE FIELD INTENSITY PATTERN
FOR W B R C PROOF OF PERFORMANCE
FEBRUARY, 1941

WBRC

MEASURED NIGHT
(11-16-59g)Station WBRC
Birmingham, Alabama5kw, DA-N,U
960 KCFCC File No. BZ -4188
Accepted 10-28-59WBRC
Birmingham, Alabama

960 KC


WOLM


Proposed Day
(4-29-69)

Station WOLM
East Moline, Illinois

1kw, DA-D, D
960 kc

granted 4/14/69 CR
increase 1180W



TOWER PLACEMENT SKETCH	PATTERN PARAMETERS						STATION DATA	
	Frequency	Power	Height	Distance	Angle	Gain	Call	WOLM
	40	0	0	0	131	1.0	960	960
	90	82	200	20	171	1.5	1 kw	1
							DA-D	
							Class III	
							162	
							120	
							90 - 2-6-20	
							20-20	
							41 24 47	
							90 23 44	
							600 111	
							590 217	

CARL E. SMITH
CONSULTING RADIO ENGINEERS

FIG. 1A
DIRECTIONAL ANTENNA
THEORETICAL HORIZONTAL PATTERN
RADIO STATION WOLM
960 kHz 1 kw DA-D

FCC File No. BP-18575
Accepted 4-9-69

Station WOLM
East Moline, Illinois

960 kc


WDLM

Measured Day
(6-27-69ct)

Station WDLM
East Moline, Illinois

1kw, DA-D, D
960 kc

BL-12361
Granted
8/6/69 license
to increase
MECV



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS						STATION DATA	
		ANGLE DEG	HEIGHT FEET	ANGLE DEG	HEIGHT FEET	ANGLE DEG	HEIGHT FEET	STATION NAME	WDLM
		90	0	0	0	133	1.0	MEASURED FIELD STRENGTH mV/m	179.5
		90	82	200	20	173	1.3	POWER kW	1
								MECHANICAL CLASS	DA-D
								PERFORMANCE CLASS	Class III
								SERVICE CLASS	No. 1 & 2
								ANTENNA HEIGHT	120
								ANTENNA DIA	90 x 256
								ANTENNA AREA	20 x 20
								ANTENNA WGT	41 24 57
								ANTENNA WGT	90 23 54
								FILE NO.	680702
								FILE NO.	681217


FIG. 6
DIRECTIONAL ANTENNA
MEASURED HORIZONTAL PATTERN
RADIO STATION WDLM
960 kHz 1 kw DA-D

WDLM

MEASURED NON-DA
(4-22-60g)

Station WDLM
East Moline, Illinois

1kw, DA-D,D
960 KC



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
	TOWER NO.	ELECTRICAL HEIGHT ft	TRUE TOWER DEVIATION deg	SPACING ft	PHASING deg	HORIZONTAL FIELD mV/m	FIELD mV/m	ELEV ANGLE deg	ELEVATION ANGLE deg	CALL	WDLM
	1	90						0	98.7	FREQUENCY	960
	2							10		POWER	0.25
	3							20		TIME OF OPERATION	DA-D
	4							30		TYPE OF OPERATION	CLASS III
	5							40		DAYTIME TOWERS	No. 1 & 2
	6							50		NIGHTTIME TOWERS	
	7							60		NO. BANDS USED	120
	8							70		LENGTH OF RADIUS	90' 256"
	9							80		GROUND WAVE DIMENSION	20' 120"
10							90		LAT	41° 24' 5"	
										LONG	90° 23' 54"
										NO. BANDS USED	120
										PATTERN NO.	600309

CARL E. SMITH
CONSULTING RADIO ENGINEERS

FIG. 6.12
250 WATT NON-DIRECTIONAL
MEASURED HORIZONTAL PATTERN
MOODY BIBLE INSTITUTE
EAST MOLINE, ILLINOIS

FCC File No. BL-7880
Accepted 4-13-60

WDLM
East Moline, Illinois

960 KC


DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WEAV Main Studio: Plattsburgh, New York
Frequency : 960 KHz Power : 5 kW Night 5 kW Day
Notification : 1780 Date : Sept. 28, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude:	<u>44</u>	<u>34</u>	<u>27</u>
West Longitude:	<u>73</u>	<u>26</u>	<u>54</u>

Note: Please retain the description sheet and the daytime and nighttime (vertical sections) directional antenna radiation patterns notified for station WEAV in United States Change List Number 628, dated Oct. 19, 1951 and attach to this supplemental Description Sheet and nighttime horizontal directional antenna radiation pattern. This notification is for the purpose of indicating only the addition of MEOV's to the nighttime horizontal directional radiation pattern.




WEAV

PROPOSED DAY
10/6/55G

STATION WEAV
PLATTSBURG, N. Y.

5 KW
DA-2, U

960 KC




WEAV

MEASURED DAY
(3/29/57g)

Station WEAV
Plattsburg, New York

5KW, DA-2, U
960 KC



3 ϕ 1.0/-174° G = 90° (256') 90° (256') 2 ϕ 1.29/+195° 90° (256') 1 ϕ 0.45/-174° N 178° E	FIELD INTENSITY VERSUS AZIMUTH	
	ELEVATION ANGLE ϕ RMS 435 MV/M	PLATTSBURG BROADCASTING CORPORATION 960 KC - 5 KW - (DA-2) PLATTSBURG, NEW YORK MEASURED DAYTIME PATTERN
	N. LATITUDE 44° 34' 27" W. LONGITUDE 73° 26' 54"	
	SUPERSEDES 561110 PATTERN NO. 570305	
	RUSSELL P. MAY CONSULTING RADIO ENGINEER WASHINGTON 5, D.C.	
FIGURE NO. 6A		

FCC File No. BL-6435
Accepted 3/19/57

Station WEAV
Plattsburg, New York


960 KC

PROPOSED NIGHT
(9/8/55G)

STATION WEAV
PLATTSBURG, NEW YORK

5 KW
DA-2, U

WEAV
960 KC





MEASURED NIGHT
(2/20/57g)

WEAV
Plattsburg, New York

5KW, DA-2, U

960 KC



FIELD INTENSITY VERSUS AZIMUTH

ELEVATION ANGLE 0°

RMS 440 MV/M

N. LATITUDE 44° 34' 27"

W. LONGITUDE 73° 26' 54"

SUPERSEDES

PATTERN NO. 561110

RUSSELL P MAY
CONSULTING RADIO ENGINEER
WASHINGTON 5, D. C.

PLATTSBURG BROADCASTING
CORPORATION
960 KC 5KW DA-2
PLATTSBURG, NEW YORK

MEASURED NIGHTTIME PATTERN

FIGURE NO. 7

FCC File No. BL-6435
Accepted 12/17/56

WEAV
Plattsburg, New York


960 KC

MEASURED NON-DIRECTIONAL
(2/20/57g)

WEAV
Plattsburg, New York

WEAV
5KW, DA-2, U
960 KC

granted license 3/25/57



FIELD INTENSITY VERSUS AZIMUTH

ELEVATION ANGLE 0°

RMS 133 MV/M (500 WATTS)

N. LATITUDE 44° 34' 27"

W. LONGITUDE 73° 26' 54"

SUPERSEDES

PATTERN NO. 561110

RUSSELL P. MAY
CONSULTING RADIO ENGINEER
WASHINGTON 3, D.C.

PLATTSBURG BROADCASTING
CORPORATION

960 KC-5 KW-(DA-2)

PLATTSBURG, NEW YORK

MEASURED NON-DIRECTIONAL
PATTERN


FIGURE NO. 5

FCC File No. BL-6435
Accepted 12/17/56


WEAV
Plattsburg, New York

960 KC

NO 340 F OIETZEN , PH PAGER
POLAR CO-ORDINATE



WELI-960 WELI
960



EUGENE DIETZEN CO
NEW HAVEN, CT

NO. 340-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE


FIG. 17
MEASURED DAYTIME PATTERN
WELI 1KW, DA-N 960KC
NEW HAVEN, CONNECTICUT
Prepared by
Lohnes & Culver Wash., D.C.
September 1947

PROPOSED NIGHT
(3-3-58g)

Station WELI
New Haven, Connecticut

5kw, DA-N,U
960 KC

*Granted CP 11/19/58
for increase in
power to 5 DA-N*



WELI

MEASURED NIGHT
(5-27-60g)

Station WELI
New Haven, Connecticut

5kw, DA-N,U

960 KC

*1-18-60
faded L for
increase in light
over*





FIGURE 8
HORIZONTAL RADIATION PATTERN
(DA-N OPERATION)
CONNECTICUT RADIO FOUNDATION, INC.
WELI 5 KW-U, DA-N 960 KC
NEW HAVEN, CONNECTICUT
Prepared by
Lohnes and Culver
Washington 4, D.C.
March 1960



North Latitude 41° 22' 14"
West Longitude 72° 56' 15"

FCC File No. BL-7888
Accepted 5-3-60

WELI
New Haven, Connecticut

960 KC


WELI

MEASURED NON-DA
(5-27-60g)

Station WELI
New Haven, Connecticut

5kw, DA-N,U

960 KC



FCC File No. BL-7888
Accepted 5-3-60

WELI
New Haven, Connecticut

960 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WFGL

Main Studio: Fitchburg, Massachusetts

Frequency: 960 kHz

Power: 1kw Night 2.5kw Day

Notification List No. 1788

Date: August 22, 1980 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 42° 35' 24"
West Longitude: 71° 49' 41"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 4

Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	SE(#1)	SC(#2)	NC(#3)	NW(#4)
INSULATORS:	250'	250'	250'	250' (87.8°)
NIGHT PHASING:	0°	+166.9°	-36.4°	+124.7°
NIGHT FIELD RATIO:	1.0	1.75	1.445	0.466
DAY PHASING:	0°	+200.85°	+100°	—
DAY FIELD RATIO:	1.0	1.674	0.509	—

SPACING AND
ORIENTATION:

Adjacent towers in a row are spaced 256.14' (90°) on
a line bearing 317.5° true.


GROUND SYSTEM: 120 - 260' equally spaced copper radials about each tower.
Radials are shortened and bonded to transverse straps along
intersections between towers. Centers of system are bonded
together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Day	298.2 mv/m	381.0 mv/m	313.2 mv/m
Night	191 mv/m		

Note: Please retain the Nighttime directional antenna radiation pattern notified for Station WFGL in United States Change List Number 757 dated May 7, 1958 and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in the Daytime operation of the station with Nighttime operation continued as previously notified.

AMENDED STANDARD PATTERN



PROPOSED DAY
(10-20-57g)


Station WFGM
Fitchburg, Massachusetts

1kw, DA-2,U

960 KC

~~WFGM~~
~~WFGL~~

*Granted CP (5/7/58)
for change in freq.
increase in hrs.
& for DA system*



A. D. RING & CO - 1/52 - 1000

~~WFGM~~
WFGM

MEASURED DAY
(3-23-59g)

Station WFGM
Fitchburg, Massachusetts

1kw, DA-2,U
960 KC





FIGURE 1-C

HORIZONTAL RADIATION PATTERN

ORIENTATION AND SPACING OF ARRAY



APPLICANT - THE WACHUSETT BCASTG. CORP.
LOCATION - FITCHBURG, MASS. (WFGM)
FREQUENCY - 960 KC/S
POWER - 1 KW-U (DA-2)
LATITUDE - 42 DEG 35 MIN 24 SEC
LONGITUDE - 71 DEG 49 MIN 45 SEC
WHEN USED - DAYTIME
RMS FIELD - 203 MV/M
DATE - DECEMBER 1958

SILLIMAN, MOFFET & ROHRER
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-7367
Accepted 2-17-59

WFGM
Fitchburg, Massachusetts


960 KC

PROPOSED NIGHT
(12-20-57g)

Station WFGM
Fitchburg, Massachusetts

1kw, DA-2, U
960 KC

~~WFGM~~
WFGL



FCC File No. BP-11,145
Accepted 12-6-57 (Amended)

WFGM
Fitchburg, Massachusetts

960 KC

revised C.P.
12/58 for change
in freq, increase
in hrs. & for
A system


A. D. RING & CO - 1/52 - 1000

~~WFGM~~
WFGM


MEASURED NIGHT
(3-23-59g)

Station WFGM
Fitchburg, Massachusetts

1kw, DA-2,U
960 KC



HORIZONTAL RADIATION PATTERN



APPLICANT	THE WACHUSETT BCASTG. CORP.
LOCATION	FITCHBURG, MASS. (WFGM)
FREQUENCY	960 KC/S
POWER	1 KW-U (DA-2)
LATITUDE	42 DEG 35 MIN 24 SEC.
LONGITUDE	71 DEG 49 MIN 43 SEC.
WHEN USED	NIGHTTIME
RMS FIELD	178 MV/M
DATE	DECEMBER 1958

ROBERT M. SILLIMAN & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-7367
Accepted 2-17-59

WFGM
Fitchburg, Massachusetts


960 KC

~~WFGM~~
WFG-L

MEASURED NIGHT NULLS
(3-23-59g)

Station WFGM
Fitchburg, Massachusetts

1kw, DA-2, U
960 KC



O MEASURED RADIAL VALUES

FIGURE 1-B

HORIZONTAL RADIATION PATTERN

EXPANDED VIEW

APPLICANT	THE WACHUSETT BCAST. CORP.
LOCATION	FITCHBURG, MASS. (WFGM)
FREQUENCY	960 KC/S
POWER	1 KW-U (DA-2)
LATITUDE	42 DEG 35 MIN 24 SEC
LONGITUDE	71 DEG 49 MIN. 45 SEC
WHEN USED	NIGHTTIME
RMS FIELD	178 MV/M
DATE	DECEMBER 1958

SILLIMAN, MOFFET & ROHRER

CONSULTING RADIO ENGINEERS

WASHINGTON, D.C.

FCC File No. BL-7367
Accepted 2-17-59

WFGM
Fitchburg, Massachusetts

960 KC

~~WFGM~~
WFGM

MEASURED NON-DA
(3-23-59g)

Station WFGM
Fitchburg, Massachusetts

1kw, DA-2,U
960 KC




FIGURE 1-D

HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY


APPLICANT: THE WACHUSETT BCAST. CORP.
LOCATION: FITCHBURG, MASS.
FREQUENCY: 960 KE/S
POWER: 1 KW-D (DA-2)
LATITUDE: 42 DEG 35 MIN 24 SEC
LONGITUDE: 71 DEG 49 MIN 43 SEC
WHEN USED: NON-DIRECTIONAL SURVEY ONLY
R.M.S. FIELD: 195 MV/M
DATE: DECEMBER 1958

SILLIMAN, MOFFET & ROHRER
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-7367
Accepted 2-17-59


WFGM
Fitchburg, Massachusetts

960 KC



COMPUTED NIGHTTIME
 HORIZONTAL PLANE PATTERN
 UNATTENUATED FIELD AT ONE MILE
 WDBJ, ROANOKE, VIRGINIA
 WFIR 960 KC, 5 KW, DA-N
 FEBRUARY 1951

WFIR



MEASURED NIGHTTIME
HORIZONTAL PLANE PATTERN
UNATTENUATED FIELD AT ONE MILE
WDBJ, ROANOKE, VIRGINIA
960 KC, 5 KW, DA-N
FEBRUARY 1951


WFIR

MEASURED
NON-DA

WDBJ, Roanoke, Virginia
(5/4/54G)

5KW, DA-N

960 kc



MEASURED NON-DIRECTIVE
UNATTENUATED FIELD AT ONE MILE
WDBJ, ROANOKE, VIRGINIA
960 KC, 5 KW, DA-N
FEBRUARY 1951

FCC File No. BZ-3203

Accepted 2/23/51

WDBJ, Roanoke, Virginia

960 kc

WFTC

PROPOSED
NIGHT


WFTC, KINSTON, N. C. NORTH

350°
10°

340°
20°

1kw, DAN

960 kc




WFTC, Kinston, N. C. 960 kc

WFTC

MEASURED
NIGHT (5/27/53G)

WFTC, KINSTON, N. C. 1kw, 5kw-LS, DA-N

960 kc



DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WGRO Main Studio: Lake City, Florida
 Frequency : 960 KHz Power : 1 kW Night 0.5 kW Day
 Notification : 1780 Date : Sept. 28, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 30 10 33
 West Longitude: 82 40 18

PREDICTED DAYTIME EFFECTIVE FIELD (omnidirectional): 130 mV/m at rated power.

NIGHTTIME ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 2


Type of elements : Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER	:	<u>S(#1)</u>	<u>N(#2)</u>	_____	_____	_____
HEIGHT ABOVE INSULATORS	:	<u>240'</u>	<u>240'</u>	<u>(84.3°)</u>	_____	_____
PHASING	:	<u>0°</u>	<u>+47°</u>	_____	_____	_____
FIELD RATIO	:	<u>1</u>	<u>0.85</u>	_____	_____	_____
SPACING AND ORIENTATION	:	Towers in a row are spaced <u>455.4'</u> (<u>160°</u>) on a line bearing <u>338°</u> true.				
GROUND SYSTEM	:	<u>120 - 190'</u> to <u>250'</u> equally spaced copper radials plus a <u>48'</u> square ground screen about each tower. Radials are shortened and bonded to a transverse strap along intersections between towers.				


PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>
Night	<u>180.72</u> mV/m	<u>192.92</u> mV/m	<u>189.97</u> mV/m

Note: This notification concerns only the addition of Nighttime operation to the station with Daytime operation continued as previously notified.



HORIZONTAL RADIATION PATTERN



2.
WHYL

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WHYL

Main Studio: Carlisle, Pennsylvania

Frequency: 960 kHz

Power: 5 kW

Notification List No. 1652

Date: October 1, 1975

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 40° 11' 34"
West Longitude: 77° 10' 28"

ANTENNA CHARACTERISTICS

Authorized for Daytime operation. (DA-D)

Number of elements: 2

Type of elements: Series-excited, uniform cross-section, guyed,
vertical steel towers.

TOWER:	NW(#2)	SE(#1)	
HEIGHT ABOVE INSULATORS:	265'	265'	(93.1°)
PHASING:	+16°	0°	
FIELD RATIO:	0.6	1.0	

SPACING AND

ORIENTATION: Elements are spaced 569.2' (200°) on a line bearing 343° true.

GROUND SYSTEM: 120-260' equally spaced copper radials about each tower.

Predicted effective Field: 395 mv/m at rated power.

Note: This notification concerns changes in means of radiation in the
directional antenna pattern and in antenna height.

WHYL





FIGURE 1-A

HORIZONTAL RADIATION PATTERN

ORIENTATION AND SPACING OF ARRAY



G = 93.1°

APPLICANT :	RICHARD FIELD LEWIS, JR., INC.
LOCATION :	CARLISLE, PA. (WHYL)
FREQUENCY :	960 KC/S
POWER :	5 KW-D(DA)
LATITUDE :	40 DEG 11 MIN. 54 SEC.
LONGITUDE :	77 DEG 10 MIN 28 SEC.
WHEN USED :	DAYTIME
R.M.S FIELD:	595 MV/M (THEORETICAL)
DATE :	MARCH 1975
SILLIMAN, MOFFET & KOWALSKI CONSULTING RADIO ENGINEERS 211 FOURTEENTH STREET N.W. WASHINGTON D.C. 20005	

WHYL

PROPOSED
DAY (6-20-56g)

STATION WHYL
CARLISLE, PA.

5 KW
DA-D, D

960 KC

granted C P 11/28/58

*granted mod.
C P 4/30/58 to
change trans.
location
(see below)*

A. D. RING & CO. - 4/52 - 1000




FIGURE 1
PROPOSED HORIZONTAL
PLANE RADIATION PATTERN
WHYL
Richard F. Lewis, Jr., Inc. of Carlisle
Carlisle, Pennsylvania
Present: 960 kc 1 kw Day
Proposed: 960 kc 5 kw Day-DA
A. D. RING & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

MEASURED DAY
(12-12-58g)

Station WHYL
Carlisle, Pennsylvania

5kw, DA-D, D
960 KC





FIGURE 1-A

HORIZONTAL RADIATION PATTERN

ORIENTATION AND SPACING OF ARRAY



APPLICANT: RICHARD FIELD LEWIS, JR., INC.

LOCATION: CARLISLE, PENNSYLVANIA (WHYL)

FREQUENCY: 960 KC/S

POWER: 5 KW-(DA)

LATITUDE: 40 DEG 15 MIN 34 SEC

LONGITUDE: 77 DEG 10 MIN 28 SEC

WHEN USED: DAYTIME

R.M.S. FIELD: 375 MV/M

DATE: OCTOBER 1958

SILLIMAN, MOFFET & ROHRER

CONSULTING RADIO ENGINEERS

WASHINGTON, D.C.

FCC File No. BL-7282
Accepted 11-18-58

WHYL
Carlisle, Pennsylvania


960 KC

WHYL

MEASURED NON-DA
(12-12-58g)

Station WHYL
Carlisle, Pennsylvania

5kw, DA-D, D
960 KC



HORIZONTAL RADIATION PATTERN

NON - DIRECTIONAL SURVEY

APPLICANT : RICHARD FIELD LEWIS, JR., INC.
LOCATION : CARLISLE, PENNSYLVANIA (WHYL)
FREQUENCY : 960 KC/S
POWER : 1 KW.
LATITUDE : 40 DEG 11 MIN. 54 SEC
LONGITUDE : 77 DEG 10 MIN 28 SEC
WHEN USED: NON-DIRECTIONAL SURVEY ONLY
RMS FIELD: 168 MV/M
DATE : OCTOBER 1958

SILLIMAN, MOFFET & ROHRER
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-7282
Accepted 11-18-58

WHYL
Carlisle, Pennsylvania


960 KC

Proposed Day
(3-27-70ct)

Station WJAZ
Albany, Georgia

SEE
REVERSE
SIDE

WJAZ
5kw, DA-D, D
960 kc



FCC File No. BP-18714
Accepted 2-25-70

Station WJAZ
Albany, Georgia

960 kc

granted license 5/10/50 to increase
daytime (N-D) power to 5 KW.


WRFC

PROPOSED
NIGHT

WRFC, ATHENS, GA.

500w, 1kw-LS, DA-N

960 kc




AMENDMENT REC'D 10/25/50 AGC 11/3/50 BP-7415

WRFC, Athens, Ga. 960 kc

WRFC

960 kc



WRFC, Athens, Ga. 960 kc

granted license 5/10/57 to
increase daytime (H-D) power to 5 KW


WRFC

MEASURED
NIGHT

WRFC, ATHENS, GA.
11/11/51G

500W, 1 K-11, U, DA-N

960 KC



granted license 5/10/54 to
increase daytime (N-D) power
to 5 KW.

WRFC


MEASURED
NON-DA

WRFC, ATHENS, GA.
11/11/51

500W, 1 KW-LS, U, DA-N

960 KC

SOUTHEAST TOWER
INPUT 1KW.



DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : WSBT Main Studio: South Bend, Indiana
Frequency : 960 KHz Power : 5 kW Night 5 kW Day
Notification : 1780 Date : Sept. 28, 1979 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude:	<u>41</u>	<u>37</u>	<u>00</u>
West Longitude:	<u>86</u>	<u>13</u>	<u>01</u>

Note: Please retain the description sheet and directional antenna radiation patterns notified for station WSBT in United States Change List Number 363, dated June 1, 1946 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only correction in the geographical coordinates of the center of the antenna system.

Description Sheet
(8-23-63ct)

Station WSBT
South Bend, Indiana

5kw, DA-2, U
960 kc

Figure 1
Description of Antenna System
WSBT South Bend, Indiana
960 Kc 5 Kw DA-2 U
October 1962

A. Number of elements:

Daytime: Four towers (#1, 2, 3 & 5)

Nighttime: Four towers (#1, 2, 3 & 4)

B. Type of elements:

Self-supporting, tapered, insulated, series fed vertical radiators

C. Top loading:

None

D. Overall height above insulator:

Towers #1, 2, 3, & 4 = 265 feet

Tower #5 = 429 feet 7 inches

E. Overall height above ground:

Towers #1, 2, 3, & 4 = 273 feet

Tower #5 = 434 feet 7 inches

F. Overall height above mean sea level:

Towers #1, 2, 3, & 4 = 1146 feet

Tower #5 = 1304 feet 7 inches

G. Orientation and spacing:

Towers #1, 2, 3 and 4 spaced at 265 feet (93°) intervals along a bearing of N 352° E. Tower #5 is spaced 586 feet (205.87°) along a bearing of N 75.5° E from the south center tower #2.


H. Ground system:

120 equally spaced radials of #10 copper wire emanating from the base of each of the towers #1, 2, 3 and 4 outward to a distance of 425 feet (150°) or to the edge of the property. The radials were bonded to copper strapping where the radials intersected between towers. Tower #5 ground system consists of 120 equally spaced radials of #10 copper wire extended to 265 feet (93°) or to the edge of the property. The radials were bonded to the ground system of towers #1, 2, 3 and 4 at the points of intersection by the use of copper strapping. In addition, 48 feet square copper ground screen at the base of each tower bonded to the copper radials. #10 copper wire spaced at 20 degree intervals and extending outward 50 feet from the base of the new 1047.55 feet TV-FM tower.

Measured Day
(8-23-63ct)

Station WSBT
South Bend, Indiana

5kw, DA-2, U
960 kc



FCC File No. BL-9871
Accepted 8-1-63

Station WSBT
South Bend, Indiana

960 kc

WSBT

PROPOSED
DAY


WSBT, SOUTH BEND, IND.

350°

340°

5kw, DA-2

960 kc




WSBT

Measured Night
(8-23-63ct)


Station WSBT
South Bend, Indiana

5kw, DA-2, U
960 kc

7-30-63
sketch of
low range
in DA




WSBT
960



W S B T
330° 960

NORTH
O



NO. 340-P DIETZEN GRAPH PAPER
POLAR CO-ORDINATE
EUGENE DIETZEN CO
PRINTED IN U.S.A.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: WTCH

Main Studio: Shawano, Wisconsin

Frequency: 960 kHz

Power: 1 kW

Notification List No. 1599

Date: September 25, 1974

Class: II

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 44° 46' 47"

West Longitude: 88° 37' 53"

ANTENNA CHARACTERISTICS

Authorized for Nighttime operation. (DA-N)

Number of elements: 2

Type of elements: Series-excited, vertical steel towers.
Tower #2 is Self-supporting, tapered. Tower
#1 is uniform cross-section, guyed.

TOWER: S(#1) N(#2)

HEIGHT ABOVE

INSULATORS: 241.5' 241.5' (84.8°)

PHASING: 0° -132.3°

FIELD RATIO: 1 0.910

SPACING AND

ORIENTATION: Elements are spaced 199' (70°) on a line bearing 11° true.

GROUND SYSTEM: 120-240' to 256' equally spaced copper radials plus a
ground screen about each tower. Radials are shortened
and bonded to a transverse strap along intersections between
towers.


Predicted effective Night Field: 195 mv/m at rated power.

Predicted effective Day Field: (omnidirectional) 188 mv/m at rated power.


Note: Please retain the Nighttime vertical angle directional antenna radiation patterns notified for Station WTCH in United States Change List Number 426 dated October 18, 1951, and attach to this Revised Description Sheet and Nighttime Horizontal pattern. This notification concerns a change to add meows of radiation to the nighttime pattern with Daytime operation continued as previously notified.

CTR NO 30812A4

960 KC




WTCH



R.M.S. = 195 MV/M

PATTERN PARAMETERS



DIRECTIONAL RADIATION PATTERN

WTCH



☐ MEASURED ☒ PROPOSED
 FREQ: 960 (KHZ) POWER: 1.0 (KW) ☐ DA-D
 N. LAT. 114° 46' 47" ☒ DA-N
 W. LONG. 38° 37' 53" ☐ N-D

LOCATION: SHAWANO, WISCONSIN

DATE: AUGUST 1970

ROBERT A. JONES
 CONSULTING ENGINEERS
 LA GRANGE, ILLINOIS

FIGURE 1



DIRECTIONAL WTCH
RADIATION PATTERN
Shawano County Leader Publishing Co.


☒ MEASURED	☐ PROPOSED
FREQ: 960 (KHZ)	POWER: 1 (KW)
N. LAT. 44° 46' 47"	☒ DA-D
W. LONG. 88° 37' 53"	☒ DA-N
	☐ N-D

LOCATION: Shawano, Wisconsin

DATE: April, 1974

ROBERT A. JONES
CONSULTING ENGINEERS
LA GRANGE, ILLINOIS

960 KC



PROPOSED DAY &
NIGHT (6/6/56g)

STATION XEDF
NVO. LAREDO, TAMPS

1000 W-N, 5000 W-D
DA-1, CLASS III-A

960 KC

XEDF

DESCRIPCION DEL SISTEMA DIRECCIONAL DE RADIACION

ESTACION X E D F
FRECUENCIA 960 KHz.
CLASE III - A

ESTUDIOS EN Nvo. Laredo, Tamps.
1000 W-N
POTENCIA 5000 Watts-D
LISTA DE CABLES 182.

(Para llenarse por la Dirección General
de Telecomunicaciones.)

FECHA 23-VIII-55.
(Para llenarse por la Dirección General
de Telecomunicaciones.)

LOCALIZACION GEOGRAFICA DEL
SISTEMA RADIADOR

LONGITUD: 99° 30' 03"
LATITUD: 27° 29' 46"

AUTORIZADO PARA OPERACION

AD - I

NUMERO DE ELEMENTOS RADIADORES

DOS

TIPO DE ELEMENTOS RADIADORES

Torres verticales de acero soportadas
con retenidas.

TORRES

Norte Sur

ALTURA SOBRE LOS AISLADORES

78.07 mts. 78.07 mts.

SEPARACION ENTRE TORRES

45° = 39.03 mts

MAGNITUDES RELATIVAS DE CORRIEN-
TES.

1 1

DEFASAMIENTO

80° 0°

AZIMUT DEL EJE DE LAS TORRES

169°

RAIZ CUADRATICA MEDIA TEORICA

391.3 mv./m.

INTENSIDAD DE CAMPO R.C.M. NO
ATENUADO A UN KILOMETRO POR -
KILOWATT DE POTENCIA RADIADA

175 mv./m.

Indíquese si la operación es diurna, nocturna o diurna-nocturna.

REVISO:

Julio L. L.

APROBO:

[Signature]


XEDF

PROPOSED DAY &
NIGHT (6/6/56g)

STATION XEDF
NVO. LAREDO, TAMPS


1000 W-N, 5000 W-D
DA-1, CLASS III-A

960 KC



PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/m. A1609m.

Esquema de las torres y su orientación
con respecto al norte geográfico.



RADIODIFUSORA

XEDF

N. Laredo Tamps.

960 Khz.

5,000 Watts

CALCULO:
EQUIPOS TELEVISORES Y ELECTRONICOS
S. DE R. L.

SUPPLEMENTAL DIRECTIONAL
ANTENNA DESCRIPTION SHEET

Station: CBZ

Main Studio: Fredericton, N.B.

Frequency: 970 KHz

Power: 10 Kw, Class III

Notification List No: 325

Date: May 17, 1974

Geographical Location of
the Center of the Antenna System:

North Latitude: 45° 55' 34" }
West Longitude: 66° 38' 12" }

Mode of Operation - DA-N
ND-D-180

Note: Please retain the description sheet and directional antenna radiation patterns notified for station CBZ in Canadian Change List Number 192 dated December 14, 1964 and revised March 8, 1965 and attach to this supplemental description sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates.

Description Sheet
(5-27-65ct)

Station CBZ
Fredericton, N. B.

10kw, DA-N, U, Class III
970 kc

CANADIAN BROADCASTING CORPORATION

page 12

ENGINEERING DIVISION MONTREAL

TITLE Change in Frequency & Mode of
Operation - CBZ Fredericton, N.B.

DWG. No.
DATE Mar. 3/65 ISS. 2
ENG. J.H.S. APP. R.E.S.

CORRECTED

DESCRIPTION OF ANTENNA SYSTEM

Station: CBZ Main Studio: Fredericton
Frequency: 970 Kc/s Power: 10 KW Class: III

Geographical Location of Antenna Centre:

Latitude: 45° 55' ³⁴ 30" N
Longitude: 66° 38' ¹³ 12" W

Antenna Characteristics:

Day and Night Operation: DA-N Notification List No. 192
No. of Elements: 2 Date: December 14, 1964
Type of Elements: Series fed, uniform cross section guyed,
vertical steel towers.
Towers: 1 (S.W.) 2 (N.E.)
Height above insulators: 160 ft. (56.7°) 160 ft. (56.7°)
Night phasing: 0° -128.8°
Night field ratio: 1.0 1.0
Day phasing: --- 0°
Day field ratio: --- 1.0
Spacing and Orientation: Elements are spaced 165 ft. 3 ins. (58.63°)
apart and lie on a line bearing 39° true north.
Ground System: 120 Radials per tower, spaced at 3° and averaging
266 ft. long, except in the area between towers,
where the radials are bonded to a common transverse
copper strap midway between the towers.
Antenna Efficiency: Day: 570 mv/m for 10 KW
Night: 555 mv/m for 10 KW

NOTE: Please retain antenna radiation patterns notified for CBZ Fredericton,
N.B. in Change List No. 192, dated December 14, 1964 and attach to this
corrected description sheet. This only concerns a correction in the
spacing of the antenna elements.


March 8, 1965.

Transmission & Development Department

Proposed Night
(1-28-65ct)

Station CBZ
Fredericton, N.B.

10kw, DA-N, U, Class III
970 kc



PROPOSED DAY
AND NIGHT (1-13-55G)

CKCH
HULL, QUEBEC

5 KW
DA-1, CLASS III-A

970 KC/S.

5-10-159 Directional Antenna Description Sheet

<u>Station:</u>	CRCH	<u>Main Studio:</u>	Hull, Quebec		
<u>Frequency:</u>	970 kc/s.	<u>Power:</u>	5 Kw.	<u>Class:</u>	III-A
<u>Notification List No.</u>	89	<u>Date:</u>	December 3, 1954		

Geographical Location of the Centre of the Antenna System: North Latitude: 45° 22' 59"
West Longitude: 75° 48' 47"

Antenna: Mode of Operation: Directive array for Day and Night operation. DA-1

Elements: Three, guyed, uniform cross-section, insulated from ground, series fed, no top loading.

<u>Tower:</u>	No. 1 (S)	No. 2 (Centre)	No. 3. (NE)
<u>Height above insulators:</u>	240' (85°)	240'	240'
<u>Spacing:</u>	173' (61.5°) between adjacent towers		
<u>Phasing:</u>	+148.2°	0°	-148.2°
<u>Field ratio:</u>	.549	1	.549

Ground System: 120 r. disks per mast, approximately .4 wavelength.
#10 1/2 S copper wire, buried approximately 8".


Predicted Effective Field: 450 mv/m (201 mv/m at 1 Yr.)

Orientation: Line of Towers: 20° east of True North

(P.C. 970 kc. 1 kw. DA-1 U III)

ALLOCATION EXTRA
1. 1944
ENGINEERING DEPT.
STANDARD BROADCAST DIVISION

970 KC/S



CKCH, HULL, QUEBEC

970 KC/S

CJYZ

Description Sheet
(8-28-67ct)

New Station
Edson, Alberta

10kw, DA-1, U, Class III
970 kc

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

Station: NEW Main Studio: Edson, Alberta

Frequency: 970 kHz Power: 10 KW

Notification List: 229 Date: July 31, 1967.

GEOGRAPHICAL LOCATION: Latitude: 53° 32' 09" North
Longitude: 116° 36' 06" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-1
Number of Elements: Two (2)
Type of Elements: Guyed steel towers, uniform cross section, base insulated for series feed.

TOWER:	#1 SOUTH	#2 NORTH
HEIGHT ABOVE INSULATORS:	200' (71°)	200' (71°)
OVERALL HEIGHT:	205'	205'
FIELD RATIO:	1.0	.92
PHASING:	0°	-124°

GROUND SYSTEM: 120 equally spaced radials per tower of No. 10 B & S gauge bare copper wire, buried approximately 8". Length of radials 406' (0.4 wavelength) with the exception of those joined along the common chord.

SPACING AND ORIENTATION

OF TOWERS: Towers are on a line bearing 20° West of True North and are spaced 225.5' (80°) apart.

PREDICTED EFFECTIVE FIELD:

590 mv/m at 1 mile for 10 KW
186 mv/m at 1 mile for 1 KW

D. E. M. ALLEN, P. ENG.

BROADCAST CONSULTING ENGINEER

CJYR

Proposed Day & Night
(8-28-67ct)

New Station
Edson, Alberta

10kw, DA-1, U, Class III
970 kc

CED. & BODK COMPANY, INC. NORWOOD, MASSACHUSETTS
PRINTED IN U.S.A.

NO. 3124. POLAR CO-ORDINATE.





FIGURE 3
HORIZONTAL RADIATION PATTERN
POLAR PLOT
NEW AM STATION EDSON, ALBERTA
970 kHz 10 kW DA-1 CLASS III
PROJECT #5581 MAY 10, 1967
CONSULTANT: D.E.M. ALLEN, P. ENG.


CJYR

10kw, DA-1, U, Class III
970 kc

New Station
Edson, Alberta

Proposed Day & Night Nulls
(8-28-67ct)








FIGURE 3A

HORIZONTAL RADIATION PATTERN
DAYTIME - EXPANDED PLOT

CKCH HULL, QUÉBEC
970 kHz 10 kW D/5 kW N DA-2 CLASS III
PROJECT #15703 REVISED MARCH 17, 1981

DEM ALLEN & ASSOCIATES LTD
CONSULTING ENGINEERS

PROJECT #15703

CKCH

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

STATION: CKCH

MAIN STUDIO: Hull, Quebec

FREQUENCY: 970 kHz

POWER: 10 kW D/5 kW N CLASS: III

NOTIFICATION LIST NO.: 374

DATE: June 5, 1978

GEOGRAPHICAL LOCATION:

Latitude: 45° 22' 59" North

Longitude: 75° 48' 47" West

ANTENNA CHARACTERISTICS:

Mode of Operation:

DA-2

Number of Elements:

3 (Three)

Type of Elements:

Guyed steel towers, uniform cross-section, base insulated for series feed

TOWER:

#1
(SW)

#2
(C)

#3
(NE)

Height above Base

Insulator:

240' (85°)

240' (85°)

240' (85°)

Overall Height:

243'

243'

243'

Field Ratio:

Nighttime

.549

1.0

.549

Daytime

.52

1.0

.52

Phasing:

Nighttime

0°

-148.2°

+63.6°

Daytime

0°

-138°

+83.8°

Orientation:

Ref.

20°

20°

Spacing:

Ref.

173' (61.5°)

346' (123°)

GROUND SYSTEM:

120 radials of #10 Bare Soft Copper wire extend from the base of each tower for a distance of 406' (0.4 wavelength) with the exception of those joined along the common chords and those extending to the edge of the property. In addition, 120 radials, 50 ft. long, extend from the base of each tower.

PREDICTED EFFECTIVE FIELD:

Nighttime:

450 mV/m at 1 mile for 5 kW


201 mV/m at 1 mile for 1 kW


Daytime:

620 mV/m at 1 mile for 10 kW

196 mV/m at 1 mile for 1 kW

January 18, 1978








FIGURE 6

HORIZONTAL RADIATION PATTERN

NIGHTTIME - EXPANDED PLOT

HULL, QUEBEC

CKCH 50 kW D / 10 kW N DA-2 CLASS III
HULL, QUEBEC

970 kHz 50 kW D / 10 kW N



PROJECT #15701

D. E. M. ALLEN & ASSOCIATES LTD.
CONSULTING ENGINEERS

CKCH

G9-10159 (NO. 101V)

CO-ORDINATE
JULY 1974






VERTICAL RADIATION PATTERNS

FIGURE 7

CKCH
 970 kHz
 PROJECT #15701
 D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

50 kW D/10 kW N
 DA-2
 HULL, QUEBEC
 CLASS III
 JANUARY 24, 1975



VERTICAL RADIATION PATTERNS

FIGURE 8

CKCH

970 kHz

PROJECT #15701

50 kW D/10 kW N

DA-2



HULL, QUEBEC

CLASS III

JANUARY 24, 1975

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

22



VERTICAL RADIATION PATTERNS

FIGURE 9

CKCH

970 kHz

50 kW D/10 kW N

DA-2

HULL, QUEBEC



CLASS III

PROJECT #15701

JANUARY 24, 1975

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS





VERTICAL RADIATION PATTERNS

FIGURE 10

CKCH

970 kHz

PROJECT #15701

50 kW D/10 kW N

DA-2

D.E.M. ALLEN & ASSOCIATES LTD., CONSULTING ENGINEERS

HULL, QUEBEC

CLASS III

JANUARY 24, 1975

SP

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KAKC Main Studio: Tulsa, Oklahoma
Frequency: 970 kHz Power: 1kw Night 2.5kw Day
Notification List No. 1789 Date: September 12, 1980 Class: III
GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM: North Latitude: 36° 11' 46"
West Longitude: 96° 02' 22"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
Number of elements: 6
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel

TOWER:	NE(#1)	SSW(#2)	C(#3)	SW(#4)	NW(#5)	WSW(#6)
HEIGHT ABOVE INSULATORS:	260'	260'	260'	260' (92.3°)	338'	338' (120°)
NIGHT PHASING:	—	—	-21.2	-71.1	0	+6.8
NIGHT FIELD RATIO:	—	—	0.587	0.285	1.0	0.975
DAY PHASING:	-105.7	-73.6	0	+3.9	-76.0	-136.7
DAY FIELD RATIO:	0.65	0.07	1.0	0.45	0.258	0.313

SPACING AND
ORIENTATION:

With Tower #3 as reference, Tower #1 is spaced 232' (82.4°) on an azimuth of 49.9° true; Tower #2 is spaced 371' (131.5°) on an azimuth of 192.6° true; Tower #4 is spaced 609' (216°) on an azimuth of 216.3° true; Tower #5 is spaced 568' (201.6°) on an azimuth of 329.1° true and Tower #6 is spaced 634' (225°) on an azimuth of 260.4° true.

GROUND SYSTEM: 120-220' to 255' equally spaced copper radials plus 120-50' interspaced radials about each tower.


KAKC
970 kHz

PREDICTED EFFECTIVE FIELDS AT RATED POWER:


	THEORETICAL		STANDARD	
	<u>RMS</u>	<u>RSS</u>	<u>RMS</u>	
Day	291.5 mv/m	350.4 mv/m	306.2 mv/m	
Night	175.9 mv/m	313.9 mv/m	184.9 mv/m	

Note: Please retain the Nighttime directional antenna radiation pattern notified for Station KAKC in United States Change List Number 1726, dated March 24, 1977 and attach to this Revised Description Sheet and Daytime pattern. This notification concerns only a change in the Daytime operation of the station with Nighttime operation continued as previously notified.

KAKC
970KHZ



N. LAT. 36°11'46"
 W. LONG. 96°02'22"



PROPOSED STANDARD HORIZONTAL RADIATION DAYTIME

UNATTENUATED FIELD STRENGTH
AT ONE MILE

HAMMETT & EDISON, INC.
CONSULTING ENGINEERS
SAN FRANCISCO

RADIO STATION KAKC
970KHZ 1KW. 2.5KW-LS. DA-2
TULSA, OKLAHOMA

760305.4


FIGURE 4

PROPOSED DAY
(12-12-58g)

Station KAKC
Tulsa, Oklahoma

500w, 1kw-1.S, DA-2, U
970 KC

*Granted license
2/17/59 to
change location
& to make
changes in
PA-system
(decrease height)*




FCC File No. BP-11462
Accepted

KAKC
Tulsa, Oklahoma

970 KC

KAKC

MEASURED DAY
(12-12-58g)Station KAKC
Tulsa, Oklahoma500w, 1kw-LS, DA-2, U
970 KC*renewed license
2/17/59*FCC File No. BL-7293
Accepted 11-25-58KAKC
Tulsa, Oklahoma

970 KC


KAKC

MEASURED NON-DA
(12-12-58g)

Station KAKC
Tulsa, Oklahoma

500w, 1kw-LS, DA-2, U
970 KC

PAGE, CREUTZ, STEEL & WALDSCHMITT
Consulting Engineers
1413 K STREET, NORTHWEST
WASHINGTON 5, D. C.



FCC File No. BL-7293
Accepted 11-25-58

KAKC
Tulsa, Oklahoma

970 KC

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KAKC Main Studio: Tulsa, Oklahoma
 Frequency: 970 kHz Power: 1 kW
 Notification List No. 1726 Date: March 24, 1977 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: $36^{\circ} 11' 42''$
 West Longitude: $96^{\circ} 02' 16''$

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 6

Type of elements: Series excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	W(#6)	N(#5)	SC(#2)	S(#4)	NE(#1)	E(#3)
HEIGHT ABOVE INSULATORS:	338'	338' (120°)	260'	260'	260'	260' (92.3°)
NIGHT PHASING:	$+6.8^{\circ}$	0°	-	-71.1°	-	-21.2°
NIGHT FIELD RATIO:	0.975	1.0	-	0.285	-	0.587
DAY PHASING:	-	-	-28°	-	0°	-
DAY FIELD RATIO:	-	-	0.7	-	1.0	-

SPACING AND

ORIENTATION: Nighttime, from reference tower #3, tower #5 is spaced 568' (201.6°) on a line bearing 329.1° true, tower #6 is spaced 634' (225.0°) in length on a line bearing 260.4° true, and tower #4 is spaced 609' (216.1°) on a line bearing 216.3° true. Daytime, elements #1 and #2 spaced 624' (222°) on a line bearing 35° true.

GROUND SYSTEM: 120-255' equally spaced copper radials plus 120-50' interspaced radials or a 32' square ground screen about each tower. Radials are shortened and bonded to transverse straps along intersection between towers. Center of system are bonded together.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL	STANDARD
	<u>RMS</u>	<u>RMS</u>
Day	190 mv/m	- mv/m
Night	175.9 mv/m	313.9 mv/m

(Cont'd)

KAKC

KAKC


2.

Note: Please retain the Daytime directional antenna radiation pattern notified for Station KAKC in United States Change List Number 318 dated June 1, 1949 and attach to this Revised Description Sheet and Nighttime patterns. This notification concerns only a change in the Nighttime operation of the station with Daytime operation continued as previously notified.

CTR NO 30826A4

KAKC

S
T
N



03W13039 HORTIAE

Standard Pattern

PROPOSED STANDARD HORIZONTAL RADIATION NIGHTTIME


UNATTENUATED FIELD STRENGTH
AT ONE MILE

FIGURE 4A

W. LAT. 38° 42' N W. LONG. 107° 15' W W. LAT. 38° 42' N W. LONG. 107° 15' W W. LAT. 38° 42' N W. LONG. 107° 15' W W. LAT. 38° 42' N W. LONG. 107° 15' W	1000' 1000' 1000' 1000' 1000' 1000' 1000' 1000'	$S_1 = S_2 = S_3 = S_4 = 1000'$ $S_5 = S_6 = S_7 = S_8 = 1000'$ $S_9 = S_{10} = S_{11} = S_{12} = 1000'$ $S_{13} = S_{14} = S_{15} = S_{16} = 1000'$ $S_{17} = S_{18} = S_{19} = S_{20} = 1000'$ $S_{21} = S_{22} = S_{23} = S_{24} = 1000'$ $S_{25} = S_{26} = S_{27} = S_{28} = 1000'$ $S_{29} = S_{30} = S_{31} = S_{32} = 1000'$ $S_{33} = S_{34} = S_{35} = S_{36} = 1000'$ $S_{37} = S_{38} = S_{39} = S_{40} = 1000'$ $S_{41} = S_{42} = S_{43} = S_{44} = 1000'$ $S_{45} = S_{46} = S_{47} = S_{48} = 1000'$ $S_{49} = S_{50} = S_{51} = S_{52} = 1000'$ $S_{53} = S_{54} = S_{55} = S_{56} = 1000'$ $S_{57} = S_{58} = S_{59} = S_{60} = 1000'$ $S_{61} = S_{62} = S_{63} = S_{64} = 1000'$ $S_{65} = S_{66} = S_{67} = S_{68} = 1000'$ $S_{69} = S_{70} = S_{71} = S_{72} = 1000'$ $S_{73} = S_{74} = S_{75} = S_{76} = 1000'$ $S_{77} = S_{78} = S_{79} = S_{80} = 1000'$ $S_{81} = S_{82} = S_{83} = S_{84} = 1000'$ $S_{85} = S_{86} = S_{87} = S_{88} = 1000'$ $S_{89} = S_{90} = S_{91} = S_{92} = 1000'$ $S_{93} = S_{94} = S_{95} = S_{96} = 1000'$ $S_{97} = S_{98} = S_{99} = S_{100} = 1000'$
HAMMETT & EDISON INC. CONSULTING ENGINEERS SAN FRANCISCO	RADIO STATION KAKC 970 KHZ. 1 KW. DA-2 TULSA, OKLAHOMA	



7509094

RADIO STATION KAKC

CALCULATED STANDARD RADIATION



Standard Pattern

RADIO STATION KAKC

CALCULATED STANDARD RADIATION



Hammell & Edison, Inc.,
Consulting Engineers

RADIO STATION KAKC

CALCULATED STANDARD RADIATION



Hammett & Edison, Inc.
Consulting Engineers

RADIO STATION KAKC

CALCULATED STANDARD RADIATION



Hammitt & Edison, Inc.
Consulting Engineers

RADIO STATION KAKC

CALCULATED STANDARD RADIATION


Hammett & Edison, Inc.
Consulting Engineers

RADIO STATION KAKC

CALCULATED STANDARD RADIATION

Honnett & Edison, Inc.
Consulting Engineers

JUL 23 1948 G



Amendment 7-16-48

BP-6713

MEASURED
DAY

KBOX, MODESTO, CALIF.
11/26/51G

1 KW, U, DA-2

~~KBOX~~
KBEE
970 KC




FIGURE NO. 10 - HORIZONTAL RADIATION PATTERN

Antenna Operation: DA-D -- 1 kw.
Radio Station KBOX - 970 kc - Modesto, Calif.

Determined RMS Field at One Mile 189 mv/m
October, 1951

~~SECRET~~
 MODESTO, CAL
 970

JUL 23 1948 G




FIGURE 1
 STANISLAUS COUNTY BROADCASTERS INC.
 MODESTO CALIFORNIA
 970 KC 1 KW DA-2
 HORIZONTAL PLANE RADIATION - NIGHT
 --- MAXIMUM PERMISSIBLE VALUES IN HORIZONTAL PLANE
 ——— EXPECTED TOLERANCE OF ARRAY ADJUSTMENT

NO. 340-P DIVISION GRAPH PAPER
 POLAR CO-ORDINATE

Amendment 7-16-48

BP-6713

MEASURED
NIGHT

KBOX, MODESTO, CALIF.
11/26/51G

1 KW, U, DA-2

~~KBOX~~
KBEE
970 KC




FIGURE NO. 11 - HORIZONTAL RADIATION PATTERN

Antenna Operation: DA-N -- 1 kw.
Radio Station KBOX - 970 kc - Modesto, Calif.

Determined RMS Field at One Mile 187 mv/m
October, 1951

APPL RECD 10/16/51 EL-4577

KBOX, MODESTO, CALIF.


970 KC

MEASURED
NON-DA

KBOX, MODESTO, CALIF.
11/26/51G

1 KW, U, DA-2

~~KBOX~~
KBEE
970 KC



KBIS

SUPPLEMENTAL DIRECTIONAL ANTENNA
DESCRIPTION SHEET

Station: KBIS

Main Studio: Bakersfield, California

Frequency: 970 kHz

Power: 1 kW

Notification List No. 1633

Date: May 20, 1975

Class: III

GEOGRAPHICAL LOCATION OF THE

CENTER OF THE ANTENNA SYSTEM: North Latitude: 35° 25' 02"
West Longitude: 119° 00' 15"

Authorized for Daytime and Nighttime operation (DA-2).

Note: Please retain the description sheet and directional antenna

radiation patterns notified for station KBIS in United States

Change List Number 1518, dated March 2, 1973, and attach to this

supplemental Description Sheet. This notification is for the

purpose of indicating only a change in the geographical coordinates

of the center of the antenna system.

CTR NO 30813A6

KBIS

DATE FILED 3-8-50

PROPOSED
DAYTIME


NEW, BAKERSFIELD, CAL.
(Marmat Radio Co.)

170°
190°

160°
200°

1kw, DA-2

970 kc



John Creutz
Consulting Radio Engineer
319 Bond Bldg. Republic 2151
Washington, D. C.

AMENDMENT FILED 3-8-50 ACC 3/17/50 BP-6184

10°
350°

NEW, Bakersfield, Cal. 970 kc


KBIS

MEASURED
DAY


KBIS, BAKERSFIELD, CALIF.
5/11/55G

U, DA-2
1 KW

970 KC



N. LAT. 35° 24' 32.9"
W. LONG. 118° 56' 51.1"



RMS = 192 MV/M

HORIZONTAL RADIATION PATTERN DAYTIME

MEASURED UNATTENUATED
FIELD INTENSITY AT ONE MILE

ROBERT L. HAMMETT
CONSULTING RADIO ENGINEER
SAN FRANCISCO

RADIO STATION KBIS
970 KC, 1 KW, DA-2
BAKERSFIELD, CALIFORNIA

550420

FIGURE 7C


FCC File No. BZ-3597 Accepted 5-6-55
(Amended)

KBIS, BAKERSFIELD,
CALIF.

970 KC

KBIS
BAKERSFIELD, CAL.
9.70

JUL 13 1948 G



NIGHT PATTERN
MARMAT B/C CO.
BAKERSFIELD, CAL.
970kc 1-5kw DA-2
6/21/48

John Creutz
Consulting Radio Engineer
319 Bond Bldg. RRepublic 2151
Washington, D. C.


PROPOSED
NIGHT NULLS

NEW, BAKERSFIELD, CAL.
(Marmat Radio Co.)

KBIS
BAKERSFIELD

1kw, DA-2

970 kc



AMENDMENT RECD 4-11-50 BP-6184

John Creutz
Consulting Radio Engineer
315 Bond Bldg. Republic 2181
Washington, D. C.
NEW, Bakersfield, Cal. 970 kc


KBIS

MEASURED
NIGHT


KBIS, BAKERSFIELD, CALIF.
5/11/55G

U. DA-2
1 KW

970 KC



N. LAT. 35° 24' 32.9"
W. LONG. 118° 56' 51.1"



RMS = 192 MV/M

HORIZONTAL RADIATION PATTERN NIGHTTIME

MEASURED UNATTENUATED
FIELD INTENSITY AT ONE MILE

ROBERT L. HAMMETT
CONSULTING RADIO ENGINEER
SAN FRANCISCO

RADIO STATION KBIS
970 KC, 1 KW, DA-2
BAKERSFIELD, CALIFORNIA

550420

FIGURE 22

FCC No. BZ-3597 (Amended) Accepted 5-6-55

KBIS, BAKERSFIELD,
CALIF.

970 KC

KCHV

Measured Non-DA
(3-30-64ct)

Station KCHV
Coachella, California

1kw, 5kw-LS, DA-2, U
970kc




FIGURE NO. 12

NON-DIRECTIONAL ANTENNA RADIATION PATTERN
BASED ON FIELD INTENSITY MEASUREMENTS

970 KC/S ● 5/1 KW ● DA-2

STATION KCHV — COACHELLA, CALIFORNIA



NOVEMBER
1963

FCC File No. BL-10406
Accepted 3-4-64

Station KCHV
Coachella, California

970kc


KCHV

PROPOSED DAY
(1-29-60g)

Station KCHV
Coachella, California

1kw,5kw-LS,DA-2,U
970 KC

3-2-62 granted
Q for DA-2



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
		TOWER NO.	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION deg	SPACING ft	PHASING deg	HORIZONTAL FIELD dB	FIELD RATIO	ELEV. ANGLE deg	ELEVATION ft	CALL	KCHV
		1	90	0	0	0	433	1.0	0	422	FREQUENCY	970
		2	90	40	100	130		0.35	10		POWER	5.0
		3	30	220	100	-130		0.35	20		TIME OF OPERATION	DAY
		4									TYPE OF OPERATION	DA-2
		5									DAYTIME TOWERS	3
		6									NIGHTTIME TOWERS	3
		7									NO. RADIALS PER TOWER	120
		8									LENGTH OF RADIALS	106
		9									GROUND WAVE DIMENSION	300 ft
		10								LAT	33° 41' 12"	
										LONG	116° 09' 34"	
										SUPERSEDES		
										PATTERN NO.		
EXHIBIT NO. 1 RADIO STATION KCHV 970 KC — 5 KW — DA-2 COACHELLA, CALIFORNIA												



JULY 1959

FCC File No. BP-13740
Accepted 1-13-60

KCHV
Coachella, California

970 KC

15


KCHV

Measured Day
(3-30-64ct)



Station KCHV
Coachella, California

1kw, 5kw-LS, DA-2, U
970kc

#201-8-26-64
Granted for DA-2
and unlimited time



POWER = 5 KW
RMS = 418 MV/M




KCHV

PROPOSED NIGHT
(1-29-60g)

Station KCHV
Coachella, California

1kw, 5kw-LS, DA-2, U
970 KC

3-2-62 granted
9 for DA-2



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
		TOWER NO.	ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	PHASING	HORIZONTAL FIELD	FIELD RATIO	ELEV. ANGLE	ELEVATION	CALL	KCHV
1	90	0	0	0	198	1.0	0	185.3	10	FREQUENCY	970	
2	90	40	100	140	0.45	0.45	10		20	POWER	1.0	
3	90	220	100	-140	0.45	0.45	20		30	TIME OF OPERATION	NIGHT	
4							30		40	TYPE OF OPERATION	DA-2	
5							40		50	DAYTIME TOWERS	3	
6							50		60	NIGHTTIME TOWERS	3	
7							60		70	NO RADIAL FIELD POWER	120	
8							70		80	LENGTH OF RADIALS	106 3000	
9							80		90	GROUND SCREEN DIMENSION		
10							90		100	LAT.	33 41 12	
11							100		110	LONG	116 09 34	
12							110		120	SUPERSEDES		
		DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☒								FACTORY NO.		
EXHIBIT NO. 1-A RADIO STATION KCHV 970 KC — 1 KW — DA-2 COACHELLA, CALIFORNIA												
JULY 1959												

FCC File No. BP-13740
Accepted 1-13-60

KCHV
Coachella, California


970 KC

KCHV


Measured Night
(3-30-64ct)

Station KCHV
Coachella, California

1kw, 5kw-LS, DA-2, U
970kc



POWER = 1.0 KW
RMS = 187 MV/M



FCC File No. BL-10406
Accepted 3-4-64

Station KCHV
Coachella, California

970kc

PROPOSED DAY
(1-29-57g)


Austin Radio Company 1 KW, DA-D, D
Austin, Texas

AUSTIN, TEX

970 K C

KIXL)

revised CP
1/24/58 for
new station




Coordinates:

30' 19" 30*
97' 40" 35*

S = 75° = 211.4'

---- MEOV



R.M.S. = 187 MV/M

G'S = 85° = 240'

J. G. ROUNTREE
CONSULTING RADIO ENGINEER
5622 DYER STREET
DALLAS 6, TEXAS

AUSTIN RADIO COMPANY

AUSTIN, TEXAS

PROPOSED 970 KC, 1000 W, DA-D

561027

FIGURE 2A

FCC File No.
BP-9661 11,247

Accepted 1-9-57

Austin Radio Co.
Austin, Texas


970 K C

KIXL

MEASURED DAY
(12-21-59g)

Station KASE
Austin, Texas

1kw, DA-D, D
970 KC



FCC File No. BL-7681
Accepted 11-16-59

KASE
Austin, Texas

970 KC


Granted for new Station 7-1-60

MEASURED NON-DA
(12-21-59g)

Station KASE
Austin, Texas

1k

KIXL



$E_{RMS} = 193 \text{ MV/M (MEASURED)}$

• RADIAL VALUES

LATITUDE: $30^{\circ} 19' 51''$
LONGITUDE: $97^{\circ} 36' 54''$

ANTENNA PARAMETERS

JOHN H. MULLANEY
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FIGURE 17

PLOT OF MEASURED
NON-DIRECTIONAL
PATTERN

RADIO STATION KASE
AUSTIN, TEXAS

G - 85°

970 KC

1 KW, DA-D

FCC File No. BL-7681
Accepted 11-16-59

KASE
Austin, Texas

970 KC

Handwritten note: 7-16-60 New Station 8-1-60

KNJU
970 kHz

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: KNJU Main Studio: Paradise, Nevada
Frequency: 970 kHz Power: 0.5kw Night 5kw Day
Notification List No. 1788 Date: August 22, 1980 Class: III

GEOGRAPHICAL LOCATION OF THE CENTER OF THE ANTENNA SYSTEM:

North Latitude: 36° 04' 23"
West Longitude: 115° 15' 05"

ANTENNA CHARACTERISTICS

Authorized for Daytime and Nighttime operation. (DA-2)
Number of elements: 5
Type of elements: Series excited, uniform cross-section,
guyed, vertical steel towers.

TOWER:	#1	#2	#3	#4	#5
HEIGHT ABOVE INSULATORS:	230'	230'	230'	230'	230' (81.65°)
NIGHT PHASING:	0°	-114.9°	-138.8°	+101.4°	---
NIGHT FIELD RATIO:	1.0	0.552	0.636	0.351	---
DAY PHASING:	---	---	+81.6°	-109.7°	0°
DAY FIELD RATIO:	---	---	0.533	0.533	1.0

SPACING AND NIGHT ORIENTATION:

NIGHT:
The towers are located at the vertices of a parallelogram
the long sides of which are 120° in length on a line bearing
13° true. The short sides are 90° in length on a line bearing
80° true.
DAY: Adjacent towers in a row are spaced 120° on a line bearing
13° true.


GROUND SYSTEM: 120 - 250' equally spaced copper radials plus a 48' square
ground screen about each tower. Radials are shortened and
bonded to transverse straps along intersections between
towers.

PREDICTED EFFECTIVE FIELDS AT RATED POWER:

	THEORETICAL		STANDARD
	RMS	RSS	RMS
Day	430.6 mv/m	408.3 mv/m	452.3 mv/m
Night	136.5 mv/m	164.1 mv/m	143.5 mv/m

36° 04' 23"
115° 15' 05"


STANDARD PATTERN
MINIMUMS AT 133°
168°, 218° & 326°
INDICATED THUS:
→



EDWARD F. LORENTZ & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

PROPOSED DAYTIME
STANDARD HORIZONTAL PATTERN
KNUU, PARADISE, NEVADA
970 KHZ, 5 KW-D/0.5 KW-N, DA-2

DA MIN



EDWARD F. LORENTZ & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

PROPOSED NIGHTTIME
STANDARD HORIZONTAL PATTERN
KNUU, PARADISE, NEVADA
970 KHZ, 5 KW-D/0.5-N, DA-2

KOIN


Fig. 1
PROPOSED NIGHTTIME
HORIZONTAL RADIATION PATTERN

KOIN 970 KC 5 KW

Portland, Ore.

Jaseky & Bailey Washington, D. C.

July 1939




KOIN
970

KOIN

10/29/48G

License---10-26-48



E. C. PAGE
CONSULTING RADIO ENGINEERS
BOND BUILDING
WASHINGTON D. C.

FIGURE 1
Measured Horizontal Plane Pattern
KOIN Portland, Oregon
970kc 5 Kw DA-N U
RWM:fl Sept. 8, 1948

KOIN

MEASURED NIGHT
(7-26-61ct)


Station KOIN
Portland, Oregon

5kw, DA-N,U
970 KC

North Latitude 45° 30' 56"
West Longitude 122° 43' 54"

FIG. 1-A

MEASURED HORIZONTAL PLANE PATTERN



FCC File No. BZ-4421
Accepted 6-16-61

KOIN
Portland, Oregon

970 KC 130°

KOIN

MEASURED NON-DA
(7-26-61ct)


Station KOIN
Portland, Oregon

5kw, DA-N, U
970 KC

North Latitude 45° 30' 56"
West Longitude 122° 43' 54"

FIG. 1

NONDIRECTIONAL MEASURED HORIZONTAL PLANE PATTERN



L. S. BOOKWALTER
AND
B. R. PAUL
ENGINEERS - PORTLAND ORE.

KOIN PORTLAND ORE.
970 KC 5 KW DA-N U
APRIL 1961

FCC File No. BZ-4421
Accepted 6-16-61

KOIN
Portland, Oregon

970 KC

KOOK

PROPOSED NIGHT
(3/22/55G)


STATION KOOK
BILLINGS, MONTANA

5KW
DA-N, 11

970 KC

11

LAT. $45^{\circ} 44' 20''$
LONG. $108^{\circ} 32' 38''$



All G's = 83.4° , top loaded with top
guy sections
RMS = 420 mV/m



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON D. C.

PATTERN: PROPOSED NIGHTTIME
FOR: KOOK, BILLINGS, MONTANA
POWER: 5 KW FREQ: 970 KC
DATE: OCT 29 1954

FILE BP-9587

Received 12/23/54 FCC

KOOK, Billings, Montana

970 K.


KOOK

PROPOSED NIGHT NULLS
(3/22/55G)

STATION KOOK
BILLINGS, MONTANA

5KW
DA-N, U

970 KC



COMMERCIAL RADIO EQUIPMENT CO.

RADIO ENGINEERING CONSULTANTS

KANSAS CITY WASHINGTON, D. C.

PATTERN: PROPOSED NIGHTTIME
FOR: KOOK, BILLINGS, MONTANA
POWER: 5 KW FREQ: 970 KC
DATE: OCT. 29, 1954

FILE 3P-9567

Received 12/23/54 FCC

KOOK, Billings, Montana

970 KC

970 kc


KOOK

Measured Non-DA
(8-22-69ct)

Station KOOK
Billings, Montana

5kw, DA-N, U
970 kc

BL-12421
Granted
8-22-69
license
covering
an amended
permit to
propose
patterns
(field) to
change
bearing &
invert
field in
transition



HORIZONTAL RADIATION PATTERN

NON-DIRECTIONAL SURVEY

APPLICANT KOOK
LOCATION BILLINGS, MONTANA
FREQUENCY 970 KC/S
POWER 5 KW
LATITUDE 45 DEG 44 MIN 00 SEC
LONGITUDE 107 DEG 52 MIN 00 SEC
WHEN USED DAYTIME
R.M.S. FIELD 425.5 mV/m
DATE APR 1 1969

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-12421
Accepted 8-15-69

Station KOOK
Billings, Montana

970 kc

Austin, Minn.
KQAQ


PROPOSED DAY
(4/5/57g)

George A. Hormell, II
Austin, Minnesota

1kw, DA-D,D
970 KC

Granted CP
9/19/57 for
new station

POLAR COORDINATE 359.31G
OFFSET 0.000000



FCC File No. BP-10,673 (Ammended)
Accepted 3/18/57

George A. Hormell, II
Austin, Minnesota

970 KC


KQAA

PROPOSED DAY
(11-17-58g)

Station KQAA
Austin, Minnesota
(801)

5kw, DA-D, D
970 KC

*Granted Mod
of CP 12/23/58
for increase
in power*



FCC File No. BMP-7935
Accepted 11-12-58 Amended

KQAA
Austin, Minnesota

970 KC


KQAO

MEASURED DAY
(5-27-60g)

Station KQAO
Austin, Minnesota

5kw, DA-1'

970 KC



*Sketch for new station
6-11-60*


KQAO

PROPOSED NIGHT
(3-8-61g)

Station KQAO
Austin, Minnesota

500w, 5kw-LS, DA-2, U
970 KC

6-20-62
wanted change
to U with
500w night and
to DA-2.



FCC File No. BP-14637
Accepted 3-2-61

Station KQAO
Austin, Minnesota


970 KC

Measured Night
(4-30-63ct)


Station KQAQ
Austin, Minnesota

KQAQ
500w, 5kw-LS, DA-2, U
970 kc

*6/24/64
to change
com DA-DID
DA-2) U.*



N.L. $43^\circ 42' 22''$
W.L. $92^\circ 56' 45''$



FCC File No. BL-9870
Accepted 4-10-63

Station KQAQ
Austin, Minnesota

970 kc

Oct. 1962

Measured Non-DA
(4-30-63ct)


Station KQAQ
Austin, Minnesota

KQAQ
500w, 5kw-LS, DA-2, U
970 kc

N.L. 43° 42' 22"
W.L. 92° 56' 45"

EUGENE DIETZEN CO.
P.O. BOX 100
MINNEAPOLIS, MINN.

NO. 340-B DIETZEN GRAPH PAPER
POLAR CO-ORDINATE



FCC File No. BL-9870
Accepted 4-10-63

Station KQAQ
Austin, Minnesota

970 kc

DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station : KREM Main Studio: Spokane, Washington
Frequency : 970 KHz Power : 1 kW Night 5 kW Day
Notification : 1780 Date : Sept. 28, 1979 Class: 111

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude:	<u>47</u>	<u>36</u>	<u>59</u>
West Longitude:	<u>117</u>	<u>21</u>	<u>55</u>

Note: Please retain the description sheet notified for station KREM in United States Change List Number 358, dated April 13, 1953 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a change in the nighttime radiation pattern MEOV's.

KREM

SITE: 47° 36' 59" N
117° 21' 55" W

PATTERN NO. 491020

HORIZONTAL PLANE RADIATION PATTERN Proposed Night Operation

Station KREM


Spokane, Wash.


970 Kc.

1 Kw.

DA-N U

FIGURE 1 - A





EXPANDED
HORIZONTAL PLANE RADIATION PATTERN
Proposed Night Operation

Station KREM

Spokane, Wash.

970 Kc.

1 Kw.

DA-N U

FIGURE 1 - B

H = 106.5°

No. 1 = 1/0°

No. 2 = 1/162°

MEOV'S FOR KREM NOTIFIED PATTERN

SILLIMAN, MOFFET & KOWALSKI
MAY 1977

MEOV

MEV/M

SITE: 47° 36' 59" N
117° 21' 55" W

PATTERN NO. 491020

KREM

PROPOSED
NIGHT

KREM, SPOKANE, WASH.

1kw, DAN

970 kc

SITE: 47° 36' 56" N
117° 22' 06" W

PATTERN NO. 491020

HORIZONTAL PLANE RADIATION PATTERN
Proposed Night Operation

Station KREM


Spokane, Wash.

970 Kc.

1 Kw.

DA-N U

Engineer: A. G. Sparling



AMENDMENT RECD 11-9-49 BP-7128

KREM, Spokane, Wash. 970 kc


KREM

PROPOSED
NIGHT NULLS

KREM, SPOKANE, WASH.

1kw, DAN

970 kc




AMENDMENT RECD 11-9-49 P-7128

KREM, Spokane, Wash. 970 kc

KREM

MEASURED NIGHT
(4/11/55G)STATION KREM
SPOKANE, WASHINGTON1KW, 5KW-LS
DA-N, U

970 KC



O MEASURED RADIAL VALUES

KREM - SPOKANE, WASHINGTON
HORIZONTAL RADIATION PATTERN
(MEASURED NIGHT)

	(NORTH)	(SOUTH)				
ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6
PHASE DEG.	0°	+ 162°				
HEIGHT DEG.	106.5°	106.5°				
FIELD RATIO	1.0	1.0				
NON-DA ANT.						

ORIENTATION - ON A LINE BEARING N 164° E

SPACING 90°

FREQUENCY: 970 KC.
 ASSIGNMENT: 5 Kw-LS, 1 Kw-N(DA)
 LONGITUDE: 117 DEG. 21 MIN. 55 SEC.
 LATITUDE: 47 DEG. 36 MIN. 59 SEC.
 WHEN USED: NIGHTTIME
 RMS FIELD: 196 MV/M
 DATE: FEBRUARY 1955

ROBERT M. SILLIMAN

CONSULTING RADIO ENGINEERS

WASHINGTON, D. C.


KF 514

MEASURED NIGHT NULLS
(4/11/55G)

STATION KREM
SPOKANE, WASHINGTON

1KW, 5KW-LS
DA-N, U

970 kc




KREM - SPOKANE, WASHINGTON HORIZONTAL RADIATION PATTERN (MEASURED NIGHT - EXPANDED VIEW)						FREQUENCY 970 KC																																			
						ASSIGNMENT: 5 KW-LS, 1 KW-N(DA)																																			
						LONGITUDE: 117 DEG 21 MIN 55 SEC																																			
						LATITUDE: 47 DEG 56 MIN 59 SEC																																			
						WHEN USED: NIGHTTIME																																			
						R.M.S. FIELD: 196 MV/M																																			
						DATE: FEBRUARY 1955																																			
(NORTH) (SOUTH) <table border="1"> <thead> <tr> <th>ANTENNA</th> <th>NO. 1</th> <th>NO. 2</th> <th>NO. 3</th> <th>NO. 4</th> <th>NO. 5</th> <th>NO. 6</th> </tr> </thead> <tbody> <tr> <td>PHASE DEG</td> <td>0°</td> <td>+162°</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>HEIGHT DEG</td> <td>106.5°</td> <td>106.5°</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>FIELD RATIO</td> <td>1.0</td> <td>1.0</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>NON-DA ANT.</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>						ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6	PHASE DEG	0°	+162°					HEIGHT DEG	106.5°	106.5°					FIELD RATIO	1.0	1.0					NON-DA ANT.							ROBERT M. SILLIMAN CONSULTING RADIO ENGINEERS WASHINGTON, D. C.
ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6																																			
PHASE DEG	0°	+162°																																							
HEIGHT DEG	106.5°	106.5°																																							
FIELD RATIO	1.0	1.0																																							
NON-DA ANT.																																									
ORIENTATION - ON A LINE BEARING N 164° E SPACING 90°																																									

KREM

MEASURED NON-DIRECTIONAL STATION KREM
(4/11/55G) SPOKANE, WASHINGTON

1KW, 5KW-LS
DA-N, U

970 KC



O MEASURED RADIAL VALUES

FIGURE 3-C

KREM - SPOKANE, WASHINGTON
HORIZONTAL RADIATION PATTERN
(MEASURED DAY NON-DIRECTIONAL)

(NORTH) (SOUTH)

ANTENNA	NO. 1	NO. 2	NO. 3	NO. 4	NO. 5	NO. 6
PHASE DEG						
HEIGHT DEG	263.5°					
FIELD RATIO						
NON-DA ANT.	*					

NOTE: NON-DIRECTIONAL TOWER FED AS A FRANKLIN.

FREQUENCY: 970 KC

ASSIGNMENT: 5 Kw-LS, 1 Kw-N(DA)

LONGITUDE: 117 DEG. 21 MIN. 55 SEC.

LATITUDE: 47 DEG. 36 MIN. 59 SEC.

WHEN USED: DAYTIME

R.M.S. FIELD: 565 MV/M

DATE: FEBRUARY 1955

ROBERT M. SILLIMAN

CONSULTING RADIO ENGINEERS

WASHINGTON, D. C.

~~KSYL~~ 970

MAR 24 1948 G







FIGURE 1 (Amended)
HORIZONTAL PLANE PATTERN
PROPOSED KPDR
ALEXANDRIA, LOUISIANA
970kc 1 Kw U DA-N
E. C. PAGE
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.
VE:FL MAR. 12, 1948

KYSL

Measured Night
(3-30-63ct)

Station KSYL
Alexandria, Louisiana

1kw, DA-N, U
970 kc



RADIO STATION KSYL
ALEXANDRIA, LOUISIANA

MEASURED DIRECTIONAL
HORIZONTAL PLANE RADIATION PATTERN
970 KC 1000 WATTS

061362-3

FIGURE 3

MERL SAXON

CONSULTING RADIO ENGINEER
LUFKIN, TEXAS

FCC File No. BZ-4833
Accepted 2-21-63

Station KSYL
Alexandria, Louisiana


970 kc

KYSL

Measured Non-DA
(3-30-63ct)

Station KSYL
Alexandria, Louisiana

1kw, DA-N, U
970 kc



① 1.0 Kw S ② Isolated N 141° E G₁ - 90° - 255' G₂ - 57° - 160' S - 70° - 197.3'	RADIO STATION KSYL ALEXANDRIA, LOUISIANA MEASURED NON-DIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN 970 KC 1000 WATTS	
	061362-2 FIGURE 2	MERL SAXON CONSULTING RADIO ENGINEER LUFKIN, TEXAS

FCC File No. BZ-4833
Accepted 2-21-63

Station KSYL
Alexandria, Louisiana

970 kc

WAMD


ABERDEEN, Md.
WAMD

PROPOSED
DAY (6/11/56g)

HARFORD CO. B/C CO.
ABERDEEN, MD.


500 W
DA-D, D

970 KC



LATITUDE: 39° 30' 35"
LONGITUDE: 76° 11' 38.3"

JOHN H. MULLANEY
CONSULTING RADIO ENGINEERS
WASHINGTON D. C.



G=71° T.L.

FIGURE 4
DAYTIME
HORIZONTAL POLAR PATTERN
HARFORD COUNTY B/CING CO.
ABERDEEN, MARYLAND
970 KC 0.5 KW DA-D


WAM

MEASURED DAY
(5/17/57g)

Station WAMD
Aberdeen, Maryland

500w, DA-BD
970 KC

*Granted license
10/1/57
BL-8947-
panted L 4-5-62
a change in
ours of operation
A-2 and
change in DA. Sept*



..... MEASURED RADIALS
xxxxx CROSS RADIALS
—— MEASURED PATTERN
---- CALCULATED PATTERN

$E_{RMS} = 128.5 \text{ MV/M}$

LATITUDE: 39° 30' 35"
LONGITUDE: 76° 11' 38.3"

ANTENNA PARAMETERS




FIGURE 18
MEASURED DAYTIME
HORIZONTAL POLAR PATTERN
RADIO STATION WAMD
ABERDEEN, MARYLAND

JOHN H. MULLANEY
CONSULTING RADIO ENGINEER
WASHINGTON, D. C.

970 KC 0.5 KW - 0A-D


FCC File No. BL-6623
Accepted 5/3/57g

WAMD
Aberdeen, Maryland 970 KC

PROPOSED NIGHT
(5-27-60g)

Station WAMD
Aberdeen, Maryland

500w, DA-2, U
970 KC



E_{RMS} 129 MV/M (BY ADJUSTMENT)

MEOV

LATITUDE: 39° 30' 35"
LONGITUDE: 76° 11' 38.3"

ANTENNA PARAMETERS

#2 1/0°
211.5'
75°
#3 0.85/-135°
164.5°
6-87.5°

JOHN H. MULLANEY
CONSULTING RADIO ENGINEERS
WASHINGTON, D. C.

FIGURE 4
(AMENDED)
HORIZONTAL POLAR PATTERN
(NIGHTTIME)
RADIO STATION WAMD
ABERDEEN, MD.

970 KC 0.5 KW, DA-2, U

FCC File No. BP-12529
Accepted 5-20-60 (Amended)


WAMD
Aberdeen, Maryland

970 KC

Measured Night
(3-30-62ct)

Station WAMD
Aberdeen, Maryland

500w, DA-2, U
970 kc



FCC File No. BL-8947
Accepted 3-13-62


Station WAMD
Aberdeen, Maryland

970 kc

Measured Non-DA
(3-30-62ct)

Station WAMD
Aberdeen, Maryland

500w, DA-2, U
970 kc



$E_{RMS} = 133 \text{ MV/M (MEASURED)}$

O = RADIAL VALUES

LATITUDE: 39° 30' 35" LONGITUDE: 76° 11' 38.3"	ANTENNA PARAMETERS *1 TOWER G = 87.5° (TOP-LOADED)	FIGURE 12 MEASURED HORIZONTAL NON-DIRECTIONAL PATTERN RADIO STATION WAMD ABERDEEN, MARYLAND 970 KC 0.5 KW, DA-2
JOHN H. MULLANEY AND ASSOCIATES WASHINGTON, D. C.		

FCC File No. BL-8947
Accepted 3-13-62

Station WAMD
Aberdeen, Maryland

970 kc

WANV

Proposed Day
(1-29-64ct)

Station WBVA
Waynesboro, Virginia

1kw, 5kw-LS, DA-2, U
970 kc

6/3/63
anted chg
on .5-D to
5-LS, DA-2





FIGURE 1

HORIZONTAL RADIATION PATTERN



FCC File No. 8MP-11115
Accepted 1-8-64

Station WBVA
Waynesboro, Virginia

970 kc

970 kc

WANV

Proposed Night Nulls
(1-29-64ct)

Station WBVA
Waynesboro, Virginia

1kw, 5kw-LS, DA-2, U
970 kc

6/3/63
noted chg
com. S-D to
1, 5-LS, DA-2.




FIGURE 4-8

EXPANDED VIEW

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. 8MP-11115
Accepted 1-8-64

Station WBVA
Waynesboro, Virginia


970 kc

WANY


Measured Day
(5-27-65ct)

Station WANY
Waynesboro, Virginia

1kw, 5kw-LS, DA-2, U
970 kc



HORIZONTAL RADIATION PATTERN



APPLICANT :	MUSIC PRODUCTIONS, INC.
LOCATION :	WAYNESBORO, VIRGINIA
FREQUENCY :	970 KHz
POWER :	5000 WATTS
LATITUDE :	38 DEG 05 MIN 12 SEC
LONGITUDE :	78 DEG 54 MIN 42 SEC
OTHER USES :	DAYTIME
F.M.S. FIELD :	393 MV/M (MEASURED)
DATE :	FEBRUARY 1965

GILLMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-10886
Accepted 4-29-65

Station WANY
Waynesboro, Virginia

970 kc


WANV

Measured Night
(5-27-65ct)


Station WANV
Waynesboro, Virginia

1kw, 5kw-LS, DA-2, U
970 kc

LIC. 5-27-65



HORIZONTAL RADIATION PATTERN



FCC File No. BL-10886
Accepted 4-29-65

Station WANV
Waynesboro, Virginia

970 kc


WANY

Measured Non-DA
(5-27-65ct)

Station WANY
Waynesboro, Virginia

1kw, 5kw-LS, DA-2, U
970 kc

LIC. 5-27-65



HORIZONTAL RADIATION PATTERN

NON - DIRECTIONAL SURVEY

APPLICANT :	MUSIC PRODUCTIONS, INC.
LOCATION :	WAYNESBORO, VIRGINIA
FREQUENCY :	970 KC/S
POWER :	1000 WATTS
LATITUDE :	38 DEG 05 MIN 12 SEC
LONGITUDE :	78 DEG 54 MIN 42 SEC
WHEN USED :	NON-DIRECTIONAL SURVEY
R.M.S. FIELD :	212 MV/M (MEASURED)
DATE :	FEBRUARY 1965

SILLIMAN, MOFFET & KOWALSKI
CONSULTING RADIO ENGINEERS
WASHINGTON, D.C.

FCC File No. BL-10886
Accepted 4-29-65

Station WANY
Waynesboro, Virginia


970 kc

WATH

Proposed Day
(5-27-69ct)

Station WATH
Athens, Ohio

5kw, DA-D, D
970 kc



FCC File No. BP-18285
Accepted 5-16-69 Amended

Station WATH
Athens, Ohio

970 kc


WAVE

PROPOSED DAY
(5-8-61g)

Station WAVE
Louisville, Kentucky

5kw, DA-2, U
970 KC

-20-62
antenna CP
change
w/ DA-1
x DA-2



A. D. RING & ASSOCIATES - 10/60 - M

FCC File No. BP-14723
Accepted 4-13-61

WAVE
Louisville, Kentucky

970 KC

MEASURED $\frac{1}{0^\circ}$ $2.5/+140^\circ$
 $1(S) \xrightarrow{146.5^\circ} 2(N) \xrightarrow{11^\circ T.}$
 $G_1 = G_2 = 88.8^\circ$





FIGURE 1

MEASURED DAYTIME HORIZONTAL PLAN
 RADIATION PATTERN

STATION WAVE
 ORION BROADCASTING, INC.
 LOUISVILLE, KENTUCKY

970 kHz 5kW-U DA-

A. D. RING & ASSOCIATES
 CONSULTING RADIO ENGINEERS

MEASURED $1/0^\circ$
COMPUTED $1/0^\circ$

$0.952/+76^\circ$
 $0.95/+88^\circ$

$\circ \text{---} 146.5^\circ \text{---} \circ \rightarrow 11^\circ \text{T.}$
1(S) 2(N)

$G_1 = G_2 = 88.8^\circ$

WAVE
201



JUNE, 1974

MV/M

600

COMPUTED & MEASURED
RMS = 424 MV/M

400

MEASURED VALUE

200

COMPUTED & MEASURED

82-8721

FIGURE 2

MEASURED NIGHTTIME HORIZONTAL PLANE
RADIATION PATTERN

STATION WAVE
ORION BROADCASTING, INC.
LOUISVILLE, KENTUCKY


970 kHz


5 kW-U

DA-2

A. D. RING & ASSOCIATES

N. LAT. $38^\circ 19' 05''$
W. LONG. $85^\circ 44' 39''$





WAVE

NO. 3124. POLAR CO-ORDINATE. CODEX BOOK COMPANY, INC. NEWPORT NEWS, VA. 23124




FIG. 4

Estimated unattenuated field at one mile in the vertical plane in the direction of WDAY and WCHH (510 from the line of radiators) for proposed 5 KW station at WAVE.

WAVE


Measured Non-DA
(3-30-63ct)

Station WAVE
Louisville, Kentucky

5kw, DA-2, U
970 kc
WAVE 970 KC

*1-26-63
renewed license
overing change
com DA-1 to DA-2*

A. D. RING & ASSOCIATES - 10/60 - M



FCC File No. BL-9792
Accepted 3-12-63

Station WAVE
Louisville, Kentucky

970 kc

* REVISED
DIRECTIONAL ANTENNA DESCRIPTION SHEET

Station: W C S H Main Studio: Portland, Maine

Frequency: 970 kc Power: 5 kw

Notification List No. 225* Date: May 2, 1947 Class III-A

GEOGRAPHICAL LOCATION
OF ANTENNA:

North Latitude: 43° 36' 21

West Longitude: 70° 19' 25

ANTENNA CHARACTERISTICS:

Authorized for Nighttime operation (DA-N)*

Number of elements: Two (2)


Type of elements: Series-fed, self-supporting, tapered, vertical steel towers.

TOWER:	<u>NORTHEAST</u>	<u>SOUTHWEST</u>	
HEIGHT ABOVE INSULATORS:	300'	300'	(106.5°)
SPACING:	325'	or	112°
NIGHT PHASING:	0°		+56°
NIGHT FIELD RATIO:	1.0		1.0
GROUND SYSTEM:	120 - 420' equally spaced radials about each tower base.		
ORIENTATION:	Elements on a line bearing 70° true, using the west tower as a reference.		

Predicted effective Field: 425 mv/m (at rated power)


*NOTE:- The change notified (From DA to DA-N) does not involve a change in the nighttime directional pattern, and presently filed patterns should, therefore, be retained. This revised description sheet should, however, be substituted for the existing description sheet.

77
970



WCSH
970

RAYMOND M. WILMOTTE
Consulting Radio Engineer
Washington, D. C.



WDAY


MEASURED
NIGHT

WDAY, FARGO, N. D.

BZ-3254

5kw, DA-N

970 kc



WDAY
FARGO, N. D.
5 KW DA 970 KC
MEASURED NIGHTTIME
RADIATION PATTERN
501130
GLENN D. GILLET & ASSOCIATES
CONSULTING RADIO ENGINEERS
WASHINGTON 4, D. C.

WDAY, Fargo, N. D. 970 kc


5kw, DA-1, U
970 kc

EXHIBIT 9-2

MP-2489

WEBR

970



WEBR INCORPORATED
BUFFALO, N. Y.

PROPOSED

DIRECTIONAL ANTENNA PATTERN

349.5° 120°
2 662160.6°
SPACING 3.524-35°
100° 2 662129.1°
H=84° 12-70°

Figure 1
Series 461219C


970 KC
5000 WATTS
DAY & NIGHT

FRANK H. McINTOSH

Consulting Radio Engineer

Washington, D.C.

3/3/48G



WE BR INCORPORATED BUFFALO, N. Y.		Figure 1 Series 471229C
		970 KC 5000 WATTS DAY & NIGHT
	PROPOSED DIRECTIONAL ANTENNA PATTERN	FRANK H. McINTOSH <i>Consulting Radio Engineer</i> Washington, D.C.


Rec'd 3-1-48

WEBR

WEBR
970

9/7/48G

970 KC 5KW DA-1



WEBR INCORPORATED BUFFALO, N. Y.		Figure 6 A Series 480312C
		970 KC 5000 WATTS DAY-NIGHT
MEASURED DIRECTIONAL ANTENNA PATTERN		FRANK H. McINTOSH Consulting Radio Engineer
		Washington, D. C.

WEBR

Measured Day & Night
(3-28-69ct)

Station WEBR
Buffalo, New York

5kw, DA-1, U
970 kc





EXHIBIT G



LATITUDE 42° 44' 41" North
LONGITUDE 78° 53' 13" West

ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MV/M FOR 1 KW	HEIGHT DEG
THEORETICAL						
1 (N)	S	E	0	1.0	-	84
2 (NG)	S	E	160.6	2.66	-	84
3 (C)	D	I	-35.0	3.52	-	84
4 (SC)	A	G	129.1	2.66	-	84
5 (S)	A	G	-70	1.0	-	84

MEASURED DIRECTIONAL
HORIZONTAL PLANE PATTERN
WEBR
BUFFALO, NEW YORK
970 KC 5 KW DA-1, U
690212

KEAR & KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

FCC File No. BL-12290
Accepted 3-11-69

Station WEBR
Buffalo, New York


970 kc

WEBR

Measured Non-DA
(3-28-69ct)

Station WEBR
Buffalo, New York

5kw, DA-1, U
970 kc



RMS = 191 MV/M

NON-DIRECTIONAL MEASURED AT 1.0 KW INPUT

EXHIBIT E

LATITUDE 42° 44' 41" North
LONGITUDE 78° 53' 13" West

ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MV/M FOR 1 KW	HEIGHT DEG
3	—	—	—	—	—	84

MEASURED NON-DIRECTIONAL
HORIZONTAL PLANE PATTERN

WEBR

BUFFALO, NEW YORK
970 KC 5KW DA-1, U

690212

KEAR & KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

FCC File No. BL-12290
Accepted 3-11-69

Station WEBR
Buffalo, New York


970 kc

WEBR

970

970 KC 5KW DA-1

9/7/48 G



○ = RADIAL MEASUREMENTS
X = CROSS RADIAL MEASUREMENTS

WEBR INCORPORATED
BUFFALO, N. Y.

MEASURED
DIRECTIONAL ANTENNA PATTERN

Figure 6B
Series 480313 C

970 KC
5000 WATTS
DAY-NIGHT

FRANK H. McINTOSH

Consulting Radio Engineer

Washington, D.C.

DIRECTIONAL ANTENNA DESCRIPTION SHEET

WFLA

Station: WFLA

Main Studio: Tampa, Florida

Frequency: 970 kHz

Power: 5 kW

Notification List No. 1658

Date: November 12, 1975

Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude: 28° 01' 14"

West Longitude: 82° 36' 34"

CONTINUED ON REVERSE

ANTENNA CHARACTERISTICS

MAY 3 1976

WASHINGTON, D.C.

Authorized for Daytime and Nighttime operation. (DA-2)

Number of elements: 5

Type of elements: Series-excited, uniform cross-section, guyed, vertical steel towers.

TOWER:	N(#1)	NE(#2)	W(#3)	S(#4)	C(#5)
HEIGHT ABOVE INSULATORS:	567'	203'	203'	203' (72°)	567' (201°)
NIGHT PHASING:	0°	-45°	+45°	0°	-
NIGHT FIELD RATIO:	1.0	1.0	0.6	0.6	-
DAY PHASING:	0°	-	-	-	+16°
DAY FIELD RATIO:	1.0	-	-	-	0.42

SPACING AND

ORIENTATION: Daytime elements #1 and #5 are spaced 614.67' (218°) on a line bearing 176° true.


Nighttime, towers #1, #2, #3 and #4 are located at the vertices of a parallelogram the long sides of which are 619.9' (220°) in length on a line bearing 186° true. The short sides are 338.1' (120°) in length on a line bearing 150° true.

GROUND SYSTEM: 120-250' equally spaced copper radials plus a 48' square ground screen about each tower. Radials are shortened along intersections between towers.

Predicted effective Night Field: 430 mv/m at rated power.

Predicted effective Day Field: 560 mv/m at rated power.

(Cont'd)



STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2039 K STREET, N.W.
WASHINGTON D.C. 20005

Figure B-1
Proposed Daytime
Horizontal Radiation Pattern
WFLA Tampa, Florida
970 kHz 5 Kw DA-2 U
October 1972

Coordinates:
N 28° 1' 14"
W 82° 36' 34"

Pattern Rms = 560 mV/m

Twr. Hts. = 200'

1 / 0'

218°

.42 / 16'


N 176° E

WFLA

2.

Note: Please retain the Daytime directional antenna radiation pattern notified for station WFLA in United States Change List Number 1572 dated March 21, 1974 and attach to this Revised Description Sheet and Nighttime patterns. This notification concerns only minor changes in means of radiation in the nighttime pattern with Daytime operation continued as previously notified.

CTR NO 30816A5



STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006

WFLA

30°

N 0° E

330°

STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006

60°

90°

120°

WFLA




FIGURE 3
PROPOSED 10° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975

150°


180°

210°

240°

270°


300°



STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006


FIGURE 4
PROPOSED 15° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975

WFLA



STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006


FIGURE 5
PROPOSED 20° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975



STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006

FIGURE 6
PROPOSED 25° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975

WFLA



STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006

FIGURE 7
PROPOSED 30° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975

STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006

FIGURE 8
PROPOSED 35° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975

200 400 600


FIGURE 8
PROPOSED 35° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975

WFLP


STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006

FIGURE 9.
PROPOSED 40° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975

WFLA




WFLA



STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2028 K STREET, N.W.
WASHINGTON, D. C. 20006


FIGURE 10
PROPOSED 45° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975




WFLA

STEEL, ANDRUS & ADAIR
CONSULTING ENGINEERS
2029 K STREET, N.W.
WASHINGTON, D. C. 20006

FIGURE 12
PROPOSED 55° VERTICAL RADIATION PATTERN
WFLA TAMPA, FLORIDA
SEPTEMBER 1975






011-24.65

WFLA 970


EUGENE DIETZEN CO

NO. 340-P DIETZEN GRAPH PAPER
PLAN CO-ORDINATE



EUGENE DIETZGEN CO
WASHINGTON, D.C.

NO. 340 P DIETZGEN GRAPH PAPER
POLAR COORDINATE



~~WTAM~~
WIIN

PROPOSED DAY
(6/26/57g)


Station WTAM
Atlanta, Georgia

5kw, DA-D,D
970 KC

*Granted Mod of CP
6/20/57 to change
Fido's location*

*Granted Mod of CP
(3/17/58) to change
trans location (see below)
This mod. also corrects
the height above sea
level to 1160 ft.*

PAGE CREDIT: STEEL & WALDSCHMIDT, INC.
COMMUNICATIONS BUILDING
1117 EIGHTH STREET, NORTHEAST
WASHINGTON 5, D. C.



NL 33° 42' 49.41"
WL 84° 20' 30.10"

Figure 7
Proposed Directional Pattern
Proposed WTAM ATLANTA, GA.
970Kc 5Kw DA-D
May 1957

FCC File No. BMP-7628
Accepted


WTAM
Atlanta, Georgia

970 KC

MEASURED DAY
(4-9-58g)

Station WVIN
Atlanta, Georgia


5kw, DA-D,D
970 KC



MEASURED NON-DA
(4-9-58g)

Station WIIN
Atlanta, Georgia

5kw, DA-D,D
970 KC



FCC File No. BL-7061
Accepted 3-31-58

WIIN
Atlanta, Georgia

970 KC


WJMX

PROPOSED
NIGHT

WJMX, FLORENCE, S. C.

1kw, 5kw-LS, DAN

970 kc



AMENDMENT RECD 11-21-49 BP-7024

WJMX, Florence, S. C. 970 kc


MEASURED
NIGHT

WJMX, FLORENCE, S. C.

1kw, 5kw-LS, DAN

970 kc

WJMX



WJMX, Florence, S. C. 970 kc

PROPOSED
DAYTIME


NEW, JACKSON, MICH.
(WKMH, Inc.)

1kw, DA-2


WKMH
JACKSON, Mich.
970 kc

1/11/50G

1-10-50



--- ALLOWED FIELD



LATITUDE $42^{\circ} 11' 39''$
LONGITUDE $84^{\circ} 25' 50''$

ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MV/M FOR 1 KW	HEIGHT DEG
1	SEE	SEE	32	1	180	87
2	SEE	SEE	170.8	1.025	180	87
3	DIAGRAM	DIAGRAM	-32	1	180	87
4	DIAGRAM	DIAGRAM	---	---	---	---

CALCULATED DAYTIME
HORIZONTAL PLANE PATTERN
FOR
PROPOSED STATION
JACKSON, MICHIGAN
970KC. 1KW U, DA-2

KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

481229

NEW, Jackson, Mich. 970 kc



W K H M

MEASURED
DAY

WKHM, JACKSON, MICH.
1/1/52

1 KW, U, DA-2

970 KC



LATITUDE		42° 11'	39"			
LONGITUDE		84° 25'	50"			
ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MV/M FOR 1 KW	HEIGHT DEG
1	S	E	32	1	180	87
2	E	E	170.5	1.825	180	87
3	D	D	— 32	1	180	87
4	I A G R A M	D I A G R A M	—	—	—	—

MEASURED DAYTIME
HORIZONTAL PLANE PATTERN
WKHM
JACKSON, MICHIGAN
970 KC. 1 KW. U, DA-2

KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

511120

PROPOSED
NIGHT



NEW, JACKSON, MICH.
(WKMH, Inc.)

1kw, DA-2

WKMH
JACKSON, MICH
970 kc

1/11/50G

1-10-50



LATITUDE 42° 11' 39"
LONGITUDE 84° 25' 50"

ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	MV/M FOR 1 KW	HEIGHT DEG
1	SEE	SEE	0	1	180	87
2	SEE	SEE	150.7°	2.11	180	87
3	DIAGRAM	DIAGRAM	-55.2°	2.11	180	87
4	DIAGRAM	DIAGRAM	95.5°	1	180	87

CALCULATED NIGHTTIME
HORIZONTAL PLANE PATTERN
FOR
PROPOSED STATION
JACKSON, MICHIGAN
970 KC. 1KW U, DA-2

KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

491221.

NEW, Jackson, Mich. 970 kc


WKHM

MEASURED
NIGHT

TECH, JACKSON, MICH.
1/21/52

1 KW, U, DA-2

970 KC




WKHM

MEASURED
NIGHT NULLS

WKHM, JACKSON, MICH.
1/21/52G

1 KW, U, DA-2

970 KC



LATITUDE
LONGITUDE

ANTENNA NUMBER	AZIMUTH DEG	SPACING DEG	PHASING DEG	FIELD RATIO	M/W FOR 1 KW	HEIGHT DEG

EXPANDED SCALE
MEASURED NIGHTTIME
HORIZONTAL PLANE PATTERN
WKHM
JACKSON, MICHIGAN
970 KC. 1 KW. U, DA-2

KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D C

81120


WKHM

MEASURED
NOT-DA

WKHM, JACKSON, MICHIGAN
1/21/52G

1 KW, U, DA-2

970 KC




MEASURED RADIALS

MEASURED 1000 WATT
NON-DIRECTIONAL PATTERN
ANTENNA NO. 2
WKHM
JACKSON, MICHIGAN
970 KC. 1 KW. U, DA-2

KEAR AND KENNEDY
CONSULTING ENGINEERS
WASHINGTON, D. C.

511120

Figure 11




WMAY

Measured Non-DA
(8-24-62ct)


Station WMAY
Springfield, Illinois

500w, 1kw-LS, DA-2, U
970 kc

Figure 9



MEASURED NONDIRECTIONAL HORIZONTAL PLANE RADIATION PATTERN



LINCOLN BROADCASTING COMPANY, INC.
SPRINGFIELD, ILLINOIS

Jules Cohen
Consulting Electronic Engineer

RADIO STATION WMAY

970 KC

0.5 KW 1 KW-LS 1 DA-1

July, 1962


FCC File NO. BL-9516
Accepted 8-9-62

Station WMAY
Springfield, Illinois

970 kc

500w, 1kw-LS, DA-2, U
970 kc

Figure 2



PROPOSED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

(1) Not used 32° T
(2) $1.18 / 110^\circ$
(3) $1.00 / 110^\circ$
(4) $0.288 / 110^\circ$

32° T
(1)
(2)
(3)
(4)

110°
110°
110°
110°

0.288°

LINCOLN BROADCASTING COMPANY, INC.
SPRINGFIELD, ILLINOIS

Jules Cohen
Consulting Electronic Engineer

PROPOSED OPERATION
RADIO STATION WMAY
970 KC

0.5 KW 1 KW-LS U DA-2
Pattern 620301

FCC File No. BP-15481
Accepted 4-18-62

Station WMAY
Springfield, Illinois


970 kc

WMAY


PROPOSED
DAYTIME

WMAY, SPRINGFIELD, ILL.

500w, 1kw-LS, DA-2 970 kc
FIGURE 7



CALCULATED HORIZONTAL PLANE RADIATION PATTERN FOR DAYTIME OPERATION



WMAY, Springfield, Ill. 970 kc

WMAY


PROPOSED
DAY NULLS

WMAY, SPRINGFIELD, ILL.

4-19-50

500w, 1kw-LS, DA-2 970 kc

FIGURE 8



CALCULATED HORIZONTAL PLANE RADIATION PATTERN FOR DAYTIME OPERATION

DETAIL IN NULLS	LINCOLN BROADCASTING COMPANY SPRINGFIELD ILLINOIS	PROPOSED NEW STATION SPRINGFIELD ILLINOIS
	WELDON & CARR CONSULTING RADIO ENGINEERS WASHINGTON D.C. DALLAS TEXAS	970 KC 0.5 KW, 1 KW-LS U DA-2 W 500314 B

WMAY, Springfield, Ill. 970 kc

WMAY

MEASURED
DAY

WMAY, SPRINGFIELD, ILL.

500w, 1kw-LS, DA-2

970 kc

Pattern No. # 501009 C

10/16/50G


TRUE NORTH

WMAY


970 KC 0.5 KW, 1 KW-LS U DA-2

DAYTIME PATTERN

10-12-50



MEASURED DAYTIME HORIZONTAL PLANE RADIATION PATTERN



LINCOLN BROADCASTING COMPANY

Figure 14

WMAY

SPRINGFIELD

ILLINOIS

970 KC 0.5 KW, 1 KW-LS U DA-2

WELDON & CARR Consulting Radio Engineers

Dallas Washington Seattle

WMAY, Springfield, Ill. 970 kc

MEASURED
DAY NULLS

WMAY, SPRINGFIELD, ILL.

500w, 1kw-LS, DA-2

970 kc

WMAY

Pattern No. 501009 D

10/16/50G


TRUE NORTH

WMAY

970 KC 0.5 KW, 1 KW-LS U DA-2

DETAIL IN MINIMA

10-12-50



MEASURED DAYTIME HORIZONTAL PLANE RADIATION PATTERN

DETAIL IN MINIMA

LINCOLN BROADCASTING COMPANY

WELDON & CARR Consulting Radio Engineers

Dallas • Washington • Seattle

Figure 15

WMAY

SPRINGFIELD ILLINOIS

970 KC 0.5 KW, 1 KW-LS U DA-2

WMAY, Springfield, Ill. 970 kc


PROPOSED
NIGHT NULLS

NEW, SPRINGFIELD, ILL.
(LINCOLN BG. CO.)

3/29/48

500w, 1kw-LS, DA2

WMAY
SPRINGFIELD, IL
970 kc
FIGURE 8.1A



CALCULATED HORIZONTAL PLANE RADIATION PATTERN FOR NIGHTTIME OPERATION

SITE: $39^{\circ} 52' 51''$ N
 $89^{\circ} 31' 27''$ W
DETAIL IN NULLS

LINCOLN BROADCASTING COMPANY
SPRINGFIELD ILLINOIS

WELDON & CARR
CONSULTING RADIO ENGINEERS
WASHINGTON DC

PROPOSED NEW STATION
SPRINGFIELD ILLINOIS

970 KC 0.5 KW, 1 KW-LS U DA-2
480304E
SUPERSEDES 470613C

New, Springfield, Ill. 970 kc


WMAY

MEASURED
NIGHT

WMAY, SPRINGFIELD, ILL.

500w, 1kw-LS, DA-2

970 kc



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

	LINCOLN BROADCASTING COMPANY WELDON & CARR Consulting Radio Engineers Dallas • Washington • Seattle	Figure 10 WMAY SPRINGFIELD ILLINOIS 970 KC 0.5 KW, 1 KW-LS U DA-2
--	--	---

WMAY, Springfield, Ill. 970 kc

WMAY

MEASURED
NIGHT NULLS

WMAY, SPRINGFIELD, ILL.

500w, 1kw-LS, DA-2

970 kc

Pattern No. W 501009 B

10/16/50G

K4sm


TRUE NORTH

WMAY

970 KC 0.5 KW, 1 KW-LS U DA-2

DETAIL IN MINIMA

10-12-50



MEASURED NIGHTTIME HORIZONTAL PLANE RADIATION PATTERN

DETAIL IN MINIMA

LINCOLN BROADCASTING COMPANY

Figure 11

WMAY

SPRINGFIELD ILLINOIS

970 KC 0.5 KW, 1 KW-LS U DA-2

WELDON & CARR Consulting Radio Engineers

Dallas - Washington - Seattle


WMAY, Springfield, Ill. 970 kc

PROPOSED NIGHT Station W A A T
(10-29-56g) Newark, New Jersey

1 KW-N, 5KW-D, DA-N, U

WNIA

970 K C



A. D. RING & ASSOCIATES - 1/56 - M

FCC File No.
BP-10,844

Accepted 10-22-56


Station W A A T
Newark, New Jersey

970 K C

VVIVIA
WAAT

MEASURED NIGHT Station W A A T 5KW-D, 1KW-N,
(12-3-56g) Newark, New Jersey DA-N, U 970 KC


A. D. RING & CO - 1/12 - 1000




~~WAAT~~
WNT/

MEASURED NON-DA Station W A A T 5 KW-D, 1KW-N,
(12-3-56) Newark, New Jersey DA-N, U 970 KC

A. D. RING & ASSOCIATES - 1/24 - M



WOZN

PROPOSED DAY
(12-15-60g)New; B.F.J. Timm
Jacksonville, Florida1kw, DA-D,D
970 KC

LIMIT -----
 CALCULATED -----
 M.E.O.V. -----

N320°E TRUE

#1 @ 1.0 / 90°

284 FT

0.65 / 0° #2

G = 68° = 190 FT

FIELD INTENSITY VERSUS AZIMUTH

ELEVATION ANGLE	0°
RMS	179 MV/M
N. LATITUDE	30° 23' 06"
W. LONGITUDE	81° 40' 06"
SUPERSEDES	691022
PATTERN NO.	601007

RUSSELL P. MAY
 CONSULTING RADIO ENGINEER
 WASHINGTON 5, D.C.

B. F. J. TIMM
 JACKSONVILLE, FLORIDA
 970 KC - 1 KW - DAYTIME - (DA-D)
 PROPOSED
 HORIZONTAL RADIATION
 PATTERN

FIGURE NO. 2A

FCC File No. BP-13649
 Accepted 11-14-60 (Amended)

B.F.J. Timm
 Jacksonville, Florida

970 KC

SUPPLEMENTAL DIRECTIONAL
ANTENNA DESCRIPTION SHEET

Station: WOZN

Main Studio: Jacksonville, Florida

Frequency: 970 kHz

Power: 1 kW

Notification List No. 1601

Date: October 9, 1974 Class: III

GEOGRAPHICAL LOCATION OF THE
CENTER OF THE ANTENNA SYSTEM:

North Latitude:	30°	23'	08"
West Longitude:	81°	40'	04"


Authorized for Daytime operation (DA-D).

Tower height above insulators: 186' (66°) both towers.

Predicted effective Day Field: (omnidirectional) 179 mv/m at rated power.

Note: Please retain the description sheet and directional antenna radiation patterns notified for a new station at Jacksonville, Florida in United States Change List Number 1123, dated August 4, 1965 and attach to this supplemental Description Sheet. This notification is for the purpose of indicating only a correction in the geographical coordinates of the center of the antenna system and in the height of the towers.

WOZN




○ MEASURED RADIAL VALUES

FIGURE 1-A

HORIZONTAL RADIATION PATTERN

SPACING AND ORIENTATION



G = 66° (BOTH TOWERS)


APPLICANT : RADIO STATION WOZN
 LOCATION : JACKSONVILLE, FLORIDA
 FREQUENCY : 970 KC/S
 POWER : 1 KW-D(DA)
 LATITUDE : 30 DEG 23 MIN 08 SEC
 LONGITUDE : 81 DEG 40 MIN 04 SEC
 WHEN USED: DAYTIME HOURS
 RMS FIELD: 179 MV/M (MEASURED)
 DATE : MARCH 1974

SILLIMAN, MOFFET & KOWALSKI
 CONSULTING RADIO ENGINEERS
 WASHINGTON, D.C.

Measured by
(3-22-71)

Station WREO
Ashtabula, Ohio

WREO
1kw.5kw-LC,DA-2,
570 kc



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	

FIG. 6.16

DA-D MEASURED HORIZONTAL PATTERN

Radio Station WREO
Ashtabula, Ohio

Carl E. Smith
Consulting Radio Engineers

FCC File No. BZ-7756
Accepted 2-22-71

Station WREO
Ashtabula, Ohio


570 kc

WREO

Measured Night
(3-22-71)

Station WREO
Ashtabula, Ohio

WREO
1 kw, 5 kw - 1, 5, 2A-2, -
970 kc



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA	
	No. 1	POWER	HEIGHT	TRUE	SPACING	PHASING	HORIZONTAL	FIELD	ELEV	ELEVATION	CALL
	S = 87.5°	1	125	0	0.0	91.6	1.00	0	193	970	WREO
	No. 2	2	90	176	87.5	87.6	2.44	10		POWER	IN/50 LS
	S = 87.5°	3	90	176	175.0	87.6	1.00	30		TIME OF OPERATION	U
	No. 3	4	90	176	262.5	91.6		50		TYPE OF OPERATION	2A-2
No. 4	1									EXPT. ME. TOWER	1, 2, 3, 4
S = 87.5°										CONTINUOUS TOWER	1, 2, 3, 4
No. 3										MAX. FIELD STRENGTH	180
S = 87.5°										MAX. POWER	142, 400
No. 4										MAX. FIELD STRENGTH	48, 48
1										MAX. POWER	41, 48, 52
176°										MAX. FIELD STRENGTH	80, 46, 45
										MAX. POWER	540713
										MAX. FIELD STRENGTH	710121

FIG. 6.17

DA-N MEASURED HORIZONTAL PATTERN

Carl E. Smith
Consulting Radio Engineers


Radio Station WREO
Ashtabula, Ohio

FCC File No. BZ-7756
Accepted 2-22-71

Station WREO
Ashtabula, Ohio

970 kc

WREO



WREO

MEASURED

WICA, ASHTABULA, OHIO


1kw, 5kw-LS, DA2

DAY 3/1/49G

License 2-24-49


970

970 kc



WICA, ASHTABULA, OHIO 970 kc

970 KC




WREO

PROPOSED
NIGHT NULLS

WICA, ASHTABULA, OHIO
10/1/52G

1 KW, 5KW-LS, U, DA-2

970 KC




WREO

MEASURED
NIGHT

WICA, Ashtabula, Ohio

1KW,5KW-LS, U, DA-2

970 kc



976 KC


WRKN

Proposed Day
(4-28-66ct)

New; Wilbur J. Martin, Sr.
Brandon, Mississippi

1kw, DA-D, D
970 kc

SP 10-14-66




WRKN

Measured Day
(7-26-67ct)

Station WRKN
Brandon, Mississippi

1kw, DA-D, D
970 kc

7-10-67
GRANTED
LICENSE
NEW AM
STATION




LATITUDE: 32° 17' 20"
LONGITUDE: 89° 59' 50"

JOHN H. MULLANEY
AND
ASSOCIATES

ANTENNA PARAMETERS

	CALCULATED	MEASURED
#1	1/0°	1/0°
#2	0.6/-16°	0.545/-97°



8 3, 92.2°/260°

Station WRKN
Brandon, Mississippi

FIGURE 11
MEASURED DIRECTIONAL
PATTERN

RADIO STATION WRKN
BRANDON, MISSISSIPPI

970 KHZ

1 KW, DA-D

FCC File No. BL-11693
Accepted 7-21-67


970 kc

Measured Non-DA
(7-26-67ct)

Station WRKN
Brandon, Mississippi

1kw, DA-D, D
970 kc

8-10-67
GRANTED
LICENSE
NEW AM
STATION



LATITUDE: 32° 17' 20"
LONGITUDE: 89° 59' 50"

JOHN H. MULLANEY
AND
ASSOCIATES

ANTENNA PARAMETERS

TOWER NO. 2 (E)
250 WATTS

FIGURE 10
MEASURED NON-DIRECTIONAL
PATTERN

RADIO STATION WRKN
BRANDON, MISSISSIPPI

970 KHZ

1 KW, DA-D

FCC File No. BL-11693
Accepted 7-21-67

Station WRKN
Brandon, Mississippi

970 kc

WTBF


PROPOSED NIGHT
(3/22/55G)

STATION WTBF
TROY, ALABAMA

500W, 5KW-LS
DA-2, U

970 KC

BP-17468
PPL. accepted 1-3-67
change operation from
500W 5KW-LS DA-2, U to
500W 5KW-LS DA-N, U
10-31-67 LICENSE
GRANTED IN
CHANGES IN
DA-2, U TO
DA-N, U



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
		TOWER NO.	ELECTRICAL HEIGHT	TRUE TOWER ORIENTATION	SPACING	PHASING	HORIZONTAL FIELD	FIELD RATIO	ELEV. ANGLE	ELEVATION RMS FIELD	CALL	WTBF
1	71	000	000	000		1		0		FREQUENCY	970	
2	71	015	270	-90°		0.9		20		POWER	0.5	
3								30		TIME OF OPERATION	NIGHT	
4								40		TYPE OF OPERATION	DA	
5								50		DAYTIME TOWERS	2-3	
6								60		NIGHTTIME TOWERS	1-3	
7								70		NO RADIALS PER TOWER	120	
8								80		LENGTH OF RADIALS	88.7 x 250	
9								90		GROUND SCREEN DIMENSIONS	24' x 24'	
10								100		LONG	31	
										W	50	
										LS	50	
										DA-2	00.6	
										SUPERSCOES		
										PATTERN NO	35019B	

CLAUDE M. GRAY
CONSULTING RADIO ENGINEER
BIRMINGHAM, ALA.

EXHIBIT
1-A-9

NIGHTTIME
PROPOSED HORIZONTAL RADIATION PATTERN
WTBF TROY, ALABAMA
0.5 KW, 5 KW LS, DA-2 970 KC


WTBF

MEASURED NIGHT
(3/4/57g)

Station ~~WTBF~~
Troy, Alabama

500w, 5kw-LS, DA-2, U
970 KC

*granted license
4/3/57*
BP-17468
PPL. accepted
to change operation from
500W, SKW-LS, DA-2, U
to 500W, SKW-LS, DA-N, U
1-3-67
10-31-67
GRANTED
LICENSE
CHANGES
FROM DA-2, U
to DA-N, U



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
		TOWER No.	ELECTRICAL HEIGHT G	TRUE TOWER ORIENTATION P	SPACING S	PHASING P	HORIZONTAL FIELD M/m	FIELD RATIO F	ELEV. ANGLE -θ°	ELEVATION RMS FIELD mV/m	CALL WTBF	FREQUENCY 970 Kc
1	71'	000°	000°	000°			0.9	0		POWER 0.3 kw	TIME OF OPERATION Night	
2								10		TYPE OF OPERATION DA		
3	71'	015°	270°	-80°			1.0	20		DAYTIME TOWERS 2 & 3		
4								30		NIGHTTIME TOWERS 1 & 3		
5								40		No RADIALS PER TOWER 120		
6								50		LENGTH OF RADIALS 141 - 250 ft		
7								60		GROUND SCREEN DIMENSIONS 24 x 24'		
8								70		LAT. 31° 50' 03.8"		
9								80		LONG. 85° 56' 00.6"		
10								90		SUPERSEDES 551208A		
		DAYTIME OPERATION ☐ NIGHTTIME OPERATION ☒								P _{max} = 143 mV/m		
CLAUDE M. GRAY CONSULTING RADIO ENGINEER BIRMINGHAM, ALA.		MEASURED HORIZONTAL RADIATION PATTERN TROY BROADCASTING CORPORATION TROY, ALABAMA										

FCC File No. BL-6530
Accepted 2/19/57

WTBF
Troy, Alabama


970 KC

WTBF

MEASURED NON-DIRECTIONAL, Station ~~WTBF~~
(3/4/57g) Troy, Alabama

500W, 5KW-LS, DA-2, U
970 KC

*granted license
4/3/57
BP-17468
APPL. accepted
to change operation from
500W, 5KW-LS, DA-2, U
500W, 5KW-LS, DA-N, U
10-31-67
GRANTED LIC.
CHANGES FROM
DA-2, U to
DA-N, U*



TOWER PLACEMENT SKETCH		PATTERN PARAMETERS								STATION DATA		
		TOWER No.	ELECTRICAL HEIGHT ft	TRUE TOWER ORIENTATION °	SPACING ft	PHASING °	HORIZONTAL FIELD RATIO dB	FIELD RATIO dB	ELEV. ANGLE °	ELEVATION RMS FIELD dB	CALL	WTBF
1	6'	0°	5'	0°	0°	0	0	0	0	FREQUENCY	970 kc	
2	71'	000°	000°	000°	000°	1.0	10	10	10	POWER	5.0 kw	
3							20	20	20	TIME OF OPERATION	ND (Proof)	
4							30	30	30	TYPE OF OPERATION	ND	
5							40	40	40	DAYTIME TOWERS	2	
6							50	50	50	NIGHTTIME TOWERS	XX	
7							60	60	60	NO RADIALS PER TOWER	120	
8							70	70	70	LENGTH OF RADIALS	141 - 250 ft	
9							80	80	80	GROUND SCREEN DIMENSION	24 x 24'	
10										LAT.	31° 50' 03.8"	
										LONG.	85° 56' 00.6"	
										RMS 425 ---	SUPERSEDES	
										PATTERN No.	561209A	
										MEASURED HORIZONTAL RADIATION PATTERN TROY BROADCASTING CORPORATION TROY, ALABAMA		

CLAUDE M. GRAY
CONSULTING RADIO ENGINEER
BIRMINGHAM, ALA

FCC File No. BL-6530
Accepted 2/19/57

WTBF
Troy, Alabama

970 KC



Proposed Day
(7-28-66ct)

Station WJRZ
Hackensack, New Jersey

WWDJ

970 kc

MCP 9-16-66



	PROPOSED DAYTIME RADIATION PATTERN
	PATTERN NO. 660222
	WJRZ - HACKENSACK, NEW JERSEY
	970 KC - 5 KW - U - DA-2
	APRIL, 1966
	<i>Gautney & Jones - Consulting Radio Engineers</i>

FCC File No. BMP-11846
Accepted 7-7-66

Station WJRZ
Hackensack, New Jersey


970 kc

N. Latitude 40° 57' 18"
W. Longitude 74° 04' 05"

PROPOSED NIGHTTIME PATTERN
PATTERN NO. 630612 (AMENDED)
WJRZ - HACKENSACK, NEW JERSEY
970 KC - 5 KW - DA-N

November, 1964

Gautney & Jones - Consulting Radio Engineers



Measured Day
(7-26-67ct)

Station WJRZ
Hackensack, New Jersey

5kw, DA-2, U
970 kc

-BL-11672

Granted

9-16-68

license

covering

increase

in

nighttime

power

and

change

in

antenna

transmitter

location

MEASURED DAYTIME DIRECTIONAL PATTERN

WJRZ - HACKENSACK, NEW JERSEY


970KC - 5KW-U - DA-2

MARCH, 1967

Gautney & Jones Communications, Inc.

THEORETICAL:	0.565 / +98.6°	1.0 / 0°	0.565 / -171.8°
326° TRUE ←	①	5 → ②	5 → ③
MEASURED:	0.565 / +99.0°	1.0 / 0°	0.565 / -171.5°
S = 90° = 253'			G = 89° = 250'

RMS = 400 MV/M



North Latitude 40° 54' 39"
West Longitude 74° 01' 42"

FCC File No. BL-11672
Accepted 7-3-67

Station WJRZ
Hackensack, New Jersey

970 kc

Measured Non-DA
(7-26-67ct)

Station WJRZ
Hackensack, New Jersey

5kw, DA-2, U
970 kc

BL-11672
Granted
9-16-68
license
covering
increase
in
nighttime
power
and
change
in
antenna
transmitter
location


MEASURED NON-DIRECTIONAL PATTERN

WJRZ - HACKENSACK, NEW JERSEY

970KC - 5KW-U - DA-2

MARCH, 1967

Gautney & Jones Communications, Inc.



FCC File No. BL-11672
Accepted 7-3-67

Station WJRZ
Hackensack, New Jersey


970 kc

Measured Night
(7-26-67ct)

Station WJRZ
Hackensack, New Jersey

5kw, DA-2, U
970 kc

BL-11672
Granted
9-16-68
license
covering
increase
in
nighttime
power
and change
in
antenna
transmitter
location




FCC File No. BL-11672
Accepted 7-3-67

Station WJRZ
Hackensack, New Jersey

970 kc


MAY 11 1948 G

APP. 3C



ANTENNA PARAMETERS

Glenn D. Gillett And Associates
Consulting Radio Engineers
National Press Building
Washington, D.C.



Ant.	Electrical Height	Free Space Orientation	Swing	Swing	Horizontal Plane Gain	Field Ratio	Gain Angle	Elevation Angle
1	90	—	—	+37	196	.80	430	
2	90	153	75	+93.7	196	1.58	40	
3	90	153	75	+117.9	196	1.29	40	
4	90	153	75	+37	196	.58	30	
5							40	
6							30	
7							40	
8							70	
9							80	
10							90	

WWSW
PITTSBURG, PA.
5 KW. DA-2 970 KC.

DAYTIME PATTERN

Latitude 40° 30' 30"
Longitude 80° 0' 30"
Superstation 470519
Reflector No. 480430

5-7-48

Proposed day

MEASURED
RAY

WWSW, PITTSBURGH, PA.

5kw, DA-2


97.00

12/1/50

N

BI-3237
11-10-40


RPP



- RADIALS
- RATIO

ANTENNA PARAMETERS

Glenn D. Gillett And Associates
Consulting Radio Engineers
National Press Building
Washington, D.C.



Antenna	Height	Base	Top	Spacing	Phasing	Horizontal Field	Field Ratio	Element Angle	Element Spacing
0	90	0	0	37		0.60	0	0	
1	90	153	75	-93.7		1.58	10	10	
2	90	153	150	-117.9		1.29	20	20	
3	90	153	225	-37		0.58	30	30	
4									
5									
6									
7									
8									
9									
10									
11									
12									
13									
14									
15									
16									
17									
18									
19									
20									

WWSW
PITTSBURGH, PA.

5 KW DA-2

970 KC

DAYTIME
HORIZONTAL RADIATION
PATTERN

Latitude 40° 30' 30"

Frequency 480.430


Longitude 80° 0' 30"

Pattern No. 491117

MAY 11 1948 G


5-7-48

APP. 3A



ANTENNA PARAMETERS

Glenn D. Gillett And Associates
Consulting Radio Engineers
National Press Building
Washington, D.C.



Power	Electrical Height	Effective Power	Spacing	Feeding	Horizontal Field	Field Ratio	Element Angle	Element Height	Element Field
No.	0'	0'	0'	0'	0'	0'	0'	0'	0'
0	90	-	-	-	-	1.0	0	450	-
1	90	153	75	97.8	-	2.17	10	418	-
2	90	153	75	97.2	-	1.62	20	333	-
3	90	153	75	177.5	-	.4	30	216	-
4	90	153	391	177.5	-	.8	40	108	-
5	90	136.2	462.5	31.8	-	1.74	50	63	-
6	90	138.5	534.5	115.2	-	1.30	60	49	-
7	90	140.3	607.5	111.5	-	.32	70	29	-
8	-	-	-	-	-	-	80	6.8	-
9	-	-	-	-	-	-	90	2.07	-
10	-	-	-	-	-	-	100	1.28	-

WWSW
PITTSBURG, PA.
5 KW. DA -2 970 KC.


NIGHT TIME
HORIZONTAL RADIATION
PATTERN

Latitude 40° 30' 30" Superlat 470519
Longitude 80° 0' 30" Station No. 480430

5-7-48

WWSW, Pittsburgh, Pa. 970 KC.

APP. 38



PROPOSED
WWSW, PITTSBURGH, PA.
5-8-48
5kw, DA-2
100-3888 dated 8/4/48
970 KC


WWSW

MEASURED
FIELD

0.01, 1000-100, 1A.


5kw, DA-2

970 kc



ANTENNA PARAMETERS

Glenn D. Gillett And Associates
Consulting Radio Engineers
National Press Building
Washington, D.C.



Frequency	Height	Power	Distance	Field	Ratio	Time	Elevation
90	0	0	111.5	1.0	0	0	0
90	153	75	97.8	2.17	40	0	0
90	153	150	49.2	1.62	20	0	0
90	153	225	17.5	0.4	30	0	0
90	133	391	47.5	0.8	40	0	0
90	136.2	462.5	31.8	1.74	50	0	0
90	138.5	534.5	115.2	1.30	60	0	0
90	140.3	607.5	111.5	0.32	70	0	0

WWSW
PITTSBURG, PA
5 KW DA-2 970 KC

NIGHTTIME
HORIZONTAL RADIATION
PATTERN

Latitude 40° 30' 30" Longitude 480430
Altitude 80° 0' 30" Date 491117

WWSW, Pittsburgh, Pa. 970 kc

Description Sheet
(3-28-68ct)

New Station
Edson, Alberta

10kw, DA-1, U, Class III
970 kc

DESCRIPTION SHEET - DIRECTIONAL ANTENNA

Station: NEW Main Studio: Edson, Alberta
Frequency: 970 kHz Power: 10 kW Class, III
Notification List: 239 Date: February 20, 1968.

GEOGRAPHICAL LOCATION: Latitude: 53° 32' 09" North
Longitude: 116° 36' 06" West

ANTENNA CHARACTERISTICS:

Mode of Operation: DA-1
Number of Elements: Two (2)
Type of Elements: Guyed steel towers, uniform
cross section, base insulated
for series feed.

TOWER:	#1 SOUTH	#2 NORTH
HEIGHT ABOVE INSULATORS:	200' (71°)	200' (71°)
OVERALL HEIGHT:	205'	205'
FIELD RATIO:	1.0	.95
PHASING:	0°	-125°

GROUND SYSTEM: 120 equally spaced radials per tower
of No. 10 B & S gauge bare copper wire, buried
approximately 8". Length of radials 406' (0.4
wavelength) with the exception of those joined
along the common chord.

SPACING AND ORIENTATION
OF TOWERS:

Towers are on a line bearing 20° West of True
North and are spaced 225.5' (80°) apart.

PREDICTED EFFECTIVE FIELD:

600 mv/m at 1 mile for 10 kW
189 mv/m at 1 mile for 1 kW

D. E. M. ALLEN, P. ENG.


BROADCAST CONSULTING ENGINEER

Revised: November 23, 1967

Proposed Day & Night
(3-28-68ct)

New Station
Edson, Alberta

10kw, DA-1, U, Class III
970 kc



Proposed Day & Night Nulls
(3-28-68ct)

New Station
Edson, Alberta

10kw, DA-1, U, Class III
970 kc




FIGURE #

HORIZONTAL PATTERN-EXPANDED SCALE

NEW AM STATION EDSON, ALBERTA

970 KHz 10 KW DA-1 CLASS III

PROJECT #5901 REVISED NOVEMBER 23, 1967

CONSULTANT D.E.M. ALLEN P. ENG.

XEDF

Description Sheet
(11-29-62ct)Station XEDF
Mexico, D.F.5kw, 10kw-LS, DA-N, U
970 kc Class II

DESCRIPCION DEL SISTEMA DIRECCIONAL DE RADIACION

OPERACION NOCTURNA

AUGUST 1961

ESTACION: **XEDF**
FRECUENCIA: 970 KHz.
CLASE: IIESTUDIOS EN MEXICO, D.F.
POTENCIAS: 10,000 W. DIURNOS.
5,000 W. NOCTURNOS

LISTA DE CAMBIOS.

FECHA: AGOSTO DE 1961.

LOCALIZACION GEOGRAFICA
DEL SISTEMA RADIADOR.LONGITUD O 99° 07' 19"
LATITUD N 19° 29' 19"

AUTORIZADO PARA OPERACION.

A D N

NUMERO DE ELEMENTOS RADIADORES.

D O S.

TIPO DE ELEMENTOS RADIADORES.

TORRES VERTICALES DE ACERO
DE SECCION UNIFORME TRIANGU
LAR SOPORTADAS CON RETENIDAS
ALIMENTACION TIPO SERIE.

TORRES:

NORTE

SUR

ALTURA SOBRE LOS AISLADORES.

103.08 Mts.
120°103.08 Mts
120°

SEPARACION ENTRE TORRES.

77.32 Metros. (90°)

MAGNITUDES RELATIVAS DE CORRIENTES

I

I

DEFASAMIENTO.

120°

0°

AZIMUT DEL EJE DE LAS TORRES

MOSTRADO EN EL LOBULO
HORIZONTAL = 41° 30' 00"

RAIZ CUADRATICA MEDIA TEORICA.

446.4961 mV/M

INTENSIDAD DE CAMPO R.C.M. NO
ATENUADO A UNA MILLA POR
KILOWATT DE POTENCIA RADIADA.

2025 mV/M


APROBO

XEDF

Proposed Night
(11-29-62ct)


Station XEDF
Mexico, D.F.

5kw, 10kw-LS, DA-N, U
970 kc Class II



PATRON DE RADIACION HORIZONTAL CALCULADO EN mV/M A 1609 METROS

ESQUEMA DE LAS TORRES Y SU ORIENTACION CON RESPECTO AL NORTE ASTRONOMICO



RADIODIFUSORA
X E D F

México, D.F.

970 KHz.
5,000 Watts.

DISEÑO

Joaquin Durán
y Filiberto Solís C

DIBUJO

E S E S M A